

FINAL

Remedial Investigation Report

CW-2 Wastewater Treatment Lime Pit Site

**U. S. Army Installation Fort Monmouth
Fort Monmouth, New Jersey**



Directorate of Public Works



March 7, 2005

***Versar* INC.**

**201 Gibraltar Road, Suite 100
Horsham, Pennsylvania 19044**

**Contract No. DACA51-00-D-0004
Delivery Order No. 16**

United States Army
Fort Monmouth, New Jersey

**Remedial Investigation Report
CW-2 Wastewater Treatment
Lime Pit Site**

Fort Monmouth, New Jersey

March 7, 2005

**REMEDIAL INVESTIGATION REPORT
FOR THE CW-2 WASTEWATER TREATMENT LIME PIT SITE
FORT MONMOUTH, NEW JERSEY**



PREPARED FOR:

**UNITED STATES ARMY FORT MONMOUTH
DIRECTORATE OF PUBLIC WORKS
BUILDING 167
FORT MONMOUTH, NJ 07703**

PREPARED BY:



March 7, 2005

VERSAR PROJECT NO. 4936.116

TABLE OF CONTENTS

EXECUTIVE SUMMARY.....	i
1.0 INTRODUCTION.....	1-1
1.1 Objectives	1-1
1.2 Report Organization.....	1-1
2.0 SITE BACKGROUND AND ENVIRONMENTAL SETTING	2-1
2.1 Site Location and Description.....	2-1
2.2 Site Background.....	2-1
2.3 Current Conditions.....	2-3
2.4 Environmental Setting	2-3
2.4.1 Regional Geology	2-3
2.4.2 Hydrogeology	2-5
2.4.3 Aquifer Classification	2-6
2.4.4 Soils.....	2-6
2.4.5 Topography and Surface Drainage	2-7
3.0 SITE ACTIVITIES.....	3-1
3.1 Groundwater Sampling Activities.....	3-1
3.2 Groundwater Depth Measurements	3-2
4.0 SITE PHYSICAL CHARACTERISTICS.....	4-1
4.1 Lithology.....	4-1
4.2 Groundwater Flow Direction	4-1
5.0 SITE CHEMICAL CHARACTERIZATION.....	5-1
5.1 Groundwater Sample Results.....	5-1
5.1.1 Volatile Organic Compounds	5-1
5.1.2 Semi-Volatile Organic Compounds.....	5-2
5.1.3 Pesticides and PCBs.....	5-2
5.1.4 TAL Metals.....	5-2
5.2 Contaminants of Concern	5-3
5.3 Quality Assurance/Quality Control.....	5-4
6.0 CONCLUSIONS	6-1
7.0 REFERENCES.....	7-1

TABLES

Table 2-1	Well Construction Summary
Table 3-1	Groundwater Sampling Summary
Table 3-2	Groundwater Elevation Summary
Table 4-1	Data for Cross Section A-A'
Table 5-1	Groundwater Sampling Results
Table 5-2	Determination of Contaminants of Concern

FIGURES

Figure 2-1	Site Location Map
Figure 2-2	Site Map
Figure 2-3	Monitoring Well Location Map
Figure 2-4	Geological Map of New Jersey
Figure 2-5	New Jersey Groundwater Classification Class IIIA
Figure 2-6	Geologic Cross Section A-A'
Figure 2-7	Outcrop and Thickness of Composite Confining Unit
Figure 2-8	Soil Map of Monmouth County
Figure 4-1	Cross Section Location Map
Figure 4-2	Geologic Cross Section A-A'
Figure 4-3a	Groundwater Contour Map (Apr-97)
Figure 4-3b	Groundwater Contour Map (Jul-97)
Figure 4-3c	Groundwater Contour Map (Oct-97)
Figure 4-3d	Groundwater Contour Map (Jan-98)
Figure 4-3e	Groundwater Contour Map (Apr-98)
Figure 4-3f	Groundwater Contour Map (Jul-98)
Figure 4-3g	Groundwater Contour Map (Nov-98)
Figure 4-3h	Groundwater Contour Map (Feb-99)
Figure 4-3i	Groundwater Contour Map (May-99)
Figure 4-3j	Groundwater Contour Map (Jun-99)
Figure 4-3k	Groundwater Contour Map (Aug-99)
Figure 4-3l	Groundwater Contour Map (Nov-99)
Figure 4-3m	Groundwater Contour Map (Feb-00)
Figure 4-3n	Groundwater Contour Map (May-00)
Figure 4-3o	Groundwater Contour Map (Aug-00)
Figure 4-3p	Groundwater Contour Map (Oct-00)
Figure 4-3q	Groundwater Contour Map (Oct-12-00)
Figure 4-3r	Groundwater Contour Map (Jan-01)

APPENDICES

Appendix A	Weston 1995-Site Investigation Report
Appendix B	Boring Logs and Monitoring Well Documents
Appendix C	Groundwater Laboratory Data Sheets

EXECUTIVE SUMMARY

VERSAR, Inc. (VERSAR) has been contracted by the United States (U.S.) Army Installation, Fort Monmouth (Fort Monmouth), Directorate of Public Works (DPW), Fort Monmouth, New Jersey to prepare a Remedial Investigation Report (RIR) for the CW-2 Wastewater Treatment Lime Pit (Lime Pit) site based on work located in the Charles Wood Area of Fort Monmouth. This report addresses the remedial investigation activities conducted at this site between April 1997 and January 2001.

The CW-2 Lime Pit site is located southeast of Building 2700 adjacent to an electrical substation. The approximate area of the site is 1,751 square feet (0.04 acres). The CW-2 Lime Pit site was reportedly a lime pit that received liquid wastes from the east and south wings of Building 2700 and then discharged to the sanitary sewer. A dye test study was conducted and presented evidence that the lime pit was also receiving wastes from a toilet from the guard shack and a restroom designated for the handicapped near the east entrance. Currently, no liquid wastes are discharged to the sewer and are managed under the installation hazardous waste program.

The Roy F. Weston, Inc. (Weston) report, *Site Investigation, Fort Monmouth, New Jersey, Main Post and Charles Wood Areas, Site Investigation Report* (December 1995), presents the results of field investigation activities that were conducted at 13 sites at the Main Post Area and eight sites at the Charles Wood Area. The results of the investigation of the CW-2 Lime Pit site are included in the Weston Site Investigation (SI) report. Initial field investigation activities were conducted between November 1994 and March 1995. The field investigation activities included subsurface soil sampling, groundwater monitoring well installation and groundwater sampling.

A total of four monitoring wells comprise the quarterly groundwater monitoring program conducted by the DPW at the CW-2 Lime Pit site. Two monitoring wells (CW2-MW30 and CW2-MW31) were installed on the northwest and southwest sides of the lime pit. Two monitoring wells (CW2-MW32 and CW2-MW33) were installed on the northeast and southeast sides of the lime pit.

The soil samples collected by Weston in December 1994 were analyzed for volatile organic compounds (VOCs), semi-volatile organic compounds (SVOCs), pesticides, polychlorinated biphenyls (PCBs) and Target Analyte List (TAL) metals. According to Weston SI, two VOCs were detected in concentrations below the New Jersey Department of Environmental Protection (NJDEP) soil cleanup criteria. Eight SVOCs were detected below NJDEP soil cleanup criteria. Three pesticides were detected below the NJDEP soil cleanup criteria. One PCB was detected slightly above the NJDEP soil cleanup criteria; however, the PCB compound was not detected in groundwater samples from the corresponding well location.

Groundwater sampling results indicate that tetrachloroethene (PCE) was detected in the groundwater in one of the wells exceeding the NJDEP GWQC. SVOCs pesticides and PCBs were not detected in groundwater samples. Three metals were detected exceeding

the GWQC. Surface water samples were collected in Wampum Brook and Mill Creek for use as background samples. No VOCs were detected in these surface water samples.

Weston concluded that the groundwater sample results for the CW-2 Lime Pit site indicate that PCE was detected in CW2-MW30, slightly exceeding the NJDEP GWQC. One PCB compound was detected slightly above the NJDEP soil cleanup criteria; however, the compound was not detected within the CW-2 Lime Pit site groundwater. The Weston SI report stated that the DPW recommended the implementation of a long-term monitoring program at the CW-2 Lime Pit site. This remedial investigation was undertaken to assess the groundwater quality at the CW-2 Lime Pit site and verify that no contaminants of concern (COCs) exist within the CW-2 Lime Pit site groundwater.

Fort Monmouth DPW conducted Remedial Investigation (RI) activities at the CW-2 Lime Pit site, including a quarterly groundwater sampling program. The purpose of this remedial investigation was to define the areal extent of potential pollutants and evaluate impacts to groundwater in the vicinity of the CW-2 Lime Pit site. RI groundwater activities were conducted from April 1997 and continued through January 2001.

A total of 126 groundwater samples were collected from four groundwater monitoring wells to evaluate potential chemical impacts to groundwater from the CW-2 Lime Pit site. The samples were collected and analyzed for VOCs, SVOCs, pesticides, PCBs and TAL metals. Two additional rounds of sampling were conducted using a low-flow groundwater sampling technique for TAL metals.

Based on the results of the groundwater quality evaluation, no VOCs, SVOCs, pesticides or PCBs were detected above the NJDEP GWQC. There were seven metals detected in groundwater samples at concentrations exceeding the NJDEP GWQC. However, none of these metals are considered to be COCs in site groundwater due to the process of elimination via categorization of background metals, reduction in concentration or non-detection of samples by low-flow sampling, and elimination of isolated and marginal detections. Therefore, no COCs exist within the groundwater and NFA is required concerning the groundwater at the CW-2 Lime Pit site.

1.0 INTRODUCTION

VERSAR has been contracted by the U.S. Army Installation, Fort Monmouth DPW, Fort Monmouth, New Jersey to prepare an RIR for the CW-2 Lime Pit site based on work located in the Charles Wood Area of Fort Monmouth. This report addresses the remedial investigation activities conducted at this site between April 1997 and January 2001.

1.1 Objectives

The objective of RI is to determine aquifer chemical and physical characteristics and to determine whether further remedial investigation or remedial action is required within the CW-2 Lime Pit site groundwater. The remedial investigation was conducted in accordance with New Jersey Administrative Code (NJAC) 7:26E - *Technical Requirements for Site Remediation* (July 1999).

The remedial investigation encompassed the following:

- Characterization of groundwater quality over time through quarterly groundwater sampling events conducted between April 1997 and January 2001.
- Investigation and evaluation of the designated aquifer uses, the associated aquifer classification, and the appropriate groundwater quality criteria for groundwater resources beneath the CW-2 Lime Pit site. The NJDEP Ground Water Quality Standards (GWQS) specify the quality criteria and designated uses for groundwater and also contain technical and general policies to ensure that the designated uses can be adequately protected.
- Comparison of the results of the groundwater quality and monitoring program with the NJDEP Ground Water Quality Criteria (GWQC).
- Formulation of an NFA proposal for consideration by the NJDEP based on the results of field and laboratory investigations and evaluation of the hydrogeologic conditions at the CW-2 Lime Pit site.

1.2 Report Organization

This report is organized to minimize repetition. The findings of the Weston report entitled, *Site Investigation, Fort Monmouth, New Jersey, Main Post and Charles Wood Areas, Site Investigation Reports* (December 1995), were used as the basis for this remedial investigation program. **Section 2.0** provides background information and a general description of the CW-2 Lime Pit site located in the Charles Wood Area of Fort Monmouth, of which a large portion was provided by Weston (1995). **Section 3.0** describes and summarizes the RI field activities conducted at the CW-2 Lime Pit site, including the groundwater sampling. **Section 4.0** presents the physical characterization of the CW-2 Lime Pit site including the lithology and groundwater conditions. Chemical

characterization of the CW-2 Lime Pit site is presented in **Section 5.0**, which includes groundwater sampling results and the determination of COCs. Conclusions and a recommendation for NFA for groundwater at the CW-2 Lime Pit site are included in **Section 6.0**. References used to prepare this RIR are listed in **Section 7.0**.

2.0 SITE BACKGROUND AND ENVIRONMENTAL SETTING

The following sections describe the site background and environmental setting of the area surrounding Fort Monmouth and the CW-2 Lime Pit site. Included is a description of the site location, background, current conditions and environmental setting.

2.1 Site Location and Description

Fort Monmouth is located in the central-eastern portion of New Jersey in Monmouth County, approximately 45 miles south of New York City and 70 miles northeast of Philadelphia (**Figure 2-1**). In addition to the Main Post, the installation includes two subposts, the Charles Wood Area and the Evans Area. The Main Post encompasses approximately 630 acres and is generally bounded by State Highway 35, Parkers Creek, Lafetra Creek, the New Jersey Transit Railroad and a residential area to the south. The post was established in 1918 during World War I (WWI) as an Army Signal Corps training center. The Main Post currently provides administrative, training and housing support functions, as well as providing many of the community facilities for Fort Monmouth. The Charles Wood Area is located one mile west of the Main Post and is comprised of approximately 511 acres. The Charles Wood Area is used primarily for research and development, testing and personnel housing units. The primary mission of Fort Monmouth is to provide command, administrative, and logistical support for Headquarters, U.S. Army Communications and Electronics Command (CECOM). CECOM is a major subordinate command of the U.S. Army Materiel Command (AMC) and is the host tenant at Fort Monmouth.

The CW-2 Lime Pit site is located southeast of Building 2700 (not shown on maps) adjacent to an electrical substation (**Figure 2-2**). The approximate area of the site is 1,751 square feet (0.04 acres). The CW-2 Lime Pit site was reportedly a lime pit that received liquid wastes from the east and south wings of Building 2700 and then discharged to the sanitary sewer. A dye test study was conducted and presented evidence that the lime pit was also receiving wastes from a toilet from the guard shack and a restroom designated for the handicapped near the east entrance. The plumbing has since been re-routed to connect directly to the sewer. Currently, no liquid wastes are discharged to the sewer and are managed under the installation hazardous waste program.

2.2 Site Background

The U.S. Army Corps of Engineers (USACE), Baltimore District, initially contracted Weston to perform a field investigation at Fort Monmouth, New Jersey. This investigation was conducted at two separate areas of Fort Monmouth, the Main Post and the Charles Wood areas. Suspected hazardous waste sites were initially identified at Fort Monmouth in a report prepared by the U.S. Army Toxic and Hazardous Materials Agency (USATHAMA, 1980). The USATHAMA report identified 37 sites with known or suspected waste materials on the Main Post and the two subposts (Charles Wood and Evans Area). A background investigation was conducted by Weston of the 37

sites and eight additional sites that were identified by Fort Monmouth and the NJDEP. Weston's findings were described in a report titled, *Investigation of Suspected Hazardous Waste Sites at Fort Monmouth, New Jersey* (1993). In this background report, additional investigations (including sampling and other field work) were recommended at 22 of the sites on the Main Post and Charles Wood areas, including the CW-2 Lime Pit site. NJDEP approved the recommendations on April 20, 1995. Additional investigations were also recommended at the Evans Area, and such investigations are being completed under the Base Realignment and Closure (BRAC) program.

The Weston report, *Site Investigation, Fort Monmouth, New Jersey, Main Post and Charles Wood Areas, Site Investigation Report* (December 1995), presents the results of field investigation activities that were conducted at 13 sites at the Main Post Area and eight sites at the Charles Wood Area. The results of the investigation of the CW-2 Lime Pit site are included in the Weston SI report. Initial field investigation activities were conducted between November 1994 and March 1995. The field investigation activities included subsurface soil sampling, groundwater monitoring well installation and groundwater sampling. The Weston SI report was used as the basis for the supplemental remedial investigations of the CW-2 Lime Pit site described in the following sections of this report.

A total of four monitoring wells (CW2-MW30, CW2-MW31, CW2-MW32 and CW2-MW33) comprise the quarterly groundwater monitoring program conducted by the DPW at the CW-2 Lime Pit site. Two monitoring wells (CW2-MW30 and CW2-MW31) were installed on the northwest and southwest sides of the lime pit. Two monitoring wells (CW2-MW32 and CW2-MW33) were installed on the northeast and southeast sides of the lime pit. The four monitoring wells were installed by J.C. Anderson in December 1994. The wells were constructed with 4-inch diameter 10 Slot PVC ranging to depths of 15-16 feet below ground surface (bgs). The monitoring well construction details are presented in **Table 2-1**. Well boring logs and monitoring well records are provided in **Appendix B**. The locations of the four monitoring wells at the CW-2 Lime Pit site are shown in **Figure 2-3**.

The soil samples collected by Weston in December 1994 were analyzed for VOCs, SVOCs, pesticides, PCBs and TAL metals. According to Weston SI, two VOCs were detected in concentrations below the NJDEP soil cleanup criteria. Eight SVOCs were detected below NJDEP soil cleanup criteria. Three pesticides were detected below the NJDEP soil cleanup criteria. One PCB in SB-30 was detected slightly above the NJDEP soil cleanup criteria; however, the PCB compound was not detected in groundwater samples from the corresponding well location CW2-MW30. PCBs were not detected in SB-31, SB-32 and SB-33.

Groundwater sampling results indicate that PCE was detected in the groundwater in one of the wells (CW2-MW32) exceeding the NJDEP GWQC. SVOCs pesticides and PCBs were not detected in groundwater samples. Three metals were detected exceeding the GWQC. Surface water samples were collected in Wampum Brook and Mill Creek for use as background samples. No VOCs were detected in these surface water samples.

Weston concluded that the groundwater sample results for the CW-2 Lime Pit site indicate that PCE was detected in CW2-MW30, slightly exceeding the NJDEP GWQC. One PCB compound was detected slightly above the NJDEP soil cleanup criteria; however, the compound was not detected within the CW-2 Lime Pit site groundwater. The Weston SI report stated that the DPW recommended the implementation of a long-term monitoring program at the CW-2 Lime Pit site. This remedial investigation was undertaken to assess the groundwater quality at the CW-2 Lime Pit site and verify that no COCs exist within the CW-2 Lime Pit site groundwater.

2.3 Current Conditions

VERSAR conducted a site walk on June 20, 2001 to assess current conditions at the CW-2 Lime Pit site. The site consisted of an electrical substation positioned southeast of Building 2700 within the parking lot area. Site photographs are not available due to the proximity of the Site to Building 2700.

2.4 Environmental Setting

The following is a description of the geological/hydrogeological setting of the area surrounding the CW-2 Lime Pit site. Included is a description of the regional geology and hydrogeology of the area surrounding Fort Monmouth, as well as descriptions of the local geology and hydrogeology of the Charles Wood Area.

2.4.1 Regional Geology

Monmouth County lies within the New Jersey Section of the Atlantic Coastal Plain physiographic province. The CW-2 Lime Pit site is located in what may be referred to as the Outer Coastal Plain subprovince, or the Outer Lowlands. The geologic map of New Jersey is provided as **Figure 2-4**.

In general, New Jersey Coastal Plain formations consist of a seaward-dipping wedge of unconsolidated deposits of clay, silt, sand and gravel. These formations typically strike northeast-southwest with a dip ranging from 10 to 60 feet per mile and were deposited on Precambrian and lower Paleozoic rocks (Zapeczka, 1989). These sediments, predominantly derived from deltaic, shallow marine and continental shelf environments, date from Cretaceous through the Quaternary Periods. The mineralogy ranges from quartz to glauconite.

The formations record several major transgressive/regressive cycles and contain units, which are generally thicker to the southeast and reflect a deeper water environment. More than 20 regional geologic units are present within the sediments of the Coastal Plain. Regressive, upward coarsening deposits are usually aquifers (e.g., Englishtown and Kirkwood Formations and the Cohansey Sand), while the transgressive deposits act as confining units (e.g., the Merchantville, Marshalltown and Navesink Formations). The individual thickness for these units varies greatly (e.g., from several feet to several hundred feet). The Coastal Plain deposits thicken to the southeast from the Fall Line

(e.g., a boundary zone between older, resistant rocks and younger, softer plain sediments) to greater than 6,500 feet in Cape May County (Brown and Zapecza, 1990).

Based on the regional geologic map (Jablonski, 1968), the Cretaceous age Red Bank and Tinton Sands outcrop at the Main Post area. The Red Bank Sand conformably overlies the Navesink Formation and dips to the southeast at 35 feet per mile. The upper member (Shrewsbury) of the Red Bank Sand is a yellowish-gray to reddish brown clayey, medium-to-coarse-grained sand that contains abundant rock fragments, minor mica and glauconite (Jablonski). The lower member (Sandy Hook) is a dark gray to black, medium-to-fine grained sand with abundant clay, mica and glauconite.

The Tinton Sand conformably overlies the Red Bank Sand and ranges from a clayey medium to very coarse-grained feldspathic-quartz and glauconite-sand to a glauconitic-coarse sand. The color varies from dark yellowish orange or light brown to moderate brown and from light olive to grayish olive. Glauconite may constitute 60 to 80 percent of the sand fraction in the upper part of the unit. The upper part of the Tinton is often highly oxidized and iron oxide encrusted (Minard, 1969). Groundwater occurs beneath the site at a depth of approximately 2 to 12 feet bgs.

The Kirkwood Formation (part of the Kirkwood-Cohansey system) crops out southeast of the Main Post and dips to the southeast at a slope of 20 feet per mile (Jablonski, 1968). The Kirkwood Formation consists of alternating layers of sand and clay. The upper unit is a light gray to yellowish-brown, fine-grained quartz sand with quartz nodules and small pebbles. The lower unit is brown silt in Monmouth County (Jablonski, 1968).

As presented in the *Site Investigation Report - Main Post and Charles Wood Areas, Fort Monmouth, New Jersey*, prepared by Weston (1995), several natural and anthropogenic factors contribute to the wide range in concentrations of metals in soils, which further impact the concentration of metals in groundwater. Soils derived from the glauconitic sands contain abundant aluminum, calcium, potassium, iron, magnesium and manganese (among others), which are likely to be present at elevated concentrations in the groundwater, particularly when sediments are entrained in the collected groundwater samples.

As presented in the Weston SI, the boring logs from monitoring well installations at the CW-2 Lime Pit site indicate that the lithology consists of asphalt (0.5 feet) underlain by alternating layers of reworked sand, silt and broken concrete gravel pieces with interbedded plant-root fragments. Borehole logs also represent a lithology consisting of light brown coarse to fine sand with silt and greenish-gray clay at this site. Groundwater saturation was observed at approximately 1-8 feet bgs at each well location during drilling activities at the CW-2 Lime Pit site. Water level elevation data collected during the Weston SI indicate that the local groundwater flow is towards the southeast toward the tributary of Wampum Brook.

2.4.2 Hydrogeology

Fort Monmouth lies in the Atlantic and Eastern Gulf Coastal Plain groundwater region (Meisler et al., 1988). This groundwater region is underlain by undeformed, unconsolidated to semi-consolidated sedimentary deposits. The chemistry of the water near the surface is variable with low dissolved solids and high iron concentrations. The water chemistry in areas underlain by glauconitic sediments (such as Red Bank, Tinton and Hornerstown Sands) is dominated by calcium, magnesium, manganese, aluminum and iron. The sediments in the area of Fort Monmouth were deposited in fluvial-deltaic to near shore environments.

The water table aquifer in the Main Post Area is identified as part of the “Navesink-Hornerstown Confining Units,” or minor aquifers. The minor aquifers include the Navesink formation, Red Bank Sand, Tinton Sand, Hornerstown Sand, Vincentown Formation, Manasquan Formation, Shark River Formation, Piney Point Formation and the basal clay of the Kirkwood Formation. These geologic formations comprise a “Composite Confining Bed” for the Wenonah Mount Laurel Aquifer (Zapeczka, 1984).

Wells installed in the Red Bank and Tinton Sands produce 2 to 25 gallons per minute (gpm) (Jablonski, 1968). Groundwater is typically encountered at the Main Post and in the surrounding areas at shallow depths below ground surface (2 to 9 feet bgs). Water in the surficial aquifer generally flows east toward the Atlantic Ocean.

Based on a review of the NJDEP GWQS (NJAC 7:9-6), January 7, 1993, Versar has determined that the site is underlain by a Class III-A aquifer. A formal presentation of this finding was made to the NJDEP on April 17, 2001. The primary designated use for Class III-A groundwater is the release or transmittal of groundwater to adjacent classification areas and surface water, as relevant. Secondary designated uses in Class III-A include any reasonable use. Further discussion of the Class III-A aquifer classification is presented in **Section 2.4.3**.

Shallow groundwater may be locally influenced within the Main Post Area by the following factors:

- Tidal influence (based on proximity to the Atlantic Ocean, rivers, and tributaries)
- Topography
- Nature of the fill material within the Main Post Area
- Presence of clay and silt lenses in the natural overburden deposits
- Local groundwater recharge areas (e.g., streams, lakes)
- Roadways, utility conduits and stormwater culverts

Due to the fluvial nature of the overburden deposits (e.g., sand and clay lenses), shallow groundwater flow direction is best determined on a case-by-case basis. The groundwater flow in the vicinity of the CW-2 Lime Pit site is towards the southeast.

2.4.3 Aquifer Classification

On review of the NJDEP Groundwater Quality Standards (N.J.A.C. 7:9-6), January 7, 1993, the CW-2 Lime Pit site is found to be underlain by a Class III-A aquifer (**Figure 2-5**). The primary designated use for Class III-A ground water is the release or transmittal of groundwater to adjacent classification areas and surface water, as relevant. Secondary designated uses in Class III-A include any reasonable uses. For an area to be classified as a Class III-A aquifer, the ground water must meet the following characteristics:

- Class III-A ground water includes portions of the saturated zones (that meet the criteria below) of the Woodbury Formation, Merchantville Formation, Marshalltown Formation, Navesink Formation, Hornerstown Formation, aquitard formations of the Potomac-Raritan-Magothy aquifer system and the Kirkwood aquifer system, portions of the glacial moraine and glacial lake deposits, and other geologic units having the characteristics of an aquitard. Class III-A areas have the following characteristics (N.J.A.C. 7:9-6.5):
 - The average thickness of a Class III-A area must be at least 50 feet.
 - Typical hydraulic conductivity of a Class II-A aquifer is approximately 0.1 feet per day or less.
 - The aerial extent defined as Class III-A must be at least 100 acres.

The shallow aquifer at Fort Monmouth meets each of the four criteria listed above. These criteria are discussed below

- As presented in **Figure 2-6**, Fort Monmouth is located within the outcrop area of the “Navesink-Hornerstown Confining Unit.” The Navesink and Hornerstown Formations are part of the Composite Confining Unit (Martin, 1998), which also includes the Red Bank Sand, Tinton Sand, Vincentown Formation, Manasquan Formation, Shark River Formation, Piney Point Formation, and the basal clay of the Kirkwood Formation (see **Section 2.4.2**).
 - **Figure 2-7** also illustrates the thickness of the Hornerstown-Navesink Confining Unit, which in the vicinity of Fort Monmouth, is approximately 125 feet.
- Published hydraulic conductivities (Martin, 1998) for the Navesink-Hornerstown Confining Unit, yielding a geometric mean of 0.12 feet per day.
- The area of Fort Monmouth is greater than 100 acres.

Due to the fluvial nature of the overburden deposits (e.g., sand and clay lenses), shallow groundwater flow direction is best determined on a case-by-case basis. The groundwater flow in the vicinity of the CW-2 Lime Pit site is assumed to be to the southeast towards a Tributary of Wampum Brook.

2.4.4 Soils

According to the U.S. Department of Agriculture (USDA), Soil Conservation Service, Monmouth County Soil Survey, the majority of the Main Post and Charles Wood areas

are covered by urban land (**Figure 2-8**). The soil survey describes urban land as areas where concrete, asphalt, buildings, shopping centers, airports or other impervious surfaces cover 80 percent or more of the surface. In addition, the survey indicated that the natural subsurface soils have largely been replaced with artificial or foreign fill materials (developed land with disturbed soils). The following soil series and classification units are mapped in the Main Post and Charles Wood areas:

- DoB Downer sandy loam (with 2 to 5 percent slopes);
- FrB Freehold sandy loam (with 2 to 5 percent slopes);
- FUB Freehold sandy loam/urban land complex (with 0 to 10 percent slopes);
- HnA Holmdel sandy loam (with 0 to 2 percent slopes);
- HV Humaquepts, frequently flooded;
- KvA Kresson loam (with 0 to 5 percent slopes);
- PT Pits, Sand and Gravel;
- UA Udorthents, smoothed; and
- UD Udorthents – urban land complex (with 0 to 3 percent slopes).

The Downer series soils are well-drained soils that are found on uplands and terraces. The soils are formed in acid, silty coastal plain sediments. The Freehold soils are also well drained and are formed in acid, loamy, coastal plain sediments that, by volume, are 1 to 10 percent glauconite and are found on uplands. The Humaquepts soils are somewhat poorly- to very poorly- drained soils that are formed in stratified, sandy, or loamy sediments of fluvial origins. The Humaquepts soils are located on the floodplain and are subject to flooding several times each year. The Kresson loam is a nearly level to gently sloping soil and is somewhat poorly drained. The soil is found on low divides and in depressions. The Udorthents soils have been altered by excavation or filling activities. In filled areas, these soils consist of loamy material that is more than 20 inches thick. The filled areas include floodplain, tidal marshes and areas with moderately, well drained to very poorly drained soils. Some Udorthent soils contain concrete, asphalt, metal and glass. The soils in the vicinity of the CW-2 Lime Pit site are classified as HnA - Holmdel sandy loam (with 0 to 2 percent slopes).

2.4.5 Topography and Surface Drainage

Over the last 80 years, the natural topography of Fort Monmouth has been altered by excavation and filling activities conducted by the military. The CW-2 Lime Pit site is located on the floodplain of Wampum Brook. The USGS topographic map (**Figure 2-1**) shows that the land surface of the site is relatively flat at an elevation of approximately 60 feet above mean sea level (amsl).

Surface water bodies in the vicinity of the Charles Wood Area include two unnamed tributaries of Wampum Brook. Wampum Brook is joined by several unnamed tributaries east of the Charles Wood Area, prior to becoming Wampum Lake. Wampum Lake discharges into Mill Creek, which flows toward the Main Post Area.

The U.S. Fish and Wildlife Service (FWS) National Wetland Inventory Long Branch quadrangle maps indicate the presence of several wetlands at the Main Post and Charles Wood areas. However, in the vicinity of the CW-2 Lime Pit site, the golf course lake is classified as palustrine open water/unknown bottom, and several areas along the unnamed tributaries of Wampum Brook are classified as palustrine forested wetland, broad-leaved deciduous.

3.0 SITE ACTIVITIES

Fort Monmouth DPW conducted RI activities at the CW-2 Lime Pit site, including a quarterly groundwater sampling program. The purpose of this remedial investigation was to define the areal extent of potential pollutants and evaluate impacts to groundwater in the vicinity of the CW-2 Lime Pit site. RI groundwater activities were conducted from April 1997 and continued through January 2001. These activities were managed by the Fort Monmouth DPW and performed by TECOM-Vinnell Services (TVS) and reported by VERSAR. The details of remedial investigation activities that occurred at the CW-2 Lime Pit site are described in the following sections.

3.1 Groundwater Sampling Activities

As a part of the remedial investigation, a quarterly groundwater sampling program was conducted by the DPW from April 1997 through January 2001 at the CW-2 Lime Pit site. Sampling activities were performed in accordance with the *Fort Monmouth Standard Sampling Operating Procedure* (1997).

Groundwater samples were collected during 16 rounds of quarterly sampling events and were analyzed for VOCs, SVOCs, pesticides, PCBs and TAL metals. Two additional low-flow sampling rounds were analyzed for TAL metals which are addressed below. A total of 126 groundwater samples were collected as a part of the groundwater sampling program, including 18 duplicate samples, 18 field blanks and 18 trip blanks for quality assurance/quality control (QA/QC), were collected from a total of four 4-inch diameter monitoring wells (CW2-MW30, CW2-MW31, CW2-MW32 and CW2-MW33).

Copies of the chain-of-custody for the laboratory analyses can be found in **Appendix C**. A summary of the groundwater sampling activities, including rounds, well IDs, sample IDs, sample locations, collection/analysis date, analytical parameters and analysis method, is provided in **Table 3-1**. The results of these analyses are discussed in **Section 5.1**.

As presented in the Weston SI Report, several natural and anthropogenic factors contribute to the wide range in concentrations of metals in soils, which further impact the concentration of metals in groundwater. Soils derived from the glauconitic sands contain abundant aluminum, calcium, potassium, iron, magnesium and manganese (among others), which are likely to be present at elevated concentrations in the groundwater, particularly when sediments are entrained in the collected groundwater samples. A low-flow sampling methodology was proposed for use by the DPW and accepted by the NJDEP to assess the impact of entrained sediments on the dissolved phase metals concentrations at the CW-2 Lime Pit site. Using a low-flow sampling methodology to reduce the presence of entrained sediment has generally yielded substantial reductions in the dissolved phase concentrations of metals, such as arsenic, antimony, beryllium, cadmium, chromium, cobalt, lead, mercury, selenium, silver, thallium and vanadium at Fort Monmouth sites. Significant decreases in the concentrations of metals characteristic of glauconitic sand also were observed. These included aluminum, barium, calcium, copper, iron, magnesium, manganese, nickel, potassium, sodium and zinc.

In consideration of the potential benefits of the low-flow sampling procedure, two additional rounds of low-flow sampling (Low-flow #1 and Low-flow #2) were conducted on August 23, 2000, August 24, 2000 and October 3, 2000 using a low-flow groundwater sampling technique. A total of 14 samples out of the total 126 groundwater samples were collected and analyzed only for TAL metals, to determine whether elevated metal concentrations observed in the groundwater samples are due to sediments rather than groundwater. The samples were analyzed by the Fort Monmouth Environmental Testing Laboratory (FMETL) for TAL metals utilizing United States Environmental Protection Agency (USEPA) Methods 3120B and 3112B. The results of these analyses are discussed in **Section 5.0**.

Sampling equipment was thoroughly decontaminated before and after each use, in accordance with the *Fort Monmouth Standard Operating Procedures* (1997). The sample containers were labeled, sealed, packed in ice and transported to the FMETL under proper chain-of-custody procedures.

3.2 Groundwater Depth Measurements

During each of the groundwater monitoring rounds, measurements of the depth-to-water in each of the monitoring wells were recorded with an accuracy of 0.01 feet. These depth-to-water measurements, recorded from April 1997 through January 2001, are presented in **Table 3-2**. The groundwater elevation at each well was calculated by subtracting the measured depth to groundwater from the elevation of the top of the well casing with the depth to water at the well. The groundwater elevations are discussed in **Section 4.2**.

4.0 SITE PHYSICAL CHARACTERISTICS

The following sections represent the findings of the site geologic and hydrogeologic characterization program for the CW-2 Lime Pit site. These sections include a detailed discussion of the physical properties of the unconsolidated soil, bedrock and groundwater underlying the study area. Groundwater elevation and water quality data collected by the DPW from April 1997 to January 2001 are presented in this section.

4.1 Lithology

The lithology encountered at the CW-2 Lime Pit site consists primarily of fill material, fine sand, silt and clay. A geologic cross section (A-A') was prepared for the CW-2 Lime Pit site. The cross section location map is included as **Figure 4-1**. The data used to create the cross section is presented in **Table 4-1**.

The cross-section A-A' is presented in **Figure 4-2**. Cross section A-A' depicts the profiles for monitoring wells CW2-MW30, CW2-MW31, CW2-MW32 and CW2-MW33. CW2-MW30, CW2-MW31, CW2-MW32 and CW2-MW33 encountered fill consisting of lumber and concrete fragments interbedded with coarse to fine sand and silt with greenish-gray clay. Groundwater was encountered at depths ranging from 1-8 feet bgs.

As stated in **Section 2.4.2**, the wide range of concentrations of metals in soils further impact the concentration of metals in groundwater. Soils derived from glauconitic sands contain abundant aluminum, calcium, potassium, iron, magnesium and manganese (among others), which are likely to be present at elevated concentrations in the groundwater, particularly when sediments are entrant during the collection of groundwater samples.

4.2 Groundwater Flow Direction

Groundwater contour maps (**Figure 4-3a** through **Figure 4-3q**) were generated based on groundwater depth measurements from the monitoring wells collected from April 1997 through January 2001. The groundwater underlying the site appears to be flowing consistently towards the southeast and east towards a tributary of Wampum Brook. However, slight changes in groundwater depth measurements from July 1997 indicate a groundwater flow reversal towards the north and northwest; this may have been caused by the presence of an extremely small site gradient and is likely to be anomalous.

5.0 SITE CHEMICAL CHARACTERIZATION

This section includes a discussion of the chemical analytical characterization of the site based on the various samples collected and analyzed from the site, including 16 rounds of groundwater monitoring well samples and two rounds of low flow groundwater sampling samples. The DPW personnel were responsible for the collection of samples during this site investigation. Sample analyses were performed by the FMETL, a New Jersey certified laboratory (Certification No. 13461).

5.1 Groundwater Sample Results

A total of 126 groundwater samples were collected from four groundwater monitoring wells to evaluate potential chemical impacts to groundwater from the CW-2 Lime Pit site. The laboratory analytical results are summarized in **Table 5-1**. This section presents the results of laboratory analyses performed for the 16 rounds of groundwater sampling that were collected from April 1997 through January 2001 from the four monitoring wells at the CW-2 Lime Pit site. The four monitoring wells CW2-MW30, CW2-MW31, CW2-MW32 and CW2-MW33 were installed in December 1994. The samples were collected and analyzed for VOCs, SVOCs, pesticides, PCBs and TAL metals. Two additional rounds of sampling were conducted on August 23, August 24 (Low Flow #1) and October 3, 2000 (Low Flow #2) using a low-flow groundwater sampling technique for TAL metals. As stated above, a low-flow sampling methodology was proposed for use by the DPW and accepted by the NJDEP to assess the impact of suspended sediments on the dissolved phase metals concentrations at the site.

As discussed in **Section 2.4.3**, Fort Monmouth is underlain by a Class III-A aquifer. The groundwater quality criteria for Class III-A is considered to be the criteria for the most stringent classification for vertically or horizontally adjacent ground waters that are not Class III-A (N.J.A.C. 7:9-6.7e). The NJDEP criteria used for comparison of groundwater analytical results were the higher of the Practical Quantitation Limits (PQLs) and the NJDEP GWQC for Class II-A aquifers (N.J.A.C. 7:9-6, Table 1). Analytes detected in groundwater samples at concentrations above the NJDEP criteria are bold and highlighted in **Table 5-1**. The laboratory data sheets are provided in **Appendix C**.

Two VOCs were detected in groundwater above below the NJDEP criteria. Four SVOCs were detected in groundwater samples below the NJDEP criteria. There were no pesticides or PCBs detected during the groundwater sampling events at any of the four groundwater monitoring wells. A total of 22 TAL metals were detected in groundwater samples during the reporting period. Seven TAL metals were detected at concentration exceeding their respective NJDEP criteria, while the remaining fifteen metals were detected at concentrations below their respective NJDEP criteria.

5.1.1 Volatile Organic Compounds

No VOCs were detected above their respective GWQC at the site.

5.1.2 Semi-Volatile Organic Compounds

No SVOCs were detected above their respective GWQC at the site.

5.1.3 Pesticides and PCBs

No pesticides or PCBs were detected at the site.

5.1.4 TAL Metals

During 16 groundwater sampling rounds and two low-flow sampling rounds, a total of seven TAL metals were detected above their respective NJDEP criteria in at least one sample at the CW-2 Lime Pit site.

Aluminum was detected at concentrations exceeding the GWQC of 200 ug/L during nine separate rounds of sampling collected at four separate monitoring well locations. Concentrations ranged from 204 ug/L in CW2-MW30 (sampling round #4) to 623 ug/L in CW2-MW33 (Low-flow #1).

Arsenic was detected at concentrations exceeding the GWQC of 8.0 ug/L during three separate rounds of sampling collected at two separate monitoring well locations. Concentrations ranged from 8.3 ug/L in CW2-MW30 (sampling round #8) to 11.5 ug/L in CW2-MW30 (sampling round #7).

Iron was detected at concentrations exceeding the GWQC of 300 ug/L during 18 separate rounds of sampling collected at four separate monitoring well locations. Concentrations ranged from 834 ug/L in CW2-MW30 (Low-flow #2) to 115,100 ug/L in CW2-MW31 (sampling round #5).

Lead was detected at concentrations exceeding the GWQC of 10 ug/L during five separate rounds of sampling collected at three separate monitoring well locations. Concentrations ranged from 21.8 ug/L in CW2-MW30 (sampling round #14) to 46.6 ug/L in CW2-MW30 (sampling round #13).

Manganese was detected at concentrations exceeding the GWQC of 50 ug/L during 18 separate rounds of sampling collected at four separate monitoring well locations. Concentrations ranged from 53.9 ug/L in CW2-MW32 (sampling round #12) to 519 ug/L in CW2-MW33 (sampling round #2).

Mercury was detected at concentrations exceeding the GWQC of 2.0 ug/L during one separate round of sampling collected at one separate monitoring well location (CW2-MW30) at a concentration of 2.3 ug/L (sampling round #7).

Sodium was detected at concentrations exceeding the GWQC of 50,000 ug/L during one separate round of sampling collected at one separate monitoring well location (CW2-MW33) at a concentration of 84,100 ug/L (Low-flow #1).

5.2 Contaminants of Concern

There were no VOCs, SVOCs, pesticides or PCBs detected in the groundwater at concentrations exceeding the NJDEP criteria. There were seven metals that were detected at concentrations exceeding the NJDEP criteria including (aluminum, arsenic, iron, lead, manganese, mercury and sodium). A discussion of these exceedences and whether they will be presented as COCs is discussed below. **Table 5-2** summarizes the process used to determine COCs and is discussed below.

As presented in the Weston SI Report (1995), several natural and man-made factors contribute to the wide range in concentrations of metals in soils, which further impact the concentration of metals in groundwater. Soils derived from the glauconitic sands contain abundant aluminum, calcium, potassium, iron, magnesium and manganese (among others), which are likely to be present at elevated concentrations in the groundwater, particularly when sediments are entrained in the collected groundwater samples. A low flow sampling methodology was proposed for use by the DPW and accepted by the NJDEP to assess the impact of suspended sediments on the dissolved phase metals concentrations at the site. Using a low flow sampling methodology to reduce the presence of suspended sediment yielded substantial reductions in the dissolved phase concentrations of metals, particularly for the constituents regarded as “non-native” (e.g., arsenic, antimony, beryllium, cadmium, chromium, cobalt, lead, mercury, selenium, silver, thallium and vanadium). Significant decreases in the concentrations of naturally occurring metals also were observed, including aluminum, barium, calcium, copper, iron, magnesium, manganese, nickel, potassium, sodium and zinc. However, the native metal constituents (e.g., those indigenous to the soil types present at Fort Monmouth) were consistently present in the groundwater, even when the low-flow sampling methodology was employed.

The seven metals detected in site groundwater at concentrations exceeding the NJDEP GWQC (aluminum, arsenic, iron, lead, manganese, mercury and sodium) are distinguished into background metals and non-native metals. The indigenous metals are compared to the Fort Monmouth Summary of site-specific Maximum Background Concentrations (MBC), identified in the Weston SI, which are presented in **Table 5-2**. The non-native metals are discussed in relation to the NJDEP GWQC only.

Of the seven metals detected that exceeded the NJDEP GWQC, four metals (aluminum, iron, manganese and sodium) are common background constituents in Monmouth County and the Main Post and Charles Wood Area soils. The water chemistry in areas underlain by glauconitic sediments (such as Red Bank, Tinton and Hornerstown Sands) is dominated by calcium, magnesium, manganese, aluminum and iron. Elevated concentrations of these metals are routinely observed in groundwater samples collected at Fort Monmouth. The groundwater analytical results for (aluminum, iron, manganese and sodium) were compared with the low flow sampling results to their respective MBCs. These four background metals are not considered to be COCs in site groundwater.

There were three non-native metals that exceeded the NJDEP GWQC (arsenic, lead and mercury). The groundwater analytical results were compared with the low-flow sampling

results to the NJDEP GWQC. The two separate rounds of low-flow sampling August 23-24, 2000 and October 3, 2000 were performed during the quarterly groundwater sampling program, using the low-flow groundwater sampling technique as discussed in **Section 3.2.1**. This technique was used to determine if the detected metal concentrations observed in the groundwater samples are a function of contaminated sediments suspended in the groundwater during the course of well purging and sampling activities, or an accurate representation of aquifer/groundwater conditions. This low-flow sampling approach resulted in reduced concentrations or non-detections of the three uncharacteristic metals (arsenic, lead and mercury), during the two rounds of low-flow groundwater sampling conducted at the site. Therefore, the three non-native metals that exceeded the NJDEP GWQC are not considered to be COCs in CW-2 Lime Pit site groundwater.

5.3 Quality Assurance/Quality Control

To verify the reliability of the analytical results, VERSAR reviewed the holding times for each sample and the results of the analysis of 18 method blanks for VOCs, 17 method blanks for SVOCs, 16 method blanks for pesticides and PCBs, 17 method blanks for TAL metals, 16 trip blanks, 18 field blanks and 18 field duplicate samples. Samples were analyzed by the FMETL within the prescribed holding time requirements for each analytical method.

Method Blanks

Laboratory method blanks accompanied each batch of samples for the CW-2 Lime Pit site. These method blanks consist of laboratory grade water that is processed identically to the samples and analyzed with the sample batch. A total of 18 method blanks for VOCs, 17 method blanks for SVOCs, 16 method blanks for pesticides and PCBs and 17 method blanks for TAL metals were analyzed with the CW-2 Lime Pit site samples.

Four SVOCs were detected in at least one method blank sample. These SVOCs were benzyl alcohol, bis(2-ethylhexyl)phthalate, diethylphthalate and di-n-butylphthalate. None of these SVOCs were detected at a concentration exceeding their respective NJDEP criteria. Their presence in only a few samples is not indicative of a widespread laboratory contamination problem.

Several metals were detected in at least one method blank sample, including aluminum, antimony, barium, beryllium, cadmium, calcium, chromium, cobalt, copper, iron, lead, magnesium, manganese, nickel, potassium, sodium, vanadium, and zinc. All of the metals were detected in only a few samples at very low concentrations. Their presence in only a few samples is not indicative of a widespread laboratory contamination problem.

Trip Blanks

Sixteen trip blanks were included as part of the CW-2 Lime Pit site sampling program to document that volatile organics were not introduced into the samples during the handling process. The trip blanks were prepared by the FMETL and consisted of sample bottles filled with laboratory deionized water. The trip blanks remained with the sample bottles in coolers and were returned to the laboratory for analysis with the groundwater samples.

Three VOCs were detected in at least one trip blank. Acetone was detected in one trip blank at a concentration below its NJDEP criteria. Chloroform was detected in three of the 16 trip blanks, with no detections exceeding the NJDEP criteria. Methylene chloride was detected in two of the trip blanks, and one of the two detected concentrations exceeded its NJDEP criteria. However, methylene chloride is a common laboratory contaminant. The detections of chloroform and acetone indicate that the sample handling procedures, including the sample glassware, may have introduced contamination into the sampling and analysis process.

Field Blanks

One field blank sample was obtained during the sampling activities each day to document the equipment decontamination procedures. A total of 18 field samples (e.g., field blanks) were collected during the CW-2 Lime Pit site sampling events. The field blanks were collected by rinsing deionized water, supplied by the laboratory, over the sampling equipment used for daily activities. The water was collected in clean laboratory-supplied sample jars and submitted for analysis along with the CW-2 Lime Pit site groundwater samples.

The results of the field blank analyses showed that three VOCs were detected in at least one field blank. Chloroform was detected in three of the 18 field blanks, all at concentrations below the NJDEP criteria. Methylene chloride was detected in two field blanks, both at concentrations below its NJDEP criteria. Acetone was detected in one field blank at a concentration below its NJDEP criteria. As noted for the trip blanks, methylene chloride is a common laboratory contaminant, and the detections of chloroform and acetone indicate that the sample handling procedures, including the sample glassware, may have introduced contamination into the sampling and analysis process. In addition, the same VOCs found in the field blanks were also found in the trip blanks, suggesting that the sampling and decontamination procedures did not introduce additional contamination.

Three SVOCs, bis(2-ethylhexyl) phthalate, diethylphthalate and di-n-butylphthalate, were each detected in at least one of the field blank samples. All three analytes were detected at low concentrations that are below their respective NJDEP criteria. In addition, each of these compounds were also identified in the method blanks; therefore, their presence in the field blank samples does not suggest that the sampling and decontamination procedures introduced additional contamination.

As noted for the method blanks, several metals were detected in at least one field blank sample, including aluminum, barium, cadmium, calcium, chromium, cobalt, copper, iron, lead, magnesium, manganese, mercury, nickel, potassium, selenium, silver, sodium, thallium and zinc. All of the metals were detected in only a few samples at very low concentrations. Because these metals were also detected in the method blank samples, the sampling and decontamination procedures do not appear to have been the source of sample contamination. However, any subsequent evaluation of the metals analytical

results must account for the possibility of laboratory contamination resulting in false positives for the environmental samples.

Duplicate Samples

Eighteen field duplicate samples were also collected during the CW-2 Lime Pit site sampling events to verify the consistency of the entire sampling and analytical procedure. The results for all of the duplicate samples were close to those obtained for the original samples. The relative percent differences (RPDs), which are the differences between the two samples being compared divided by their average, indicate the relative levels of precision maintained by the laboratory throughout its analytical procedures. The RPDs for the duplicate samples VOCs was 28.0%. The RPDs for the duplicate samples SVOCs ranged from 3.9% to 70.5%, and their average RPD was 27.0%. These RPDs are well below the established limit of 30% for laboratory duplicate samples and indicate that a high level of precision was maintained throughout the sampling and analytical procedures.

The RPDs for the duplicate samples metals analyses ranged from 0.0% to 195.9%, however, the average RPDs for all of the metals results is 40.1%. This indicates that, overall, good precision was maintained, but that the metals results were much more varied than those for the VOCs or SVOCs. The apparent metals contamination noted in the method and field blanks may have impacted the precision of the metals analysis.

The QC sample results indicate good precision for all of the analyses. However, the presence of metals in the method blanks and field blanks indicate that contamination may have been introduced by the sampling and analysis procedures. Therefore, any subsequent evaluation of the metals analytical results must account for the possibility of laboratory contamination resulting in false positives for the environmental samples.

6.0 CONCLUSIONS

Geologic publications show that the CW-2 Lime Pit site is located within an aquitard (the Navesink-Hornerstown Confining Unit). The low hydraulic conductivity of the aquitard and the thickness of the aquitard at the site conform to the requirements of a Class III-A aquifer, as specified in the NJDEP GWQS (NJAC 7:9-6, January 7, 1993).

The analytical results for the groundwater samples collected at the CW-2 Lime Pit site between April 1997 and January 2001 indicate that no COCs exist within the CW-2 Lime Pit site groundwater. The Class II-A criteria were used for comparison with site-specific data obtained from the various groundwater sampling rounds because the GWQS (NJAC 7:9-6.7e) state that the groundwater quality criteria to be used for Class III-A aquifers are the most stringent criteria associated with vertically or horizontally adjacent groundwaters that are not Class III-A.

Based on the results of the groundwater quality evaluation, no VOCs, SVOCs, pesticides or PCBs were detected above the NJDEP GWQC. There were seven metals (aluminum, arsenic, iron, lead, manganese, mercury and sodium) detected in groundwater samples at concentrations exceeding the NJDEP GWQC. However, none of these metals are considered to be COCs in site groundwater due to the process of elimination via categorization of background metals, reduction in concentration or non-detection of samples by low-flow sampling, and elimination of isolated and marginal detections. Therefore, no COCs exist within the groundwater and NFA is required concerning the groundwater at the CW-2 Lime Pit site.

7.0 REFERENCES

- Jablonski, L.A., 1968. *Groundwater Resources of Monmouth County, New Jersey*. USGS Special Report 23. USGS, Washington, DC.
- Meisler, H., J.A. Miller, L.L. Knobel, and R.L. Wait. 1988. "Region 22, Atlantic and Eastern Gulf Coastal Plan." In: *Hydrogeology: The Geology of North America*, W. Back, J.S. Rosenhein, and P.R. Seaber, editors. Vol. 0-2. pp. 209-218.
- Minard, J.P., 1969. *Geology of Sandy Hook Quadrangle in Monmouth County, New Jersey*. U.S. Government Printing Office, Washington, DC.
- New Jersey Administrative Code (NJAC) 7:26E - *Technical Requirements for Site Remediation*.
- New Jersey Geological Survey Map, 1994.
- TVS (TECOM-Vinnell Services), 2000. *SITE INVESTIGATION PLAN – Installation Landfill Program Sediment Sampling Plan for Nine Former Landfill Sites*.
- USGS (U.S. Geological Survey), 1981. Long Branch Quadrangle Map.
- WESTON (Roy F. Weston, Inc.), 1995. *Site Investigation Report - Main Post and Charles Wood Areas, Fort Monmouth, New Jersey*, December 1995.
- Zapeczka, O. 1989. *Hydrogeologic Framework of the New Jersey Coastal Plain*. USGS Professional Paper 1404-B. U.S. Government Printing Office, Washington, DC.

TABLES

Table 2-1
Well Construction Summary
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Well ID	NJDEP Permit Number	Northing	Easting	Elevation of Inner Casing Survey Mark	Elevation of Ground Surface	Hole Diameter	Total Depth of Well	Depth to Top of Screen	Screen Length	Screen Diameter	Screen Material	Date of Construction
Units	--	ft	ft	ft (amsl) ⁽¹⁾	ft (amsl) ⁽¹⁾	in	ft (bgs) ⁽²⁾	ft (bgs) ⁽²⁾	ft	in	--	--
CW2-MW30	29-32594	532816.326	607651.584	51.71	49.47	12	16.0	6.0	10.0	4.0	10 Slot PVC	12/16/1994
CW2-MW31	29-32595	532840.193	607643.906	51.58	49.67	12	15.0	5.0	10.0	4.0	10 Slot PVC	12/16/1994
CW2-MW32	29-32596	532839.306	607663.447	51.38	49.47	12	15.0	5.0	10.0	4.0	10 Slot PVC	12/16/1994
CW2-MW33	29-32597	532816.056	607672.515	51.09	49.18	12	15.0	5.0	10.0	4.0	10 Slot PVC	12/15/1994

Notes:

⁽¹⁾amsl = above mean sea level

⁽²⁾bgs = below ground surface

Where a difference in reported data exists between a monitoring well permit and the corresponding boring log, data from the permit was used.

Table 3-1
Groundwater Sampling Summary
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Round #	Monitoring Well	Lab Sample ID	Date Collected	Date Analysis Started	Sample Type	Matrix	Analytical Parameters	Analysis Method
1	MW-30	2472.03	04/24/97	05/02/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-31	2472.04	04/24/97	05/02/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-32	2472.05	04/24/97	05/02/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-33	2472.06	04/24/97	05/02/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Field Blank	2472.02	04/24/97	05/02/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Duplicate	2472.07	04/24/97	05/02/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
2	MW-30	2788.03	07/10/97	07/15/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-31	2788.04	07/10/97	07/15/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-32	2788.06	07/10/97	07/15/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-33	2788.07	07/10/97	07/15/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Trip	2788.01	07/10/97	07/15/97	GW	Aqueous	VOCs	Method 624
	Field Blank	2788.02	07/10/97	07/15/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
3	MW-30	3088.03	10/22/97	10/28/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-31	3088.04	10/22/97	10/28/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-32	3088.05	10/22/97	10/29/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-33	3088.06	10/22/97	10/29/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Trip	3088.01	10/22/97	10/29/97	GW	Aqueous	VOCs	Method 624
	Field Blank	3088.02	10/22/97	10/29/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
4	Duplicate	3088.07	10/22/97	10/29/97	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-30	3271.03	01/08/98	01/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-31	3271.04	01/08/98	01/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-32	3271.05	01/08/98	01/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-33	3271.06	01/08/98	01/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Trip	3271.01	01/08/98	01/14/98	GW	Aqueous	VOCs	Method 624
5	Field Blank	3271.02	01/08/98	01/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Duplicate	3271.07	01/08/98	01/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-30	3462.03	04/07/98	04/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-31	3462.04	04/07/98	04/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-32	3462.05	04/07/98	04/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-33	3462.06	04/07/98	04/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
6	Trip	3462.01	04/07/98	04/14/98	GW	Aqueous	VOCs	Method 624
	Field Blank	3462.02	04/07/98	04/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Duplicate	3462.07	04/07/98	04/14/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-30	3723.03	07/14/98	07/18/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-31	3723.04	07/14/98	07/18/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-32	3723.05	07/14/98	07/18/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
7	MW-33	3723.06	07/14/98	07/18/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Trip	3723.01	07/14/98	07/18/98	GW	Aqueous	VOCs	Method 624
	Field Blank	3723.02	07/14/98	07/18/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Duplicate	3723.07	07/14/98	07/18/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-30	4083.03	11/24/98	11/30/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-31	4083.04	11/24/98	11/30/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
8	MW-32	4083.05	11/24/98	11/30/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-33	4083.06	11/24/98	11/30/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Trip	4083.01	11/24/98	11/30/98	GW	Aqueous	VOCs	Method 624
	Field Blank	4083.02	11/24/98	11/30/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Duplicate	4083.07	11/24/98	11/30/98	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-30	4271.01	02/11/99	02/16/99	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
9	MW-31	4271.02	02/11/99	02/16/99	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-32	4271.03	02/11/99	02/16/99	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-33	4271.04	02/11/99	02/16/99	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Trip	4271.05	02/11/99	02/16/99	GW	Aqueous	VOCs	Method 624
	Field Blank	4271.06	02/11/99	02/16/99	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B

Table 3-1
Groundwater Sampling Summary
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Round #	Sample ID	Monitoring Well ID	Date Collected	Date Analysis Started	Matrix	Sample Type	Analytical Parameters	Analysis Method
LF1	MW-30	5660.02	08/24/00	08/25/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	MW-31	5657.02	08/23/00	08/25/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	MW-32	5657.03	08/23/00	08/25/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	MW-33	5657.04	08/23/00	08/25/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	Trip	5660.01	08/23/00	08/25/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	Field Blank	5660.02	08/23/00	08/25/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	Duplicate	5660.07	08/23/00	08/25/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
LF2	MW-30	5765.05	10/03/00	10/04/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	MW-31	5765.02	10/03/00	10/04/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	MW-32	5765.04	10/03/00	10/04/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	MW-33	5765.06	10/03/00	10/04/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	Trip	5765.01	10/03/00	10/04/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	Field Blank	5765.03	10/03/00	10/04/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
	Duplicate	5765.07	10/03/00	10/04/00	GW	Aqueous	TAL Metals	Method 3120B and 3112B
16	MW-30	53/146	01/11/01	01/12/01	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-31	54/147	01/11/01	01/12/01	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-32	55/148	01/11/01	01/12/01	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	MW-33	56/149	01/11/01	01/12/01	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Trip	50/143	01/11/01	01/12/01	GW	Aqueous	VOCS	Method 624
	Field Blank	51/144	01/11/01	01/12/01	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B
	Duplicate	52/145	01/11/01	01/12/01	GW	Aqueous	VOCs, SVOCs, Pesticides, PCBs and TAL Metals	Method 624, 625, 608, 3120B, 3112B

Notes:

GW : Groundwater

VOCs: Volatile Organic Compounds

SVOCs: Semi Volatile Organic Compounds

PCBs: Poly Chloronated Biphenols

*Low Flow Sampling Method was used to collect sample

Table 3-2
Groundwater Elevation Summary
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Round #		#1			#2			#3			#4		
Well ID	Elev. of Inner Casing Survey Mark	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.
CW2MW30	51.71	04/24/97	6.45	45.26	07/10/97	7.05	44.66	10/22/97	7.60	44.11	01/08/98	5.20	46.51
CW2MW31	51.58	04/24/97	6.38	45.20	07/10/97	7.00	44.58	10/22/97	7.50	44.08	01/08/98	6.30	45.28
CW2MW32	51.38	04/24/97	6.65	44.73	07/10/97	7.20	44.18	10/22/97	7.70	43.68	01/08/98	4.50	46.88
CW2MW33	51.09	04/24/97	8.95	42.14	07/10/97	9.10	44.99	10/22/97	9.10	41.99	01/08/98	9.00	42.09

Notes:

- 1) Elevation in feet
above mean sea level.
- 2) Depth to water: depth in feet
from the inner casing survey mark.
- 3) NA: Not Available

Table 3-2
Groundwater Elevation Summary
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Round #		#5			#6			#7			#8		
Well ID	Elev. of Inner Casing Survey Mark	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.
CW2MW30	51.71	04/07/98	6.56	45.15	07/14/98	6.89	44.82	11/24/98	7.86	43.85	02/11/99	7.24	44.47
CW2MW31	51.58	04/07/98	6.35	45.23	07/14/98	6.71	44.87	11/24/98	7.78	43.80	02/11/99	7.07	44.51
CW2MW32	51.38	04/07/98	6.81	44.57	07/14/98	7.06	44.32	11/24/98	7.94	43.44	02/11/99	7.33	44.05
CW2MW33	51.09	04/07/98	9.50	41.59	07/14/98	9.09	42.00	11/24/98	9.13	41.96	02/11/99	8.13	42.96

Notes:

- 1) Elevation in feet
above mean sea level.
- 2) Depth to water: depth in feet
from the inner casing survey mark.
- 3) NA: Not Available

Table 3-2
Groundwater Elevation Summary
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Round #		#9			#10			#11			#12		
Well ID	Elev. of Inner Casing Survey Mark	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.
CW2MW30	51.71	06/09/99	7.21	44.50	08/04/99	7.43	44.28	11/03/99	7.02	44.69	02/15/00	7.02	44.69
CW2MW31	51.58	06/09/99	7.15	44.43	08/04/99	7.65	43.93	11/03/99	7.18	44.40	02/15/00	7.03	44.55
CW2MW32	51.38	06/09/99	7.49	43.89	08/04/99	7.85	43.53	11/03/99	6.53	44.85	02/15/00	6.54	44.84
CW2MW33	51.09	06/09/99	9.13	41.96	08/04/99	9.15	41.90	11/03/99	6.14	44.95	02/15/00	9.09	42.00

Notes:

- 1) Elevation in feet
above mean sea level.
- 2) Depth to water: depth in feet
from the inner casing survey mark.
- 3) NA: Not Available

Table 3-2
Groundwater Elevation Summary
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Round #		#13			#14			Low-flow #1			#15		
Well ID	Elev. of Inner Casing Survey Mark	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.
CW2MW30	51.71	05/08/00	7.15	44.56	08/02/00	6.86	44.85	08/23/00	7.10	44.61	10/03/00	6.73	44.98
CW2MW31	51.58	05/08/00	6.96	44.62	08/02/00	6.73	44.85	08/24/00	6.60	44.98	10/03/00	7.65	43.93
CW2MW32	51.38	05/08/00	7.29	43.25	08/02/00	5.93	45.45	08/24/00	6.95	44.43	10/03/00	7.20	44.18
CW2MW33	51.09	05/08/00	8.13	42.96	08/02/00	NA	NA	08/24/00	8.70	42.39	10/03/00	8.85	42.24

Notes:

- 1) Elevation in feet
above mean sea level.
- 2) Depth to water: depth in feet
from the inner casing survey mark.
- 3) NA: Not Available

Table 3-2
Groundwater Elevation Summary
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

		Round # Low-flow #2			#16		
Well ID	Elev. of Inner Casing Survey Mark	Date	Depth to Water	Ground-water Elev.	Date	Depth to Water	Ground-water Elev.
CW2MW30	51.71	10/12/00	7.31	44.4	01/11/01	7.32	44.39
CW2MW31	51.58	10/12/00	7.16	44.42	01/11/01	7.16	44.42
CW2MW32	51.38	10/12/00	7.35	44.03	01/11/01	6.98	44.40
CW2MW33	51.09	10/12/00	9.11	41.98	01/11/01	9.14	41.95

Notes:

- 1) Elevation in feet above mean sea level.
- 2) Depth to water: depth in feet from the inner casing survey mark.
- 3) NA: Not Available

Table 4-1
Data for Cross-Section
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Well ID	Units	CW2-MW31	CW2-MW32	CW2-MW30	CW2-MW33
Elevation of Top of Casing	ft (amsl)	51.58	51.38	51.71	51.09
Elevation of Ground Surface	ft (amsl)	49.67	49.47	49.47	49.18
Elevation of Top of Screen	ft (amsl)	46.58	46.38	45.71	46.09
Elevation of Groundwater (1//11/01)	ft (amsl)	7.16	6.98	7.32	9.14
Elevation of Top of Unit 2	ft (amsl)	49.17	48.97	48.97	48.68
Elevation of Top of Unit 3	ft (amsl)	39.67	39.47	39.47	41.88
Elevation of Bottom of Well	ft (amsl)	34.67	34.47	33.47	34.18
Distance from Point A on Cross-Section	ft	0.00	9.40	28.80	38.00

Explanation of Units

Surface Materials:

Unit 1 (not in table) = Brown topsoil

Unit 2 = Fill: Brown, green, and gray poorly sorted sand and gravel, trace wood fragments and iron oxide stains.

Tinton Sand:

Unit 3 = greenish gray quartz sand and silt, trace mica and .layers of sub-rounded quartz gravel

Notes:

All measurements in feet.

amsl: above mean sea level.

NA: Not Applicable.

Table 5-1
Groundwater Sampling Results
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

		MW2-MW30 NJDEP#2932594																			
Field Sample Location	NJDEP	Site Specific	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30	CW2-MW30 ⁽¹⁾	CW2-MW30 ⁽¹⁾	CW2-MW30	CW2-MW30
Lab Sample ID	Clean-up	MBC(1)	2472.03	2788.03	3088.03	3271.03	3462.03	3723.03	4083.03	4271.01	4539.03	4686.04	4911.04	5175.04	5401.04	5591.04	5660.02	5765.05	5784.04	53/146	
Sample Date	Criteria		04/24/97	07/10/97	10/22/97	01/08/98	04/07/98	07/14/98	11/24/98	02/11/99	06/09/99	08/04/99	11/03/99	02/15/00	05/08/00	08/02/00	08/24/00	10/03/00	10/12/00	01/11/01	
Round Number			1	2	3	4	5	6	7	8	9	10	11	12	13	14	LF1	LF2	15	16	
Volatiles (ug/L)																					
Acetone	700	N/A	ND	ND	ND	ND	ND	9.84	ND	ND	8.09	ND	ND	ND	ND	ND	NA	NA	ND	ND	
Chloroform	6	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND	
Semi-Volatiles (ug/L)																					
bis(2-ethylhexyl)phthalate	30	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND	
Diethylphthalate	5000	N/A	ND	ND	4.74	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	2.84	
Di-n-butylphthalate	900	N/A	ND	0.98	4.73	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND	
Butylbenzylphthalate ⁽³⁾	100	N/A	ND	ND	1.01	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND	
PCB/Pesticides (ug/L)																					
			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND	
Metals (ug/L)																					
Aluminum	200	121000	ND	25	175	204	196	65.7	ND	505	521	304	92.7	20.4	105	ND	65.2	39.5	100	38.1	
Antimony	20	N/A	ND	ND	ND	ND	ND	3.5	3.99	ND	2.58	ND	ND	ND	ND	4.5	4.12	ND	ND	ND	
Arsenic	8	N/A	4	5	5	ND	5.6	ND	11.5	8.3	6.33	9.05	6.06	ND	ND	ND	4.27	ND	3.95	3.48	
Barium	2000	699	ND	ND	112.5	30.9	35.5	85.5	250	80.4	111	127	72.7	24.3	61.7	60.2	61.3	51.9	67	62.1	
Beryllium	20	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Cadmium	4	N/A	ND	2	ND	ND	ND	ND	0.721	1.08	2.06	ND	ND	0.787	ND	ND	ND	ND	ND	ND	
Calcium	NLE	45400	41000	49030	68240	41070	41000	75000	109000	66600	87400	83300	55300	28700	59800	68100	84600	64600	67000	59600	
Chromium	100	N/A	ND	1	2.7	5.2	ND	ND	3.75	5.85	5.43	3.82	2.38	ND	7.19	1.5	ND	2.06	3	1.29	
Cobalt	NLE	N/A	0.7	20	ND	ND	ND	ND	ND	0.646	0.675	ND	ND	0.822	ND	ND	ND	ND	ND	ND	
Copper	1000	65.6	14	ND	17	21	3.8	4.37	4.28	9.5	51.5	77.7	12.4	7.24	327	72.1	ND	25.1	35.4	ND	
Iron	300	431000	9110	12590	34760	2795	3504	10900	27500	11000	8210	44800	6540	1840	7410	2040	2180	834	8150	9730	
Lead	10	N/A	ND	ND	5	4	ND	ND	3.15	ND	ND	6.02	ND	ND	46.6	21.8	ND	ND	ND	ND	
Magnesium	NLE	62700	4500	5330	6640	3390	3437	5270	9310	5290	6800	7890	4300	2480	4910	4670	5950	4540	5060	4690	
Manganese	50	331	69	73	171.3	5	39.3	57.8	182	100	145	212	36.3	2.69	73.1	15.2	19.5	7.75	39.1	54.6	
Mercury	2	N/A	ND	ND	0.2	ND	ND	ND	2.3	ND	ND	ND	0.2	0.3	ND	ND	ND	ND	ND	0.2	
Nickel	100	187	ND	ND	1.5	2.8	3.5	0.63	1.59	8.79	1.6	8.53	2.24	0.599	17.6	6.54	ND	4.67	1.95	2.38	
Potassium	NLE	137000	6900	10420	12240	7240	5793	13800	12500	6930	12700	10800	8930	5440	7670	11300	9500	9160	8770	7410	
Selenium	50	N/A	ND	2	ND	ND	ND	ND	5.27	5.17	ND	ND	4.01	ND	ND	ND	ND	ND	ND	7.2	
Silver	20	N/A	10	6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Sodium	50000	21500	14000	33050	19320	5450	13010	14300	17400	32400	25700	47200	15400	15700	24500	7280	14200	9420	20200	22200	
Vanadium	NLE	N/A	ND	4	ND	ND	2.3	1.22	1.45	3.76	3.65	3.02	2.19	1.58	3.17	1.63	ND	2.09	2.67	1.25	
Zinc	5000	233	6	ND	72	76	17.2	21.4	3.33	16.6	ND	56.6	2.24	5.75	429	164	33.8	18.7	38.1	7.46	

Notes

All concentrations in micrograms per liter (ug/L), equivalent to parts per billion (ppb) except for Wet Chemistry

NJDEP Criteria: Higher of Practical Quantitation Limits (PQLs) & Groundwater Quality Criteria (GWQC) NJAC 7:9-6

Exceedences of NJDEP GWQS are shaded and **bold**

ND: Analyte not detected in sample

NA: Not Applicable NS: Not Sampled

⁽¹⁾ MBC - Maximum Background Criteria for native metals

(Weston 1995).

⁽²⁾Low Flow Sampling Method used to collect sample

LF: Low Flow Sampling

Table 5-1
Groundwater Sampling Results
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

			CW2-MW31		NJDEP#2932595																	
Field Sample Location Lab Sample ID Sample Date	NJDEP Clean-up Criteria	Site Specific MBC(1)	CW2-MW31 2472.04 04/24/97	CW2-MW31 2788.04 07/10/97	CW2-MW31 3088.04 10/22/97	CW2-MW31 3271.04 01/08/98	CW2-MW31 3462.04 04/07/98	CW2-MW31 3723.04 07/14/98	CW2-MW31 4083.04 11/24/98	CW2-MW31 4271.02 02/11/99	CW2-MW31 4539.04 06/09/99	CW2-MW31 4686.05 08/04/99	CW2-MW31 4911.05 11/03/99	CW2-MW31 5175.05 02/15/00	CW2-MW31 5401.05 05/08/00	CW2-MW31 5591.05 08/02/00	CW2-MW31 ⁽¹⁾ 5657.02 08/23/00	CW2-MW31 ⁽²⁾ 5765.02 10/03/00	CW2-MW31 5784.05 10/12/00	CW2-MW31 54/147 01/11/01		
Round Number			1	2	3	4	5	6	7	8	9	10	11	12	13	14	LF1	LF2	15	16		
Volatiles (ug/L)																						
Acetone	700	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND		
Chloroform	6	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND		
Semi-Volatiles (ug/L)																						
bis(2-ethylhexyl)phthalate	30	N/A	ND	ND	ND	ND	1.01	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND		
Diethylphthalate	5000	N/A	ND	ND	1.58	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	2.37		
Di-n-butylphthalate	900	N/A	ND	ND	1.3	3.75	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND		
Butylbenzylphthalate ⁽³⁾	100	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND		
PCB/Pesticides (ug/L)																						
			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND		
Metals (ug/L)																						
Aluminum	200	121000	ND	ND	93	129	ND	390	ND	ND	27.9	ND	14.9	11.7	ND	14.7	42.7	38.5	20.6	ND		
Antimony	20	N/A	ND	ND	ND	ND	ND	3.67	3.03	4.22	ND	ND	ND	ND	ND	5.66	2.74	ND	ND	ND		
Arsenic	8	N/A	2	1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Barium	2000	699	ND	ND	197.3	204.7	249	295	275	273	348	361	265	264	305	326	245	235	288	252		
Beryllium	20	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Cadmium	4	N/A	ND	ND	ND	ND	ND	ND	ND	1.65	3.5	1.06	1.45	ND	ND	ND	ND	ND	ND	ND		
Calcium	NLE	45400	40200	41990	45780	44460	48520	58800	56700	56500	60100	59600	53400	53600	52500	53700	54000	50500	49800	56800		
Chromium	100	N/A	ND	ND	11.2	1.4	ND	ND	3.33	3.4	ND	ND	1.08	1.57	1.37	ND	1.11	0.968	ND	ND		
Cobalt	NLE	N/A	ND	ND	ND	4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Copper	1000	65.6	11	ND	11	36	ND	34.5	ND	28.3	15.7	ND	3.69	14	ND	ND	ND	11.8	6.12	ND		
Iron	300	431000	59900	11830	52340	68450	115100	83600	72800	71900	104000	77500	64600	111000	86000	68900	69000	65000	62100	78800		
Lead	10	N/A	ND	ND	6	25	ND	4.85	2.33	ND	ND	ND	ND	ND	ND	2.44	ND	ND	ND	ND		
Magnesium	NLE	62700	5680	5780	5430	5250	5663	6500	6800	6740	7070	7120	6610	6660	6650	6610	6610	6230	6170	7030		
Manganese	50	331	277	267	243.5	240	266	311	322	316	326	347	309	301	343	294	300	275	294	294		
Mercury	2	N/A	ND	ND	0.6	ND	ND	ND	0.3	ND	ND	ND	ND	0.4	ND	ND	ND	ND	ND	0.2		
Nickel	100	187	ND	ND	1.4	49.8	ND	ND	0.595	ND	1.11	4.98	ND	ND	ND	ND	ND	ND	ND	ND		
Potassium	NLE	137000	8960	9560	11040	9800	12490	12800	11500	10100	11200	11600	11600	9400	10200	10400	10600	10100	9980	10600		
Selenium	50	N/A	ND	1	ND	ND	ND	ND	4.14	3.93	ND	ND	ND	ND	ND	ND	ND	ND	ND	5.28		
Silver	20	N/A	14	7	ND	15	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Sodium	50000	21500	11100	11420	11920	10310	8927	8970	9900	14600	13000	12900	12500	12100	12600	8200	12700	11900	11300	12600		
Vanadium	NLE	N/A	ND	ND	ND	ND	ND	ND	ND	4.23	2.4	ND	ND	2.08	0.655	ND	1.65	ND	ND	ND		
Zinc	5000	233	ND	ND	476	996	29.1	26.2	6.51	6.67	ND	6.86	35.5	10.8	15.2	13	25.2	15	27.3	9.44		

Notes

All concentrations in micrograms per liter (ug/L), equivalent to parts per billion (ppb) except for Wet Chemistry

NJDEP Criteria: Higher of Practical Quantitation Limits (PQLs) & Groundwater Quality Criteria (GWQC) NJAC 7-9-6

Exceedences of NJDEP GWQS are shaded and **bold**

ND: Analyte not detected in sample

NA: Not Applicable NS: Not Sampled

⁽¹⁾ MBC - Maximum Background Criteria for native metals (Weston 1995).

⁽²⁾ Low Flow Sampling Method used to collect sample

LF: Low Flow Sampling

Table 5-1
Groundwater Sampling Results
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

			CW2-MW32		NJDEP#2932596															
Field Sample Location Lab Sample ID Sample Date	NJDEP Clean-up Criteria	Site Specific MBC(1)	CW2-MW32 2472.05 04/24/97	CW2-MW32 2788.06 07/10/97	CW2-MW32 3088.05 10/22/97	CW2-MW32 3271.05 01/08/98	CW2-MW32 3462.05 04/07/98	CW2-MW32 3723.05 07/14/98	CW2-MW32 4083.05 11/24/98	CW2-MW32 4271.03 02/11/99	CW2-MW32 4539.05 06/09/99	CW2-MW32 4686.06 08/04/99	CW2-MW32 4911.06 11/03/99	CW2-MW32 5175.06 02/15/00	CW2-MW32 5401.06 05/08/00	CW2-MW32 5591.06 08/02/00	CW2-MW32 ⁽¹⁾ 5657.03 08/23/00	CW2-MW32 ⁽²⁾ 5765.04 10/03/00	CW2-MW32 5784.06 10/12/00	CW2-MW32 55/148 01/11/01
Round Number			1	2	3	4	5	6	7	8	9	10	11	12	13	14	LF1	LF2	15	16
Volatiles (ug/L)																				
Acetone	700	N/A	ND	ND	ND	ND	ND	7.02	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Chloroform	6	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Semi-Volatiles (ug/L)																				
bis(2-ethylhexyl)phthalate	30	N/A	1.54	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Diethylphthalate	5000	N/A	ND	ND	1.95	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	2.05
Di-n-butylphthalate	900	N/A	ND	1.63	1.45	2.98	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Butylbenzylphthalate ⁽³⁾	100	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
PCB/Pesticides (ug/L)																				
			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Metals (ug/L)																				
Aluminum	200	121000	ND	2.1	297	163	ND	78.1	166	137	59.5	67.4	162	95.7	51.4	21.8	53.7	35.1	238	63.2
Antimony	20	N/A	ND	ND	ND	ND	ND	2.27	3.33	3.81	ND	ND	ND	ND	ND	5.58	2.36	ND	ND	ND
Arsenic	8	N/A	2	1	ND	ND	ND	2.51	9.32	ND	ND	ND	4.09	ND	ND	4.14	ND	ND	4.55	5.59
Barium	2000	699	ND	ND	166.9	22.8	109	203	230	42.5	202	247	61.7	70	193	51.3	51.3	34.1	166	49.9
Beryllium	20	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Cadmium	4	N/A	ND	ND	ND	ND	0.6	ND	ND	1.07	2.06	2.25	0.837	ND	0.585	ND	ND	ND	ND	ND
Calcium	NLE	45400	77000	80510	67870	62370	71090	88700	66900	104000	70700	71700	95100	76600	71800	114000	131000	103000	73300	91500
Chromium	100	N/A	ND	ND	11.3	4.9	ND	ND	4.6	3.79	0.572	ND	3.64	1.98	2.63	1.9	ND	1.85	3.05	1.6
Cobalt	NLE	N/A	0.9	ND	ND	ND	0.7	ND	ND	ND	0.857	ND	ND	ND	ND	0.583	ND	ND	ND	ND
Copper	1000	65.6	27	ND	17	38	13.7	31.1	38.3	92.7	28.6	6.23	44.9	25.5	27.9	ND	ND	59.3	31	ND
Iron	300	431000	18400	270	51100	1484	19280	67500	106000	4480	64300	76000	11500	11300	55700	4700	2100	1630	39900	11500
Lead	10	N/A	ND	ND	7	ND	ND	3.99	4.08	ND	ND	ND	ND	ND	ND	2.96	1.73	ND	ND	ND
Magnesium	NLE	62700	4750	9830	7570	6140	7413	8570	7650	10100	7880	8270	9380	8120	8300	10600	12400	9530	7890	9330
Manganese	50	331	125	181	260.7	3.7	287	287	342	7.02	310	369	27	53.9	382	8.74	3.61	4.59	326	23
Mercury	2	N/A	ND	ND	ND	ND	ND	ND	0.3	ND	ND	ND	ND	0.2	ND	ND	ND	ND	ND	ND
Nickel	100	187	ND	ND	2.5	3.4	6.9	2.03	1.22	5.03	ND	1.7	4.57	2.21	3	2.71	ND	4.42	2.71	1.26
Potassium	NLE	137000	6740	8340	13540	3590	10210	10200	12100	3670	10700	11900	4990	6220	9220	5340	5600	4160	8360	3000
Selenium	50	N/A	ND	1	ND	ND	ND	ND	4.04	5.27	ND	ND	5.66	3.74	ND	ND	ND	ND	ND	5.34
Silver	20	N/A	11	7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Sodium	50000	21500	22250	22950	17300	15990	10860	10700	11200	35700	15500	14800	21000	27500	15600	17900	25600	18100	14800	20000
Vanadium	NLE	N/A	ND	ND	ND	ND	ND	ND	11	1.95	5.48	2.84	4.91	3.69	6.8	3.25	ND	3.05	6.87	3.87
Zinc	5000	233	121	16	461	84	257	145	127	59.4	18.7	24.8	41.1	29.2	79.9	29.6	56.8	72.8	119	36.5

Notes

All concentrations in micrograms per liter (ug/L), equivalent to parts per billion (ppb) except for Wet Chemistry

NJDEP Criteria: Higher of Practical Quantitation Limits (PQLs) & Groundwater Quality Criteria (GWQC) NJAC 7:9-6

Exceedences of NJDEP GWQS are shaded and **bold**

ND: Analyte not detected in sample
 NA: Not Applicable NS: Not Sampled

⁽¹⁾ MBC - Maximum Background Criteria for native metals
 (Weston 1995).

⁽²⁾ Low Flow Sampling Method used to collect sample

LF: Low Flow Sampling

Table 5-1
Groundwater Sampling Results
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

			CW2-MW33				NJDEP#2932597													
Field Sample Location	NJDEP Clean-up Criteria	Site Specific MBC(1)	CW2-MW33 2472.06 04/24/97	CW2-MW33 2788.05 07/10/97	CW2-MW33 3088.06 10/22/97	CW2-MW33 3271.06 01/08/98	CW2-MW33 3462.06 04/07/98	CW2-MW33 3723.06 07/14/98	CW2-MW33 4083.06 11/24/98	CW2-MW33 4271.04 02/11/99	CW2-MW33 4539.06 06/09/99	CW2-MW33 4686.07 08/04/99	CW2-MW33 4911.07 11/03/99	CW2-MW33 5175.07 02/15/00	CW2-MW33 5401.07 05/08/00	CW2-MW33 5591.07 08/02/00	CW2-MW33 ⁽¹⁾ 5657.04 08/23/00	CW2-MW33 ⁽²⁾ 5765.06 10/03/00	CW2-MW33 5784.07 10/12/00	CW2-MW33 56/149 01/11/01
Round Number			1	2	3	4	5	6	7	8	9	10	11	12	13	14	LF1	LF2	15	16
Volatiles (ug/L)																				
Acetone	700	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	9.26	ND	ND	NA	NA	ND	ND
Chloroform	6	N/A	ND	ND	ND	ND	1.07	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Semi-Volatiles (ug/L)																				
bis(2-ethylhexyl)phthalate	30	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Diethylphthalate	5000	N/A	ND	ND	4.65	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	1.71
Di-n-butylphthalate	900	N/A	ND	1.98	4.67	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Butylbenzylphthalate ⁽³⁾	100	N/A	ND	ND	1.17	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
PCB/Pesticides (ug/L)																				
			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NA	NA	ND	ND
Metals (ug/L)																				
Aluminum	200	121000	ND	595.1	94	217	119	411	125	67.8	336	69.8	52.8	96.2	29.3	38.2	623	31.9	109	37.1
Antimony	20	N/A	ND	ND	ND	ND	ND	ND	2.82	2.49	ND	ND	ND	ND	ND	4.04	ND	ND	ND	ND
Arsenic	8	N/A	3	ND	ND	6	3.4	ND	ND	ND	5.82	3.25	ND	2.67	ND	ND	ND	ND	3.69	3.02
Barium	2000	699	90	670	126.5	310.9	123	144	119	72.9	212	158	46.7	159	121	83.6	189	175	144	204
Beryllium	20	N/A	ND	0.08	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Cadmium	4	N/A	ND	ND	ND	ND	ND	ND	ND	1.04	2.06	0.561	1.38	ND	ND	ND	ND	ND	ND	ND
Calcium	NLE	45400	67200	75930	39300	72300	31310	27500	32000	32100	42100	35100	18100	45500	36100	23900	60800	51600	37300	51900
Chromium	100	N/A	ND	ND	1.1	3	ND	ND	4.87	2.4	2.07	0.7	1.3	1.45	0.845	ND	ND	2.63	1.17	5.9
Cobalt	NLE	N/A	0.7	ND	ND	ND	ND	ND	ND	0.768	ND	ND	ND	ND	0.77	ND	ND	ND	ND	ND
Copper	1000	65.6	9	8	12	10	ND	19.5	3.71	17.3	6.04	ND	3.98	ND	ND	ND	ND	28.9	165	182
Iron	300	431000	88600	10260	26770	104700	19780	35900	26400	11300	69600	35900	19500	54400	36500	13400	59800	45500	38800	106000
Lead	10	N/A	ND	ND	4	4	ND	4.19	ND	ND	ND	ND	ND	3.77	ND	1.5	2.44	ND	29.7	41.2
Magnesium	NLE	62700	3110	8250	5370	7660	5651	3790	5360	6010	4990	5360	3260	5340	5870	2660	8740	5490	4720	5890
Manganese	50	331	424	519	151.8	341.7	110	130	87.8	81.2	214	149	47.2	201	242	81.4	281	257	188	251
Mercury	2	N/A	ND	ND	0.2	ND	ND	ND	0.4	0.13	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.2
Nickel	100	187	ND	ND	1.4	3.2	2.2	1.86	1.61	3.15	ND	1.27	2.75	1.8	0.949	ND	ND	2.69	4.79	7.5
Potassium	NLE	137000	11000	12400	7680	13430	6223	8300	5250	4770	8140	7690	3490	8500	7120	6080	10200	10200	9320	9650
Selenium	50	N/A	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Silver	20	N/A	16	8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Sodium	50000	21500	12000	13630	16360	11780	14730	15600	17800	37000	19000	16100	8950	14800	19900	5230	84100	9890	19800	12800
Vanadium	NLE	N/A	ND	ND	ND	ND	ND	2.6	1.4	ND	4.91	ND	ND	ND	1.78	0.821	ND	1.34	1.4	0.866
Zinc	5000	233	ND	24	49	69	ND	55	13.5	11.1	ND	7.3	20.8	11.5	6.37	16.4	29.5	36.8	257	346

Notes

All concentrations in micrograms per liter (ug/L), equivalent to parts per billion (ppb) except for Wet Chemistry

NJDEP Criteria: Higher of Practical Quantitation Limits (PQLs) & Groundwater Quality Criteria (GWQC) NJAC 7:9-6

Exceedences of NJDEP GWQS are shaded and **bold**

ND: Analyte not detected in sample

NA: Not Applicable NS: Not Sampled

⁽¹⁾ MBC - Maximum Background Criteria for native metals (Weston 1995).

⁽²⁾ Low Flow Sampling Method used to collect sample

LF: Low Flow Sampling

Table 5-2
Determination of Contaminant of Concern
CW-2 Wastewater Treatment Lime Pit Site
Fort Monmouth, New Jersey

Analyte	NJDEP Cleanup Criteria ⁽¹⁾	Site Specific Groundwater MBC ⁽²⁾	Maximum Result	No. of NJDEP Criteria Exceedences	No. of Site Maximum Background Exceedences	Comments
Volatiles						
Acetone	700	N/A	9.84	0	N/A	No exceedance of NJDEP GWQC
Chloroform	6	N/A	1.07	0	N/A	No exceedance of NJDEP GWQC
Semi-Volatiles						
bis(2-ethylhexyl)phthalate	30	N/A	1.54	0	N/A	No exceedance of NJDEP GWQC
Diethylphthalate	5000	N/A	4.74	0	N/A	No exceedance of NJDEP GWQC
Di-n-butylphthalate	900	N/A	4.67	0	N/A	No exceedance of NJDEP GWQC
Butylbenzylphthalate	100	N/A	1.17	0	N/A	No exceedance of NJDEP GWQC
Pesticides/PCBs: None Detected						
Metals						
Aluminum	200	121000	623	12	0	Not a Contaminant of Concern. Background metal.
Antimony	20	N/A	5.66	0	N/A	No exceedance of NJDEP GWQC
Arsenic	8	N/A	11.5	4	N/A	Not a Contaminant of Concern. Low flow sampling has no exceedances.
Barium	2000	699	670	0	0	No exceedance of NJDEP GWQC
Beryllium	20	N/A	0.08	0	N/A	No exceedance of NJDEP GWQC
Cadmium	4	N/A	2.25	0	N/A	No exceedance of NJDEP GWQC
Calcium	NLE	45400	131000	0	54	No exceedance of NJDEP GWQC
Chromium	100	N/A	11.3	0	N/A	No exceedance of NJDEP GWQC
Cobalt	NLE	N/A	20	N/A	N/A	No limits established.
Copper	1000	65.6	327	0	6	No exceedance of NJDEP GWQC
Iron	300	431000	115100	71	0	Not a Contaminant of Concern. Background metal.
Lead	10	N/A	46.6	5	N/A	Not a Contaminant of Concern. Low flow sampling has no exceedances.
Magnesium	NLE	62700	12400	N/A	0	No limits established.
Manganese	50	331	519	57	8	Not a Contaminant of Concern. Background metal.
Mercury	2	N/A	2.3	1	N/A	Detected at MW30 on 11/24/98. Isolated detection. Low flow sampling presents no exceedances.
Nickel	100	187	49.8	0	0	No exceedance of NJDEP GWQC
Potassium	NLE	137000	13800	N/A	0	No limits established.
Selenium	50	N/A	7.2	0	N/A	No exceedance of NJDEP GWQC
Silver	20	N/A	16	0	N/A	No exceedance of NJDEP GWQC
Sodium	50000	21500	84100	1	13	Not a Contaminant of Concern due to proximity of seawater. Background metal.
Thallium	10	N/A	ND	0	N/A	No exceedance of NJDEP GWQC
Vanadium	NLE	N/A	11	N/A	N/A	No limits established.
Zinc	5000	233	996	0	7	No exceedance of NJDEP GWQC

Notes:

All concentrations in micrograms per liter (ug/L), equivalent to parts per billion (ppb).

NJDEP GWQC: New Jersey Department of Environmental Protection Groundwater Quality Criteria.

N/A = Not Applicable

Exceeds NJDEP GWQC =

ND: Analyte not detected in sample

NLE: No limit established for this analyte

⁽¹⁾Higher of Practical Quantitation Limits (PQLs) and Groundwater Quality Criteria (GWQC) per N.J.A.C. 7:9-6

⁽²⁾Fort Monmouth Summary of Site-specific Groundwater Maximum Background Concentrations (MBC);

MBCs are shown for background (native) metals only.

⁽³⁾Interim Criteria used as NJDEP criteria

FIGURES




FIGURE 2-1

Site Location Map
CW-2 Lime Pit Site
Fort Monmouth, New Jersey

Versar INC.

LONG BRANCH, N. J.

40073-C8-TF-024

1954

PHOTOREVISED 1981

DMA 6164 I SE-SERIES V822

NEW
JERSEY

QUADRANGLE LOCATION

Mapped, edited and published by the Geological Survey

Scale: 1" = 2000'

March 7, 2005



ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
TITLE: FIGURE 2-2 SITE LAYOUT MAP CW-2 LIME PIT SITE FORT MONMOUTH, NEW JERSEY				
DRAWN BY: JM		DATE DRAWN: 01 JUL 01		
CHECKED BY:		DATE CHECKED: 01 JUL 01		
APPROVED BY:		DATE APPROVED:		
 2558 PEARL BUCK ROAD, SUITE 1 BRISTOL, NJ 08807 609-788-7844		DRAWING No.: CW2		
		FILE No.: CW2		
		SCALE: 1" = 60'		
SHEET		OF		REV.: A



ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

= MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
TITLE: FIGURE 2-3 MONITORING WELL LOCATION MAP CW-2 LIME PIT SITE FORT MONMOUTH, NEW JERSEY				
DRAWN BY: JM		DATE DRAWN: 01 JUL 01		
CHECKED BY:		DATE CHECKED: 01 JUL 01		
APPROVED BY:		DATE APPROVED:		
 2558 PEARL BUCK ROAD, SUITE 1 BRISTOL, PA 19007 (215) 788-7844		DRAWING No.: CW2		
		FILE No.: CW2		
		SCALE: 1" = 60'		
SHEET		OF	REV.:	A

Geologic Map of New Jersey





Figure 2-4
Geological Map of New Jersey
CW-2 Lime Pit Site
Fort Monmouth, New Jersey

Source: New Jersey Geologic Survey, 1994, *Geologic Map of New Jersey*.

Versar INC.



Source: New Jersey Groundwater Quality Standards, NJAC 7:9-6

Fort Monmouth





FIGURE 2-6

**Geologic Cross-Section
CW-2 Lime Pit Site
Fort Monmouth, New Jersey**

Source: Zapecza, O. 1989. *Hydrogeologic Framework of the New Jersey Coastal Plain*.
USGS Professional Paper 1404-B. U.S. Government Printing Office, Washington, DC.

Versar INC.

201 Gibraltar Rd., Ste. 100
Horsham, PA 19044
(215) 957-0955






FIGURE 2-7


**Outcrop and Thickness of
Composite Confining Unit
CW-2 Lime Pit Site
Fort Monmouth, New Jersey**

Source: Zapecza, O. 1989. *Hydrogeologic Framework of the New Jersey Coastal Plain*.
USGS Professional Paper 1404-B. U.S. Government Printing Office, Washington, DC.

Versar INC. 201 Gibraltar Rd., Ste. 100
Horsham, PA 19044
(215) 957-0955




ELEVATION
(FT MSL)



- NOTES:
- 1) CROSS SECTION LINE (A TO A') IS SHOWN ON FIGURE 4-1.
 - 2) VERTICAL SCALE: 1" = 3';
HORIZONTAL SCALE: 1" = 20';
VERTICAL EXAGGERATION = 6.66.
 - 3) FT MSL: FEET ABOVE MEAN SEA LEVEL
 - 4) TOC = ELEVATION OF INNER WELL CASING SURVEY MARK (FT MSL).
 - 5) GROUNDWATER ELEVATION SHOWN IN FEET.
 - 6) EACH OF THE WELLS HAS A DIAMETER OF 4 INCHES, WHICH IS ENLARGED ON THIS DRAWING FOR PRESENTATION.
 - 7) BOUNDARIES ARE DASHED WHERE INFERRED.

UNIT	SYMBOL	DESCRIPTION
(1)		TOPSOIL AND ROOTS
(2)		BROWN MEDIUM TO COARSE SAND - FILL
(3)		GREENISH-GRAY TO BLACK SILTY CLAY

REV.	REVISIONS	APPROVED	DRAWN BY
TITLE: FIGURE 4-2 GEOLOGIC CROSS SECTION FROM A TO A' CW-2 - LIME PIT SITE FORT MONMOUTH, NEW JERSEY			
DRAWN BY: TJK/TJW		DATE DRAWN: 16 OCT 01	
CHECKED BY:		DATE CHECKED:	
APPROVED BY:		DATE APPROVED:	
		DRAWING No: FIGURE 4-2	
2558 PEARL BUCK ROAD, SUITE 1 BRISTOL, PA 19007 (215) 788-7844		FILE No: CW-6 Figure 4-2 SCALE: 1" = 10' (VERT 1"=3')	
SHEET 1 OF 1		REV: A	




ROAD PAVED	==	WOODED AREA	~~~~~
ROAD/TRAILS UNPAVED	- - -	TREE/BUSH	⊗
FENCE	- x -	LIGHT POLE	⊕
BUILDING	▭	UTILITY POLE	⊗
APPROXIMATE BOUNDARY	▭	BROOK/CREEK	~~~~~
BASE BOUNDARY	▭	WRIGHT AREA	⊗

NOTES:
CONTOUR INTERVAL IS 0.25 FEET.
← = GW FLOW
⊕ = MONITORING WELL LOCATION

REV.	REVISION	APPROVED	DATE	DRAWN BY
------	----------	----------	------	----------

TITLE:
FIGURE 4-3a
GROUNDWATER CONTOUR MAP (Apr 97)
CW-2 LIME PIT SITE
FORT MONMOUTH, NEW JERSEY


DRAWN BY: JM	DATE DRAWN: 04 MAR 02
CHECKED BY:	DATE CHECKED: 04 MAR 02
APPROVED BY:	DATE APPROVED:
Versar inc. 201 GIBRALTAR ROAD, SUITE 100 ROSELAND, NJ 07068 CELL: 907-0000	DRAWING No: CW2 FILE No: CW2 FIG. 4-3a SCALE: 1" = 10' SHEET OF REV: A



ROAD PAVED		WOODED AREA	
ROAD/TRAILS UNPAVED		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:
CONTOUR INTERVAL IS 0.25 FEET.
← = GW FLOW
⊕ = MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
TITLE: FIGURE 4-3b GROUNDWATER CONTOUR MAP (Jul 97) CW-2 LIME PIT SITE FORT MONMOUTH, NEW JERSEY				
DRAWN BY: JM		DATE DRAWN: 04 MAR 02		
CHECKED BY:		DATE CHECKED: 04 MAR 02		
APPROVED BY:		DATE APPROVED:		
 201 GIBRALTAR ROAD, SUITE 100 ROSELAND, PA 19084 TEL: 957-0585		DRAWING No.: CW2		
		FILE No.: CW2 FIG. 4-3b		
		SCALE: 1" = 10'		
SHEET		OF		REV. A



ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

CONTOUR INTERVAL IS 0.25 FEET.


= GW FLOW

= MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
 FIGURE 4-3c
 GROUNDWATER CONTOUR MAP (Oct 97)
 CW-2 LIME PIT SITE
 FORT MONMOUTH, NEW JERSEY

DRAWN BY: JM	DATE DRAWN: 04 MAR 02
CHECKED BY:	DATE CHECKED: 04 MAR 02
APPROVED BY:	DATE APPROVED:
	DRAWING No.: CW2
201 GIBRALTAR ROAD, SUITE 100 ROCKY HILL, CT 06067 TEL: 957-0585	FILE No.: CW2 FIG. 4-3c
SCALE: 1" = 10'	SHEET OF REV: A



ROAD (PAVED)		VOIDED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

CONTOUR INTERVAL IS 0.25 FEET.

= GW FLOW

= MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
TITLE: FIGURE 4-3d GROUNDWATER CONTOUR MAP (Jan 98) CW-2 LIME PIT SITE FORT MONMOUTH, NEW JERSEY				
DRAWN BY: JM		DATE DRAWN: 04 MAR 02		
CHECKED BY:		DATE CHECKED: 04 MAR 02		
APPROVED BY:		DATE APPROVED:		
 201 GIBRALTAR ROAD, SUITE 100 ROSELAND, NJ 07068 (908) 957-0585		DRAWING No.: CW2		
		FILE No.: CW2 FIG. 4-3d		
		SCALE: 1" = 10'		
SHEET		OF		REV. A

CW2-MW31

CW2-MW32

CW2-MW30

CW2-MW33

45

44

43

42

ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

CONTOUR INTERVAL IS 0.25 FEET.

= GW FLOW

= MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
FIGURE 4-3e
GROUNDWATER CONTOUR MAP (APR 98)
CW-2 LIME PIT SITE
FORT MONMOUTH, NEW JERSEY

DRAWN BY: JM DATE DRAWN: 04 MAR 02

CHECKED BY: DATE CHECKED: 04 MAR 02

APPROVED BY: DATE APPROVED:

DRAWING No.: CW2

FILE No.: CW2-FIG. 4-3e

SCALE: 1" = 10'

SHEET OF REV. A

Versar inc.
201 GIBRALTAR ROAD, SUITE 100
ROCKY HILL, CT 06067
(860) 957-0585

CW2-MW31

CW2-MW32

CW2-MW30

CW2-MW33

MH

MH

43

ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

CONTOUR INTERVAL IS 0.25 FEET.

= GW FLOW

= MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
FIGURE 4-3f
GROUNDWATER CONTOUR MAP (Jul 98)
CW-2 LIME PIT SITE
FORT MONMOUTH, NEW JERSEY

DRAWN BY: JM DATE DRAWN: 04 MAR 02

CHECKED BY: DATE CHECKED: 04 MAR 02

APPROVED BY: DATE APPROVED:


DRAWING No.: CW2


FILE No.: CW2 FIG. 4-3f


SCALE: 1" = 10'

SHEET OF REV. A

Versar inc.
201 GIBRALTAR ROAD, SUITE 100
HORSINGEORGE, PA 19044
(610) 957-0585








ROAD PAVED		WOODED AREA	
ROAD/TRAILS UNPAVED		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:
CONTOUR INTERVAL IS 0.25 FEET.
 = GW FLOW
 = MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
FIGURE 4-31
GROUNDWATER CONTOUR MAP (May 99)
CW-2 LIME PIT SITE
FORT MONMOUTH, NEW JERSEY


DRAWN BY: JM	DATE DRAWN: 04 MAR 02
CHECKED BY:	DATE CHECKED: 04 MAR 02
APPROVED BY:	DATE APPROVED:
 201 GIBRALTAR ROAD, SUITE 100 ROSELAND, NJ 07068 TEL: 907-0585	
DRAWING No.: CW2	FILE No.: CW2 FIG. 4-31
SCALE: 1" = 10'	SHEET OF REV. A



ROAD PAVED		WOODED AREA	
ROAD/TRAILS UNPAVED		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:
CONTOUR INTERVAL IS 0.25 FEET.
 = GW FLOW
 = MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
TITLE: FIGURE 4-3J GROUNDWATER CONTOUR MAP (Jun 99) CW-2 LIME PIT SITE FORT MONMOUTH, NEW JERSEY				
DRAWN BY: JM		DATE DRAWN: 04 MAR 02		
CHECKED BY:		DATE CHECKED: 04 MAR 02		
APPROVED BY:		DATE APPROVED:		
 201 GIBRALTAR ROAD, SUITE 100 ROSELAND, NJ 07068 TEL: 907-0585		DRAWING No.: CW2		
		FILE No.: CW2 FIG. 4-3J		
		SCALE: 1" = 10'		
SHEET		OF	REV.	A



ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:
CONTOUR INTERVAL IS 0.25 FEET.
 = GW FLOW
 = MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
FIGURE 4-31
GROUNDWATER CONTOUR MAP (Nov 99)
CW-2 LIME PIT SITE
FORT MONMOUTH, NEW JERSEY

DRAWN BY: JM	DATE DRAWN: 04 MAR 02
CHECKED BY:	DATE CHECKED: 04 MAR 02
APPROVED BY:	DATE APPROVED:
 201 GIBRALTAR ROAD, SUITE 100 HORSINGEORGE, PA 19044 (610) 957-0585	DRAWING No.: CW2 FILE No.: CW2 FIG. 4-31 SCALE: 1" = 10' SHEET OF REV. A

CW2-MW31

CW2-MW32

CW2-MW30

CW2-MW33

44

43

ROAD PAVED		WOODED AREA	
ROAD/TRAILS UNPAVED		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

CONTOUR INTERVAL IS 0.25 FEET.

= GW FLOW

= MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
 FIGURE 4-3m
 GROUNDWATER CONTOUR MAP (Feb 00)
 CW-2 LIME PIT SITE
 FORT MONMOUTH, NEW JERSEY

DRAWN BY: JM DATE DRAWN: 04 MAR 02

CHECKED BY: DATE CHECKED: 04 MAR 02

APPROVED BY: DATE APPROVED:


DRAWING No.: CW2

FILE No.: CW2 FIG. 4-3m

SCALE: 1" = 10'

SHEET OF REV. A

Versar inc.
 201 GIBRALTAR ROAD, SUITE 100
 HORSINGHAM, PA 19044
 (610) 957-0585



ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

CONTOUR INTERVAL IS 0.25 FEET.



= GW FLOW




= MONITORING WELL LOCATION


REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
FIGURE 4-3n
GROUNDWATER CONTOUR MAP (May 00)
CW-2 LIME PIT SITE
FORT MONMOUTH, NEW JERSEY

DRAWN BY: JM	DATE DRAWN: 04 MAR 02
CHECKED BY:	DATE CHECKED: 04 MAR 02
APPROVED BY:	DATE APPROVED:
DRAWING No.: CW2	
FILE No.: CW2 FIG. 4-3n	
SCALE: 1" = 10'	
SHEET OF	REV. A

Versar inc.
201 GIBB LANE ROAD, SUITE 100
HORSINGEORGE, PA 19044
TEL: 957-0585





ROAD PAVED		WOODED AREA	
ROAD/TRAILS UNPAVED		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:
CONTOUR INTERVAL IS 0.25 FEET.
 = GW FLOW
 = MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
FIGURE 4-3p
GROUNDWATER CONTOUR MAP (Oct 00)
CW-2 LIME PIT SITE
FORT MONMOUTH, NEW JERSEY

DRAWN BY: JM	DATE DRAWN: 04 MAR 02
CHECKED BY:	DATE CHECKED: 04 MAR 02
APPROVED BY:	DATE APPROVED:
 201 GIBRALTAR ROAD, SUITE 100 ROCKY HILL, CT 06067 TEL: 957-0585	DRAWING No.: CW2 FILE No.: CW2 FIG. 4-3p SCALE: 1" = 10' SHEET OF REV. A

CW2-MW31



CW2-MW32




CW2-MW30



CW2-MW33



MH



44

43

ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

CONTOUR INTERVAL IS 0.25 FEET.

= GW FLOW

= MONITORING WELL LOCATION

REV.	REVISION	APPROVED	DATE	DRAWN BY
TITLE: FIGURE 4-3q GROUNDWATER CONTOUR MAP (Oct 12-00) CW-2 LIME PIT SITE FORT MONMOUTH, NEW JERSEY				
DRAWN BY: JM		DATE DRAWN: 04 MAR 02		
CHECKED BY:		DATE CHECKED: 04 MAR 02		
APPROVED BY:		DATE APPROVED:		
 201 GIBRALTAR ROAD, SUITE 100 HORSINGHAM, PA 19044 (610) 957-0585		DRAWING No.: CW2		
		FILE No.: CW2 FIG. 4-3q		
		SCALE: 1" = 10'		
SHEET		OF		REV. A

CW2-MW31

CW2-MW32

CW2-MW30

CW2-MW33

MH

MH

44

43

42

ROAD (PAVED)		WOODED AREA	
ROAD/TRAILS (UNPAVED)		TREE/BUSH	
FENCE		LIGHT POLE	
BUILDING		UTILITY POLE	
APPROXIMATE BOUNDARY		BROOK/CREEK	
BASE BOUNDARY		MARSHY AREA	

NOTES:

CONTOUR INTERVAL IS 0.25 FEET.

= GW FLOW

= MONITORING WELL LOCATION

REV.	REVISIONS	APPROVED	DATE	DRAWN BY
------	-----------	----------	------	----------

TITLE:
FIGURE 4-3r
GROUNDWATER CONTOUR MAP (Jan 01)
CW-2 LIME PIT SITE
FORT MONMOUTH, NEW JERSEY

DRAWN BY: JM DATE DRAWN: 04 MAR 02

CHECKED BY: DATE CHECKED: 04 MAR 02

APPROVED BY: DATE APPROVED:

DRAWING No.: CW2

FILE No.: CW2 FIG. 4-3r

SCALE: 1" = 10'

SHEET OF REV. A

Versar inc.
201 GIBRALTAR ROAD, SUITE 100
ROSELAND, NJ 07068
TEL: 907-0585

APPENDICES

Appendix A

CW-2 Lime Pit Site Investigation Report, Roy F. Weston, Inc., 1995

4.3.3 Wastewater Treatment Lime Pit 2 (CW-2)

4.3.3.1 Site Location

Wastewater Treatment Lime Pit 2 (CW-2) is located southeast of the Hexagon Building (Building 2700) at Charles Wood near an electrical substation (Figure 4.3-3). The approximate area of site CW-2 is 1,751 ft² (0.04 acre).

4.3.3.2 Site History

Like Lime Pit 1, Lime Pit 2 (CW-2) was built concurrently with the Hexagon Building; construction was completed in 1952. Liquid wastes from the east and south wings of the Hexagon Building passed through this pit before being discharged to the sanitary sewer. Additional details, including the estimated quantities of wastes discharged through the lime pits, pit construction, and cleanout and replacement of the limestone, were discussed in Subsection 4.3.2.2.

Unlike Lime Pit 1, during cleanout this pit was found to have received sewage. A dye test was conducted and revealed that toilets from the guard shack and a bathroom for the handicapped near the east entrance were mistakenly connected to this pit. The plumbing has been rerouted to discharge the wastewater from the toilets directly to the sanitary sewer.

In October 1992, the pit was cleaned out, inspected, and the limestone chips replaced. A vacuum truck was used to remove the sludge and stones from the pit, after which the pit was rinsed with water. All sludge, stones, and rinse water were placed in drums and disposed of as a hazardous waste. At present, laboratory wastes are managed under the installation hazardous waste program, which forbids the discharge of these wastes to the sewer.

4.3.3.3 Sampling Effort

As in the case of Lime Pit 1, the elevated concentrations of HHCs in sludge, rinse, and grab samples suggest the possibility that solvents were discharged into the lime pits and that they may

have migrated from the lime pits into surrounding soils and possibly into groundwater. To investigate this potential, a monitor well was constructed on each side of the lime pit (MW-30 through MW-33, shown in Figure 4.3-3). Continuous split-spoon samples were screened with an HNu or OVM. According to the CDAP, if any VOCs were detected, soil samples were to be collected from 7- to 9-ft bgs (near the base of the neutralization pit), from the interval with the highest instrument readings, and from just above the water table; otherwise, one sample was to be collected from the 7- to 9-ft interval of each boring. Because no elevated OVM readings were recorded during borehole activities, one sample from the 7- to 9-ft bgs interval was collected for the required parameters. Soil samples were analyzed for TCL +30 parameters and TAL metals. Two rounds of groundwater samples were collected from each well and analyzed for TCL +30 parameters and TAL metals.

4.3.3.4 Hydrogeologic Interpretation

Lithologic logs from site monitor wells MW-30 and MW-31 indicate that the lithology consists of a thin soil cover (0.3 ft) underlain by fill material and reworked natural sediments. The components of the manmade materials consisted of quartz gravel and concrete, wood fragments, and pieces of old electrical conduit. The reworked natural sediments consisted of an interbedded green-gray silty fine-grained sand and green-gray fine-grained sandy silt. Lithologic logs from MW-32 and MW-33 indicate that the lithology consists of a thin soil cover (0.3 ft) underlain by shallow fill material and probable natural sediments. The filled material consisted of concrete fragments (to 2 ft bgs). The probable natural sediments consisted of an interbedded olive-gray moderately sorted silty fine-grained sand and a green moderately sorted very micaceous fine-grained sandy silt.

Groundwater saturation was observed between 1 and 8 ft bgs. The four monitor wells were screened across the water table and total depths ranged from 15 to 16 ft bgs. Water-level elevation data, measured on 6 March 1995, prior to the March 1995 sampling round, indicate that local groundwater flow is eastward (Figure 4.3-4). Based on groundwater elevation measurements, monitor wells MW-32 and MW-33 are downgradient of the former lime pit.

4.3.3.5 Soil Sampling Results

Four soil samples, one in each monitor well borehole, were collected and analyzed for the parameters listed in Table 3.6-1. Samples were collected between 7 and 9 ft bgs. The compounds detected in site soils, with the corresponding sample identifications, are listed in Appendix D. Table 4.3-5 compares site soil quality with the NJDEP SCC, and then compares the results with the subsequent site-specific and Monmouth County maximum background levels, where appropriate.

VOCs

Two VOCs (methylene chloride and 2-butanone) were detected in concentrations above laboratory quantitation limits. Methylene chloride and 2-butanone are common laboratory contaminants. Both compounds were detected in concentrations well below the NJDEP SCC.

SVOCs

Eight SVOCs were detected above laboratory quantitation limits in soil borings, but in concentrations below the NJDEP SCC. All SVOCs detected below quantitation limits were found in concentrations below the NJDEP SCC where established.

Pesticides/PCBs

Three pesticides (4,4'-DDE, 4,4'-DDD, and 4,4'-DDT) were detected in concentrations above laboratory quantitation limits, but were well below the NJDEP SCC.

One PCB (Aroclor-1254) in SB-30 was detected slightly above the laboratory quantitation limit as well as the NJDEP SCC (Figure 4.3-5). However, the PCB compound was not detected in groundwater samples from the corresponding well location, MW-30. PCBs were not detected in SB-31, SB-32, and SB-33.

Table 4.3-5
Fort Monmouth - Charles Wood
Summary of Detected Compounds
in Soils from Site CW-2

COMPOUND	METHOD DETECTION LIMIT	RESIDENTIAL DIRECT CONTACT SOIL CLEANUP CRITERIA	MAXIMUM BACKGROUND CONCENTRATION	ANALYTICAL RESULTS			
				SB30-A02 12/16/94 (7-9 ft bgs)	SB31-A02 12/16/94 (7-9 ft bgs)	SB32-A02 12/16/94 (7-9 ft bgs)	SB33-A02 12/16/94 (7-9 ft bgs)
	(mg/kg)	(mg/kg)	(mg/kg)				
VOC's (mg/kg)							
Methylene Chloride	0.0027	49	ND	0.088	0.086	0.017	ND
2-Butanone	0.0041	1000	ND	ND	0.012 J	0.008 J	ND
SVOC's (mg/kg)							
Napthalene	0.277	230	ND	0.15 J	ND	ND	ND
2-Methylnaphthalene	0.287	NLE	ND	0.1 J	ND	ND	ND
Acenaphthene	0.221	3400	ND	0.17 J	ND	ND	ND
Dibenzofuran	0.215	NLE	ND	0.093 J	ND	ND	ND
Fluorene	0.208	2300	ND	0.21 J	ND	ND	ND
Phenanthrene	0.165	NLE	ND	1.3	ND	ND	0.075 J
Anthracene	0.152	10000	ND	0.33 J	ND	ND	ND
Carbazole	0.145	NLE	ND	0.18 J	ND	ND	ND
Fluoranthene	0.198	2300	0.042 J	1.5	ND	ND	0.073 J
Pyrene	0.178	1700	0.048 J	1.1	ND	ND	0.067 J
Benzo(a)anthracene	0.162	0.9	0.046 J	0.69	ND	ND	ND
Chrysene	0.145	9	0.083 J	0.71	ND	ND	0.043 J
bis(2-Ethylhexyl)phthalate	0.32	49	0.170 J	0.16 J	0.1 J	0.059 J	ND
Benzo(b)fluoranthene	0.188	0.9	0.078 J	0.79	ND	ND	ND
Benzo(k)fluoranthene	0.205	0.9	0.041 J	0.28 J	ND	ND	ND
Benzo(a)pyrene	0.162	0.66	0.047 J	0.62	0.13 J	0.053 J	0.094 J
Indeno(1,2,3-cd)pyrene	0.234	0.9	ND	0.37 J	ND	ND	ND
Benzo(g,h,i)perylene	0.224	NLE	0.042 J	0.35 J	ND	ND	ND
Dibenzo(a,h)anthracene	0.198	0.66	ND	0.089 J	ND	ND	ND
PESTICIDES (mg/kg)							
Aroclor-1254	0.039	0.49	ND	0.75 D	ND	ND	ND
4,4'-DDE	0.0037	2	0.071	0.0035 JP	0.0035 J	ND	0.0083 P
4,4'-DDD	0.0037	3	ND	0.012 P	0.0098	0.0073	0.26
4,4'-DDT	0.0037	2	0.053	0.062 P	0.0058	ND	0.046
METALS TOTAL (mg/kg)							
Aluminum	3.9	NLE	15700	6450	5430	2920	7310
Arsenic	0.35	20	31.6	5.7	8.5	2.6	15.7
Barium	0.17	700	26	36.2	58.6	23.6	326
Beryllium	0.1	1	1.7	0.58	0.51	0.28	1.5
Calcium	2.2	NLE	653	655	976	502	1270
Cadmium	0.86	1	ND	ND	ND	ND	0.9
Cobalt	0.71	NLE	4.5	0.95	4.2	0.91	5.9
Chromium	1.6	500	128	69.9	48.6	32.2	56.5
Copper	2.2	600	7.27 ¹	2.7	2.9	2.7	5.5
Iron	0.58	NLE	45500	20400	19200	11100	17600
Lead	0.4	400 ²	15.1 ¹	8.1	7.5	3.1	5.6
Magnesium	9.6	NLE	3960	1720	1270	776	1880
Manganese	0.18	NLE	120 ¹	25.1	24.8	12.5	35.1
Nickel	1.4	250	8.3	4.9	11.2	2.6	23.2
Potassium	(12.3-25.8)	NLE	10600	4210	2610	1980	3350
Selenium	0.3	63	0.85	0.29	0.7	0.2	4.2
Vanadium	0.53	370	59.6	36.6	29.1	19.4	23.6
Zinc	0.41	1500	55.6	27.8	44.2	19.3	63.9

Compounds exceeding NJDEP soil cleanup criteria are noted by bold numbers.

J- Indicates that the concentration value was estimated due to detection at or near the quantification limit

P- The percent difference between the results from two GC columns is greater than 25% the lower of the two values is reported

ND - Indicates that the compound was not detected at or below the quantification limits

NLE- No Level Established

ft bgs. - feet below ground surface.

Note: MDL's for metal analysis is actually the highest detection limit with potassium given as a range due to high variability.

¹ Monmouth County maximum background concentrations.

² NJDEP criteria are referenced in Site Remediation News, Winter 1995.

D - Surrogate or matrix spike recoveries were not obtained because the extract was diluted for analysis.

Metals

As indicated in Table 4.3-5, of the 18 metals detected in site soil, only beryllium in SB-33 was found at a concentration slightly exceeding the NJDEP SCC. Although beryllium was detected in a concentration greater than the established Monmouth County background level, the metal was detected below the site-specific background level.

4.3.3.6 Groundwater Sampling Results

Monitor wells at site CW-2 were sampled for the analytical parameters listed in Table 3.8-1. The analytical results for groundwater samples from the individual sampling rounds are listed in Appendix D. Table 4.3-6 compares the average concentrations of the detected compounds from the February and March sampling rounds with the NJDEP GWQC, and then compares the results with the site-specific and Monmouth County maximum background levels, where appropriate.

VOCs

Tetrachloroethene was the only VOC detected in site groundwater. The compound was detected in a concentration that was below the quantitation limit but slightly exceeding the NJDEP GWQC from the March sampling round only in MW-32 (Figure 4.3-5). Tetrachloroethene was not detected in MW-32 in the February sampling round.

SVOCs

One SVOC (di-n-butyl phthalate) was detected above the laboratory quantitation limit in MW-31 from the March sampling round. Di-n-butyl phthalate was detected well below the NJDEP GWQC. SVOCs detected below the laboratory quantitation limit were also detected below the NJDEP GWQC.

Table 4.3-6
Fort Monmouth - Charles Wood
Summary of Average Concentrations of Detected
Compounds in Groundwater - Site CW-2

COMPOUND	METHOD DETECTION LIMIT (µg/L)	NJDEP GROUNDWATER QUALITY CRITERIA (µg/L)	MAXIMUM BACKGROUND CONCENTRATION (µg/L)	ANALYTICAL RESULTS (µg/L)			
				SAMPLING DATE			
				MW30 2/21/95, 3/14/95 (avg.)	MW31 2/21/95, 3/14/95 (avg.)	MW32 2/21/95, 3/14/95 (avg.)	MW33 2/21/95, 3/14/95 (avg.)
VOC's (µg/L)							
Tetrachloroethene (PCE) ¹	2.7**	1*	ND	ND	ND	4J	ND
SVOC's (µg/L)							
1,2,4 Trichlorobenzene	9.6**	9	ND	ND	5J	ND	ND
bis-(2ethylhexyl)phthalate	9.7	30*	600	2J	ND	1.5 J	1.5 J
Di-n-butylphthalate	6.5	900	ND	4J	5.5	4J	4J
METALS TOTAL (µg/L)							
Aluminum	24	200	8210	129	17.65	447.5	676
Arsenic	1.9	8*	25.1	ND	ND	ND	1.5
Barium	1.7	2000	400 ¹	233.5	180.5	211	234
Calcium	10.4	NLE	8700	63600	36050	46250	51250
Cobalt	2.3	NLE	30.6	ND	ND	ND	2.9
Chromium	2.9	100	49.6	ND	ND	ND	2.15
Copper	1.9	1000	730 ¹	3.8	2.15	2	11.9
Iron	6.4	300	27000 ¹	45750	36350	48950	54450
Potassium	685	NLE	4630	9980	8710	9580	8455
Magnesium	18.3	NLE	25000 ¹	7045	4775	5595	6100
Manganese	1.8	50	480 ¹	365	222.5	268.5	273
Sodium	30.5	50000	36400	17100	10325	11800	14350
Nickel	10.8	100	48.3	10.65	ND	11.75	2.7
Lead	1.1	10*	<100 ¹	ND	ND	0.7	3.3
Vanadium	2.3	NLE	28.9	ND	ND	3.05	5.15
Zinc	3.8	5000	133	5.7	3.9	13.85	25.6

¹ Same compound as listed by NJDEP Tetrachloroethylene

Compounds exceeding NJDEP groundwater quality criteria are noted by bold numbers.

*PQL - Practical Quantitation Limit - was used as the NJDEP groundwater quality criteria

NLE - No Level Established

J - Indicates that the concentration value was estimated due to detection at or near the quantitation limits

ND - Indicates that the compound was not detected at or below the quantitation limit

** Method detection limit exceeded NJDEP groundwater quality criteria

¹ - Monmouth County maximum background concentrations.

Pesticides/PCBs

Pesticides/PCBs were not detected in the site monitor wells from either sampling round.

Metals

As indicated in Table 4.3-6, of the 16 metals detected in site groundwater, 3 metals (aluminum, iron, and manganese) were found in concentrations exceeding the NJDEP GWQC. In addition, iron was detected in concentrations greater than those determined for site-specific and Monmouth County maximum background at Charles Wood. The presence of iron in exceedence of the NJDEP GWQC may be attributable to the high concentrations of iron present in natural soil found in Monmouth County. Therefore, iron is not identified as a compounds of concern. Although manganese was detected in concentrations above the site-specific background level in MW-30, MW-32, and MW-33, manganese was found in concentrations below the Monmouth County background level. Aluminum was found in concentrations below both the site-specific and Monmouth County maximum background levels.

4.3.3.7 Recommendations

The results of the soil sampling indicate that one PCB compound (Aroclor-1254) was detected in SB-30 at a concentration slightly above the NJDEP SCC. PCB compounds were not detected in the other three soil borings. In addition, PCBs were not detected in groundwater samples in the corresponding well location, MW-30.

Groundwater sampling results indicate that PCE was detected in the groundwater in one of the four wells (MW-32) in one of the two sampling rounds at levels slightly exceeding the NJDEP GWQC.

Although NJDEP groundwater criteria were exceeded by one VOC at this site, immediate remedial action is not required. The source of contamination has been eliminated since chemicals are not being disposed of in the pit. The pit was cleaned in October 1992 and the limestone

sludge was removed and disposed of as a hazardous waste. Hazardous waste is currently collected for proper disposal off-site and waste is no longer disposed of in the pit. Shallow groundwater flows toward and discharges to the headwaters of Wampum Brook, as indicated by water-level measurements from site monitor wells. There are no known uses of groundwater at or downgradient of the site. Surface-water samples were taken in Wampum Brook in the Charles Wood area and Mill Creek (as Wampum Brook is called further to the east) for use as background samples. No VOCs were detected in these samples, therefore, there is no immediate threat to human health.

The extent of PCE concentrations in groundwater will be investigated by soil-gas survey techniques. The soil-gas survey will be performed on an established grid pattern to estimate the lateral extent of VOCs in the vicinity of the neutralization pit. The results of the soil-gas survey will be used to locate two additional monitor wells if necessary. DPW proposes that a long-term groundwater monitoring program be developed and implemented for the site. Aqueous samples would be collected and analyzed on a quarterly basis to further evaluate water quality conditions at the site. Groundwater samples would be collected from existing monitor wells and from the two newly installed monitor wells. Compounds of concern identified in the first two rounds of sampling would be targeted for the monitoring program. When the additional monitor wells are installed, soil samples will be collected for PCB analysis because of the detection of PCBs in a soil sample collected from SB-30.

currently collected for proper disposal off-site and waste is no longer disposed of in the pit. Shallow groundwater flows toward and discharges to the headwaters of Wampum Brook, as indicated by water-level measurements in site monitor wells. There are no known uses of groundwater between the acid neutralization pit and Wampum Brook. Surface-water samples were taken in Wampum Brook in the Charles Wood area and Mill Creek (as Wampum Brook is called further to the east) for use as background samples. No VOCs were detected in these samples, therefore, there is no immediate threat to human health.

The extent of VOC concentrations in groundwater will be investigated by soil-gas survey techniques. The soil-gas survey will be performed on an established grid pattern to estimate the lateral extent of VOCs in the vicinity of the neutralization pit. The results of the soil-gas survey will be used to locate two additional monitor wells, if necessary, at the downgradient edge of the plume. DPW proposes that a long-term groundwater monitoring program be developed and implemented for the site. Aqueous samples would be collected and analyzed on a quarterly basis to further evaluate water quality conditions at the site. Groundwater samples would be collected from existing monitor wells and the two newly installed monitor wells. Compounds of concern identified in the first two rounds of sampling would be targeted for the monitoring program.

6.2.2 Wastewater Treatment Lime Pit 2 (CW-2)

Investigation activities performed at site CW-2 included the following:

- Collection of soil samples from four soil borings.
- Installation and sampling of four monitor wells at each of the soil boring locations.

6.2.2.1 Conclusions

The results of the soil sampling indicate that one PCB compound (Aroclor-1254) was detected in SB-30 at a concentration slightly above the NJDEP SCC. PCB compounds were not detected

in the other three soil borings. In addition, PCBs were not detected in groundwater samples in the corresponding well location, MW-30.

Groundwater sampling results indicate that PCE was detected in the groundwater in one of the four wells (MW-32) in one of the two sampling rounds at levels slightly exceeding the NJDEP GWQC.

6.2.2.2 Recommendations

Although NJDEP groundwater criteria were exceeded by one VOC at this site, immediate remedial action is not required. The source of contamination has been eliminated since chemicals are not being disposed of in the pit. The pit was cleaned in October 1992 and the limestone sludge was removed and disposed of as a hazardous waste. Hazardous waste is currently collected for proper disposal off-site and waste is no longer disposed of in the pit. Shallow groundwater flows toward and discharges to the headwaters of Wampum Brook, as indicated by water-level measurements in site monitor wells. There are no known uses of groundwater between the acid neutralization pit and Wampum Brook. Surface-water samples were taken in Wampum Brook in the Charles Wood area and Mill Creek (as Wampum Brook is called further to the east) for use as background samples. No VOCs were detected in these samples, therefore, there is no immediate threat to human health.

The extent of PCE concentrations in groundwater will be investigated by soil-gas survey techniques. The soil-gas survey will be performed on an established grid pattern to estimate the lateral extent of VOCs in the vicinity of the neutralization pit. The results of the soil-gas survey will be used to locate two additional monitor wells if necessary. DPW proposes that a long-term groundwater monitoring program be developed and implemented for the site. Aqueous samples would be collected and analyzed on a quarterly basis to further evaluate water quality conditions at the site. Groundwater samples would be collected from existing monitor wells and from the two newly installed monitor wells. Compounds of concern identified in the first two rounds of sampling would be targeted for the monitoring program. When the additional monitor wells are

Appendix B

Boring Logs and Monitoring Well Construction Records

Borehole Location Data**Roy F. WESTON, Inc.**

BOREHOLE ID : CW2-MW30
BEGIN DATE : 12/16/94

PROJECT NAME: FT. MONMOUTH
END DATE : 12/16/94

LOGGER/COMPANY : K. VALENTI

BOREHOLE COMPLETED IN (<O>verburden edrock) :

TOTAL DEPTH : 16.00

DEPTH TO BEDROCK : 0.00

BOREHOLE DIAMETER #1: 12.00

INTERVAL: 0.00 ft. to 16.00 ft. BGS

METHOD : HSA

FLUID : WATER

BOREHOLE DIAMETER #2: 3.00

INTERVAL: 12.00 ft. to 14.00 ft. BGS

METHOD : SPS

FLUID :

BOREHOLE DIAMETER #3:

INTERVAL:

METHOD :

FLUID :

DRILLING COMPANY : J.C. ANDERSON

DRILLER : WELLS REEVE

DRILL RIG TYPE : CME-55

	ESTIMATED	SURVEYED
SURFACE ELEVATION :	0.000	49.470
N. COORDINATE :	0.0000	
E. COORDINATE :	0.0000	
WELL PERMIT.....(Y)es (N)o: N	PERMIT # : NJ 29 32594	
HOLE ABANDONED... (Y)es (N)o: N		
WELL INSTALLED... (Y)es (N)o: Y		
WELL CLUSTER.....(Y)es (N)o: N	No. OF WELLS : 0	
WELL NEST.....(Y)es (N)o: N	No. OF WELLS : 0	
PUMPS INSTALLED.. (Y)es (N)o: N	TYPE	DEPTH
	PURGE :	0.00
	SAMPLE :	0.00

BOREHOLE TESTING

BOREHOLE GEOPHYSICS..... (Y)es (N)o: N

SLUG TESTS..... (Y)es (N)o: N

PACKER TESTS..... (Y)es (N)o: N

PUMPING TESTS..... (Y)es (N)o: N

COMMENTS :

1st location moved after collecting one spoon with no rec.

Latitude-North: 40 deg 17' 43.3"

Longitude-West: 74 deg 05' 10.4"

Well Completion Summary

Roy F. WESTON, Inc.

CLIENT FT. MONMOUTH
SITE NAME CHARLES WOOD AREA

DRILLING FIRM J.C. ANDERSON
INSPECTOR K. VALENTI

WELL ID CW2-MW30
START DATE 12/16/94
COMPLETION DATE 12/16/94

WATER LEVELS

		DEPTH		ELEV.	DRILLING SUMMARY	
Protective Casing 4.00 inch	2.24	TC	51.71	Driller	WELLS REEVE	
	0.00	GS	49.47	Drilling Fluid	WATER	
				Well Type	SINGLE CASSED SCREENED	
	WELL DESIGN CONSTRUCTION					
				Casing #1 Diameter: 4.00 inch	Interval: 0.00 to 6.00 ft.	
				Type : PVC SCH 40		
				Stick Up Inner Casing: 2.24 ft.	Protective Casing: 2.68 ft.	
				Casing Grout: PORTLAND CEMENT	Interval: 0.00 to 2.00 ft.	
				Seal Type: BENTONITE	Interval: 2.00 to 4.00 ft.	
				Sand Pack Type : #1 MORIE	Interval: 4.00 to 16.00 ft.	
				Grain Size : UNIFORM	Median Diameter:	
				Screen Diameter: 4.00	Interval: 6.00 to 15.54 ft.	
				Type : PVC	Slots: 0.010 inches	
	2.00	BN	47.47	Silt Trap Interval: 15.54 to 16.00 ft.		
	4.00	SP	45.47	Backfill Type : Interval: 0.00 to 0.00 ft.		
					WELL DEVELOPMENT	
	6.00	SC	43.47	Date	01/08/95	
				Method	Bailing/surge blocking	
				Yield	1 gpm	
				Purged Volume	68 gal	
COMMENTS						
	15.54	BS	33.93	TC = Top of Casing	SP = Top Sand Pack	
				GS = Ground Surface	SC = Top Screen	
				BN = Top Seal	BS = Bottom Screen	
	16.00	TD	33.47	TD = Total Depth		
= Grout = Seal = Sand Pack = Formation Additional Comments:						

NOTE: Well Diagram not to Scale

Elevations are feet above mean sea level

Borehole Log

Roy F. WESTON, Inc.

PROJECT :	FT. MONMOUTH	TOTAL DEPTH :	16.00
SITE NAME :	CHARLES WOOD AREA	LOGGER :	K. VALENTI
BORING ID :	CW2-MW30	DRILLING COMPANY :	J.C. ANDERSON
NORTHING :	0.0000 estimated	DRILLING RIG :	CME-55
EASTING :	0.0000 estimated	DATE STARTED :	12/16/94
ELEVATION :	49.470 surveyed	DATE COMPLETED :	12/16/94

ELEVATION	DEPTH	MATERIAL	% RECOVERY	CLASSIFICATION	COLOR	STRENGTH	MOISTURE	BLOW COUNT	FIELD INSTRUMENT READING	COMMENTS
			65	Silty sand, SM	BROWN	LSE	MST	10 11 10 12	HNU 2.0	Top 3" bgs = topsoil. Some organics-roots. 1st hole abandoned with HNU=10.0.
48	1			Poorly graded sand with silt, SP-SM	LT BROWN	LSE	MST		HNU 0.0	Lt brown sand (little silt, mottles noted.)
				No Sample Recovered						
47	2		65	Silty sand, SM	DK GRAY TO BRN	LSE	WET	8 9 13 11	HNU 20.0	Noted mottling with iron (Fe) staining.
46	3			Silty sand, SM	DK GRAY	SFT	WET		HNU 20.0	Fine silt (some) finer sands. SPS is wet.
				No Sample Recovered						
45	4		75	Silty sand, SM	GRAY BROWN	SFT	WET	15 17 11 7	HNU 7.0	Gray mottles noted.
				Sandy elastic silt, MH	GREENISH GRAY	SFT	WET		HNU 0.0	6" piece of wood noted at bottom of spoon/
44	5			No Sample Recovered						
43	6		20	Sandy elastic silt, MH	GRAYISH GREEN	SFT	WET	5 6 5 4	HNU 3.0	Same as above interval. Wood pieces.
				No Sample Recovered						
42	7									
41	8		50	Sandy silt, ML	GREENISH GRAY	SFT	WET	5 4 4 3	HNU 150.0	3" SPS used. Same lith. as noted in previous interval. Sampled W2-SB30
40	9			No Sample Recovered						
39	10		80	Silty sand, SM	GREENISH GRAY	LSE	WET		HNU 0.0	3" SPS used. Fine sands little silt.

Borehole Log

Roy F. WESTON, Inc.

PROJECT : FT. MONMOUTH
 SITE NAME : CHARLES WOOD AREA
 BORING ID : CW2-MW30
 NORTHING : 0.0000 estimated
 EASTING : 0.0000 estimated
 ELEVATION : 49.470 surveyed

TOTAL DEPTH : 16.00
 LOGGER : K. VALENTI
 DRILLING COMPANY : J.C. ANDERSON
 DRILLING RIG : CME-55
 DATE STARTED : 12/16/94
 DATE COMPLETED : 12/16/94

ELEVATION	DEPTH	MATERIAL	% RECOVERY	CLASSIFICATION	COLOR	STRENGTH	MOISTURE	BLOW COUNT	FIELD INSTRUMENT READING	COMMENTS
38	11			Silty sand, SM	GREENISH GRAY	LSE	WET		HNU 0.0	3" SPS used. Fine sands little silt.
				No Sample Recovered						
37	12		100	Silty sand, SM	GREENISH GRAY	SFT	WET	4	HNU 0.0	Mostly quartz sand.
36	13									
35	14		50	Well-graded sand, SW	GREENISH GRAY	LSE	MST	3	HNU 0.0	Some white quartz stones.
				Elastic silt, MH	DK GRAY BLACK	FRM	MST	3	HNU 0.0	Set well at 16' bgs. ID of borehole 16' bgs.
34	15			No Sample Recovered						
33	16									
32	17									
31	18									
30	19									
29	20									

BOREHOLE /WELL ID	SMP NUM	LTH NUM	LITHOLOGY INT. (FT BGS)	SAMPLING METHOD	SIZE GRAVEL	GRAVEL PCT.	SIZE SAND	SAND PCT	SILT PCT	CLAY PCT	ORGANIC PCT	ROCK TYPE	PLAST	SORT	STRENGTH	MOISTURE	STRAT UNIT
CW2-MW30	1	1	0.00	0.80	SPS		1	60	35	0	4		NON	MOD	LSE	MST	
CW2-MW30	1	2	0.80	1.30	SPS		0	90	10	0	0		NON	MOD	LSE	MST	
CW2-MW30	1	3	1.30	2.00	SPS		0	0	0	0	0						
CW2-MW30	2	1	2.00	2.80	SPS		1	55	39	5	0		LOW	MOD	LSE	WET	
CW2-MW30	2	2	2.80	3.30	SPS		0	70	30	0	0		LOW	WEL	SFT	WET	
CW2-MW30	2	3	3.30	4.00	SPS		0	0	0	0	0						
CW2-MW30	3	1	4.00	4.50	SPS		0	65	35	0	0		LOW	POR	SFT	WET	
CW2-MW30	3	2	4.50	5.50	SPS		0	35	60	5	0		MOD	MOD	SFT	WET	
CW2-MW30	3	3	5.50	6.00	SPS		0	0	0	0	0						
CW2-MW30	4	1	6.00	6.40	SPS		0	40	60	0	0		MOD	WEL	SFT	WET	
CW2-MW30	4	2	6.40	8.00	SPS		0	0	0	0	0						
CW2-MW30	5	1	8.00	9.00	SPS		0	40	60	0	0		LOW	MOD	SFT	WET	
CW2-MW30	5	2	9.00	10.00	SPS		0	0	0	0	0						
CW2-MW30	6	1	10.00	11.60	SPS		0	F 85	15	0	0		LOW	WEL	LSE	WET	
CW2-MW30	6	2	11.60	12.00	SPS		0	0	0	0	0						
CW2-MW30	7	1	12.00	14.00	SPS		5	80	15	0	0		NON	MOD	SFT	WET	
CW2-MW30	8	1	14.00	14.30	SPS		10	80	5	0	0		NON	POR	LSE	MST	
CW2-MW30	8	2	14.30	15.00	SPS		0	0	90	10	0		MOD	WEL	FRM	MST	
CW2-MW30	8	3	15.00	16.00	SPS		0	0	0	0	0						

Borehole Location Data**Roy F. WESTON, Inc.**

BOREHOLE ID : CW2-MW31

PROJECT NAME: FT. MONMOUTH

BEGIN DATE : 12/16/94

END DATE : 12/16/94

LOGGER/COMPANY : K. VALENTI

BOREHOLE COMPLETED IN (<O>verburden edrock) : 0

TOTAL DEPTH : 16.00

DEPTH TO BEDROCK : 0.00

BOREHOLE DIAMETER #1: 12.00

INTERVAL: 0.00 ft. to 16.00 ft. BGS

METHOD : HSA

FLUID : WATER

BOREHOLE DIAMETER #2:

INTERVAL:

METHOD :

FLUID :

BOREHOLE DIAMETER #3:

INTERVAL:

METHOD :

FLUID :

DRILLING COMPANY : J.C. ANDERSON

DRILLER : STEVE BURGER

DRILL RIG TYPE : MOBILE B-57

	ESTIMATED	SURVEYED
SURFACE ELEVATION :	0.000	49.670
N. COORDINATE :	0.0000	
E. COORDINATE :	0.0000	
WELL PERMIT.....(Y)es (N)o: N	PERMIT # : NJ 29 32595	
HOLE ABANDONED... (Y)es (N)o: N		
WELL INSTALLED... (Y)es (N)o: Y		
WELL CLUSTER.....(Y)es (N)o: N	No. OF WELLS : 0	
WELL NEST.....(Y)es (N)o: N	No. OF WELLS : 0	
PUMPS INSTALLED.. (Y)es (N)o: N	TYPE	DEPTH
	PURGE :	0.00
	SAMPLE :	0.00

BOREHOLE TESTING

BOREHOLE GEOPHYSICS.....(Y)es (N)o: N

SLUG TESTS.....(Y)es (N)o: N

PACKER TESTS.....(Y)es (N)o: N

PUMPING TESTS.....(Y)es (N)o: N

COMMENTS :

SPS/augered to 8' bgs. Severed wire (subsurface) @approx. 2'
bgs. Abandoned location. Moved location 1'. Latitude-North:
40 deg 17' 43.6"/Longitude-West: 74 deg 05' 10.5"

Well Completion Summary

Roy F. WESTON, Inc.

CLIENT FT. MONMOUTH
SITE NAME CHARLES WOOD AREA

DRILLING FIRM J.C. ANDERSON
INSPECTOR K. VALENTI

WELL ID CW2-MW31
START DATE 12/16/94
COMPLETION DATE 12/16/94

WATER LEVELS

		DEPTH		ELEV.	DRILLING SUMMARY	
Protective Casing 4.00 inch		1.91	TC	51.58	Driller	STEVE BURGER
		0.00	GS	49.67	Drilling Fluid	WATER
					Well Type	SINGLE CASSED SCREENED
	WELL DESIGN CONSTRUCTION					
	Casing #1 Diameter: 4.00 inch Interval: 0.00 to 5.00 ft. Type : PVC SCH 40 Stick Up Inner Casing: 1.91 ft. Protective Casing: 2.51 ft. Casing Grout: PORTLAND CEMENT Interval: 0.00 to 1.00 ft. Seal Type: BENTONITE Interval: 1.00 to 3.00 ft. Sand Pack Type : #1 MORIE Interval: 3.00 to 16.00 ft. Grain Size : UNIFORM Median Diameter: Screen Diameter: 4.00 Interval: 5.00 to 14.54 ft. Type : PVC Slots: 0.010 inches Silt Trap Interval: 14.45 to 15.00 ft. Backfill Type : Interval: 0.00 to 0.00 ft.					
		1.00	BN	48.67	WELL DEVELOPMENT Date 01/05/95 Method Bailing Yield <1 gpm Purged Volume 25 gal	
		3.00	SP	46.67		
		5.00	SC	44.67		
		14.54	BS	35.13	COMMENTS TC = Top of Casing SP = Top Sand Pack = Grout GS = Ground Surface SC = Top Screen = Seal BN = Top Seal BS = Bottom Screen = Sand Pack TD = Total Depth = Formation	
		15.00	TD	34.67		
Additional Comments:						

NOTE: Well Diagram not to Scale

Elevations are feet above mean sea level

Borehole Log

Roy F. WESTON, Inc.

PROJECT : FT. MONMOUTH
SITE NAME : CHARLES WOOD AREA
BORING ID : CW2-MW31
NORTHING : 0.0000 estimated
EASTING : 0.0000 estimated
ELEVATION : 49.670 surveyed

TOTAL DEPTH : 16.00
LOGGER : K. VALENTI
DRILLING COMPANY : J.C. ANDERSON
DRILLING RIG : MOBILE B-57
DATE STARTED : 12/16/94
DATE COMPLETED : 12/16/94

ELEVATION	DEPTH	MATERIAL	% RECOVERY	CLASSIFICATION	COLOR	STRENGTH	MOISTURE	BLOW COUNT	FIELD INSTRUMENT READING	COMMENTS
48	1		100	Silty sand, SM	BROWN	LSE	MST	5 6 7	HNU 3.0	Fill. Top 3" organics/topsoil. Brown little silt, mostly sand.
47	2		75	Silty sand, SM	BROWN	SFT	MST	10 10 10 11	HNU 1.0	Fill. Same lithology as previous interval. Some orange iron (Fe) staining noted throughout spoon.
46	3			Silty sand, SM	GRAY	FRM	MST	5 6 6 7	HNU 1.0	Fill. More silt than above interval. Firm but able to crush between fingers.
45	4		50	Sandy elastic silt, MH	DK GRAY	FRM	MST	7 8 5	HNU 0.0	Fill. Same as previous interval. More silt/clay texture. Water present at 5' bgs.
44	5			No Sample Recovered						
43	6		75	Sandy elastic silt, MH	DK GRAY	SFT	WET	4 4 7 9	HNU 2.0	Same lithology as previous interval.
42	7			Silty sand, SM	GRAYISH GREEN	SFT	WET		HNU 2.0	Uncertain. Mostly fine sands. Sample CW2-SB31 collected. Wine at depth noted by auger cuttings.
41	8		60	Silty sand, SM	GRAYISH GREEN	SFT	SAT	2 2 6	HNU 0.0	Same lithology previous interval. Sample CW2-SB31 collected.
40	9			No Sample Recovered						
39	10		75	Silty sand, SM	GRAY GREEN	SFT	SAT	2 2 4 3	HNU 0.0	Uncertain.

Borehole Log

Roy F. WESTON, Inc.

PROJECT : FT. MONMOUTH
 SITE NAME : CHARLES WOOD AREA
 BORING ID : CW2-MW31
 NORTHING : 0.0000 estimated
 EASTING : 0.0000 estimated
 ELEVATION : 49.670 surveyed

TOTAL DEPTH : 16.00
 LOGGER : K. VALENTI
 DRILLING COMPANY : J.C. ANDERSON
 DRILLING RIG : MOBILE B-57
 DATE STARTED : 12/16/94
 DATE COMPLETED : 12/16/94

ELEVATION	DEPTH	MATERIAL	% RECOVERY	CLASSIFICATION	COLOR	STRENGTH	MOISTURE	BLOW COUNT	FIELD INSTRUMENT READING	COMMENTS
38	11			Silty sand, SM	GRAY GREEN	SFT	SAT		HNU 0.0	Uncertain.
				No Sample Recovered						
37	12		75	Poorly graded sand with silt, SP-SM	DK GREEN GRAY	LSE	SAT	2	HNU 0.0	Mostly sand with little silt.
								6		
36	13			Elastic silt, MH	DK GRAY	FRM	MST		HNU 0.0	
				No Sample Recovered						
35	14		50	Elastic silt, MH	DK GRAY	FRM	MST	5	HNU 0.0	Same lithology as previous interval.
								10		
34	15			No Sample Recovered				7		
33	16									
32	17									
31	18									
30	19									
29	20									

BOREHOLE	SMP	LTH	LITHOLOGY INT.	SAMPLING	SIZE	GRAVEL	SIZE	SAND	SILT	CLAY	ORGANIC	ROCK	STRAT			
/WELL ID	NUM	NUM	(FT BGS)	METHOD	GRAVEL	PCT.	SAND	PCT	PCT	PCT	PCT	TYPE	PLAST	SORT	STRENGTH	MOISTURE UNIT
CW2-MW31	1	1	0.00	2.00	SPS		0		80	20	0	0	LOW	MOD	LSE	MST
CW2-MW31	2	1	2.00	3.00	SPS		0		85	15	0	0	LOW	MOD	SFT	MST
CW2-MW31	2	2	3.00	3.50	SPS		0		60	40	0	0	LOW	WEL	FRM	MST
CW2-MW31	2	3	3.50	4.00	SPS		0		0	0	0	0				
CW2-MW31	3	1	4.00	5.00	SPS		0	F	40	55	5	0	MOD	WEL	FRM	MST
CW2-MW31	3	2	5.00	6.00	SPS		0		0	0	0	0				
CW2-MW31	4	1	6.00	7.00	SPS		0		40	55	5	0	MOD	MOD	SFT	WET
CW2-MW31	4	2	7.00	7.50	SPS		0	F	80	20	0	0	LOW	WEL	SFT	WET
CW2-MW31	4	3	7.50	8.00	SPS		0		0	0	0	0				
CW2-MW31	5	1	8.00	9.20	SPS		0		80	20	0	0	LOW	WEL	SFT	SAT
CW2-MW31	5	2	9.20	10.00	SPS		0		0	0	0	0				
CW2-MW31	6	1	10.00	11.50	SPS		0		80	20	0	0	LOW	WEL	SFT	SAT
CW2-MW31	6	2	11.50	12.00	SPS		0		0	0	0	0				
CW2-MW31	7	1	12.00	13.00	SPS		0		90	10	0	0	NON	WEL	LSE	SAT
CW2-MW31	7	2	13.00	13.50	SPS		0		0	80	20	0	MOD	WEL	FRM	MST
CW2-MW31	7	3	13.50	14.00	SPS		0		0	0	0	0				
CW2-MW31	8	1	14.00	15.00	SPS		0		0	80	20	0	MOD	WEL	FRM	MST
CW2-MW31	8	2	15.00	16.00	SPS		0		0	0	0	0				

Borehole Location Data**Roy F. WESTON, Inc.**

BOREHOLE ID : CW2-MW32
BEGIN DATE : 12/16/94

PROJECT NAME: FT. MONMOUTH
END DATE : 12/16/94

LOGGER/COMPANY : P. THOMAS

BOREHOLE COMPLETED IN (<O>verburden edrock) : 0

TOTAL DEPTH : 15.00

DEPTH TO BEDROCK : 0.00

BOREHOLE DIAMETER #1: 12.25

INTERVAL: 0.00 ft. to 15.00 ft. BGS

METHOD : HSA

FLUID : NONE

BOREHOLE DIAMETER #2:

INTERVAL:

METHOD :

FLUID :

BOREHOLE DIAMETER #3:

INTERVAL:

METHOD :

FLUID :

DRILLING COMPANY : J.C. ANDERSON

DRILLER : STEVE BURGER

DRILL RIG TYPE : MOBILE B-57

	ESTIMATED	SURVEYED
SURFACE ELEVATION :	0.000	49.470
N. COORDINATE :	0.0000	
E. COORDINATE :	0.0000	
WELL PERMIT.....(Y)es (N)o: N	PERMIT # : NJ 29 32596	
HOLE ABANDONED... (Y)es (N)o: N		
WELL INSTALLED... (Y)es (N)o: Y		
WELL CLUSTER.....(Y)es (N)o: N	No. OF WELLS : 0	
WELL NEST.....(Y)es (N)o: N	No. OF WELLS : 0	
PUMPS INSTALLED..(Y)es (N)o: N	TYPE	DEPTH
	PURGE :	0.00
	SAMPLE :	0.00

BOREHOLE TESTING

BOREHOLE GEOPHYSICS.....(Y)es (N)o: N

SLUG TESTS.....(Y)es (N)o: N

PACKER TESTS.....(Y)es (N)o: N

PUMPING TESTS.....(Y)es (N)o: N

COMMENTS :

Latitude North: 40 deg 17' 43.6"

Longitude West: 74 deg 05' 10.3"

Well Completion Summary

Roy F. WESTON, Inc.

CLIENT FT. MONMOUTH
SITE NAME CHARLES WOOD AREA

DRILLING FIRM J.C. ANDERSON
INSPECTOR P. THOMAS

WELL ID CW2-MW32
START DATE 12/16/94
COMPLETION DATE 12/16/94

WATER LEVELS

		DEPTH		ELEV.	DRILLING SUMMARY	
Protective Casing 4.00 inch		1.91	TC	51.38	Driller	STEVE BURGER
		0.00	GS	49.47	Drilling Fluid	NONE
					Well Type	SINGLE CASSED SCREENED
	WELL DESIGN CONSTRUCTION					
					Casing #1 Diameter: 4.00 inch Type : PVC SCH 40	Interval: 0.00 to 5.00 ft.
				Stick Up Inner Casing: 1.91 ft.	Protective Casing: 2.61 ft.	
				Casing Grout: CEMENT/BENT	Interval: 0.00 to 0.80 ft.	
				Seal Type: BENTONITE SLURRY	Interval: 0.80 to 3.00 ft.	
				Sand Pack Type : NO. 1 MORIE Grain Size : UNIFORM	Interval: 3.00 to 5.00 ft.	
				Screen Diameter: 4.00 Type : PVC	Median Diameter: Interval: 5.00 to 14.54 ft. Slots: 0.010 inches	
		0.80	BN	48.67	Silt Trap Interval: 14.54 to 15.00 ft.	
		3.00	SP	46.47	Backfill Type : Interval: 0.00 to 0.00 ft.	
		5.00	SC	44.47	WELL DEVELOPMENT	
					Date	01/05/95
					Method	Bailing/surge blocking
					Yield	1 gpm
					Purged Volume	46 gal
		14.54	BS	34.93	COMMENTS	
					TC = Top of Casing	SP = Top Sand Pack
					GS = Ground Surface	SC = Top Screen
					BN = Top Seal	BS = Bottom Screen
					TD = Total Depth	
		15.00	TD	34.47		
Additional Comments: Depths measured below ground surface.						

NOTE: Well Diagram not to Scale

Elevations are feet above mean sea level

Borehole Log

Roy F. WESTON, Inc.

PROJECT : FT. MONMOUTH
 SITE NAME : CHARLES WOOD AREA
 BORING ID : CW2-MW32
 NORTHING : 0.0000 estimated
 EASTING : 0.0000 estimated
 ELEVATION : 49.470 surveyed

TOTAL DEPTH : 15.00
 LOGGER : P. THOMAS
 DRILLING COMPANY : J.C. ANDERSON
 DRILLING RIG : MOBILE B-57
 DATE STARTED : 12/16/94
 DATE COMPLETED : 12/16/94

ELEVATION	DEPTH	MATERIAL	% RECOVERY	CLASSIFICATION	COLOR	STRENGTH	MOISTURE	BLOW COUNT	FIELD INSTRUMENT READING	COMMENTS
			40	Silty sand, SM	BROWN	SFT	SAT	3 10 12	HNU 0.0	0-0.4 topsoil.
48	1			No Sample Recovered						
47	2		20	Silty sand with gravel, SM	BROWN	LSE	SAT	13 20 10 10	HNU 0.0	Note: Top 4-4.1 - gravel (concrete?)
				No Sample Recovered						
46	3									
45	4		20	Silty sand, SM	GRAY	SFT	SAT	5 5 5	HNU 0.0	
				No Sample Recovered						
44	5									
43	6		60	Silty sand, SM	BROWN/GRAY	LSE	SAT	3 3 14	HNU 0.0	
42	7			No Sample Recovered						
41	8		65	Silty sand, SM	OLIVE/GRAY	LSE	SAT	4 7 9 7	HNU 0.0	
40	9			Silty sand with gravel, SM	BROWN	LSE	SAT		HNU 0.0	
				No Sample Recovered						
39	10		75	Sandy silt, ML	GRAY	SFT	WET	5 4 5 5	HNU 0.0	v. micaceous

Borehole Log

Roy F. WESTON, Inc.

PROJECT : FT. MONMOUTH
 SITE NAME : CHARLES WOOD AREA
 BORING ID : CW2-MW32
 NORTHING : 0.0000 estimated
 EASTING : 0.0000 estimated
 ELEVATION : 49.470 surveyed

TOTAL DEPTH : 15.00
 LOGGER : P. THOMAS
 DRILLING COMPANY : J.C. ANDERSON
 DRILLING RIG : MOBILE B-57
 DATE STARTED : 12/16/94
 DATE COMPLETED : 12/16/94

ELEVATION	DEPTH	MATERIAL	% RECOVERY	CLASSIFICATION	COLOR	STRENGTH	MOISTURE	BLOW COUNT	FIELD INSTRUMENT READING	COMMENTS
38	11			Sandy silt, ML	GRAY	SFT	WET		HNU 0.0	v. micaceous
				No Sample Recovered						
37	12		60	Sandy silt, ML	GRAY	SFT	WET	3 3 6 12	HNU 0.0	
36	13			No Sample Recovered						
35	14			Interval Not Sampled						Set well at 15' bgs.
34	15									
33	16									
32	17									
31	18									
30	19									
29	20									

DATE: 06/20/95 **** Roy F. WESTON, Inc. LITHOLOGICAL DATA FOR - CLIENT ID: USAC2 *** PAGE: 14

BOREHOLE	SMP	LTH	LITHOLOGY	INT.	SAMPLING	SIZE	GRAVEL	SIZE	SAND	SILT	CLAY	ORGANIC	ROCK	STRAT			
/WELL ID	NUM	NUM	(FT BGS)		METHOD	GRAVEL	PCT.	SAND	PCT	PCT	PCT	PCT	TYPE	PLAST	SORT	STRENGTH	MOISTURE UNIT
CW2-MW32	1	1	0.00	0.80	SPS	C	10	MF	45	25	5	15		NON	POR	SFT	SAT
CW2-MW32	1	2	0.80	2.00	SPS		0		0	0	0	0					
CW2-MW32	2	1	2.00	2.40	SPS	MF	15	MF	55	25	5	0		NON	POR	LSE	SAT
CW2-MW32	2	2	2.40	4.00	SPS		0		0	0	0	0					
CW2-MW32	3	1	4.00	4.40	SPS		0	MF	60	30	10	0		LOW	MOD	SFT	SAT
CW2-MW32	3	2	4.40	6.00	SPS		0		0	0	0	0					
CW2-MW32	4	1	6.00	7.20	SPS		0	MFC	75	20	5	0		NON	MOD	LSE	SAT
CW2-MW32	4	2	7.20	8.00	SPS		0		0	0	0	0					
CW2-MW32	5	1	8.00	9.00	SPS		0	MF	75	20	5	0		NON	MOD	LSE	SAT
CW2-MW32	5	2	9.00	9.30	SPS	MCF	35	MF	50	15	0	0		NA	POR	LSE	SAT
CW2-MW32	5	3	9.30	10.00	SPS		0		0	0	0	0					
CW2-MW32	6	1	10.00	11.50	SPS		0	F	40	55	5	0		NON	MOD	SFT	WET
CW2-MW32	6	2	11.50	12.00	SPS		0		0	0	0	0					
CW2-MW32	7	1	12.00	13.20	SPS		0	F	40	55	5	0		NON	WEL	SFT	WET
CW2-MW32	7	2	13.20	14.00	SPS		0		0	0	0	0					
CW2-MW32	8	1	14.00	15.00	NS		0		0	0	0	0					

Borehole Location Data**Roy F. WESTON, Inc.**

BOREHOLE ID : CW2-MW33
BEGIN DATE : 12/15/94

PROJECT NAME: FT. MONMOUTH
END DATE : 12/15/94

LOGGER/COMPANY : P. THOMAS

BOREHOLE COMPLETED IN (<O>verburden edrock) : 0

TOTAL DEPTH : 15.00

DEPTH TO BEDROCK : 0.00

BOREHOLE DIAMETER #1: 12.25

INTERVAL: 0.00 ft. to 15.00 ft. BGS

METHOD : HSA

FLUID : NONE

BOREHOLE DIAMETER #2:

INTERVAL:

METHOD :

FLUID :

BOREHOLE DIAMETER #3:

INTERVAL:

METHOD :

FLUID :

DRILLING COMPANY : J.C. ANDERSON

DRILLER : STEVE BURGER

DRILL RIG TYPE : MOBILE B-57

	ESTIMATED	SURVEYED
SURFACE ELEVATION :	0.000	49.180

N. COORDINATE : 0.0000

E. COORDINATE : 0.0000

WELL PERMIT.....(Y)es (N)o: N PERMIT # : NJ 29 32597

HOLE ABANDONED... (Y)es (N)o: N

WELL INSTALLED... (Y)es (N)o: Y

WELL CLUSTER..... (Y)es (N)o: N No. OF WELLS : 0

WELL NEST..... (Y)es (N)o: N No. OF WELLS : 0

PUMPS INSTALLED.. (Y)es (N)o: N

	TYPE	DEPTH
PURGE :		0.00
SAMPLE :		0.00

BOREHOLE TESTING

BOREHOLE GEOPHYSICS..... (Y)es (N)o: N

SLUG TESTS..... (Y)es (N)o: N

PACKER TESTS..... (Y)es (N)o: N

PUMPING TESTS..... (Y)es (N)o: N

COMMENTS :

Latitude-North: 40 deg 17' 43.3"

Longitude-West: 74 deg 05' 10.2"

Well Completion Summary

Roy F. WESTON, Inc.

CLIENT FT. MONMOUTH
SITE NAME CHARLES WOOD AREA

DRILLING FIRM J.C. ANDERSON
INSPECTOR P. THOMAS

WELL ID CW2-MW33
START DATE 12/15/94
COMPLETION DATE 12/15/94

WATER LEVELS

		DEPTH		ELEV.	DRILLING SUMMARY	
Protective Casing 4.00 inch	1.91	TC	51.09	Driller	STEVE BURGER	
	0.00	GS	49.18	Drilling Fluid	NONE	
				Well Type	SINGLE CASSED SCREENED	
	WELL DESIGN CONSTRUCTION					
	Casing #1 Diameter: 4.00 inch Interval: 0.00 to 5.00 ft. Type : PVC SCH 40 Stick Up Inner Casing: 1.91 ft. Protective Casing: 1.99 ft. Casing Grout: CEMENT/BENT Interval: 0.00 to 0.50 ft. Seal Type: BENTONITE SLURRY Interval: 0.50 to 3.00 ft. Sand Pack Type : NO. 3 MORIE Interval: 3.00 to 15.00 ft. Grain Size : UNIFORM Median Diameter: Screen Diameter: 4.00 Interval: 5.00 to 14.54 ft. Type : PVC Slots: 0.010 inches Silt Trap Interval: 14.54 to 15.00 ft. Backfill Type : Interval: 0.00 to 0.00 ft.					
0.50	BN	48.68	WELL DEVELOPMENT Date 01/24/95 Method Surge Blocking/Bailing Yield 1 gpm Purged Volume 60 gal			
3.00	SP	46.18				
5.00	SC	44.18				
14.54	BS	34.64				
15.00	TD	34.18				
COMMENTS TC = Top of Casing SP = Top Sand Pack = Grout GS = Ground Surface SC = Top Screen = Seal BN = Top Seal BS = Bottom Screen = Sand Pack TD = Total Depth = Formation						
Additional Comments: Depths measured below ground surface.						

NOTE: Well Diagram not to Scale

Elevations are feet above mean sea level

Borehole Log

Roy F. WESTON, Inc.

PROJECT	: FT. MONMOUTH	TOTAL DEPTH	: 15.00
SITE NAME	: CHARLES WOOD AREA	LOGGER	: P. THOMAS
BORING ID	: CW2-MW33	DRILLING COMPANY	: J.C. ANDERSON
NORTHING	: 0.0000 estimated	DRILLING RIG	: MOBILE B-57
EASTING	: 0.0000 estimated	DATE STARTED	: 12/15/94
ELEVATION	: 49.180 surveyed	DATE COMPLETED	: 12/15/94

ELEVATION	DEPTH	MATERIAL	RECOVERY %	CLASSIFICATION	COLOR	STRENGTH	MOISTURE	BLOW COUNT	FIELD INSTRUMENT READING	COMMENTS
			70	Silt with sand, ML	BROWN	SFT	MST	6	HNU 0.0	Topsoil: plant/grass fragments.
				Silty sand, SM	BROWN	SFT	MST	11	HNU 0.0	
48	1			No Sample Recovered				12		
			60	Silty sand, SM	BROWN	SFT	MST	11	HNU 0.0	
47	2							10		
46	3			No Sample Recovered				9		
			80	Silty sand, SM	GRAY	SFT	SAT	3	HNU 0.1	
45	4							4		
44	5			No Sample Recovered						
			75	Silty sand, SM	GRAY	SFT	SAT	3	HNU 0.0	Note at 7.3 to 7.5' bgs occurrence of green sand layer (75% sand/25% silt)
43	6							5		
42	7			Silty sand, SM	GREEN	LSE	SAT		HNU 0.0	
				No Sample Recovered						
			60	Silty sand, SM	GREEN	LSE	SAT	6	HNU 0.0	
41	8							6		
40	9			No Sample Recovered						
			45	Silty sand, SM	GREEN	LSE	SAT	5	HNU 0.0	
39	10							10		
								8		

Borehole Log

Roy F. WESTON, Inc.

PROJECT :	FT. MONMOUTH	TOTAL DEPTH :	15.00
SITE NAME :	CHARLES WOOD AREA	LOGGER :	P. THOMAS
BORING ID :	CW2-MW33	DRILLING COMPANY :	J.C. ANDERSON
NORTHING :	0.0000 estimated	DRILLING RIG :	MOBILE B-57
EASTING :	0.0000 estimated	DATE STARTED :	12/15/94
ELEVATION :	49.180 surveyed	DATE COMPLETED :	12/15/94

ELEVATION	DEPTH	MATERIAL	% RECOVERY	CLASSIFICATION	COLOR	STRENGTH	MOISTURE	BLOW COUNT	FIELD INSTRUMENT READING	COMMENTS
				Silty sand, SM	GREEN	LSE	SAT		HNU 0.0	
38	11			No Sample Recovered						
37	12			No Sample Recovered						
36	13									
35	14			Interval Not Sampled						Augered interval.
34	15									
33	16									
32	17									
31	18									
30	19									
29	20									

BOREHOLE /WELL ID	SMP NUM	LTH NUM	LITHOLOGY INT. (FT BGS)	SAMPLING METHOD	SIZE GRAVEL	GRAVEL PCT.	SIZE SAND	SAND PCT	SILT PCT	CLAY PCT	ORGANIC PCT	ROCK TYPE	PLAST	SORT	STRENGTH	MOISTURE	STRAT UNIT
CW2-MW33	1	1	0.00	0.60	SPS		0	FM	15	30	15	40	NON	POR	SFT	MST	
CW2-MW33	1	2	0.60	1.40	SPS	FM	10	MFC	60	20	5	5	NON	MOD	SFT	MST	
CW2-MW33	1	3	1.40	2.00	SPS		0		0	0	0						
CW2-MW33	2	1	2.00	3.20	SPS		0	MFC	60	35	5	0	NON	MOD	SFT	MST	
CW2-MW33	2	2	3.20	4.00	SPS		0		0	0	0						
CW2-MW33	3	1	4.00	5.60	SPS		0	MFC	55	35	10	0	NON	MOD	SFT	SAT	
CW2-MW33	3	2	5.60	6.00	SPS		0		0	0	0						
CW2-MW33	4	1	6.00	7.30	SPS		0	MFC	55	35	10	0	NON	MOD	SFT	SAT	
CW2-MW33	4	2	7.30	7.50	SPS		0	MF	75	25	0	0	NA	MOD	LSE	SAT	
CW2-MW33	4	3	7.50	8.00	SPS		0		0	0	0						
CW2-MW33	5	1	8.00	9.20	SPS	F	10	MF	70	20	0	0	NA	MOD	LSE	SAT	
CW2-MW33	5	2	9.20	10.00	SPS		0		0	0	0						
CW2-MW33	6	1	10.00	10.90	SPS	F	10	MF	70	20	0	0	NON	MOD	LSE	SAT	
CW2-MW33	6	2	10.90	12.00	SPS		0		0	0	0						
CW2-MW33	7	1	12.00	14.00	SPS		0		0	0	0						
CW2-MW33	8	1	14.00	15.00	NS		0		0	0	0						

Appendix C

Groundwater Laboratory Data Sheets

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-3484

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT

FOR

Directorate of Public Works

Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
2472.03	MW-30	29-32594	04/24/97
2472.04	MW-31	29-32595	04/24/97
2472.05	MW-32	29-32596	04/24/97
2472.06	MW-33	29-32597	04/24/97

NJDEP Laboratory Certification # 13461

Report Date: 7 October, 1997

Daniel Wright
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3111D
Antimony	3113B
Arsenic	3113B
Barium	3111D
Beryllium	3113B
Cadmium	3111B
Calcium	3111B
Chromium	3111D
Cobalt	3113B
Copper	3111B
Iron	3111B
Lead	3113B
Magnesium	3111B
Manganese	3111B
Mercury	3112B
Nickel	3111B
Potassium	3111B
Selenium	3113B
Silver	3111B
Sodium	3111B
Thallium	3113B
Vanadium	3111D
Zinc	3111B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (908)532-4359 Fax (908)532-3484 EMail:appleby@doim6.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: J. Fallon		Project No:		Analysis Parameters								Comments:	
Phone #:		Location: Bldg 2700 CW-2											
(V)DERA ()OMA ()Other:				Samplers Name / Company: Ray PoGwist / TUS		Sample #	TCL WA	TCL BNA	TCL PEST	TAL METALS			
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles						Remarks / Preservation Method		
2472	1 Trip Blank	4/24/97	0800	AQ	2	X					(VQA-HCL) (METALS-HW03)		
	2 Field Blank		1000		5	X	X	X	X		all samples kept ≤ 40x		
	3 Bldg 2700 MW-30		1115		5	X	X	X	X		#2932544		
	4 Bldg 2700 MW-31		1035		5	✓	✓	X	X		#2932545		
	5 Bldg 2700 MW-32		1510		5	X	X	X	X		#2932546		
	6 Bldg 2700 MW-33		1420		3	X	X	X	X		#2932547		
	7 Field Dup					X			X				
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):			
[Signature]		4/24/97		[Signature]									
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):			
Report Type: () Full, () Reduced, () Standard, () Screen / non-certified						Remarks:							
Turnaround time: () Standard 4 wks, () Rush Days, () ASAP Verbal Hrs.													

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: 2700
MW# 30
NJDEP ID# 2932594
NJDEP CERT# 13461
SAMPLING CONTRACTOR TVS
SAMPLER RAY POGWIST

DATE: 04/27/97 WEATHER: SUNNY 40-50'S

ELEVATION OF CASING SURVEY MARK

DTW: 6.45

DEPTH OF WELL: 17.90

HEIGHT OF WATER 11.45

11.45 X 0.65 X 3 = 22.33

GAL OF H2O TO BE EVACUATED 22.33 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALIC

PURGE RATE 0.3 GPM

Hnu READING N/A

PURGE START TIME: 9:15

pH: 6.45 TEMP 51.7 DEG F

DISSOLVED O2 3.2 PPM SPECIFIC CONDUCTIVITY 315 us/cm

PURGE END TIME: 11:10

pH: 6.32 TEMP 51.5 DEG F

DISSOLVED O2 2.8 PPM SPECIFIC CONDUCTIVITY 231 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 6.72 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 22.4 GAL

pH: 6.30 TEMP 51.2 DEG °C

DISSOLVED O2 2.6 PPM SPECIFIC CONDUCTIVITY 230 us/cm

COMMENTS: _____

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: 2700

MW# 31

NJDEP ID# 2932595

NJDEP CERT# 13461

SAMPLING CONTRACTOR TVS

SAMPLER RAY POGWIST

DATE: 04/24/97

WEATHER: RAIN 40-50'S

ELEVATION OF CASING SURVEY MARK

DTW: 6.38

DEPTH OF WELL: 16.80

HEIGHT OF WATER 10.42

10.42 X 0.65 X 3 = 20.32

GAL OF H2O TO BE EVACUATED 20.32 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.3 GPM

Hnu READING N/A

PURGE START TIME: 9:25

pH: 6.30 TEMP 51.6 DEG F

DISSOLVED O2 3.4 PPM SPECIFIC CONDUCTIVITY 552 us/cm

PURGE END TIME: 10:30

pH: 6.35 TEMP 50.5 DEG F

DISSOLVED O2 2.8 PPM SPECIFIC CONDUCTIVITY 510 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 7.80 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon @ bailer

TOTAL VOLUME PURGED: 20.4 GAL

pH: 6.38 TEMP 50.4 DEG F

DISSOLVED O2 2.7 PPM SPECIFIC CONDUCTIVITY 502 us/cm

COMMENTS: _____

U.S. ARMY FORT MOMOUTH MONITORING WELL SAMPLING DATASHEET

BLDG 2700
MW# 32
NJDEP ID# 29-32596
NJDEP CERT# 13461
SAMPLING CONTRATOR TVS
SAMPLER RAY POGWIST

DATE 4/24/97 WEATHER PT. SUNNY 50'S

ELEVATION OF CASING SURVEY MARK

DTW 6.65

DEPTH OF WELL 16.80

HEIGHT OF WATER 10.15

$10.15 \times 0.65 \times 3 = 19.79$

GAL OF H2O TO BE EVACUATED 19.8 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.3 GPM

PURGE START TIME 13:25

pH 6.91 TEMP 52.9 DEG F

DISSOLVED O2 3.4 PPM SPECIFIC CONDUCTIVITY 490 us/cm

PURGE END TIME 15:00

pH 7.41 TEMP 52.6 DEG F

DISSOLVED O2 3.0 PPM SPECIFIC CONDUCTIVITY 503 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 9.20 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 19.0 GAL

pH 7.45 TEMP 52.5 DEG F

DISSOLVED O2 2.8 PPM SPECIFIC CONDUCTIVITY 505 us/cm

COMMENTS: _____

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: 2700

MW# 33

NJDEP ID# 2932597

NJDEP CERT# 13461

SAMPLING CONTRACTOR TVS

SAMPLER RAY POGWIST _

DATE: 04/24/97

WEATHER: PT. SUNNY 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 8.95

DEPTH OF WELL: 16.00

HEIGHT OF WATER 7.05

7.05 X 0.65 X 3 = 13.75

GAL OF H2O TO BE EVACUATED 3.75 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.3 GPM

Hnu READING N/A

PURGE START TIME: 13:35

pH: 6.57 TEMP 55.6 DEG F

DISSOLVED O2 3.2 PPM SPECIFIC CONDUCTIVITY 7.55 us/cm

PURGE END TIME: 14:20

pH: 6.42 TEMP 55.5 DEG F

DISSOLVED O2 3.0 PPM SPECIFIC CONDUCTIVITY 735 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 9.10 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon @ bailer

TOTAL VOLUME PURGED: 13.75 GAL

pH: 6.41 TEMP 55.5 DEG F

DISSOLVED O2 2.9 PPM SPECIFIC CONDUCTIVITY 732 us/cm

COMMENTS: _____

Organic Data Qualifiers

Form 1:

This form reports concentrations of Tentatively Identified Compounds. Form 1E is the Volatile report, Form 1F is for Semi-Volatiles.

Qualifiers are:

- J** Estimated Value
- N** Presumptive evidence of a compound
- E** Concentration exceeds calibration range
- D** Diluted sample
- A** TIC is a suspected aldol condensation product

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **V00731.D**
 Operator **Paul Skelton**
 Date Acquired **05/ 2/97 10:54**

Sample Name **Daily Blank**
 Field ID
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v00732.d**
 Operator **Paul Skelton**
 Date Acquired **05/ 2/97 11:47**

Sample Name **2472.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v00733.d**
 Operator **Paul Skelton**
 Date Acquired **05/ 2/97 12:35**

Sample Name **2472.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v00734.d**
 Operator **Paul Skelton**
 Date Acquired **05/ 2/97 13:18**

Sample Name **2472.03**
 Field ID **Bldg 2700 MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v00735.d**
 Operator **Paul Skelton**
 Date Acquired **05/ 2/97 14:06**

Sample Name **2472.04**
 Field ID **Bldg 2700 MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v00736.d**
 Operator **Paul Skelton**
 Date Acquired **05/ 2/97 15:11**

Sample Name **2472.05**
 Field ID **Bldg 2700 MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v00737.d**
 Operator **Paul Skelton**
 Date Acquired **05/ 2/97 16:00**

Sample Name **2472.06**
 Field ID **Bldg 2700 MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v00738.d**
 Operator **Paul Skelton**
 Date Acquired **05/ 2/97 16:46**

Sample Name **2472.07**
 Field ID **Field Duplicate**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Daily Blank

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 2472 Location _____ SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Daily Blank
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00731.D
Level: (low/med) LOW Date Received: 05/02/97
% Moisture: not dec. _____ Date Analyzed: 05/02/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Trip Blank

Lab Name: FMETL Project B2700
 NJDEP # 13461 Case No.: 2472 Location CW2 SDG No.: _____
 Matrix: (soil/water) WATER Lab Sample ID: 2472.01
 Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00732.D
 Level: (low/med) LOW Date Received: 04/24/97
 % Moisture: not dec. _____ Date Analyzed: 05/02/97
 GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
 Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0

(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Project B2700
NJDEP # 13461 Case No.: 2472 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2472.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00733.D
Level: (low/med) LOW Date Received: 04/24/97
% Moisture: not dec. _____ Date Analyzed: 05/02/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW30

Lab Name: FMETL Project B2700
 NJDEP # 13461 Case No.: 2472 Location CW2 SDG No.: _____
 Matrix: (soil/water) WATER Lab Sample ID: 2472.03
 Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00734.D
 Level: (low/med) LOW Date Received: 04/24/97
 % Moisture: not dec. _____ Date Analyzed: 05/02/97
 GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
 Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 1

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1. 001066-40-6	Silanol, trimethyl-	13.91	31	JN

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW31

Lab Name: FMETL Project B2700
 NJDEP # 13461 Case No.: 2472 Location CW2 SDG No.:
 Matrix: (soil/water) WATER Lab Sample ID: 2472.04
 Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00735.D
 Level: (low/med) LOW Date Received: 04/24/97
 % Moisture: not dec. Date Analyzed: 05/02/97
 GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
 Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1. 001066-40-6	Silanol, trimethyl-	13.92	12	JN

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW32

Lab Name: FMETL Project B2700
 NJDEP # 13461 Case No.: 2472 Location CW2 SDG No.: _____
 Matrix: (soil/water) WATER Lab Sample ID: 2472.05
 Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00736.D
 Level: (low/med) LOW Date Received: 04/24/97
 % Moisture: not dec. _____ Date Analyzed: 05/02/97
 GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
 Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1. 001066-40-6	Silanol, trimethyl-	13.91	4	JN

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW33

Lab Name: FMETL Project B2700
NJDEP # 13461 Case No.: 2472 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2472.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00737.D
Level: (low/med) LOW Date Received: 04/24/97
% Moisture: not dec. _____ Date Analyzed: 05/02/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1. 001066-40-6	Silanol, trimethyl-	13.91	30	JN

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Dup

Lab Name: FMETL Project B2700
NJDEP # 13461 Case No.: 2472 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2472.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00738.D
Level: (low/med) LOW Date Received: 04/24/97
% Moisture: not dec. _____ Date Analyzed: 05/02/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1. 001066-40-6	Silanol, trimethyl-	13.92	5	JN

Organic Data Qualifiers

Form 1:

This form reports concentrations of Tentatively Identified Compounds. Form 1E is the Volatile report, Form 1F is for Semi-Volatiles.

Qualifiers are:

- J** Estimated Value
- N** Presumptive evidence of a compound
- E** Concentration exceeds calibration range
- D** Diluted sample
- A** TIC is a suspected aldol condensation product

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0172.d**
 Operator **Paul Skelton**
 Date Acquired **05/21/97 15:57**

Sample Name **Ext Blank 04/28/97**
 Field ID
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82	ug/L	5000
86-73-7	Fluorene			not detected	0.29	ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23	ug/L	20
103-33-3	Azobenzene			not detected	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82	ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08	ug/L	1
85-01-8	Phenanthrene			not detected	0.18	ug/L	
120-12-7	Anthracene			not detected	0.19	ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23	ug/L	900
206-44-0	Fluoranthene			not detected	0.41	ug/L	300
92-87-5	Benzidine			not detected	1.45	ug/L	50
129-00-0	Pyrene			not detected	0.32	ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47	ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22	ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46	ug/L	60
218-01-9	Chrysene			not detected	0.20	ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51	ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82	ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37	ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32	ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31	ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79	ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28	ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40	ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0184.d**
 Operator **Paul Skelton**
 Date Acquired **05/22/97 01:01**

Sample Name **2472.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0185.d**
 Operator **Paul Skelton**
 Date Acquired **05/22/97 01:46**

Sample Name **2472.03**
 Field ID **MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0186.d**
 Operator **Paul Skelton**
 Date Acquired **05/22/97 02:30**

Sample Name **2472.04**
 Field ID **MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82	ug/L	5000
86-73-7	Fluorene			not detected	0.29	ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23	ug/L	20
103-33-3	Azobenzene			not detected	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82	ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08	ug/L	1
85-01-8	Phenanthrene			not detected	0.18	ug/L	
120-12-7	Anthracene			not detected	0.19	ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23	ug/L	900
206-44-0	Fluoranthene			not detected	0.41	ug/L	300
92-87-5	Benzidine			not detected	1.45	ug/L	50
129-00-0	Pyrene			not detected	0.32	ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47	ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22	ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46	ug/L	60
218-01-9	Chrysene			not detected	0.20	ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51	ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82	ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37	ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32	ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31	ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79	ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28	ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40	ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0189.d**
 Operator **Paul Skelton**
 Date Acquired **05/22/97 04:42**

Sample Name **2472.05**
 Field ID **MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate	25.52	56669	1.54 ug/L	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0188.d**
 Operator **Paul Skelton**
 Date Acquired **05/22/97 03:58**

Sample Name **2472.06**
 Field ID **MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

Ext. Blank

Lab Name: FMETL Contract: _____
Cert. No. 13461 Case No.: 2472 Project _____ SDG. _____
Matrix: (soil/water) WATER Lab Sample ID: Ext Blank 04/28
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0172.D
Level: (low/med) LOW Date Received: 04/28/97
% Moisture: _____ decanted: (Y/N) N Date Analyzed: 05/21/97
Concentrated Extract Volume: 1 (uL) Dilution Factor: 1.0
Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.95	43	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

Field Blank

Lab Name: FMETL Location: 2700
 Cert. No. 13461 Case No.: 2472 Project CW2 SDG. _____
 Matrix: (soil/water) WATER Lab Sample ID: 2472.02
 Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0184.D
 Level: (low/med) LOW Date Received: 04/24/97
 % Moisture: _____ decanted: (Y/N) N Date Analyzed: 05/22/97
 Concentrated Extract Volume: 1 (uL) Dilution Factor: 1.0
 Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)
 GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	5.24	27	JN
2. 000000-00-0	(E)-3-Chloro-2-methyl-2-pentenal	7.97	52	JN
3. 003855-82-1	1,4-Dichlorobenzene-d4	8.77	29	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

MW30

Lab Name: FMETL Location: 2700
 Cert. No. 13461 Case No.: 2472 Project CW2 SDG.
 Matrix: (soil/water) WATER Lab Sample ID: 2472.03
 Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0185.D
 Level: (low/med) LOW Date Received: 04/24/97
 % Moisture: decanted: (Y/N) N Date Analyzed: 05/22/97
 Concentrated Extract Volume: 1 (uL) Dilution Factor: 1.0
 Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)
 GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 4 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	5.24	18	JN
2. 000000-00-0	(E)-3-Chloro-2-methyl-2-pentenal	7.97	51	JN
3. 002199-69-1	Benzene-1,2,3,4-d4-, 5,6-dichloro	8.77	31	JN
4. 000057-10-3	Hexadecanoic acid	20.44	9	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID.
TENTATIVELY IDENTIFIED COMPOUNDS

MW31

Lab Name: FMETL Location: 2700

Cert. No. 13461 Case No.: 2472 Project CW2 SDG.

Matrix: (soil/water) WATER Lab Sample ID: 2472.04

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0186.D

Level: (low/med) LOW Date Received: 04/24/97

% Moisture: decanted: (Y/N) N Date Analyzed: 05/22/97

Concentrated Extract Volume: 1 (uL) Dilution Factor: 1.0

Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	5.36	330	JN
2. 000000-00-0	(E)-3-Chloro-2-methyl-2-pentenal	7.99	60	JN
3. 002199-69-1	Benzene-1,2,3,4-d4-, 5,6-dichloro	8.77	35	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID.
TENTATIVELY IDENTIFIED COMPOUNDS

MW32

Lab Name: FMETL Location: 2700

Cert. No. 13461 Case No.: 2472 Project CW2 SDG.

Matrix: (soil/water) WATER Lab Sample ID: 2472.05

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0189.D

Level: (low/med) LOW Date Received: 04/24/97

% Moisture: decanted: (Y/N) N Date Analyzed: 05/22/97

Concentrated Extract Volume: 1 (uL) Dilution Factor: 1.0

Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 5 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	5.36	440	JN
2. 000000-00-0	(E)-3-Chloro-2-methyl-2-pentenal	7.99	100	JN
3. 003855-82-1	1,4-Dichlorobenzene-d4	8.76	26	JN
4. 000057-10-3	Hexadecanoic acid	20.46	18	JN
5. 074685-33-9	3-Eicosene, (E)-	25.04	8	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID.
TENTATIVELY IDENTIFIED COMPOUNDS

MW33

Lab Name: FMETL Location: 2700

Cert. No. 13461 Case No.: 2472 Project CW2 SDG.

Matrix: (soil/water) WATER Lab Sample ID: 2472.06

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0188.D

Level: (low/med) LOW Date Received: 04/24/97

% Moisture: decanted: (Y/N) N Date Analyzed: 05/22/97

Concentrated Extract Volume: 1 (uL) Dilution Factor: 1.0

Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 002213-32-3	1-Pentene, 2,4-dimethyl-	6.68	9	JN
2. 000000-00-0	(E)-3-Chloro-2-methyl-2-pentenal	7.97	41	JN
3. 003855-82-1	1,4-Dichlorobenzene-d4	8.76	30	JN

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 2472.02
DPW, SELFM-PW-EV Date Rec'd: 4/24/97
Bldg. 173 Extraction Date: 4/28/97
Ft. Monmouth, NJ 07703 Analysis Date: 6/7/97

Analysis: EPA Method 608 Location : CW-2, Bldg.2700
Matrix: Aqueous Ft. Monmouth
Analyst: D. Wright Field ID: Field Blank
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	2472.03
	DPW, SELFM-PW-EV	Date Rec'd:	4/24/97
	Bldg. 173	Extraction Date:	4/28/97
	Ft. Monmouth, NJ 07703	Analysis Date:	6/7/97

Analysis:	EPA Method 608	Location :	CW-2, Bldg.2700
Matrix:	Aqueous		Ft. Monmouth
Analyst:	D. Wright	Field ID:	MW-30
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	2472.04
	DPW, SELFM-PW-EV	Date Rec'd:	4/24/97
	Bldg. 173	Extraction Date:	4/28/97
	Ft. Monmouth, NJ 07703	Analysis Date:	6/7/97

Analysis:	EPA Method 608	Location :	CW-2, Bldg.2700
Matrix:	Aqueous		Ft. Monmouth
Analyst:	D. Wright	Field ID:	MW-31
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	2472.05
	DPW, SELFM-PW-EV	Date Rec'd:	4/24/97
	Bldg. 173	Extraction Date:	4/28/97
	Ft. Monmouth, NJ 07703	Analysis Date:	6/7/97

Analysis:	EPA Method 608	Location :	CW-2, Bldg.2700
Matrix:	Aqueous		Ft. Monmouth
Analyst:	D. Wright	Field ID:	MW-32
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 2472.06
DPW, SELFM-PW-EV Date Rec'd: 4/24/97
Bldg. 173 Extraction Date: 4/28/97
Ft. Monmouth, NJ 07703 Analysis Date: 6/7/97

Analysis: EPA Method 608 Location : CW-2, Bldg.2700
Matrix: Aqueous Ft. Monmouth
Analyst: D. Wright Field ID: MW-33
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 2472.02
Sample Received: 4/24/97
Sample Matrix: Aqueous

Site: CW-2 (Bldg. 2700)
Ft. Monmouth, New Jersey

Field ID: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	7/1/97	ND	100	200
Antimony	5/1/97	ND	1.0	20
Arsenic	4/30/97	ND	1.0	8
Barium	7/1/97	ND	30	2000
Beryllium	5/1/97	ND	0.6	20
Cadmium	5/28/97	ND	2.0	4
Calcium	7/1/97	ND	30	NA
Chromium	7/1/97	ND	7.0	100
Cobalt	5/1/97	0.5	0.3	NA
Copper	6/30/97	7.0	3.0	1000
Iron	5/13/97	ND	10	300
Lead	5/1/97	ND	0.5	10
Magnesium	7/1/97	ND	50	NA
Manganese	6/30/97	9.0	5.0	50
Mercury	5/8/97	ND	0.2	2
Nickel	6/30/97	ND	10	100
Potassium	6/30/97	ND	40	NA
Selenium	5/1/97	ND	1.0	50
Silver	5/7/97	8.0	3.0	20
Sodium	6/30/97	ND	10	50000
Thallium	4/30/97	ND	1.0	10
Vanadium	7/1/97	ND	200	NA
Zinc	6/30/97	2.0	2.0	5000

ND = Not Detected. MDL = Method Detection Limit. NA = Not Applicable

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 2472.03
 Sample Received: 4/24/97
 Sample Matrix: Aqueous

Site: CW-2 (Bldg. 2700)
 Ft. Monmouth, New Jersey

Field ID: MW-30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	7/1/97	ND	100	200
Antimony	5/1/97	ND	1.0	20
Arsenic	4/30/97	4.0	1.0	8
Barium	7/1/97	ND	30	2000
Beryllium	5/1/97	ND	0.6	20
Cadmium	5/28/97	ND	2.0	4
Calcium	7/1/97	41000	30	NA
Chromium	7/1/97	ND	7.0	100
Cobalt	5/1/97	0.7	0.3	NA
Copper	6/30/97	1.7	3.0	1000
Iron	5/13/97	9110	10	300
Lead	5/1/97	ND	0.5	10
Magnesium	7/1/97	4500	50	NA
Manganese	6/30/97	69	5.0	50
Mercury	5/8/97	ND	0.2	2
Nickel	6/30/97	ND	10	100
Potassium	6/30/97	6900	40	NA
Selenium	5/1/97	ND	1.0	50
Silver	5/7/97	10	3.0	20
Sodium	6/30/97	14000	10	50000
Thallium	4/30/97	ND	1.0	10
Vanadium	7/1/97	ND	200	NA
Zinc	6/30/97	6.0	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 2472.04
Sample Received: 4/24/97
Sample Matrix: Aqueous

Site: CW-2 (Bldg. 2700)
Ft. Monmouth, New Jersey

Field ID: MW-31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	7/1/97	ND	100	200
Antimony	5/1/97	ND	1.0	20
Arsenic	4/30/97	2.0	1.0	8
Barium	7/1/97	ND	30	2000
Beryllium	5/1/97	ND	0.6	20
Cadmium	5/28/97	ND	2.0	4
Calcium	7/1/97	40200	30	NA
Chromium	7/1/97	ND	7.0	100
Cobalt	5/1/97	ND	0.3	NA
Copper	6/30/97	11	3.0	1000
Iron	5/13/97	59900	10	300
Lead	5/1/97	ND	0.5	10
Magnesium	7/1/97	5680	50	NA
Manganese	6/30/97	277	5.0	50
Mercury	5/8/97	ND	0.2	2
Nickel	6/30/97	ND	10	100
Potassium	6/30/97	8960	40	NA
Selenium	5/1/97	ND	1.0	50
Silver	5/7/97	14	3.0	20
Sodium	6/30/97	11100	10	50000
Thallium	4/30/97	ND	1.0	10
Vanadium	7/1/97	ND	200	NA
Zinc	6/30/97	ND	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 2472.05
Sample Received: 4/24/97
Sample Matrix: Aqueous

Site: CW-2 (Bldg. 2700)
Ft. Monmouth, New Jersey

Field ID: MW-32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	7/1/97	ND	100	200
Antimony	5/1/97	ND	1.0	20
Arsenic	4/30/97	2.0	1.0	8
Barium	7/1/97	ND	30	2000
Beryllium	5/1/97	ND	0.6	20
Cadmium	5/28/97	ND	2.0	4
Calcium	7/1/97	77000	30	NA
Chromium	7/1/97	ND	7.0	100
Cobalt	5/1/97	0.9	0.3	NA
Copper	6/30/97	27	3.0	1000
Iron	5/13/97	18400	10	300
Lead	5/1/97	ND	0.5	10
Magnesium	7/1/97	4750	50	NA
Manganese	6/30/97	125	5.0	50
Mercury	5/8/97	ND	0.2	2
Nickel	6/30/97	ND	10	100
Potassium	6/30/97	6740	40	NA
Selenium	5/1/97	ND	1.0	50
Silver	5/7/97	11	3.0	20
Sodium	6/30/97	22250	10	50000
Thallium	4/30/97	ND	1.0	10
Vanadium	7/1/97	ND	200	NA
Zinc	6/30/97	121	2.0	5000

ND = Not Detected. MDL = Method Detection Limit. NA = Not Applicable

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW. SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 2472.06
Sample Received: 4/24/97
Sample Matrix: Aqueous

Site: CW-2 (Bldg. 2700)
Ft. Monmouth, New Jersey

Field ID: MW-33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	7/1/97	ND	100	200
Antimony	5/1/97	ND	1.0	20
Arsenic	4/30/97	3.0	1.0	8
Barium	7/1/97	90	30	2000
Beryllium	5/1/97	ND	0.6	20
Cadmium	5/28/97	ND	2.0	4
Calcium	7/1/97	67200	30	NA
Chromium	7/1/97	ND	7.0	100
Cobalt	5/1/97	0.7	0.3	NA
Copper	6/30/97	9.0	3.0	1000
Iron	5/13/97	88600	10	300
Lead	5/1/97	ND	0.5	10
Magnesium	7/1/97	3110	50	NA
Manganese	6/30/97	424	5.0	50
Mercury	5/8/97	ND	0.2	2
Nickel	6/30/97	ND	10	100
Potassium	6/30/97	11000	40	NA
Selenium	5/1/97	ND	1.0	50
Silver	5/7/97	16	3.0	20
Sodium	6/30/97	12000	10	50000
Thallium	4/30/97	ND	1.0	10
Vanadium	7/1/97	ND	200	NA
Zinc	6/30/97	ND	2.0	5000

ND = Not Detected. MDL = Method Detection Limit. NA = Not Applicable

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 2472.07
Sample Received: 4/24/97
Sample Matrix: Aqueous

Site: CW-2 (Bldg. 2700)
Ft. Monmouth, New Jersey

Field ID: Field DUP

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	7/1/97	ND	100	200
Antimony	5/1/97	ND	1.0	20
Arsenic	4/30/97	3.0	1.0	8
Barium	7/1/97	ND	30	2000
Beryllium	5/1/97	ND	0.6	20
Cadmium	5/28/97	ND	2.0	4
Calcium	7/1/97	78200	30	NA
Chromium	7/1/97	ND	7.0	100
Cobalt	5/1/97	0.8	0.3	NA
Copper	6/30/97	30	3.0	1000
Iron	5/13/97	17350	10	300
Lead	5/1/97	ND	0.5	10
Magnesium	7/1/97	3700	50	NA
Manganese	6/30/97	117	5.0	50
Mercury	5/8/97	ND	0.2	2
Nickel	6/30/97	ND	10	100
Potassium	6/30/97	6610	40	NA
Selenium	5/1/97	ND	1.0	50
Silver	5/7/97	14	3.0	20
Sodium	6/30/97	23100	10	50000
Thallium	4/30/97	ND	1.0	10
Vanadium	7/1/97	ND	200	NA
Zinc	6/30/97	120	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-3484

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
2788.03	MW-30	29-32594	07/10/97
2788.04	MW-31	29-32595	07/10/97
2788.06	MW-32	29-32596	07/10/97
2788.05	MW-33	29-32597	07/10/97

NJDEP Laboratory Certification # 13461

Report Date: 2 December, 1997

Daniel Wright
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3111D
Antimony	3113B
Arsenic	3113B
Barium	3111D
Beryllium	3113B
Cadmium	3111B
Calcium	3111B
Chromium	3111D
Cobalt	3113B
Copper	3111B
Iron	3111B
Lead	3113B
Magnesium	3111B
Manganese	3111B
Mercury	3112B
Nickel	3111B
Potassium	3111B
Selenium	3113B
Silver	3111B
Sodium	3111B
Thallium	3113B
Vanadium	3111D
Zinc	3111B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (908)532-4359 Fax (908)532-3484 EMail:appleby@doim6.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: <u>I Fallon</u>		Project No:		Analysis Parameters								Comments:	
Phone #: <u>X 26223</u>		Location: <u>Bldg 2700</u>											
(X)DERA ()OMA ()Other:													
Samplers Name / Company: <u>Ray Pignatelli / TUS</u>				Sample #									Remarks / Preservation Method
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles	TEL UVA + 15	TAL METALS	TEL EVA + 15	T.L POST / PCB				
<u>2788</u>	<u>Trip Blank</u>	<u>7/10/97</u>	<u>0800</u>	<u>AW</u>	<u>2</u>	<u>X</u>						<u>All Samples kept ≤ 4°C</u> <u>(Voa-Hcl) (Metals-HNO₃)</u> <u>#2932594</u> <u>#2932595</u> <u>#2932597</u> <u>#2932596</u> <u>#2931783</u> <u>#2930969</u>	
<u>2</u>	<u>Field Blank</u>		<u>1000</u>		<u>5</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>				
<u>3</u>	<u>Bldg 2700 NW 30</u>		<u>1100</u>		<u>5</u>								
<u>4</u>	<u>Bldg 2700 NW 31</u>		<u>1110</u>		<u>5</u>								
<u>5</u>	<u>Bldg 2700 NW 33</u>		<u>1120</u>		<u>5</u>								
<u>6</u>	<u>Bldg 2700 NW 32</u>		<u>1425</u>		<u>5</u>								
<u>7</u>	<u>Bldg 2700 NW 26</u>		<u>1435</u>		<u>5</u>								
<u>8</u>	<u>Bldg 2700 NW 2004</u>		<u>1515</u>		<u>5</u>								
<u>9</u>	<u>Field Dup</u>		<u>—</u>		<u>5</u>								
Relinquished by (signature): <u>[Signature]</u>		Date/Time: <u>7/10/97 13:30</u>		Received by (signature): <u>[Signature]</u>		Date/Time: <u>7-10-97</u>		Relinquished by (signature):		Date/Time:		Received by (signature):	
Relinquished by (signature):		Date/Time:		Received by (signature):		Date/Time:		Relinquished by (signature):		Date/Time:		Received by (signature):	
Report Type: () Full, () Reduced, (X) Standard, () Screen / non-certified						Remarks:							
Turnaround time: (X) Standard 4 wks, () Rush Days, () ASAP Verbal Hrs.													

**U.S. ARMY FORT MOMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: 2700
MW#: 30
NJDEP ID#: 2932594
NJDEP CERT#: 13461
SAMPLING CONTRATOR: TVS
SAMPLER: RAY POGWIST

DATE: 7/10/97

WEATHER: PT. SUNNY 70'S

ELEVATION OF CASING SURVEY MARK:

DTW: 7.05

DEPTH OF WELL: 17.90

HEIGHT OF WATER: 10.85

10.85 X 0.65 X 3 = 21.15

GAL OF H2O TO BE EVACUATED: 21.16

PURGE METHOD (FLOW OF >0.5 TO <5.0 GPM) : PERISTALTIC

PURGE RATE IN GPM: 0.3

Hnu in PPM: 0

PURGE START TIME: 9:30

pH: 7.90 TEMP IN ° C: 21.7

DISSOLVED O₂ IN PPM: 2.0 SPECIFIC CONDUCTIVITY IN us/cm: 130

PURGE END TIME: 10:40

pH: 7.40 TEMP IN °C: 22.7

DISSOLVED O₂ IN PPM: 1.5 SPECIFIC CONDUCTIVITY IN us/cm: 190

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING IN FT: 9.95

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED IN GAL.: 21.16

pH: 7.39 TEMP IN °C: 22.8

DISSOLVED O₂ IN PPM: 1.5 SPECIFIC CONDUCTIVITY IN us/cm: 190

COMMENTS: _____

U.S. ARMY FORT MOMOUTH MONITORING WELL SAMPLING DATASHEET

BLDG: 2700

MW#: 31

NJDEP ID#: 2932595

NJDEP CERT#: 13461

SAMPLING CONTRATOR: TVS

SAMPLER: RAY POGWIST

DATE: 7/10/97

WEATHER: PT. SUNNY 70'S

ELEVATION OF CASING SURVEY MARK:

DTW: 7.00

DEPTH OF WELL: 16.80

HEIGHT OF WATER: 9.8

9.8 X 0.65 X 3 = 19.11

GAL OF H2O TO BE EVACUATED: 19.11

PURGE METHOD (FLOW OF >0.5 TO <5.0 GPM) : PERISTALTIC

PURGE RATE IN GPM: 0.3

Hnu in PPM: 0

PURGE START TIME: 9:45

pH: 7.70

TEMP IN °C: 22.2

DISSOLVED O₂ IN PPM: 2.1

SPECIFIC CONDUCTIVITY IN us/cm: 200

PURGE END TIME: 10:50

pH: 7.35

TEMP IN °C: 21.2

DISSOLVED O₂ IN PPM: 1.7

SPECIFIC CONDUCTIVITY IN us/cm: 180

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING IN FT: 8.05

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED IN GAL.: 19.11

pH: 7.31

TEMP IN °C: 21.3

DISSOLVED O₂ IN PPM: 1.6

SPECIFIC CONDUCTIVITY IN us/cm: 180

COMMENTS:

**U.S. ARMY FORT MOMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: 2700
MW#: 32
NJDEP ID#: 2932596
NJDEP CERT#: 13461
SAMPLING CONTRATOR: TVS
SAMPLER: RAY POGWIST

DATE: 7/10/97 WEATHER: PT. CLOUDY 70'S

ELEVATION OF CASING SURVEY MARK:
DTW: 7.20
DEPTH OF WELL: 16.80
HEIGHT OF WATER: 9.60
 $9.60 \times 0.65 \times 3 = 18.72$
GAL OF H2O TO BE EVACUATED: 18.72
PURGE METHOD (FLOW OF >0.5 TO <5.0 GPM) : PERISTALTIC
PURGE RATE IN GPM: 0.3
Hnu in PPM: 0

PURGE START TIME: 13:15
pH: 7.85 TEMP IN °C: 21.5
DISSOLVED O₂ IN PPM: 2.5 SPECIFIC CONDUCTIVITY IN us/cm: 190

PURGE END TIME: 14:20
pH: 8.37 TEMP IN °C: 22.2
DISSOLVED O₂ IN PPM: 2.0 SPECIFIC CONDUCTIVITY IN us/cm: 180

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING IN FT: 8.80
sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer
TOTAL VOLUME PURGED IN GAL.: 18.72

pH: 8.32 TEMP IN °C: 22.1
DISSOLVED O₂ IN PPM: 2.0 SPECIFIC CONDUCTIVITY IN us/cm:

COMMENTS: _____

U.S. ARMY FORT MOMOUTH MONITORING WELL SAMPLING DATASHEET

BLDG: 2700

MW#: 33

NJDEP ID#: 2932597

NJDEP CERT#: 13461

SAMPLING CONTRATOR: TVS

SAMPLER: RAY POGWIST

DATE: 7/10/97

WEATHER: PT. SUNNY 70'S

ELEVATION OF CASING SURVEY MARK:

DTW: 9.10

DEPTH OF WELL: 16.00

HEIGHT OF WATER: 6.90

6.90 X 0.65 X 3 = 13.45

GAL OF H2O TO BE EVACUATED: 13.46

PURGE METHOD (FLOW OF >0.5 TO <5.0 GPM) : PERISTALTIC

PURGE RATE IN GPM: 0.3

Hnu in PPM: 0

PURGE START TIME: 10:10

pH: 6.68

TEMP IN °C: 21.5

DISSOLVED O₂ IN PPM: 2.5

SPECIFIC CONDUCTIVITY IN us/cm: 270

PURGE END TIME: 10:55

pH: 6.65

TEMP IN °C: 22.0

DISSOLVED O₂ IN PPM: 2.4

SPECIFIC CONDUCTIVITY IN us/cm: 250

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING IN FT: 9.20

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED IN GAL.: 13.46

pH: 6.65

TEMP IN °C: 22.1

DISSOLVED O₂ IN PPM: 2.3

SPECIFIC CONDUCTIVITY IN us/cm: 250

COMMENTS:

Organic Data Qualifiers

Form 1:

This form reports concentrations of Tentatively Identified Compounds. Form 1E is the Volatile report, Form 1F is for Semi-Volatiles.

Qualifiers are:

- | | |
|----------|---|
| J | Estimated Value |
| N | Presumptive evidence of a compound |
| E | Concentration exceeds calibration range |
| D | Diluted sample |
| A | TIC is a suspected aldol condensation product |

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **V01259.D**
 Operator **Paul Skelton**
 Date Acquired **07/14/19 -1:9:**

Sample Name **Daily Blank**
 Field ID **Daily Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v01276.d**
 Operator **Paul Skelton**
 Date Acquired **07/15/19 -1:0:**

Sample Name **2788.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v01277.d**
 Operator **Paul Skelton**
 Date Acquired **07/15/19 -1:1:**

Sample Name **2788.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v01278.d**
 Operator **Paul Skelton**
 Date Acquired **07/15/19 -1:2:**

Sample Name **2788.03**
 Field ID **Bldg 2700 MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v01279.d**
 Operator **Paul Skelton**
 Date Acquired **07/15/19 -1:3:**

Sample Name **2788.04**
 Field ID **Bldg 2700 MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v01287.d**
 Operator **Skelton**
 Date Acquired **07/15/19 -1:6:**

Sample Name **2788.06**
 Field ID **Bldg 2700 MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v01286.d**
 Operator **Skelton**
 Date Acquired **07/15/19 -1:5:**

Sample Name **2788.05**
 Field ID **Bldg 2700 MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Daily Blank

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: _____ Location _____ SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Daily Blank
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V01259.D
Level: (low/med) LOW Date Received: _____
% Moisture: not dec. _____ Date Analyzed: 07/14/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Trip Blank

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V01276.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: not dec. _____ Date Analyzed: 07/15/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V01277.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: not dec. _____ Date Analyzed: 07/15/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW30

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V01278.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: not dec. _____ Date Analyzed: 07/15/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1.	unknown hydrocarbon	13.93	5	J

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW31

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V01279.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: not dec. _____ Date Analyzed: 07/15/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW32

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V01287.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: not dec. _____ Date Analyzed: 07/15/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0

(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW33

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V01286.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: not dec. _____ Date Analyzed: 07/15/97
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

Organic Data Qualifiers

Form 1:

This form reports concentrations of Tentatively Identified Compounds. Form 1E is the Volatile report, Form 1F is for Semi-Volatiles.

Qualifiers are:

- J** Estimated Value
- N** Presumptive evidence of a compound
- E** Concentration exceeds calibration range
- D** Diluted sample
- A** TIC is a suspected aldol condensation product

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN0323.D**
 Operator **Skelton**
 Date Acquired **07/31/97 14:11**

Sample Name **Extraction Blank**
 Field ID **07/15/97**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40

132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10
84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0341.d**
 Operator **Skelton**
 Date Acquired **08/ 1/97 05:49**

Sample Name **2788.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0342.d**
 Operator **Skelton**
 Date Acquired **08/ 1/97 06:36**

Sample Name **2788.03**
 Field ID **Bldg 2700 MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.44	82010	0.98 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0343.d**
 Operator **Skelton**
 Date Acquired **08/ 1/97 07:23**

Sample Name **2788.04**
 Field ID **Bldg 2700 MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0345.d**
 Operator **Skelton**
 Date Acquired **08/ 1/97 08:59**

Sample Name **2788.06**
 Field ID **Bldg 2700 MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.44	153602	1.63 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0344.d**
 Operator **Skelton**
 Date Acquired **08/ 1/97 08:10**

Sample Name **2788.05**
 Field ID **Bldg 2700 MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40
132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10

84-66-2	Diethylphthalate			not detected	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.44	180698	1.98 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

SBLK

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: _____ Location _____ SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Extraction Blau
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0323.D
Level: (low/med) LOW Date Received: _____
% Moisture: _____ decanted: (Y/N) N Date Analyzed: 07/31/97
Concentrated Extract Volume: 1000 (uL) Dilution Factor: 1.0
Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 2788 Location B.2700 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 2788.02

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0341.D

Level: (low/med) LOW Date Received: 07/10/97

% Moisture: _____ decanted: (Y/N) N Date Analyzed: 08/01/97

Concentrated Extract Volume: 1000 (uL) Dilution Factor: 1.0

Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW30

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.03
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0342.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: _____ decanted: (Y/N) N Date Analyzed: 08/01/97
Concentrated Extract Volume: 1000 (uL) Dilution Factor: 1.0
Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW31

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.04
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0343.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: _____ decanted: (Y/N) N Date Analyzed: 08/01/97
Concentrated Extract Volume: 1000 (uL) Dilution Factor: 1.0
Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW32

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.06
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0345.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: _____ decanted: (Y/N) N Date Analyzed: 08/01/97
Concentrated Extract Volume: 1000 (uL) Dilution Factor: 1.0
Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000112-92-5	1-Octadecanol	24.98	9	JN
2.	unknown hydrocarbon	27.13	11	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW33

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 2788 Location B.2700 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 2788.05
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0344.D
Level: (low/med) LOW Date Received: 07/10/97
% Moisture: _____ decanted: (Y/N) N Date Analyzed: 08/01/97
Concentrated Extract Volume: 1000 (uL) Dilution Factor: 1.0
Injection Volume: 1.0 (uL) Soil Aliquot Volume: 1 (uL)
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000112-92-5	1-Octadecanol	24.98	11	JN
2.	unknown hydrocarbon	27.13	12	J

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	Extraction Blank
	DPW, SELFM-PW-EV	Date Rec'd:	NA
	Bldg. 173	Extraction Date:	7/14/97
	Ft. Monmouth, NJ 07703	Analysis Date:	8/18/97

Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary: Rtx-5 30m/.32mmID/.25um

Column-Confirmation: Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 2788.02
DPW, SELFM-PW-EV Date Rec'd: 7/10/97
Bldg. 173 Extraction Date: 7/14/97
Ft. Monmouth, NJ 07703 Analysis Date: 8/18/97

Analysis: EPA Method 608 Location : CW-2
Matrix: Aqueous
Analyst: D. Wright Field ID: Field Blank
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	2788.03
	DPW, SELFM-PW-EV	Date Rec'd:	7/10/97
	Bldg. 173	Extraction Date:	7/14/97
	Ft. Monmouth, NJ 07703	Analysis Date:	8/19/97

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-30
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary: Rtx-5 30m/.32mmID/.25um

Column-Confirmation: Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 2788.04
DPW, SELFM-PW-EV Date Rec'd: 7/10/97
Bldg. 173 Extraction Date: 7/14/97
Ft. Monmouth, NJ 07703 Analysis Date: 8/19/97

Analysis: EPA Method 608 Location : CW-2
Matrix: Aqueous
Analyst: D. Wright Field ID: MW-31
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary: Rtx-5 30m/.32mmID/.25um
Column-Confirmation: Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID #:	2788.06
	DPW, SELFM-PW-EV	Date Rec'd:	7/10/97
	Bldg. 173	Extraction Date:	7/14/97
	Ft. Monmouth, NJ 07703	Analysis Date:	8/19/97

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-32
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary: Rtx-5 30m/.32mmID/.25um

Column-Confirmation: Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID #: 2788.05
DPW, SELFM-PW-EV Date Rec'd: 7/10/97
Bldg. 173 Extraction Date: 7/14/97
Ft. Monmouth, NJ 07703 Analysis Date: 8/19/97

Analysis: EPA Method 608 Location: CW-2
Matrix: Aqueous
Analyst: D. Wright Field ID: MW-33
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NA	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NA	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NA	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NA = Not Applicable

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: Method Blank
 Sample Received: NA
 Sample Matrix: Aqueous

Site: Bldg. 2700
 Ft. Monmouth, New Jersey

Field ID#: NA

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	08/21/97	ND	0.5	200
Antimony	08/12/97	ND	0.5	20
Arsenic	08/05/97	ND	1.0	8
Barium	10/21/97	ND	30.0	2000
Beryllium	08/13/97	ND	0.06	20
Cadmium	10/24/97	ND	2.0	4
Calcium	07/30/97	ND	30.0	NA
Chromium	07/24/97	ND	0.4	100
Cobalt	09/22/97	ND	20.0	NA
Copper	08/29/97	ND	3.0	1000
Iron	08/27/97	ND	10.0	300
Lead	07/18/97	ND	0.5	10
Manganese	08/27/97	7.0	5.0	50
Magnesium	09/18/97	ND	50.0	NA
Mercury	08/06/97	ND	0.2	2
Nickel	08/29/97	ND	10.0	100
Potassium	09/18/97	ND	40.0	NA
Selenium	08/06/97	ND	1.0	50
Silver	07/21/97	ND	3.0	20
Sodium	09/18/97	ND	10.0	50000
Thallium	08/06/97	ND	1.0	10
Vanadium	08/04/97	ND	1.0	NA
Zinc	08/29/97	ND	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 2788.02
 Sample Received: 7/10/97
 Sample Matrix: Aqueous

Site: Bldg. 2700
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	08/21/97	12.7	0.5	200
Antimony	08/12/97	ND	0.5	20
Arsenic	08/05/97	ND	1.0	8
Barium	10/21/97	ND	30.0	2000
Beryllium	08/13/97	ND	0.06	20
Cadmium	10/24/97	ND	2.0	4
Calcium	07/30/97	220.0	30.0	NA
Chromium	07/24/97	ND	0.4	100
Cobalt	09/22/97	ND	20.0	NA
Copper	08/29/97	ND	3.0	1000
Iron	08/27/97	60.0	10.0	300
Lead	07/18/97	ND	0.5	10
Manganese	08/27/97	26.0	5.0	50
Magnesium	09/18/97	90.0	50.0	NA
Mercury	08/06/97	ND	0.2	2
Nickel	08/29/97	ND	10.0	100
Potassium	09/18/97	ND	40.0	NA
Selenium	08/06/97	ND	1.0	50
Silver	07/21/97	5.0	3.0	20
Sodium	09/18/97	680.0	10.0	50000
Thallium	08/06/97	ND	1.0	10
Vanadium	08/04/97	ND	1.0	NA
Zinc	08/29/97	2.0	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 2788.03
 Sample Received: 7/10/97
 Sample Matrix: Aqueous

Site: Bldg. 2700
 Ft. Monmouth, New Jersey

Field ID#: MW-30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	08/21/97	25.0	0.5	200
Antimony	08/12/97	ND	0.5	20
Arsenic	08/05/97	5.0	1.0	8
Barium	10/21/97	ND	30.0	2000
Beryllium	08/13/97	ND	0.06	20
Cadmium	10/24/97	2.0	2.0	4
Calcium	07/30/97	49030.0	30.0	NA
Chromium	07/24/97	1.0	0.4	100
Cobalt	09/22/97	20.0	20.0	NA
Copper	08/29/97	ND	3.0	1000
Iron	08/27/97	12590.0	10.0	200
Lead	07/18/97	ND	0.5	10
Manganese	08/27/97	73.0	5.0	50
Magnesium	09/18/97	5330.0	50.0	NA
Mercury	08/06/97	ND	0.2	2
Nickel	08/29/97	ND	10.0	100
Potassium	09/18/97	10420.0	40.0	NA
Selenium	08/06/97	2.0	1.0	50
Silver	07/21/97	6.0	3.0	20
Sodium	09/18/97	33050.0	10.0	50000
Thallium	08/06/97	ND	1.0	10
Vanadium	08/04/97	4.0	1.0	NA
Zinc	08/29/97	ND	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 2788.04
 Sample Received: 7/10/97
 Sample Matrix: Aqueous

Site: Bldg. 2700
 Ft. Monmouth, New Jersey

Field ID#: MW-31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	08/21/97	ND	0.5	200
Antimony	08/12/97	ND	0.5	20
Arsenic	08/05/97	1.0	1.0	8
Barium	10/21/97	ND	30.0	2000
Beryllium	08/13/97	ND	0.06	20
Cadmium	10/24/97	ND	2.0	4
Calcium	07/30/97	41990.0	30.0	NA
Chromium	07/24/97	ND	0.4	100
Cobalt	09/22/97	ND	20.0	NA
Copper	08/29/97	ND	3.0	1000
Iron	08/27/97	11830.0	10.0	300
Lead	07/18/97	ND	0.5	10
Manganese	08/27/97	267.0	5.0	50
Magnesium	09/18/97	5780.0	50.0	NA
Mercury	08/06/97	ND	0.2	2
Nickel	08/29/97	ND	10.0	100
Potassium	09/18/97	9560.0	40.0	NA
Selenium	08/06/97	1.0	1.0	50
Silver	07/21/97	7.0	3.0	20
Sodium	09/18/97	11420.0	10.0	50000
Thallium	08/06/97	ND	1.0	10
Vanadium	08/04/97	ND	1.0	NA
Zinc	08/29/97	ND	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 2788.06
 Sample Received: 7/10/97
 Sample Matrix: Aqueous

Site: Bldg. 2700
 Ft. Monmouth, New Jersey

Field ID#:MW-32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	08/21/97	2.1	0.5	200
Antimony	08/12/97	ND	0.5	20
Arsenic	08/05/97	1.0	1.0	8
Barium	10/21/97	ND	30.0	2000
Beryllium	08/13/97	ND	0.06	20
Cadmium	10/24/97	ND	2.0	4
Calcium	07/30/97	80510.0	30.0	NA
Chromium	07/24/97	ND	0.4	100
Cobalt	09/22/97	ND	20.0	NA
Copper	08/29/97	ND	3.0	1000
Iron	08/27/97	270.0	10.0	300
Lead	07/18/97	ND	0.5	10
Manganese	08/27/97	181.0	5.0	50
Magnesium	09/18/97	9830.0	50.0	NA
Mercury	08/06/97	ND	0.2	2
Nickel	08/29/97	ND	10.0	100
Potassium	09/18/97	8340.0	40.0	NA
Selenium	08/06/97	1.0	1.0	50
Silver	07/21/97	7.0	3.0	20
Sodium	09/18/97	22950.0	10.0	50000
Thallium	08/06/97	ND	1.0	10
Vanadium	08/04/97	ND	1.0	NA
Zinc	08/29/97	16.0	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 2788.05
 Sample Received: 7/10/97
 Sample Matrix: Aqueous

Site: Bldg. 2700
 Ft. Monmouth, New Jersey

Field ID#:MW-33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	MDL (ug/L)	GW Criteria (ug/L)
Aluminum	08/21/97	595.1	0.5	200
Antimony	08/12/97	ND	0.5	20
Arsenic	08/05/97	ND	1.0	8
Barium	10/21/97	670.0	30.0	2000
Beryllium	08/13/97	0.08	0.06	20
Cadmium	10/24/97	ND	2.0	4
Calcium	07/30/97	75930.0	30.0	NA
Chromium	07/24/97	ND	0.4	100
Cobalt	09/22/97	ND	20.0	NA
Copper	08/29/97	8.0	3.0	1000
Iron	08/27/97	10260.0	10.0	300
Lead	07/18/97	ND	0.5	10
Manganese	08/27/97	519.0	5.0	50
Magnesium	09/18/97	8250.0	50.0	NA
Mercury	08/06/97	ND	0.2	2
Nickel	08/29/97	ND	10.0	100
Potassium	09/18/97	12400.0	40.0	NA
Selenium	08/06/97	ND	1.0	50
Silver	07/21/97	8.0	3.0	20
Sodium	09/18/97	13630.0	10.0	50000
Thallium	08/06/97	ND	1.0	10
Vanadium	08/04/97	ND	1.0	NA
Zinc	08/29/97	24.0	2.0	5000

ND = Not Detected, MDL = Method Detection Limit, NA = Not Applicable

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-3484

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
3088.03	MW-30	29-32594	10/22/97
3088.04	MW-31	29-32595	10/22/97
3088.05	MW-32	29-32596	10/22/97
3088.06	MW-33	29-32597	10/22/97

NJDEP Laboratory Certification # 13461

Report Date: 8 January, 1998


Daniel Wright
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (908)532-4359 Fax (908)532-3484 EMail:appleby@doim6.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: <u>J. Fallon</u>				Project No:		Analysis Parameters							Comments:	
Phone #: <u>x 26223</u>				Location: <u>Bldg 1700</u>		VOA + 15	TAL METALS	TEL BNA + 15	TEL Pest/ P/B					HNU
() DERA () OMA () Other:														
Samplers Name / Company: <u>Ryan Bobwist / TUS</u>				Sample #										
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles								Remarks / Preservation Method	
3088 01	TRIP Blank	10/22/97	0800	AG	2	X							All Samples kept ≤ 40C	
02	Field Blank		1000		5	X	X	X	X				VOA- Hel	
03	MW 30 #2932594		1130									0	Metals- HNO ₃	
04	MW 31 #2932595		1140									0		
05	MW 32 #2932596		1450									0		
06	MW 33 #2932597		1910									0		
07	Field Dup											0		
Relinquished by (signature): <u>Thayer C. Post</u>				Date/Time: <u>10/23/97 1540</u>		Received by (signature): <u>[Signature]</u>				Date/Time:		Received by (signature):		
Relinquished by (signature):				Date/Time:		Relinquished by (signature):				Date/Time:		Received by (signature):		
Report Type: () Full, () Reduced, ☒ Standard, () Screen / non-certified						Remarks:								
Turnaround time: ☒ Standard 4 wks, () Rush _____ Days, () ASAP Verbal _____ Hrs.														

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATASHEET

SITE: CW-2

MW#: 30

NJDEP ID# 2932594

NJDEP CERT# 13461

SAMPLING CONTRATOR TVS

SAMPLER RAY POGWIST

DATE: 10/22/97

WEATHER: SUNNY 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 7.60

DEPTH OF WELL: 17.90

HEIGHT OF WATER: 10.3

10.3 X 0.65 X 3 = 20.085

GAL OF H2O TO BE EVACUATED: 20.2 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

Hnu READING: PPM 0

PURGE START TIME: 9:45

pH: 6.70 TEMP 17.5 DEG °C

DISSOLVED O2 2.6 PPM SPECIFIC CONDUCTIVITY 480 us/cm

PURGE END TIME: 11:26

pH: 6.66 TEMP 20.5 DEG °C

DISSOLVED O2 4.2 PPM SPECIFIC CONDUCTIVITY 460 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 12.0 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon @ bailer

TOTAL VOLUME PURGED: 20.2 GAL

pH: 6.65 TEMP 20.6 DEG °C

DISSOLVED O2 4.1 PPM SPECIFIC CONDUCTIVITY 450 us/cm

COMMENTS: _____

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATASHEET

SITE: CW-2

MW#: 31

NJDEP ID# 2932595

NJDEP CERT# 13461

SAMPLING CONTRATOR TVS

SAMPLER RAY POGWIST

DATE: 10/22/97

WEATHER: SUNNY 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 7.50

DEPTH OF WELL: 16.80

HEIGHT OF WATER: 9.30

9.30 X 0.65 X 3 = 18.135

GAL OF H2O TO BE EVACUATED: 18.2 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

Hnu READING: PPM 0

PURGE START TIME: 10:00

pH: 6.84 TEMP 17.5 DEG °C

DISSOLVED O2 3.0 PPM SPECIFIC CONDUCTIVITY 470 us/cm

PURGE END TIME: 11:31

pH: 6.62 TEMP 19.4 DEG °C

DISSOLVED O2 4.4 PPM SPECIFIC CONDUCTIVITY 340 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 10.50 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 18.2 GAL

pH: 6.64 TEMP 19.3 DEG °C

DISSOLVED O2 4.4 PPM SPECIFIC CONDUCTIVITY 330 us/cm

COMMENTS: _____

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

SITE: CW-2

MW#: 32

NJDEP ID# 2932596

NJDEP CERT# 13461

SAMPLING CONTRATOR TVS

SAMPLER RAY POGWIST

DATE: 10/22/97

WEATHER: SUNNY 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 7.70

DEPTH OF WELL: 16.80

HEIGHT OF WATER: 9.10

9.10 X 0.65 X 3 = 17.745

GAL OF H2O TO BE EVACUATED: 17.8 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

Hnu READING: PPM 0

PURGE START TIME: 13:15

pH: 8.22 TEMP 18.1 DEG °C

DISSOLVED O2 2.6 PPM SPECIFIC CONDUCTIVITY 360 us/cm

PURGE END TIME: 14:49

pH: 7.38 TEMP 18.5 DEG °C

DISSOLVED O2 3.6 PPM SPECIFIC CONDUCTIVITY 390 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 12.30 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 17.8 GAL

pH: 7.35 TEMP 18.5 DEG °C

DISSOLVED O2 3.8 PPM SPECIFIC CONDUCTIVITY 400 us/cm

COMMENTS: _____

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATASHEET

SITE: CW-2

MW#: 33

NJDEP ID# 2932597

NJDEP CERT# 13461

SAMPLING CONTRATOR TVS

SAMPLER RAY POGWIST

DATE: 10/22/97

WEATHER: SUNNY 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 9.10

DEPTH OF WELL: 16.00

HEIGHT OF WATER: 6.90

6.90 X 0.65 X 3 = 13.455

GAL OF H2O TO BE EVACUATED: 13.6 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

Hnu READING: PPM 0

PURGE START TIME: 13:00

pH: 6.30 TEMP 18.1 DEG °C

DISSOLVED O2 1.9 PPM SPECIFIC CONDUCTIVITY 460 us/cm

PURGE END TIME: 14:08

pH: 5.92 TEMP 20.3 DEG °C

DISSOLVED O2 1.8 PPM SPECIFIC CONDUCTIVITY 330 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 9.15 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon @ bailer

TOTAL VOLUME PURGED: 13.6 GAL

pH: 5.96 TEMP 20.5 DEG °C

DISSOLVED O2 1.8 PPM SPECIFIC CONDUCTIVITY 300 us/cm

COMMENTS: _____

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit
J : Compound identified below detection limit
B : Compound in both sample and blank
D : Results from dilution of sample
U : Compound searched for but not detected

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02292.d
 Operator Skelton
 Date Acquired 10/24/19 -1:3:

Sample Name Daily Blank
 Field ID Daily Blank
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Amount	MDL	Qualifiers	GW Criteria
107028	Acrolein			not detected	6.25 ug/L		na
107131	Acrylonitrile			not detected	6.25 ug/L		na
75650	tert-Butyl alcohol			not detected	12.50 ug/L		na
1634044	Methyl-tert-Butyl ether			not detected	2.50 ug/L		na
108203	Di-isopropyl ether			not detected	1.25 ug/L		na
	Dichlorodifluoromethane			not detected	3.63 ug/L		na
74-87-3	Chloromethane			not detected	0.79 ug/L		30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L		5
74-83-9	Bromomethane			not detected	1.45 ug/L		10
75-00-3	Chloroethane			not detected	2.20 ug/L		na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L		na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L		2
67-64-1	Acetone			not detected	1.57 ug/L		700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L		na
75-09-2	Methylene Chloride			not detected	1.66 ug/L		2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L		100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L		70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L		na
78-93-3	2-Butanone			not detected	2.06 ug/L		300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L		10
67-66-3	Chloroform			not detected	0.43 ug/L		6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L		30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L		2
71-43-2	Benzene			not detected	0.51 ug/L		1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L		2
79-01-6	Trichloroethene			not detected	0.94 ug/L		1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L		1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L		1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L		na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L		na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L		400
108-88-3	Toluene			not detected	0.73 ug/L		1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L		na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L		3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L		1
591-78-6	2-Hexanone			not detected	1.12 ug/L		na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L		10
108-90-7	Chlorobenzene			not detected	0.66 ug/L		4
100-41-4	Ethylbenzene			not detected	1.14 ug/L		700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L		na
1330-20-7	o-Xylene			not detected	1.92 ug/L		na
100-42-5	Styrene			not detected	1.57 ug/L		100
75-25-2	Bromoform			not detected	1.68 ug/L		4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L		2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L		600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L		74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L		600

Qualifiers

B = Compound found in related blank

E = Value above linier range

D = Value from dilution

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02293.d
 Operator Skelton
 Date Acquired 10/24/19 -1:4:

Sample Name 3088.01
 Field ID Trip Blank
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Amount	MDL	Qualifiers	GW Criteria
107028	Acrolein			not detected	6.25 ug/L		na
107131	Acrylonitrile			not detected	6.25 ug/L		na
75650	tert-Butyl alcohol			not detected	12.50 ug/L		na
1634044	Methyl-tert-Butyl ether			not detected	2.50 ug/L		na
108203	Di-isopropyl ether			not detected	1.25 ug/L		na
	Dichlorodifluoromethane			not detected	3.63 ug/L		na
74-87-3	Chloromethane			not detected	0.79 ug/L		30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L		5
74-83-9	Bromomethane			not detected	1.45 ug/L		10
75-00-3	Chloroethane			not detected	2.20 ug/L		na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L		na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L		2
67-64-1	Acetone			not detected	1.57 ug/L		700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L		na
75-09-2	Methylene Chloride			not detected	1.66 ug/L		2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L		100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L		70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L		na
78-93-3	2-Butanone			not detected	2.06 ug/L		300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L		10
67-66-3	Chloroform			not detected	0.43 ug/L		6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L		30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L		2
71-43-2	Benzene			not detected	0.51 ug/L		1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L		2
79-01-6	Trichloroethene			not detected	0.94 ug/L		1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L		1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L		1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L		na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L		na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L		400
108-88-3	Toluene			not detected	0.73 ug/L		1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L		na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L		3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L		1
591-78-6	2-Hexanone			not detected	1.12 ug/L		na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L		10
108-90-7	Chlorobenzene			not detected	0.66 ug/L		4
100-41-4	Ethylbenzene			not detected	1.14 ug/L		700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L		na
1330-20-7	o-Xylene			not detected	1.92 ug/L		na
100-42-5	Styrene			not detected	1.57 ug/L		100
75-25-2	Bromoform			not detected	1.68 ug/L		4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L		2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L		600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L		74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L		600

Qualifiers

B = Compound found in related blank

E = Value above linier range

D = Value from dilution

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02294.d
 Operator Skelton
 Date Acquired 10/24/19 -1:5:

Sample Name 3088.02
 Field ID Field Blank
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Amount	MDL	Qualifiers	GW Criteria
107028	Acrolein			not detected	6.25 ug/L		na
107131	Acrylonitrile			not detected	6.25 ug/L		na
75650	tert-Butyl alcohol			not detected	12.50 ug/L		na
1634044	Methyl-tert-Butyl ether			not detected	2.50 ug/L		na
108203	Di-isopropyl ether			not detected	1.25 ug/L		na
	Dichlorodifluoromethane			not detected	3.63 ug/L		na
74-87-3	Chloromethane			not detected	0.79 ug/L		30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L		5
74-83-9	Bromomethane			not detected	1.45 ug/L		10
75-00-3	Chloroethane			not detected	2.20 ug/L		na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L		na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L		2
67-64-1	Acetone			not detected	1.57 ug/L		700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L		na
75-09-2	Methylene Chloride			not detected	1.66 ug/L		2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L		100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L		70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L		na
78-93-3	2-Butanone			not detected	2.06 ug/L		300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L		10
67-66-3	Chloroform			not detected	0.43 ug/L		6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L		30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L		2
71-43-2	Benzene			not detected	0.51 ug/L		1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L		2
79-01-6	Trichloroethene			not detected	0.94 ug/L		1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L		1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L		1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L		na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L		na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L		400
108-88-3	Toluene			not detected	0.73 ug/L		1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L		na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L		3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L		1
591-78-6	2-Hexanone			not detected	1.12 ug/L		na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L		10
108-90-7	Chlorobenzene			not detected	0.66 ug/L		4
100-41-4	Ethylbenzene			not detected	1.14 ug/L		700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L		na
1330-20-7	o-Xylene			not detected	1.92 ug/L		na
100-42-5	Styrene			not detected	1.57 ug/L		100
75-25-2	Bromoform			not detected	1.68 ug/L		4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L		2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L		600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L		74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L		600

Qualifiers

B = Compound found in related blank

E = Value above linier range

D = Value from dilution

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02297.d
 Operator Skelton
 Date Acquired 10/24/19 -1:7:

Sample Name 3088.03
 Field ID MW30
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Amount	MDL	Qualifiers	GW Criteria
107028	Acrolein			not detected	6.25 ug/L		na
107131	Acrylonitrile			not detected	6.25 ug/L		na
75650	tert-Butyl alcohol			not detected	12.50 ug/L		na
1634044	Methyl-tert-Butyl ether			not detected	2.50 ug/L		na
108203	Di-isopropyl ether			not detected	1.25 ug/L		na
	Dichlorodifluoromethane			not detected	3.63 ug/L		na
74-87-3	Chloromethane			not detected	0.79 ug/L		30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L		5
74-83-9	Bromomethane			not detected	1.45 ug/L		10
75-00-3	Chloroethane			not detected	2.20 ug/L		na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L		na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L		2
67-64-1	Acetone			not detected	1.57 ug/L		700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L		na
75-09-2	Methylene Chloride			not detected	1.66 ug/L		2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L		100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L		70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L		na
78-93-3	2-Butanone			not detected	2.06 ug/L		300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L		10
67-66-3	Chloroform			not detected	0.43 ug/L		6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L		30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L		2
71-43-2	Benzene			not detected	0.51 ug/L		1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L		2
79-01-6	Trichloroethene			not detected	0.94 ug/L		1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L		1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L		1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L		na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L		na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L		400
108-88-3	Toluene			not detected	0.73 ug/L		1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L		na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L		3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L		1
591-78-6	2-Hexanone			not detected	1.12 ug/L		na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L		10
108-90-7	Chlorobenzene			not detected	0.66 ug/L		4
100-41-4	Ethylbenzene			not detected	1.14 ug/L		700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L		na
1330-20-7	o-Xylene			not detected	1.92 ug/L		na
100-42-5	Styrene			not detected	1.57 ug/L		100
75-25-2	Bromoform			not detected	1.68 ug/L		4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L		2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L		600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L		74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L		600

Qualifiers

B = Compound found in related blank

E = Value above linier range

D = Value from dilution

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02298.d
 Operator Skelton
 Date Acquired 10/24/19 -1:8:

Sample Name 3088.04
 Field ID MW31
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Amount	MDL	Qualifiers	GW Criteria
107028	Acrolein			not detected	6.25 ug/L		na
107131	Acrylonitrile			not detected	6.25 ug/L		na
75650	tert-Butyl alcohol			not detected	12.50 ug/L		na
1634044	Methyl-tert-Butyl ether			not detected	2.50 ug/L		na
108203	Di-isopropyl ether			not detected	1.25 ug/L		na
	Dichlorodifluoromethane			not detected	3.63 ug/L		na
74-87-3	Chloromethane			not detected	0.79 ug/L		30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L		5
74-83-9	Bromomethane			not detected	1.45 ug/L		10
75-00-3	Chloroethane			not detected	2.20 ug/L		na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L		na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L		2
67-64-1	Acetone			not detected	1.57 ug/L		700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L		na
75-09-2	Methylene Chloride			not detected	1.66 ug/L		2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L		100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L		70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L		na
78-93-3	2-Butanone			not detected	2.06 ug/L		300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L		10
67-66-3	Chloroform			not detected	0.43 ug/L		6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L		30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L		2
71-43-2	Benzene			not detected	0.51 ug/L		1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L		2
79-01-6	Trichloroethene			not detected	0.94 ug/L		1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L		1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L		1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L		na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L		na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L		400
108-88-3	Toluene			not detected	0.73 ug/L		1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L		na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L		3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L		1
591-78-6	2-Hexanone			not detected	1.12 ug/L		na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L		10
108-90-7	Chlorobenzene			not detected	0.66 ug/L		4
100-41-4	Ethylbenzene			not detected	1.14 ug/L		700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L		na
1330-20-7	o-Xylene			not detected	1.92 ug/L		na
100-42-5	Styrene			not detected	1.57 ug/L		100
75-25-2	Bromoform			not detected	1.68 ug/L		4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L		2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L		600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L		74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L		600

Qualifiers

B = Compound found in related blank

E = Value above linier range

D = Value from dilution

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02299.d
 Operator Skelton
 Date Acquired 10/24/19 -1:8:

Sample Name 3088.05
 Field ID MW32
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Amount	MDL	Qualifiers	GW Criteria
107028	Acrolein			not detected	6.25 ug/L		na
107131	Acrylonitrile			not detected	6.25 ug/L		na
75650	tert-Butyl alcohol			not detected	12.50 ug/L		na
1634044	Methyl-tert-Butyl ether			not detected	2.50 ug/L		na
108203	Di-isopropyl ether			not detected	1.25 ug/L		na
	Dichlorodifluoromethane			not detected	3.63 ug/L		na
74-87-3	Chloromethane			not detected	0.79 ug/L		30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L		5
74-83-9	Bromomethane			not detected	1.45 ug/L		10
75-00-3	Chloroethane			not detected	2.20 ug/L		na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L		na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L		2
67-64-1	Acetone			not detected	1.57 ug/L		700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L		na
75-09-2	Methylene Chloride			not detected	1.66 ug/L		2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L		100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L		70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L		na
78-93-3	2-Butanone			not detected	2.06 ug/L		300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L		10
67-66-3	Chloroform			not detected	0.43 ug/L		6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L		30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L		2
71-43-2	Benzene			not detected	0.51 ug/L		1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L		2
79-01-6	Trichloroethene			not detected	0.94 ug/L		1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L		1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L		1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L		na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L		na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L		400
108-88-3	Toluene			not detected	0.73 ug/L		1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L		na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L		3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L		1
591-78-6	2-Hexanone			not detected	1.12 ug/L		na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L		10
108-90-7	Chlorobenzene			not detected	0.66 ug/L		4
100-41-4	Ethylbenzene			not detected	1.14 ug/L		700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L		na
1330-20-7	o-Xylene			not detected	1.92 ug/L		na
100-42-5	Styrene			not detected	1.57 ug/L		100
75-25-2	Bromoform			not detected	1.68 ug/L		4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L		2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L		600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L		74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L		600

Qualifiers

B = Compound found in related blank

E = Value above linier range

D = Value from dilution

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02300.d
 Operator Skelton
 Date Acquired 10/24/19 -1:9:

Sample Name 3088.06
 Field ID MW33
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Amount	MDL	Qualifiers	GW Criteria
107028	Acrolein			not detected	6.25 ug/L		na
107131	Acrylonitrile			not detected	6.25 ug/L		na
75650	tert-Butyl alcohol			not detected	12.50 ug/L		na
1634044	Methyl-tert-Butyl ether			not detected	2.50 ug/L		na
108203	Di-isopropyl ether			not detected	1.25 ug/L		na
	Dichlorodifluoromethane			not detected	3.63 ug/L		na
74-87-3	Chloromethane			not detected	0.79 ug/L		30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L		5
74-83-9	Bromomethane			not detected	1.45 ug/L		10
75-00-3	Chloroethane			not detected	2.20 ug/L		na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L		na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L		2
67-64-1	Acetone			not detected	1.57 ug/L		700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L		na
75-09-2	Methylene Chloride			not detected	1.66 ug/L		2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L		100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L		70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L		na
78-93-3	2-Butanone			not detected	2.06 ug/L		300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L		10
67-66-3	Chloroform			not detected	0.43 ug/L		6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L		30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L		2
71-43-2	Benzene			not detected	0.51 ug/L		1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L		2
79-01-6	Trichloroethene			not detected	0.94 ug/L		1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L		1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L		1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L		na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L		na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L		400
108-88-3	Toluene			not detected	0.73 ug/L		1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L		na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L		3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L		1
591-78-6	2-Hexanone			not detected	1.12 ug/L		na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L		10
108-90-7	Chlorobenzene			not detected	0.66 ug/L		4
100-41-4	Ethylbenzene			not detected	1.14 ug/L		700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L		na
1330-20-7	o-Xylene			not detected	1.92 ug/L		na
100-42-5	Styrene			not detected	1.57 ug/L		100
75-25-2	Bromoform			not detected	1.68 ug/L		4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L		2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L		600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L		74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L		600

Qualifiers

B = Compound found in related blank

E = Value above linier range

D = Value from dilution

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02301.d
 Operator Skelton
 Date Acquired 10/24/19 -1:0:

Sample Name 3088.07
 Field ID Field Dup
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Amount	MDL	Qualifiers	GW Criteria
107028	Acrolein			not detected	6.25 ug/L		na
107131	Acrylonitrile			not detected	6.25 ug/L		na
75650	tert-Butyl alcohol			not detected	12.50 ug/L		na
1634044	Methyl-tert-Butyl ether			not detected	2.50 ug/L		na
108203	Di-isopropyl ether			not detected	1.25 ug/L		na
	Dichlorodifluoromethane			not detected	3.63 ug/L		na
74-87-3	Chloromethane			not detected	0.79 ug/L		30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L		5
74-83-9	Bromomethane			not detected	1.45 ug/L		10
75-00-3	Chloroethane			not detected	2.20 ug/L		na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L		na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L		2
67-64-1	Acetone			not detected	1.57 ug/L		700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L		na
75-09-2	Methylene Chloride			not detected	1.66 ug/L		2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L		100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L		70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L		na
78-93-3	2-Butanone			not detected	2.06 ug/L		300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L		10
67-66-3	Chloroform			not detected	0.43 ug/L		6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L		30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L		2
71-43-2	Benzene			not detected	0.51 ug/L		1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L		2
79-01-6	Trichloroethene			not detected	0.94 ug/L		1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L		1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L		1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L		na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L		na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L		400
108-88-3	Toluene			not detected	0.73 ug/L		1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L		na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L		3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L		1
591-78-6	2-Hexanone			not detected	1.12 ug/L		na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L		10
108-90-7	Chlorobenzene			not detected	0.66 ug/L		4
100-41-4	Ethylbenzene			not detected	1.14 ug/L		700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L		na
1330-20-7	o-Xylene			not detected	1.92 ug/L		na
100-42-5	Styrene			not detected	1.57 ug/L		100
75-25-2	Bromoform			not detected	1.68 ug/L		4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L		2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L		600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L		74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L		600

Qualifiers

B = Compound found in related blank

E = Value above linier range

D = Value from dilution

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

Daily Blank

Lab Name: FMETL NJDEP # 13461
Project: _____ Case No.: 3088 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Daily Blank
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02292.D
Level: (low/med) LOW Date Received: 10/23/97
% Moisture: not dec. _____ Date Analyzed: 10/24/97
GC Column: Rtx502.2 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

Trip Blank

Lab Name: FMETL NJDEP # 13461
Project: _____ Case No.: 3088 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3088.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02293.D
Level: (low/med) LOW Date Received: 10/23/97
% Moisture: not dec. _____ Date Analyzed: 10/24/97
GC Column: Rtx502.2 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

Field Blank

Lab Name: FMETL NJDEP # 13461
Project: _____ Case No.: 3088 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3088.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02294.D
Level: (low/med) LOW Date Received: 10/23/97
% Moisture: not dec. _____ Date Analyzed: 10/24/97
GC Column: Rtx502.2 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

MW30

Lab Name: FMETL NJDEP # 13461
Project: _____ Case No.: 3088 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3088.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02297.D
Level: (low/med) LOW Date Received: 10/23/97
% Moisture: not dec. _____ Date Analyzed: 10/24/97
GC Column: Rtx502.2 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1.	unknown hydrocarbon	13.83	6	J

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

MW31

Lab Name: FMETL NJDEP # 13461
Project: _____ Case No.: 3088 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3088.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02298.D
Level: (low/med) LOW Date Received: 10/23/97
% Moisture: not dec. _____ Date Analyzed: 10/24/97
GC Column: Rtx502.2 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1.	unknown hydrocarbon	13.83	11	J

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

MW32

Lab Name: FMETL NJDEP # 13461
Project: _____ Case No.: 3088 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3088.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02299.D
Level: (low/med) LOW Date Received: 10/23/97
% Moisture: not dec. _____ Date Analyzed: 10/24/97
GC Column: Rtx502.2 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

MW33

Lab Name: FMETL NJDEP # 13461
Project: _____ Case No.: 3088 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3088.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02300.D
Level: (low/med) LOW Date Received: 10/23/97
% Moisture: not dec. _____ Date Analyzed: 10/24/97
GC Column: Rtx502.2 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1.	unknown hydrocarbon	6.50	10	J
2.	unknown hydrocarbon	13.83	7	J

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

Field Dup

Lab Name: FMETL NJDEP # 13461
Project: _____ Case No.: 3088 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3088.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02301.D
Level: (low/med) LOW Date Received: 10/23/97
% Moisture: not dec. _____ Date Analyzed: 10/24/97
GC Column: Rtx502.2 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0636.d**
 Operator **Skelton**
 Date Acquired **10/28/97 17:38**

Sample Name **Extraction Blank**
 Field ID **10/27/97**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40

132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10
84-66-2	Diethylphthalate	16.42	146079	1.66 ug/L	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate			not detected	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0642.d**
 Operator **Skelton**
 Date Acquired **10/28/97 21:53**

Sample Name **3088.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40

132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10
84-66-2	Diethylphthalate	16.43	173075	1.90 ug/L	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.29	203159	1.35 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0643.d**
 Operator **Skelton**
 Date Acquired **10/28/97 22:36**

Sample Name **3088.03**
 Field ID **MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40

132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10
84-66-2	Diethylphthalate	16.43	425642	4.74 ug/L	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.30	707494	4.73 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate	23.77	75719	1.01 ug/L	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0644.d**
 Operator **Skelton**
 Date Acquired **10/28/97 23:18**

Sample Name **3088.04**
 Field ID **MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40

132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10
84-66-2	Diethylphthalate	16.43	153490	1.58 ug/L	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.29	210883	1.30 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0645.d**
 Operator **Skelton**
 Date Acquired **10/29/97 00:00**

Sample Name **3088.05**
 Field ID **MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40

132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10
84-66-2	Diethylphthalate	16.43	172779	1.95 ug/L	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.29	214070	1.45 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate			not detected	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0646.d**
 Operator **Skelton**
 Date Acquired **10/29/97 00:42**

Sample Name **3088.06**
 Field ID **MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40

132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10
84-66-2	Diethylphthalate	16.43	427149	4.65 ug/L	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.29	718494	4.67 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benzydine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate	23.77	88747	1.17 ug/L	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0647.d**
 Operator **Skelton**
 Date Acquired **10/29/97 01:24**

Sample Name **3088.07**
 Field ID **Field Dup**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
110-86-1	Pyridine			not detected	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	0.94 ug/L	20
62-53-3	Aniline			not detected	0.15 ug/L	
108-95-2	Phenol			not detected	0.47 ug/L	4000
111-44-4	bis(2-Chloroethyl)ether			not detected	0.48 ug/L	10
95-57-8	2-Chlorophenol			not detected	0.18 ug/L	40
541-73-1	1,3-Dichlorobenzene			not detected	0.15 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	0.23 ug/L	75
100-51-6	Benzyl alcohol			not detected	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	0.16 ug/L	600
	2-Methylphenol			not detected	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	0.61 ug/L	300
	4-Methylphenol			not detected	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	0.36 ug/L	20
67-72-1	Hexachloroethane			not detected	0.33 ug/L	10
98-95-3	Nitrobenzene			not detected	0.46 ug/L	10
78-59-1	Isophorone			not detected	0.35 ug/L	100
88-75-5	2-Nitrophenol			not detected	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	0.27 ug/L	100
111-91-1	bis(2-Chloroethoxy)methane			not detected	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	0.12 ug/L	20
65-85-0	Benzoic Acid			not detected	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	0.25 ug/L	9
91-20-3	Naphthalene			not detected	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	0.38 ug/L	1
59-50-7	4-Chloro-3-methylphenol			not detected	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	1.50 ug/L	50
88-06-2	2,4,6-Trichlorophenol			not detected	0.42 ug/L	20
	2,4,5-Trichlorophenol			not detected	0.31 ug/L	700
91-58-7	2-Chloronaphthalene			not detected	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	0.18 ug/L	7000
208-96-8	Acenaphthylene			not detected	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	0.26 ug/L	
83-32-9	Acenaphthene			not detected	0.26 ug/L	400
51-28-5	2,4-Dinitrophenol			not detected	0.69 ug/L	40

132-64-9	Dibenzofuran			not detected	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	0.27 ug/L	
121-14-2	2,4-Dinitrotoluene			not detected	0.36 ug/L	10
84-66-2	Diethylphthalate	16.43	388876	4.47 ug/L	0.82 ug/L	5000
86-73-7	Fluorene			not detected	0.29 ug/L	300
7005-72-3	4-Chlorophenyl-phenylether			not detected	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	0.23 ug/L	20
103-33-3	Azobenzene			not detected	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	0.82 ug/L	10
87-86-5	Pentachlorophenol			not detected	1.08 ug/L	1
85-01-8	Phenanthrene			not detected	0.18 ug/L	
120-12-7	Anthracene			not detected	0.19 ug/L	2000
84-74-2	Di-n-butylphthalate	20.30	722116	5.03 ug/L	0.23 ug/L	900
206-44-0	Fluoranthene			not detected	0.41 ug/L	300
92-87-5	Benidine			not detected	1.45 ug/L	50
129-00-0	Pyrene			not detected	0.32 ug/L	200
85-68-7	Butylbenzylphthalate	23.77	110095	1.52 ug/L	0.47 ug/L	100
56-55-3	Benzo[a]anthracene			not detected	0.22 ug/L	10
91-94-1	3,3'-Dichlorobenzidine			not detected	0.46 ug/L	60
218-01-9	Chrysene			not detected	0.20 ug/L	20
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	0.51 ug/L	30
117-84-0	Di-n-octylphthalate			not detected	0.82 ug/L	100
205-99-2	Benzo[b]fluoranthene			not detected	0.37 ug/L	10
207-08-9	Benzo[k]fluoranthene			not detected	0.32 ug/L	2
50-32-8	Benzo[a]pyrene			not detected	0.31 ug/L	20
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	0.79 ug/L	20
53-70-3	Dibenz[a,h]anthracene			not detected	0.28 ug/L	20
191-24-2	Benzo[g,h,i]perylene			not detected	0.40 ug/L	

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

EXT. BLANK

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 3088 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Extraction Blank
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0636.D
Level: (low/med) LOW Date Received: 10/22/97
% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/27/97
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/28/97
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	5.04	32	JN
2. 000111-46-6	Ethanol, 2,2'-oxybis-	7.60	31	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 3088 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3088.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0642.D
Level: (low/med) LOW Date Received: 10/22/97
% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/27/97
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/28/97
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown hydrocarbon	5.04	22	J
2. 000111-46-6	Ethanol, 2,2'-oxybis-	7.67	57	JN
3. 000084-64-0	1,2-Benzenedicarboxylic acid, but	19.36	9	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW30

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3088 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3088.03

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0643.D

Level: (low/med) LOW Date Received: 10/22/97

% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/27/97

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/28/97

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 5 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown hydrocarbon	5.05	20	J
2. 000111-77-3	Ethanol, 2-(2-methoxyethoxy)-	6.89	11	JN
3. 000111-46-6	Ethanol, 2,2'-oxybis-	7.62	30	JN
4. 000084-74-2	Dibutyl phthalate	19.37	30	JN
5. 000301-02-0	9-Octadecenamide, (Z)-	26.97	8	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW31

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3088 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3088.04

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0644.D

Level: (low/med) LOW Date Received: 10/22/97

% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/27/97

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/28/97

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown hydrocarbon	5.05	17	J
2. 000111-46-6	Ethanol, 2,2'-oxybis-	7.60	34	JN
3. 000084-64-0	1,2-Benzenedicarboxylic acid, but	19.36	9	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW32

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3088 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3088.05

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0645.D

Level: (low/med) LOW Date Received: 10/22/97

% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/27/97

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/29/97

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown hydrocarbon	5.05	29	J
2. 000111-46-6	Ethanol, 2,2'-oxybis-	7.61	40	JN
3. 000084-74-2	Dibutyl phthalate	19.36	8	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW33

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3088 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3088.06

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0646.D

Level: (low/med) LOW Date Received: 10/22/97

% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/27/97

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/29/97

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 4 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	5.06	32	JN
2. 000111-77-3	Ethanol, 2-(2-methoxyethoxy)-	6.88	11	JN
3. 000111-46-6	Ethanol, 2,2'-oxybis-	7.61	30	JN
4. 000084-69-5	1,2-Benzenedicarboxylic acid, bis	19.38	29	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Dup

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3088 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3088.07

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0647.D

Level: (low/med) LOW Date Received: 10/22/97

% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/27/97

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/29/97

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 4 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown hydrocarbon	5.05	28	J
2. 000111-77-3	Ethanol, 2-(2-methoxyethoxy)-	6.88	11	JN
3. 000111-46-6	Ethanol, 2,2'-oxybis-	7.65	49	JN
4. 000084-64-0	1,2-Benzenedicarboxylic acid, but	19.37	28	JN

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	Extraction Blank
	DPW, SELFM-PW-EV	Date Rec'd:	
	Bldg. 173	Extraction Date:	10/23/97
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/97
Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3088.02
	DPW, SELFM-PW-EV	Date Rec'd:	10/22/97
	Bldg. 173	Extraction Date:	10/23/97
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/97
Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	Field Blank
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 3088.03
DPW, SELFM-PW-EV Date Rec'd: 10/22/97
Bldg. 173 Extraction Date: 10/23/97
Ft. Monmouth, NJ 07703 Analysis Date: 12/2/97

Analysis: EPA Method 608 Location : CW-2
Matrix: Aqueous
Analyst: D. Wright Field ID: MW-30
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3088.04
	DPW, SELFM-PW-EV	Date Rec'd:	10/22/97
	Bldg. 173	Extraction Date:	10/23/97
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/97

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-31
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army DPW, SELFM-PW-EV Bldg. 173 Ft. Monmouth, NJ 07703	Lab. ID # : 3088.05 Date Rec'd: 10/22/97 Extraction Date: 10/23/97 Analysis Date: 12/2/97	
---	--	--

Analysis: EPA Method 608 Matrix: Aqueous Analyst: D. Wright Ext. Meth: Sep. Funnel	Location : CW-2 Field ID: MW-32	
---	--	--

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3088.06
	DPW, SELFM-PW-EV	Date Rec'd:	10/22/97
	Bldg. 173	Extraction Date:	10/23/97
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/97

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-33
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3088.07
	DPW, SELFM-PW-EV	Date Rec'd:	10/22/97
	Bldg. 173	Extraction Date:	10/23/97
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/97

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	Field DUP
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: Method Blank
 Sample Received: NA
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: NA

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	ND	200	10.0
Antimony	01/29/98	ND	20	2.0
Arsenic	01/29/98	ND	8	2.0
Barium	01/29/98	ND	2000	0.5
Beryllium	01/29/98	ND	20	0.5
Cadmium	01/29/98	ND	4	0.5
Calcium	01/29/98	ND	NLE	10.0
Chromium	01/29/98	ND	100	0.5
Cobalt	01/29/98	ND	NLE	0.5
Copper	01/29/98	ND	1000	3.0
Iron	01/29/98	ND	300	5.0
Lead	01/29/98	ND	10	2.0
Magnesium	01/29/98	ND	NLE	10.0
Manganese	01/29/98	ND	50	0.5
Mercury	11/10/97	ND	2	0.2
Nickel	01/29/98	ND	100	0.5
Potassium	01/29/98	ND	NLE	10.0
Selenium	01/29/98	ND	50	3.0
Silver	01/29/98	ND	20	3.0
Sodium	01/29/98	ND	50000	10.0
Thallium	01/29/98	ND	10	3.0
Vanadium	01/29/98	ND	NLE	1.0
Zinc	01/29/98	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established,
 NA = Not Applicable

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3088.02
 Sample Received: 10/22/97
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	163.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	4.2	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	1570.0	NLE	20.0
Chromium	01/29/98	1.5	100	1.0
Cobalt	01/29/98	1.6	NLE	1.0
Copper	01/29/98	15.0	1000	6.0
Iron	01/29/98	173.0	300	10.0
Lead	01/29/98	5.0	10	4.0
Magnesium	01/29/98	250.0	NLE	20.0
Manganese	01/29/98	2.9	50	1.0
Mercury	11/10/97	ND	2	0.2
Nickel	01/29/98	2.9	100	1.0
Potassium	01/29/98	ND	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	790.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	82.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3088.03
 Sample Received: 10/22/97
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	175.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	5.0	8	4.0
Barium	01/29/98	112.5	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	68240.0	NLE	20.0
Chromium	01/29/98	2.7	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	17.0	1000	6.0
Iron	01/29/98	34760.0	300	10.0
Lead	01/29/98	5.0	10	4.0
Magnesium	01/29/98	6640.0	NLE	20.0
Manganese	01/29/98	171.3	50	1.0
Mercury	11/10/97	0.2	2	0.2
Nickel	01/29/98	1.5	100	1.0
Potassium	01/29/98	12240.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	19320.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	72.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3088.04
 Sample Received: 10/22/97
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	93.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	197.3	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	45780.0	NLE	20.0
Chromium	01/29/98	11.2	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	11.0	1000	6.0
Iron	01/29/98	52340.0	300	10.0
Lead	01/29/98	6.0	10	4.0
Magnesium	01/29/98	5430.0	NLE	20.0
Manganese	01/29/98	243.5	50	1.0
Mercury	11/10/97	0.6	2	0.2
Nickel	01/29/98	1.4	100	1.0
Potassium	01/29/98	11040.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	11920.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	476.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3088.05
 Sample Received: 10/22/97
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	297.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	166.9	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	67870.0	NLE	20.0
Chromium	01/29/98	11.3	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	17.0	1000	6.0
Iron	01/29/98	51100.0	300	10.0
Lead	01/29/98	7.0	10	4.0
Magnesium	01/29/98	7570.0	NLE	20.0
Manganese	01/29/98	260.7	50	1.0
Mercury	11/10/97	ND	2	0.2
Nickel	01/29/98	2.5	100	1.0
Potassium	01/29/98	13540.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	17300.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	461.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3088.06
 Sample Received: 10/22/97
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	94.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	126.5	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	39300.0	NLE	20.0
Chromium	01/29/98	1.1	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	12.0	1000	6.0
Iron	01/29/98	26770.0	300	10.0
Lead	01/29/98	4.0	10	4.0
Magnesium	01/29/98	5370.0	NLE	20.0
Manganese	01/29/98	151.8	50	1.0
Mercury	11/10/97	0.2	2	0.2
Nickel	01/29/98	1.4	100	1.0
Potassium	01/29/98	7680.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	16360.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	49.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3088.07
 Sample Received: 10/22/97
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Dup.

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	30.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	119.0	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	37940.0	NLE	20.0
Chromium	01/29/98	2.0	100	1.0
Cobalt	01/29/98	1.2	NLE	1.0
Copper	01/29/98	8.0	1000	6.0
Iron	01/29/98	2576.0	300	10.0
Lead	01/29/98	384.0	10	4.0
Magnesium	01/29/98	5100.0	NLE	20.0
Manganese	01/29/98	147.0	50	1.0
Mercury	11/10/97	0.3	2	0.2
Nickel	01/29/98	ND	100	1.0
Potassium	01/29/98	6820.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	17220.0	50000	20.0
Thallium	01/29/98	6.0	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	112.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-3484

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT

FOR

Directorate of Public Works

Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
3271.03	MW-30	29-32594	01/08/98
3271.04	MW-31	29-32595	01/08/98
3271.05	MW-32	29-32596	01/08/98
3271.06	MW-33	29-32597	01/08/98

NJDEP Laboratory Certification # 13461


Report Date: 18 February,1998


Daniel Wright
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (908)532-4359 Fax (908)532-3484 EMail:appleby@doim6.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: <u>I. Fallon</u>		Project No:		Analysis Parameters								Comments:	
Phone #: <u>X 2 6 4 3</u>		Location: <u>Bldg 2700</u>											
(X)DERA ()OMA ()Other:		<u>CLW-2</u>											
Samplers Name / Company: <u>Ray POGWIST / TUS</u>				Sample #									Remarks / Preservation Method
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles	TCL VOA + 15	TAL Metals	TCL BNA 125	TCL PST PCB				
32711	01 Trip Blank	11/8/98	0800	AB	2	X							
	02 Field Blank		1000		5	X	X	X	X				
	03 MW30 #2932594		1130										
	04 MW31 #2932595		1120										
	05 MW32 #2932596		1505										
	06 MW33 #2932597		1420										
	07 Field Dup												
Relinquished by (signature): <u>[Signature]</u>		Date/Time: <u>11/8/98 1520</u>		Received by (signature): <u>[Signature]</u>		Relinquished by (signature):		Date/Time:		Received by (signature):			
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):			
Report Type: () Full, () Reduced, () Standard, () Screen / non-certified						Remarks:							
Turnaround time: () Standard 4 wks, () Rush ____ Days, () ASAP Verbal ____ Hrs.													

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: CW-2

MW# 30

NJDEP ID# 2932594

NJDEP CERT# 13461

SAMPLING CONTRATOR TVS

SAMPLER RAY POGWIST

DATE: 01/08/98

WEATHER: OVERCAST 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 5.20

DEPTH OF WELL: 17.90

HEIGHT OF WATER 12.7

12.7 X 0.65 X 3 = 24.765

GAL OF H2O TO BE EVACUATED 24.8 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

Hnu READING COULD NOT USE-WEATER

PURGE START TIME: 9:25

pH: 9.64

TEMP 13.1 DEG °C

DISSOLVED O2 4.7 PPM SPECIFIC CONDUCTIVITY 120 us/cm

PURGE END TIME: 11:29

pH: 7.30

TEMP 13.2 DEG °C

DISSOLVED O2 4.2 PPM SPECIFIC CONDUCTIVITY 130 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 7.20 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon @ bailer

TOTAL VOLUME PURGED: 24.8 GAL

pH: 7.30

TEMP 13.2 DEG °C

DISSOLVED O2 4.2 PPM SPECIFIC CONDUCTIVITY 130 us/cm

COMMENTS: _____

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: CW-2
MW# 31
NJDEP ID# 2932595
NJDEP CERT# 13461
SAMPLING CONTRATOR TVS
SAMPLER RAY POGWIST _

DATE: 01/08/98 WEATHER: OVERCAST 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 6.30

DEPTH OF WELL: 16.80

HEIGHT OF WATER 10.5

10.5 X 0.65 X 3 = 20.475

GAL OF H2O TO BE EVACUATED 20.6 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALIC

PURGE RATE 0.2 GPM

Hnu READING COULD NOT USE-WEATER

PURGE START TIME: 9:35

pH: 8.64 TEMP 13.9 DEG °C

DISSOLVED O2 1.4 PPM SPECIFIC CONDUCTIVITY 180 us/cm

PURGE END TIME: 11:18

pH: 6.40 TEMP 15.3 DEG °C

DISSOLVED O2 1.0 PPM SPECIFIC CONDUCTIVITY 170 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 7.10 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 20.6 GAL

pH: 6.35 TEMP 15.2 DEG °C

DISSOLVED O2 0.9 PPM SPECIFIC CONDUCTIVITY 170 us/cm

COMMENTS: _____

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: CW-2

MW# 32

NJDEP ID# 2932596

NJDEP CERT# 13461

SAMPLING CONTRATOR TVS

SAMPLER RAY POGWIST _

DATE: 01/08/98

WEATHER: OVERCAST 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 4.5

DEPTH OF WELL: 16.80

HEIGHT OF WATER 12.30

12.30 X 0.65 X 3 = 23.985

GAL OF H2O TO BE EVACUATED 24 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

H_{nu} READING COULD NOT USE-WEATER

PURGE START TIME: 13:00

pH: 6.46 TEMP 10.7 DEG °C

DISSOLVED O2 5.2 PPM SPECIFIC CONDUCTIVITY 150 us/cm

PURGE END TIME: 15:00

pH: 7.11 TEMP 11.5 DEG °C

DISSOLVED O2 4.8 PPM SPECIFIC CONDUCTIVITY 160 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 6.90 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 24 GAL

pH: 7.15 TEMP 11.6 DEG °C

DISSOLVED O2 4.8 PPM SPECIFIC CONDUCTIVITY 160 us/cm

COMMENTS: _____

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: CW-2

MW# 33

NJDEP ID# 2932597

NJDEP CERT# 13461

SAMPLING CONTRATOR TVS

SAMPLER RAY POGWIST _

DATE: 01/08/98

WEATHER: OVERCAST 50'S

ELEVATION OF CASING SURVEY MARK

DTW: 9.00

DEPTH OF WELL: 16.00

HEIGHT OF WATER 7.0

7.0 X 0.65 X 3 = 13.65

GAL OF H2O TO BE EVACUATED 13.8 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

Hnu READING COULD NOT USE-WEATER

PURGE START TIME: 13:15

pH: 6.76 TEMP 16.3 DEG °C

DISSOLVED O2 2.1 PPM SPECIFIC CONDUCTIVITY 200 us/cm

PURGE END TIME: 14:19

pH: 5.58 TEMP 16.5 DEG °C

DISSOLVED O2 1.0 PPM SPECIFIC CONDUCTIVITY 200 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 13.8 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 13.8 GAL

pH: 5.59 TEMP 16.5 DEG °C

DISSOLVED O2 0.9 PPM SPECIFIC CONDUCTIVITY 200 us/cm

COMMENTS: _____

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit

J : Compound identified below detection limit

B : Compound in both sample and blank

D : Results from dilution of sample

U : Compound searched for but not detected

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02752.d
 Operator Skelton
 Date Acquired 14 Jan 1998 12:08

Sample Name VBLK14
 Field ID VBLK14
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v02753.d**
 Operator **Skelton**
 Date Acquired **14 Jan 1998 13:26**

Sample Name **3271.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform	18.26	9417	1.34 ug/L	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v02754.d**
 Operator **Skelton**
 Date Acquired **14 Jan 1998 14:18**

Sample Name **3271.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform	18.27	8334	1.15 ug/L	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **v02755.d**
 Operator **Skelton**
 Date Acquired **14 Jan 1998 15:07**

Sample Name **3271.03**
 Field ID **MW30**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02756.d
 Operator Skelton
 Date Acquired 14 Jan 1998 15:58

Sample Name 3271.04
 Field ID MW31
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02757.d
 Operator Skelton
 Date Acquired 14 Jan 1998 16:49

Sample Name 3271.05
 Field ID MW32
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name v02758.d
 Operator Skelton
 Date Acquired 14 Jan 1998 17:39

Sample Name 3271.06
 Field ID MW33
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **V02759.D**
 Operator **Skelton**
 Date Acquired **14 Jan 1998 18:28**

Sample Name **3271.07**
 Field ID **Field Dup**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

VBK14

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 3271 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: VBK14
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02752.D
Level: (low/med) LOW Date Received: 01/08/98
% Moisture: not dec. _____ Date Analyzed: 01/14/98
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Trip Blank

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 3271 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3271.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02753.D
Level: (low/med) LOW Date Received: 01/08/98
% Moisture: not dec. _____ Date Analyzed: 01/14/98
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 3271 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3271.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02754.D
Level: (low/med) LOW Date Received: 01/08/98
% Moisture: not dec. _____ Date Analyzed: 01/14/98
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW30

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 3271 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3271.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02755.D
Level: (low/med) LOW Date Received: 01/08/98
% Moisture: not dec. _____ Date Analyzed: 01/14/98
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1

(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1.	unknown hydrocarbon	13.81	15	J

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW31

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 3271 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3271.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02756.D
Level: (low/med) LOW Date Received: 01/08/98
% Moisture: not dec. _____ Date Analyzed: 01/14/98
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1.	unknown hydrocarbon	13.80	30	J

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW32

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 3271 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3271.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02757.D
Level: (low/med) LOW Date Received: 01/08/98
% Moisture: not dec. _____ Date Analyzed: 01/14/98
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1.	unknown hydrocarbon	13.81	33	J

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW33

Lab Name: FMETL Project _____
NJDEP # 13461 Case No.: 3271 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3271.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02758.D
Level: (low/med) LOW Date Received: 01/08/98
% Moisture: not dec. _____ Date Analyzed: 01/14/98
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 1

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1. 001066-40-6	Silanol, trimethyl-	13.81	50	JN

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Dup

Lab Name: FMETL Project _____

NJDEP # 13461 Case No.: 3271 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3271.07

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V02759.D

Level: (low/med) LOW Date Received: 01/08/98

% Moisture: not dec. _____ Date Analyzed: 01/14/98

GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 2

CAS NO.	COMPOUND	RT	EST. CONC.	Q
1.	unknown hydrocarbon	6.50	8	J
2. 001066-40-6	Silanol, trimethyl-	13.80	65	JN

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0910.d**

Operator **Skelton**

Date Acquired **01/27/98 16:48**

Sample Name **SBLK17**

Misc Info **01/09/98**

Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bn0910.d

Operator Skelton

Date Acquired 01/27/98 16:48

Sample Name SBLK17

Misc Info 01/09/98

Sample Multiplier 1

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L
86-73-7	Fluorene			not detected	300	0.29	ug/L
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L
120-12-7	Anthracene			not detected	2000	0.19	ug/L
84-74-2	Di-n-butylphthalate	20.22	899160	7.96 ug/L	900	0.23	ug/L
206-44-0	Fluoranthene			not detected	300	0.41	ug/L
92-87-5	Benzidine			not detected	50	1.45	ug/L
129-00-0	Pyrene			not detected	200	0.32	ug/L
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L
218-01-9	Chrysene			not detected	20	0.20	ug/L
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L

Qualifiers

E = Value exceeded linear range

D = Value from dilution

B = Compound in related blank

MDL = Method Detection Limit

NLE = No Limit Established

R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0930.d**
 Operator **Skelton**
 Date Acquired **01/28/98 06:49**

Sample Name **3271-2**
 Misc Info **FIELD BLANK**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bn0930.d

Operator Skelton

Date Acquired 01/28/98 06:49

Sample Name 3271-2

Misc Info FIELD BLANK

Sample Multiplier 1

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate	20.20	198093	1.86 ug/L	900	0.23 ug/L	B
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate	25.21	1166369	22.37 ug/L	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

Qualifiers

E = Value exceeded linear range
D = Value from dilution
B = Compound in related blank
MDL = Method Detection Limit
NLE = No Limit Established
R.T. = Retention Time

NLE = No Limit Established
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0931.d**
 Operator **Skelton**
 Date Acquired **01/28/98 07:31**

Sample Name **3271-3**
 Misc Info **MW 30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bn0931.d

Operator Skelton

Date Acquired 01/28/98 07:31

Sample Name 3271-3

Misc Info MW 30

Sample Multiplier 1

121-14-2	2,4-Dinitrotoluene		not detected	10	0.36	ug/L
84-66-2	Diethylphthalate		not detected	5000	0.82	ug/L
86-73-7	Fluorene		not detected	300	0.29	ug/L
7005-72-3	4-Chlorophenyl-phenylether		not detected	NLE	0.31	ug/L
100-01-6	4-Nitroaniline		not detected	NLE	0.90	ug/L
534-52-1	4,6-Dinitro-2-methylphenol		not detected	NLE	0.44	ug/L
86-30-6	n-Nitrosodiphenylamine		not detected	20	0.23	ug/L
103-33-3	Azobenzene		not detected	NLE	0.80	ug/L
101-55-3	4-Bromophenyl-phenylether		not detected	NLE	0.55	ug/L
118-74-1	Hexachlorobenzene		not detected	10	0.82	ug/L
87-86-5	Pentachlorophenol		not detected	1	1.08	ug/L
85-01-8	Phenanthrene		not detected	NLE	0.18	ug/L
120-12-7	Anthracene		not detected	2000	0.19	ug/L
84-74-2	Di-n-butylphthalate		not detected	900	0.23	ug/L
206-44-0	Fluoranthene		not detected	300	0.41	ug/L
92-87-5	Benzidine		not detected	50	1.45	ug/L
129-00-0	Pyrene		not detected	200	0.32	ug/L
85-68-7	Butylbenzylphthalate		not detected	100	0.47	ug/L
56-55-3	Benzo[a]anthracene		not detected	10	0.22	ug/L
91-94-1	3,3'-Dichlorobenzidine		not detected	60	0.46	ug/L
218-01-9	Chrysene		not detected	20	0.20	ug/L
117-81-7	bis(2-Ethylhexyl)phthalate		not detected	30	0.51	ug/L
117-84-0	Di-n-octylphthalate		not detected	100	0.82	ug/L
205-99-2	Benzo[b]fluoranthene		not detected	10	0.37	ug/L
207-08-9	Benzo[k]fluoranthene		not detected	2	0.32	ug/L
50-32-8	Benzo[a]pyrene		not detected	20	0.31	ug/L
193-39-5	Indeno[1,2,3-cd]pyrene		not detected	20	0.79	ug/L
53-70-3	Dibenz[a,h]anthracene		not detected	20	0.28	ug/L
191-24-2	Benzo[g,h,i]perylene		not detected	NLE	0.40	ug/L

Qualifiers

E = Value exceeded linear range

D = Value from dilution

B = Compound in related blank

MDL = Method Detection Limit

NLE = No Limit Established

R.T. = Retention Time

Semi-Volatile Analysis Report

NJDEP Certification #13461

Data File Name bn0932.d

Operator Skelton

Date Acquired 01/28/98 08:13

Sample Name 3271-4

Misc Info MW 31

Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn0932.d**
 Operator **Skelton**
 Date Acquired **01/28/98 08:13**

Sample Name **3271-4**
 Misc Info **MW 31**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L	
86-73-7	Fluorene			not detected	300	0.29	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L	
120-12-7	Anthracene			not detected	2000	0.19	ug/L	
84-74-2	Di-n-butylphthalate	20.21	447067	3.75 ug/L	900	0.23	ug/L	B
206-44-0	Fluoranthene			not detected	300	0.41	ug/L	
92-87-5	Benzidine			not detected	50	1.45	ug/L	
129-00-0	Pyrene			not detected	200	0.32	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L	
218-01-9	Chrysene			not detected	20	0.20	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0933.d**

Operator **Skelton**

Date Acquired **01/28/98 08:55**

Sample Name **3271-5**

Misc Info **MW 32**

Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn0933.d**

Operator **Skelton**

Date Acquired **01/28/98 08:55**

Sample Name **3271-5**

Misc Info **MW 32**

Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L	
86-73-7	Fluorene			not detected	300	0.29	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L	
120-12-7	Anthracene			not detected	2000	0.19	ug/L	
84-74-2	Di-n-butylphthalate	20.20	326963	2.98 ug/L	900	0.23	ug/L	B
206-44-0	Fluoranthene			not detected	300	0.41	ug/L	
92-87-5	Benzidine			not detected	50	1.45	ug/L	
129-00-0	Pyrene			not detected	200	0.32	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L	
218-01-9	Chrysene			not detected	20	0.20	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L	

Qualifiers

E = Value exceeded linear range

D = Value from dilution

B = Compound in related blank

MDL = Method Detection Limit

NLE = No Limit Established

R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn0934.d**
 Operator **Skelton**
 Date Acquired **01/28/98 09:44**

Sample Name **3271.06**
 Misc Info **MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn0934.d**
 Operator **Skelton**
 Date Acquired **01/28/98 09:44**

Sample Name **3271.06**
 Misc Info **MW33**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L	
86-73-7	Fluorene			not detected	300	0.29	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L	
120-12-7	Anthracene			not detected	2000	0.19	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23	ug/L	
206-44-0	Fluoranthene			not detected	300	0.41	ug/L	
92-87-5	Benzidine			not detected	50	1.45	ug/L	
129-00-0	Pyrene			not detected	200	0.32	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L	
218-01-9	Chrysene			not detected	20	0.20	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN0935.D**

Operator **Skelton**

Date Acquired **01/28/98 10:27**

Sample Name **3271.07**

Misc Info **Field Dup**

Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN0935.D**

Operator **Skelton**

Date Acquired **01/28/98 10:27**

Sample Name **3271.07**

Misc Info **Field Dup**

Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L	
86-73-7	Fluorene			not detected	300	0.29	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L	
120-12-7	Anthracene			not detected	2000	0.19	ug/L	
84-74-2	Di-n-butylphthalate	20.21	693773	6.10 ug/L	900	0.23	ug/L	B
206-44-0	Fluoranthene			not detected	300	0.41	ug/L	
92-87-5	Benzidine			not detected	50	1.45	ug/L	
129-00-0	Pyrene			not detected	200	0.32	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L	
218-01-9	Chrysene			not detected	20	0.20	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L	

Qualifiers

E = Value exceeded linear range

D = Value from dilution

B = Compound in related blank

MDL = Method Detection Limit

NLE = No Limit Established

R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

SBLK17

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3271 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: SBLK17

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0910.D

Level: (low/med) LOW Date Received: 01/08/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 01/09/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 01/27/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 4 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown hydrocarbon	4.99	26	J
2. 000301-02-0	9-Octadecenamide, (Z)-	23.73	8	JN
3. 000103-23-1	Hexanedioic acid, bis(2-ethylhex	24.03	77	JN
4. 000301-02-0	9-Octadecenamide, (Z)-	26.89	16	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

Lab Name: <u>FMETL</u>		Lab Code <u>13461</u>	Field Blank
Project _____	Case No.: <u>3271</u>	Location <u>CW-2</u>	SDG No.: _____
Matrix: (soil/water) <u>WATER</u>		Lab Sample ID: <u>3271-2</u>	
Sample wt/vol: <u>1000</u> (g/ml) <u>ML</u>		Lab File ID: <u>BN0930.D</u>	
Level: (low/med) <u>LOW</u>		Date Received: <u>01/08/98</u>	
% Moisture: _____	decanted: (Y/N) <u>N</u>	Date Extracted: <u>01/09/98</u>	
Concentrated Extract Volume: <u>1000</u> (uL)		Date Analyzed: <u>01/28/98</u>	
Injection Volume: <u>1.0</u> (uL)		Dilution Factor: <u>1.0</u>	
GPC Cleanup: (Y/N) <u>N</u> pH: <u>7</u>			

CONCENTRATION UNITS:

Number TICs found: 4 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	4.99	24	JN
2. 000301-02-0	9-Octadecenamide, (Z)-	23.74	15	JN
3. 000103-23-1	Hexanedioic acid, bis(2-ethylhex	24.07	310	JN
4. 001120-16-7	Dodecanamide	26.88	32	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

Lab Name: <u>FMETL</u>	Lab Code <u>13461</u>	MW 30
Project _____	Case No.: <u>3271</u>	Location <u>CW-2</u> SDG No.: _____
Matrix: (soil/water) <u>WATER</u>	Lab Sample ID: <u>3271-3</u>	
Sample wt/vol: <u>1000</u> (g/ml) <u>ML</u>	Lab File ID: <u>BN0931.D</u>	
Level: (low/med) <u>LOW</u>	Date Received: <u>01/08/98</u>	
% Moisture: _____ decanted: (Y/N) <u>N</u>	Date Extracted: <u>01/09/98</u>	
Concentrated Extract Volume: <u>1000</u> (uL)	Date Analyzed: <u>01/28/98</u>	
Injection Volume: <u>1.0</u> (uL)	Dilution Factor: <u>1.0</u>	
GPC Cleanup: (Y/N) <u>N</u> pH: <u>7</u>		

CONCENTRATION UNITS:

Number TICs found: 8 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 019549-87-2	2,4-Dimethyl-1-heptene	4.91	10	JN
2.	unknown hydrocarbon	5.01	39	J
3.	unknown hydrocarbon	19.26	9	J
4. 000057-10-3	Hexadecanoic acid	20.15	9	JN
5. 000057-11-4	Octadecanoic acid	22.00	13	JN
6. 000301-02-0	9-Octadecenamide, (Z)-	23.74	16	JN
7. 004337-65-9	Hexanedioic acid, mono(2-ethylh	24.06	270	JN
8. 001120-07-6	Nonanamide	26.88	34	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW 31

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3271 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3271-4

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0932.D

Level: (low/med) LOW Date Received: 01/08/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 01/09/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 01/28/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 5 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	5.01	50	J
2.	unknown	19.27	15	J
3.	unknown	23.75	16	J
4. 000103-23-1	Hexanedioic acid, bis(2-ethylhex	24.09	390	JN
5. 001120-16-7	Dodecanamide	26.88	32	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

MW 32

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3271 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3271-5

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0933.D

Level: (low/med) LOW Date Received: 01/08/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 01/09/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 01/28/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 5 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	5.01	49	J
2.	unknown hydrocarbon	19.27	10	J
3.	unknown	23.75	14	J
4. 000103-23-1	Hexanedioic acid, bis(2-ethylhex	24.06	190	JN
5. 001120-07-6	Nonanamide	26.89	31	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW 33

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3271 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3271.06

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0934.D

Level: (low/med) LOW Date Received: 01/08/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 01/09/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 01/28/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 5 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	4.99	33	J
2.	unknown	19.26	10	J
3.	unknown	23.74	16	J
4. 000103-23-1	Hexanedioic acid, bis(2-ethylhex	24.07	330	JN
5. 000301-02-0	9-Octadecenamide, (Z)-	26.88	33	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

Field Dup

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3271 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3271.07

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN0935.D

Level: (low/med) LOW Date Received: 01/08/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 01/09/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 01/28/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 5 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	4.99	37	JN
2.	unknown hydrocarbon	19.28	19	J
3.	unknown	23.76	14	J
4. 000103-23-1	Hexanedioic acid, bis(2-ethylhex	24.11	470	JN
5. 001120-07-6	Nonanamide	26.89	29	JN

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	Extraction Blank
	DPW, SELFM-PW-EV	Date Rec'd:	
	Bldg. 173	Extraction Date:	1/12/98
	Ft. Monmouth, NJ 07703	Analysis Date:	2/21/98
Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3271.02
	DPW, SELFM-PW-EV	Date Rec'd:	1/8/98
	Bldg. 173	Extraction Date:	1/12/98
	Ft. Monmouth, NJ 07703	Analysis Date:	2/21/98

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	Field Blank
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Column-Confirmation:

Rtx-5 30m/.32mmID/.25um

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 3271.03
DPW, SELFM-PW-EV Date Rec'd: 1/8/98
Bldg. 173 Extraction Date: 1/12/98
Ft. Monmouth, NJ 07703 Analysis Date: 2/21/98

Analysis: EPA Method 608 Location : CW-2
Matrix: Aqueous
Analyst: D. Wright Field ID: MW-30
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3271.04
	DPW, SELFM-PW-EV	Date Rec'd:	1/8/98
	Bldg. 173	Extraction Date:	1/12/98
	Ft. Monmouth, NJ 07703	Analysis Date:	2/21/98

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-31
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 3271.05
DPW, SELFM-PW-EV Date Rec'd: 1/8/98
Bldg. 173 Extraction Date: 1/12/98
Ft. Monmouth, NJ 07703 Analysis Date: 2/21/98

Analysis: EPA Method 608 Location : CW-2
Matrix: Aqueous
Analyst: D. Wright Field ID: MW-32
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Column-Confirmation:

Rtx-5 30m/.32mmID/.25um

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3271.06
	DPW, SELFM-PW-EV	Date Rec'd:	1/8/98
	Bldg. 173	Extraction Date:	1/12/98
	Ft. Monmouth, NJ 07703	Analysis Date:	2/21/98

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-33
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3271.07
	DPW, SELFM-PW-EV	Date Rec'd:	1/8/98
	Bldg. 173	Extraction Date:	1/12/98
	Ft. Monmouth, NJ 07703	Analysis Date:	2/21/98

Analysis:	EPA Method 608	Location :	CW-2
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	Field DUP
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Column-Confirmation:

Rtx-5 30m/.32mmID/.25um

Rtx-1701 30m/.32mmID/.25um

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: Method Blank
 Sample Received: NA
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: NA

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	ND	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	ND	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	ND	NLE	20.0
Chromium	01/29/98	ND	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	ND	1000	6.0
Iron	01/29/98	ND	300	10.0
Lead	01/29/98	ND	10	4.0
Magnesium	01/29/98	ND	NLE	20.0
Manganese	01/29/98	ND	50	1.0
Mercury	01/14/98	ND	2	0.2
Nickel	01/29/98	ND	100	1.0
Potassium	01/29/98	ND	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	ND	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	ND	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3271.02
 Sample Received: 01/08/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	114.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	3.8	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	1040.0	NLE	20.0
Chromium	01/29/98	1.5	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	12.0	1000	6.0
Iron	01/29/98	62.0	300	10.0
Lead	01/29/98	ND	10	4.0
Magnesium	01/29/98	190.0	NLE	20.0
Manganese	01/29/98	1.8	50	1.0
Mercury	01/14/98	ND	2	0.2
Nickel	01/29/98	1.9	100	1.0
Potassium	01/29/98	ND	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	890.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	67.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3271.03
 Sample Received: 01/08/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	204.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	30.9	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	41070.0	NLE	20.0
Chromium	01/29/98	5.2	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	21.0	1000	6.0
Iron	01/29/98	2795.0	300	10.0
Lead	01/29/98	4.0	10	4.0
Magnesium	01/29/98	3390.0	NLE	20.0
Manganese	01/29/98	5.0	50	1.0
Mercury	01/14/98	ND	2	0.2
Nickel	01/29/98	2.8	100	1.0
Potassium	01/29/98	7240.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	5450.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	76.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3271.04
 Sample Received: 01/08/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	129.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	204.7	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	44460.0	NLE	20.0
Chromium	01/29/98	1.4	100	1.0
Cobalt	01/29/98	4.0	NLE	1.0
Copper	01/29/98	36.0	1000	6.0
Iron	01/29/98	68450.0	300	10.0
Lead	01/29/98	25.0	10	4.0
Magnesium	01/29/98	5250.0	NLE	20.0
Manganese	01/29/98	240.0	50	1.0
Mercury	01/14/98	ND	2	0.2
Nickel	01/29/98	49.8	100	1.0
Potassium	01/29/98	9800.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	15.0	20	6.0
Sodium	01/29/98	10310.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	996.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3271.05
 Sample Received: 01/08/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	163.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	22.8	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	62370.0	NLE	20.0
Chromium	01/29/98	4.9	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	38.0	1000	6.0
Iron	01/29/98	1484.0	300	10.0
Lead	01/29/98	ND	10	4.0
Magnesium	01/29/98	6140.0	NLE	20.0
Manganese	01/29/98	3.7	50	1.0
Mercury	01/14/98	ND	2	0.2
Nickel	01/29/98	3.4	100	1.0
Potassium	01/29/98	3590.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	15990.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	84.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3271.06
 Sample Received: 01/08/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW 33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	217.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	6.0	8	4.0
Barium	01/29/98	310.9	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	72300.0	NLE	20.0
Chromium	01/29/98	3.0	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	10.0	1000	6.0
Iron	01/29/98	104700.0	300	10.0
Lead	01/29/98	4.0	10	4.0
Magnesium	01/29/98	7660.0	NLE	20.0
Manganese	01/29/98	341.7	50	1.0
Mercury	01/14/98	ND	2	0.2
Nickel	01/29/98	3.2	100	1.0
Potassium	01/29/98	13430.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	11780.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	69.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3271.07
 Sample Received: 01/08/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Dup.

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	01/29/98	132.0	200	20.0
Antimony	01/29/98	ND	20	4.0
Arsenic	01/29/98	ND	8	4.0
Barium	01/29/98	190.2	2000	1.0
Beryllium	01/29/98	ND	20	1.0
Cadmium	01/29/98	ND	4	1.0
Calcium	01/29/98	42040.0	NLE	20.0
Chromium	01/29/98	1.0	100	1.0
Cobalt	01/29/98	ND	NLE	1.0
Copper	01/29/98	16.0	1000	6.0
Iron	01/29/98	65180.0	300	10.0
Lead	01/29/98	7.0	10	4.0
Magnesium	01/29/98	4980.0	NLE	20.0
Manganese	01/29/98	223.8	50	1.0
Mercury	01/14/98	ND	2	0.2
Nickel	01/29/98	1.5	100	1.0
Potassium	01/29/98	9220.0	NLE	20.0
Selenium	01/29/98	ND	50	6.0
Silver	01/29/98	ND	20	6.0
Sodium	01/29/98	9700.0	50000	20.0
Thallium	01/29/98	ND	10	6.0
Vanadium	01/29/98	ND	NLE	2.0
Zinc	01/29/98	133.0	5000	2.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-3484

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT

FOR

Directorate of Public Works

Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
3462.03	MW-30	29-32594	04/07/98
3462.04	MW-31	29-32595	04/07/98
3462.05	MW-32	29-32596	04/07/98
3462.06	MW-33	29-32597	04/07/98

NJDEP Laboratory Certification # 13461

Report Date: 31 July, 1998



Daniel Wright Date: 08/4/98
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608

CW-3



**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

SITE: CW-2
MW# 30
NJDEP ID# 2932594
NJDEP CERT# 13461
SAMPLING CONTRACTOR TVS
SAMPLER MARK LAURA

DATE: 04/07/98 WEATHER: SUNNY 40'S

ELEVATION OF CASING SURVEY MARK

DTW: 6.56

DEPTH OF WELL: 17.90

HEIGHT OF WATER 11.34

11.34 X 0.65 X 3 = 22

GAL OF H2O TO BE EVACUATED 22 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.3 GPM

Hnu READING 0

PURGE START TIME: 9:35

pH: 7.05 TEMP 14.8 DEG °C
DISSOLVED O2 3.67 PPM SPECIFIC CONDUCTIVITY 111 us/cm

PURGE END TIME: 11:28

pH: 7.14 TEMP 14.5 DEG °C
DISSOLVED O2 1.79 PPM SPECIFIC CONDUCTIVITY 170 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 9.57 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon @ bailer

TOTAL VOLUME PURGED: 22 GAL

pH: 8.30 TEMP 14.5 DEG °C
DISSOLVED O2 2.99 PPM SPECIFIC CONDUCTIVITY 130 us/cm

COMMENTS: _____

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATASHEET

SITE: CW-2
MW# 31
NJDEP ID# 2932595
NJDEP CERT# 13461
SAMPLING CONTRACTOR TVS
SAMPLER MARK LAURA

DATE: 04/07/98

WEATHER: SUNNY 40'S

ELEVATION OF CASING SURVEY MARK

DTW: 6.35

DEPTH OF WELL: 16.80

HEIGHT OF WATER 10.45

10.45 X 0.65 X 3 = 20.5

GAL OF H2O TO BE EVACUATED 20.5 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

Hnu READING 0

PURGE START TIME: 9:42

pH: 6.89 TEMP 14.4 DEG °C
DISSOLVED O2 1.47 PPM SPECIFIC CONDUCTIVITY 130 us/cm

PURGE END TIME: 11:33

pH: 9.33 TEMP 13.8 DEG °C
DISSOLVED O2 1.07 PPM SPECIFIC CONDUCTIVITY 140 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 6.95 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon @ bailer

TOTAL VOLUME PURGED: 20.5 GAL

pH: 6.84 TEMP 13.1 DEG °C
DISSOLVED O2 2.94 PPM SPECIFIC CONDUCTIVITY 120 us/cm

COMMENTS: Well very turbid with rust colored particles.

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

BLDG: CW-2
MW# 32
NJDEP ID# 2932596
NJDEP CERT# 13461
SAMPLING CONTRACTOR TVS
SAMPLER MARK LAURA

DATE: 04/07/98 WEATHER: SUNNY 40'S

ELEVATION OF CASING SURVEY MARK

DTW: 6.81

DEPTH OF WELL: 16.80

HEIGHT OF WATER 9.99

9.99 X 0.65 X 3 = 19.50

GAL OF H2O TO BE EVACUATED 19.50 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.2 GPM

Hnu READING 0

PURGE START TIME: 9:50

pH: 8.06 TEMP 13.4 DEG °C

DISSOLVED O2 1.82 PPM SPECIFIC CONDUCTIVITY 140 us/cm

PURGE END TIME: 11:26

pH: 9.65 TEMP 13.5 DEG °C

DISSOLVED O2 1.56 PPM SPECIFIC CONDUCTIVITY 180 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 7.7 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 19.50 GAL

pH: 6.69 TEMP 13.3 DEG °C

DISSOLVED O2 2.56 PPM SPECIFIC CONDUCTIVITY 120 us/cm

COMMENTS: _____

**U.S. ARMY FORT MONMOUTH
MONITORING WELL SAMPLING DATASHEET**

SITE: CW-2
MW# 33
NJDEP ID# 2932597
NJDEP CERT# 13461
SAMPLING CONTRACTOR TVS
SAMPLER MARK LAURA

DATE: 04/07/98 WEATHER: SUNNY 40'S

ELEVATION OF CASING SURVEY MARK

DTW: 9.5

DEPTH OF WELL: 16.00

HEIGHT OF WATER 6.50

6.50 X 0.65 X 3 = 12.67

GAL OF H2O TO BE EVACUATED 12.67 GAL

PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) PERISTALTIC

PURGE RATE 0.3 GPM

Hnu READING 0

PURGE START TIME: 9:54

pH: 6.57 TEMP 14.5 DEG °C

DISSOLVED O2 2.25 PPM SPECIFIC CONDUCTIVITY 160 us/cm

PURGE END TIME: 11:41

pH: 7.08 TEMP 15.1 DEG °C

DISSOLVED O2 2.33 PPM SPECIFIC CONDUCTIVITY 170 us/cm

DEPTH TO H2O AFTER PURGING AND BEFORE SAMPLING 9.11 FT

sampling method : dedicated (law NJDEP FSPM 1992) teflon ® bailer

TOTAL VOLUME PURGED: 12.67 GAL

pH: 6.91 TEMP 16.4 DEG °C

DISSOLVED O2 2.26 PPM SPECIFIC CONDUCTIVITY 120 us/cm

COMMENTS: _____

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit
J : Compound identified below detection limit
B : Compound in both sample and blank
D : Results from dilution of sample
U : Compound searched for but not detected

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00106.d
 Operator Skelton
 Date Acquired 14 Apr 1998 1:33 pm

Sample Name VBLK01
 Field ID VBLK01
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00113.d
 Operator Skelton
 Date Acquired 14 Apr 1998 7:34 pm

Sample Name 3462.01
 Field ID Trip Blank
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride	12.82	43849	2.98 ug/L	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00114.d
 Operator Skelton
 Date Acquired 14 Apr 1998 8:20 pm

Sample Name 3462.02
 Field ID Field Blank
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone	10.47	32359	6.87 ug/L	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam **vb00115.d**
 Operator **Skelton**
 Date Acquired **14 Apr 1998 9:06 pm**

Sample Name **3462.03**
 Field ID **MW30**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam **vb00116.d**
 Operator **Skelton**
 Date Acquired **14 Apr 1998 9:52 pm**

Sample Name **3462.04**
 Field ID **MW31**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00117.d
 Operator Skelton
 Date Acquired 14 Apr 1998 10:38 pm

Sample Name 3462.05
 Field ID MW32
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00118.d
 Operator Skelton
 Date Acquired 14 Apr 1998 11:24 pm

Sample Name 3462.06
 Field ID MW33
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform	17.66	26840	1.07 ug/L	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam VB00127.D
 Operator Skelton
 Date Acquired 15 Apr 1998 8:05 am

Sample Name 3462.07
 Field ID Field Dup
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
107028	Acrolein			not detected	nle	6.25 ug/L	
107131	Acrylonitrile			not detected	nle	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	74	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

VBLK01

Lab Name: FMETL Project CW2
NJDEP# 13461 Case No.: 3462 SDG No Location B2700
Matrix: (soil/water) WATER Lab Sample ID: VBLK01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00106.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: not dec. Date Analyzed: 04/14/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Trip Blank

Lab Name: FMETL Project CW2
NJDEP# 13461 Case No.: 3462 SDG No Location B2700
Matrix: (soil/water) WATER Lab Sample ID: 3462.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00113.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: not dec. Date Analyzed: 04/14/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Project CW2
NJDEP# 13461 Case No.: 3462 SDG No Location B2700
Matrix: (soil/water) WATER Lab Sample ID: 3462.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00114.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: not dec. Date Analyzed: 04/14/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW30

Lab Name: FMETL Project CW2
NJDEP# 13461 Case No.: 3462 SDG No Location B2700
Matrix: (soil/water) WATER Lab Sample ID: 3462.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00115.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: not dec. Date Analyzed: 04/14/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW31

Lab Name: FMETL Project CW2
NJDEP# 13461 Case No.: 3462 SDG No Location B2700
Matrix: (soil/water) WATER Lab Sample ID: 3462.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00116.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: not dec. Date Analyzed: 04/14/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW32

Lab Name: FMETL Project CW2
NJDEP# 13461 Case No.: 3462 SDG No Location B2700
Matrix: (soil/water) WATER Lab Sample ID: 3462.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00117.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: not dec. Date Analyzed: 04/14/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW33

Lab Name: FMETL Project CW2
NJDEP# 13461 Case No.: 3462 SDG No Location B2700
Matrix: (soil/water) WATER Lab Sample ID: 3462.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00118.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: not dec. Date Analyzed: 04/14/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Dup

Lab Name: FMETL Project CW2
NJDEP# 13461 Case No.: 3462 SDG No Location B2700
Matrix: (soil/water) WATER Lab Sample ID: 3462.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00127.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: not dec. Date Analyzed: 04/15/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN1477.D**
 Operator **FITZPATRICK**
 Date Acquired **04/11/19 -1:1:**

Sample Name **SBLK 5**
 Misc Info
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN1477.D**
 Operator **FITZPATRICK**
 Date Acquired **04/11/19 -1:1:**

Sample Name **SBLK 5**
 Misc Info
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L
86-73-7	Fluorene			not detected	300	0.29	ug/L
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L
120-12-7	Anthracene			not detected	2000	0.19	ug/L
84-74-2	Di-n-butylphthalate			not detected	900	0.23	ug/L
206-44-0	Fluoranthene			not detected	300	0.41	ug/L
92-87-5	Benzidine			not detected	50	1.45	ug/L
129-00-0	Pyrene			not detected	200	0.32	ug/L
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L
218-01-9	Chrysene			not detected	20	0.20	ug/L
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn1506.d**

Operator **FITZPATRICK**

Date Acquired **04/27/19 -1:9:**

Sample Name **3462.02**

Misc Info **FIELD BLANK**

Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn1506.d**
 Operator **FITZPATRICK**
 Date Acquired **04/27/19 -1:9:**

Sample Name **3462.02**
 Misc Info **FIELD BLANK**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L	
86-73-7	Fluorene			not detected	300	0.29	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L	
120-12-7	Anthracene			not detected	2000	0.19	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23	ug/L	
206-44-0	Fluoranthene			not detected	300	0.41	ug/L	
92-87-5	Benzidine			not detected	50	1.45	ug/L	
129-00-0	Pyrene			not detected	200	0.32	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L	
218-01-9	Chrysene			not detected	20	0.20	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name bn1507.d
 Operator FITZPATRICK
 Date Acquired 04/27/19 -1:0:

Sample Name 3462.03
 Misc Info MW-30
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn1507.d**
 Operator **FITZPATRICK**
 Date Acquired **04/27/19 -1:0:**

Sample Name **3462.03**
 Misc Info **MW-30**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L	
86-73-7	Fluorene			not detected	300	0.29	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L	
120-12-7	Anthracene			not detected	2000	0.19	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23	ug/L	
206-44-0	Fluoranthene			not detected	300	0.41	ug/L	
92-87-5	Benzidine			not detected	50	1.45	ug/L	
129-00-0	Pyrene			not detected	200	0.32	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L	
218-01-9	Chrysene			not detected	20	0.20	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN1481.D**
 Operator **FITZPATRICK**
 Date Acquired **04/11/19 -1:4:**

Sample Name **3462.04**
 Misc Info **MW-31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN1481.D**
 Operator **FITZPATRICK**
 Date Acquired **04/11/19 -1:4:**

Sample Name **3462.04**
 Misc Info **MW-31**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L	
86-73-7	Fluorene			not detected	300	0.29	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L	
120-12-7	Anthracene			not detected	2000	0.19	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23	ug/L	
206-44-0	Fluoranthene			not detected	300	0.41	ug/L	
92-87-5	Benzidine			not detected	50	1.45	ug/L	
129-00-0	Pyrene			not detected	200	0.32	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L	
218-01-9	Chrysene			not detected	20	0.20	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate	25.11	59222	1.01 ug/L	30	0.51	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN1482.D**
 Operator **FITZPATRICK**
 Date Acquired **04/11/19 -1:5:**

Sample Name **3462.05**
 Misc Info **MW-32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN1482.D**
 Operator **FITZPATRICK**
 Date Acquired **04/11/19 -1:5:**

Sample Name **3462.05**
 Misc Info **MW-32**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36	ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82	ug/L	
86-73-7	Fluorene			not detected	300	0.29	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23	ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82	ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08	ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18	ug/L	
120-12-7	Anthracene			not detected	2000	0.19	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23	ug/L	
206-44-0	Fluoranthene			not detected	300	0.41	ug/L	
92-87-5	Benidine			not detected	50	1.45	ug/L	
129-00-0	Pyrene			not detected	200	0.32	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46	ug/L	
218-01-9	Chrysene			not detected	20	0.20	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31	ug/L	
193-39-5	Indenof[1,2,3-cd]pyrene			not detected	20	0.79	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn1510.d**
 Operator **FITZPATRICK**
 Date Acquired **04/28/19 -1:2:**

Sample Name **3462.06**
 Misc Info **MW-33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn1510.d**
 Operator **FITZPATRICK**
 Date Acquired **04/28/19 -1:2:**

Sample Name **3462.06**
 Misc Info **MW-33**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

Qualifiers

E = Value exceeded linear range

D = Value from dilution

B = Compound in related blank

MDL = Method Detection Limit

NLE = No Limit Established

R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN1511.D**
 Operator **FITZPATRICK**
 Date Acquired **04/28/19 -1:1:**

Sample Name **3462.07**
 Misc Info **FIELD DUP**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN1511.D**

Operator **FITZPATRICK**

Date Acquired **04/28/19 -1:1:**

Sample Name **3462.07**

Misc Info **FIELD DUP**

Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate	21.89	348466	2.60 ug/L	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate	26.90	138955	2.46 ug/L	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

Qualifiers

E = Value exceeded linear range

D = Value from dilution

B = Compound in related blank

MDL = Method Detection Limit

NLE = No Limit Established

R.T. = Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

SBLK 51

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 3462 Location B.2700 SDG No.: CW 2
Matrix: (soil/water) WATER Lab Sample ID: SBLK51
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN1477.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: _____ decanted: (Y/N) N Date Extracted: 04/08/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 04/11/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	4.85	59	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD BLANK

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3462 Location B.2700 SDG No.: CW 2

Matrix: (soil/water) WATER Lab Sample ID: 3462.02

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN1506.D

Level: (low/med) LOW Date Received: 04/07/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 04/08/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 04/27/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW-30

Lab Name: FMETL Lab Code 13461
 Project _____ Case No.: 3462 Location B.2700 SDG No.: CW2
 Matrix: (soil/water) WATER Lab Sample ID: 3462.03
 Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN1507.D
 Level: (low/med) LOW Date Received: 04/07/98
 % Moisture: _____ decanted: (Y/N) N Date Extracted: 04/08/98
 Concentrated Extract Volume: 1000 (uL) Date Analyzed: 04/27/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

MW-31

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 3462 Location B.2700 SDG No.: CW2
Matrix: (soil/water) WATER Lab Sample ID: 3462.04
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN1481.D
Level: (low/med) LOW Date Received: 04/07/98
% Moisture: _____ decanted: (Y/N) N Date Extracted: 04/08/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 04/11/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	4.83	30	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

MW-32

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3462 Location B.2700 SDG No.: CW 2

Matrix: (soil/water) WATER Lab Sample ID: 3462.05

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN1482.D

Level: (low/med) LOW Date Received: 04/07/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 04/08/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 04/11/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000123-42-2	2-Pentanone, 4-hydroxy-4-methyl	4.84	22	JN

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

Lab Name: FMETL Lab Code 13461 MW-33

Project _____ Case No.: 3462 Location B.2700 SDG No.: CW2

Matrix: (soil/water) WATER Lab Sample ID: 3462.06

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN1510.D

Level: (low/med) LOW Date Received: 04/07/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 04/08/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 04/28/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.51	21	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD DUP

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3462 Location B.2700 SDG No.: CWZ

Matrix: (soil/water) WATER Lab Sample ID: 3462.07

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN1511.D

Level: (low/med) LOW Date Received: 04/07/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 04/08/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 04/28/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 4 (ug/L or ug/Kg) UG/L _____

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.51	15	J
2.	unknown	25.79	33	J
3.	unknown	26.13	10	J
4.	unknown	26.24	20	J

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : PBLK63
Date Rec'd:
Extraction Date: 4/8/98
Analysis Date: 5/13/98

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: D. Wright
Ext. Meth: Sep. Funnel

Location :

Field ID:

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Column-Confirmation:

Rtx-5 30m/.32mmID/.25um

Rtx-1701 30m/.32mmID/.25um

Signal #1 : C:\HPCHEM\1\DATA\980513\P02730.D\ECD1A.CH Vial: 1
Signal #2 : C:\HPCHEM\1\DATA\980513\P02730.D\ECD2B.CH
Acq On : 13 May 98 10:17 am Operator: Skelton
Sample : PBLK63 Inst : Dual ECD
Misc : Multiplr: 1.00
IntFile Signal #1: EVENTS.E IntFile Signal #2: EVENTS2.E
Quant Time: May 13 14:06 1998 Quant Results File: PEST06.RES

Quant Method : C:\HPCHEM\1\METHODS\PEST06.M (Chemstation Integrator)
Title : pesticide cali table
Last Update : Tue May 12 15:19:47 1998
Response via : Initial Calibration
DataAcq Meth : PEST06.M

Volume Inj. :
Signal #1 Phase : Signal #2 Phase:
Signal #1 Info : Signal #2 Info :

Compound	R.T.	Response	Conc Units

System Monitoring Compounds			
1) SAB Tetrachlor-m-xylene	20.26	44617	5.423 ug/L
Spiked Amount 100.000		Recovery =	5.42%
20) SAB Decachlorobiphenyl	36.32	79330	12.108 ug/L
Spiked Amount 100.000		Recovery =	12.11%
22) SAB Tetrachlor-m-xylene #2	22.03	56205	6.008 ug/L
Spiked Amount 100.000		Recovery =	6.01%
41) SAB Decachlorobiphenyl #2	40.33	97272	11.388 ug/L
Spiked Amount 100.000		Recovery =	11.39%

Target Compounds

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 3462.02
Date Rec'd: 4/7/98
Extraction Date: 4/8/98
Analysis Date: 5/13/98

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: D. Wright
Ext. Meth: Sep. Funnel

Location : Bldg. 2700
CW-2
Field ID: Field Blank

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab. ID # : 3462.03
Date Rec'd: 4/7/98
Extraction Date: 4/8/98
Analysis Date: 5/13/98

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: D. Wright
Ext. Meth: Sep. Funnel

Location : Bldg. 2700
 CW-2
Field ID: MW30(#2932594)

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 3462.04
Date Rec'd: 4/7/98
Extraction Date: 4/8/98
Analysis Date: 5/13/98

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: D. Wright
Ext. Meth: Sep. Funnel

Location : Bldg. 2700
CW-2
Field ID: MW31(#2932595)

Pesticide/PCB	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 3462.05
Date Rec'd: 4/7/98
Extraction Date: 4/8/98
Analysis Date: 5/13/98

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: D. Wright
Ext. Meth: Sep. Funnel

Location : Bldg. 2700
CW-2
Field ID: MW32(#2932596)

	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Column-Confirmation:

Rtx-5 30m/.32mmID/.25um

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 3462.06
Date Rec'd: 4/7/98
Extraction Date: 4/8/98
Analysis Date: 5/13/98

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: D. Wright
Ext. Meth: Sep. Funnel

Location : Bldg. 2700
CW-2
Field ID: MW33#2932597)

	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 3465.07
Date Rec'd: 4/7/98
Extraction Date: 4/8/98
Analysis Date: 5/13/98

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: D. Wright
Ext. Meth: Sep. Funnel

Location : Bldg. 2700
CW-2
Field ID: Field Dup

	Dilution Factor	Retention Time	GW Criteria	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0023	ND
beta-BHC	1		0.20	0.0026	ND
gamma-BHC	1		0.20	0.0026	ND
delta-BHC	1		NLE	0.0029	ND
Heptachlor	1		0.40	0.0027	ND
Aldrin	1		0.04	0.0028	ND
Heptachlor Epoxide	1		0.20	0.0024	ND
Endosulfan I	1		0.40	0.0024	ND
4,4'-DDE	1		0.10	0.0034	ND
Dieldrin	1		0.03	0.0019	ND
Endrin	1		2.00	0.0030	ND
Endrin Ketone	1		NLE	0.0100	ND
Endosulfan II	1		0.40	0.0027	ND
4,4'-DDD	1		0.10	0.0066	ND
4,4'-DDT	1		0.10	0.0015	ND
Endosulfan-Sulfate	1		0.40	0.0010	ND
Methoxychlor	1		NLE	0.0100	ND
Alpha-chlordane	1		0.50	0.0140	ND
Gamma-chlordane	1		0.50	0.0140	ND
Toxaphene	1		3.00	0.0182	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

Column-Primary:

Rtx-5 30m/.32mmID/.25um

Column-Confirmation:

Rtx-1701 30m/.32mmID/.25um

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3462
 Sample Preparation: 05/26/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

METHOD BLANK SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	05/28/98	ND	200	10.0
Antimony	05/28/98	2.8	20	2.0
Arsenic	05/28/98	ND	8	2.0
Barium	05/28/98	ND	2000	0.5
Beryllium	05/28/98	ND	20	0.5
Cadmium	05/28/98	ND	4	0.5
Calcium	05/28/98	53	NLE	20.0
Chromium	05/28/98	ND	100	0.5
Cobalt	05/28/98	ND	NLE	0.5
Copper	05/28/98	ND	1000	3.0
Iron	05/28/98	55	300	10.0
Lead	05/28/98	ND	10	2.0
Magnesium	05/28/98	78	NLE	20.0
Manganese	05/28/98	ND	50	0.5
Mercury	04/10/98	ND	2	0.2
Nickel	05/28/98	1.4	100	0.5
Potassium	05/28/98	ND	NLE	20.0
Selenium	05/28/98	ND	50	3.0
Silver	05/28/98	ND	20	3.0
Sodium	05/28/98	ND	50000	20.0
Thallium	05/28/98	ND	10	3.0
Vanadium	05/28/98	ND	NLE	1.0
Zinc	05/28/98	2.8	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3462.02
 Sample Received: 04/07/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	05/28/98	ND	200	10.0
Antimony	05/28/98	ND	20	2.0
Arsenic	05/28/98	ND	8	2.0
Barium	05/28/98	1.3	2000	0.5
Beryllium	05/28/98	ND	20	0.5
Cadmium	05/28/98	ND	4	0.5
Calcium	05/28/98	76.0	NLE	20.0
Chromium	05/28/98	ND	100	0.5
Cobalt	05/28/98	ND	NLE	0.5
Copper	05/28/98	12.0	1000	3.0
Iron	05/28/98	63.0	300	10.0
Lead	05/28/98	ND	10	2.0
Magnesium	05/28/98	ND	NLE	20.0
Manganese	05/28/98	1.5	50	0.5
Mercury	04/10/98	ND	2	0.2
Nickel	05/28/98	5.8	100	0.5
Potassium	05/28/98	ND	NLE	20.0
Selenium	05/28/98	ND	50	3.0
Silver	05/28/98	ND	20	3.0
Sodium	05/28/98	ND	50000	20.0
Thallium	05/28/98	ND	10	3.0
Vanadium	05/28/98	ND	NLE	1.0
Zinc	05/28/98	8.2	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 3462.03
Sample Received: 04/07/98
Sample Matrix: Aqueous

Site: CW-2
Ft. Monmouth, New Jersey

Field ID#: MW-30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	05/28/98	196	200	10.0
Antimony	05/28/98	ND	20	2.0
Arsenic	05/28/98	5.6	8	2.0
Barium	05/28/98	35.5	2000	0.5
Beryllium	05/28/98	ND	20	0.5
Cadmium	05/28/98	ND	4	0.5
Calcium	05/28/98	41000	NLE	20.0
Chromium	05/28/98	ND	100	0.5
Cobalt	05/28/98	ND	NLE	0.5
Copper	05/28/98	3.8	1000	3.0
Iron	05/28/98	3504	300	10.0
Lead	05/28/98	ND	10	2.0
Magnesium	05/28/98	3437	NLE	20.0
Manganese	05/28/98	39.3	50	0.5
Mercury	04/10/98	ND	2	0.2
Nickel	05/28/98	3.5	100	0.5
Potassium	05/28/98	5793	NLE	20.0
Selenium	05/28/98	ND	50	3.0
Silver	05/28/98	ND	20	3.0
Sodium	05/28/98	13010	50000	20.0
Thallium	05/28/98	ND	10	3.0
Vanadium	05/28/98	2.3	NLE	1.0
Zinc	05/28/98	17.2	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3462.04
 Sample Received: 04/07/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	05/28/98	ND	200	10.0
Antimony	05/28/98	ND	20	2.0
Arsenic	05/28/98	ND	8	2.0
Barium	05/28/98	249	2000	0.5
Beryllium	05/28/98	ND	20	0.5
Cadmium	05/28/98	ND	4	0.5
Calcium	05/28/98	48520	NLE	20.0
Chromium	05/28/98	ND	100	0.5
Cobalt	05/28/98	ND	NLE	0.5
Copper	05/28/98	ND	1000	3.0
Iron	05/28/98	115100	300	10.0
Lead	05/28/98	ND	10	2.0
Magnesium	05/28/98	5663	NLE	20.0
Manganese	05/28/98	266	50	0.5
Mercury	04/10/98	ND	2	0.2
Nickel	05/28/98	ND	100	0.5
Potassium	05/28/98	12490	NLE	20.0
Selenium	05/28/98	ND	50	3.0
Silver	05/28/98	ND	20	3.0
Sodium	05/28/98	8927	50000	20.0
Thallium	05/28/98	ND	10	3.0
Vanadium	05/28/98	ND	NLE	1.0
Zinc	05/28/98	29.1	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3462.05
 Sample Received: 04/07/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	05/28/98	ND	200	10.0
Antimony	05/28/98	ND	20	2.0
Arsenic	05/28/98	ND	8	2.0
Barium	05/28/98	109	2000	0.5
Beryllium	05/28/98	ND	20	0.5
Cadmium	05/28/98	0.6	4	0.5
Calcium	05/28/98	71090	NLE	20.0
Chromium	05/28/98	ND	100	0.5
Cobalt	05/28/98	0.7	NLE	0.5
Copper	05/28/98	13.7	1000	3.0
Iron	05/28/98	19280	300	10.0
Lead	05/28/98	ND	10	2.0
Magnesium	05/28/98	7413	NLE	20.0
Manganese	05/28/98	287	50	0.5
Mercury	04/10/98	ND	2	0.2
Nickel	05/28/98	6.9	100	0.5
Potassium	05/28/98	10210	NLE	20.0
Selenium	05/28/98	ND	50	3.0
Silver	05/28/98	ND	20	3.0
Sodium	05/28/98	10860	50000	20.0
Thallium	05/28/98	ND	10	3.0
Vanadium	05/28/98	ND	NLE	1.0
Zinc	05/28/98	257	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3462.06
 Sample Received: 04/07/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	05/28/98	119	200	10.0
Antimony	05/28/98	ND	20	2.0
Arsenic	05/28/98	3.4	8	2.0
Barium	05/28/98	123	2000	0.5
Beryllium	05/28/98	ND	20	0.5
Cadmium	05/28/98	ND	4	0.5
Calcium	05/28/98	31310	NLE	20.0
Chromium	05/28/98	ND	100	0.5
Cobalt	05/28/98	ND	NLE	0.5
Copper	05/28/98	ND	1000	3.0
Iron	05/28/98	19780	300	10.0
Lead	05/28/98	ND	10	2.0
Magnesium	05/28/98	5651	NLE	20.0
Manganese	05/28/98	110	50	0.5
Mercury	04/10/98	ND	2	0.2
Nickel	05/28/98	2.2	100	0.5
Potassium	05/28/98	6223	NLE	20.0
Selenium	05/28/98	ND	50	3.0
Silver	05/28/98	ND	20	3.0
Sodium	05/28/98	14730	50000	20.0
Thallium	05/28/98	ND	10	3.0
Vanadium	05/28/98	ND	NLE	1.0
Zinc	05/28/98	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3462.07
 Sample Received: 04/07/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey


Field ID#: Field Dup.

TAL-METALS RESULTS SUMMARY (ug/L)


Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	05/28/98	ND	200	10.0
Antimony	05/28/98	ND	20	2.0
Arsenic	05/28/98	2.9	8	2.0
Barium	05/28/98	272	2000	0.5
Beryllium	05/28/98	ND	20	0.5
Cadmium	05/28/98	ND	4	0.5
Calcium	05/28/98	49420	NLE	20.0
Chromium	05/28/98	ND	100	0.5
Cobalt	05/28/98	ND	NLE	0.5
Copper	05/28/98	ND	1000	3.0
Iron	05/28/98	140300	300	10.0
Lead	05/28/98	ND	10	2.0
Magnesium	05/28/98	5702	NLE	20.0
Manganese	05/28/98	271	50	0.5
Mercury	04/10/98	ND	2	0.2
Nickel	05/28/98	ND	100	0.5
Potassium	05/28/98	12710	NLE	20.0
Selenium	05/28/98	ND	50	3.0
Silver	05/28/98	ND	20	3.0
Sodium	05/28/98	13270	50000	20.0
Thallium	05/28/98	ND	10	3.0
Vanadium	05/28/98	ND	NLE	1.0
Zinc	05/28/98	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established


Silanol, trimethyl-
(ug/l)




Hexadecanoic Acid
(ug/l)




(E)-3-Chloro-2-methyl-2-pentenal
(ug/l)




Benzene-1,2,3,4-d4-,5,6-dichloro
(ug/l)




2-Pentanone,4-hydroxy-4-methyl
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)



Aluminum
(ug/l)



Arsenic
(ug/l)



SOURCE: MW30

Sampling Dates:
04/24/97 - 04/07/98

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Lead	Depth to Water								Notes
Units:	-	ugl	Feet								-
NJDEP Criteria:	-	10	-								-
04/24/97	FMETL	-	6.45								V,S,P,M
07/10/97	FMETL	ND	7.05								V,S,P,M
10/22/97	FMETL	5.0	7.60								V,S,P,M
01/08/98	FMETL	4.0	5.20								V,S,P,M
04/07/98	FMETL	ND	6.56								V,S,P,M

SOURCE: MW30

Sampling Dates:
04/24/97 - 04/07/98

NOTES:
Page 2 of 2.



FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4



**U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV**



SOURCE: MW30

Sampling Dates:
04/24/97 - 04/07/98

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4, Graph



**U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV**

	Lab	Silanol, trimethyl-	bis(2-Ethyl- hexyl phthalate	(E)-3-Chloro- 2-methyl- 2-pentenal	Benzene-1,2,3,4, -d4,5,6-dichloro	12-Pentanone 4-hydroxy- 4-methyl	Iron	Manganese	Aluminum	Arsenic	Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	-
NJDEP Criteria:	-	NLE	30	NLE	NLE	NLE	300	50	200	8	-
04/24/97	FMETL	12	ND	60	35	330	59900	277	-	-	V,S,P,M
07/10/97	FMETL	ND	ND	ND	ND	ND	11830	267	ND	1.0	V,S,P,M
10/22/97	FMETL	ND	ND	ND	ND	ND	52300	243	93	ND	V,S,P,M
01/08/98	FMETL	ND	ND	ND	ND	ND	68450	240	129	ND	V,S,P,M
04/07/98	FMETL	ND	1.01	ND	ND	ND	115100	266	ND	ND	V,S,P,M

SOURCE: MW31

Sampling Dates:
04/24/97 - 04/07/98

NOTES:

Page 1 of 2.










FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: MW31

Sampling Dates:
04/24/97 - 04/07/98

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Lead	Depth to Water								Notes
Units:	-	ugl	Feet								-
NJDEP Criteria:	-	10	-								-
04/24/97	FMETL	-	6.38								V,S,P,M
07/10/97	FMETL	ND	7.00								V,S,P,M
10/22/97	FMETL	6.0	7.50								V,S,P,M
01/08/98	FMETL	25	6.30								V,S,P,M
04/07/98	FMETL	ND	6.35								V,S,P,M

SOURCE: MW31

Sampling Dates:
04/24/97 - 04/07/98

NOTES:
Page 2 of 2.



FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: MW31

Sampling Dates:
04/24/97 - 04/07/98

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Silanol, trimethyl-	bis(2-Ethyl hexyl phthalate	Hexadeca noic Acid	(E)-3-Chloro 2-methyl- 2-pentenal	Pentanone 4-hydroxy- 4-methyl	Iron	Manganese	Aluminum	Lead	Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ugl	-
NJDEP Criteria:	-	NLE	30	NLE	NLE	NLE	300	50	200	10	-
04/24/97	FMETL	4	1.54	18	100	440	18400	125	-	-	V,S,P,M
07/10/97	FMETL	ND	ND	ND	ND	ND	270	181	595	ND	V,S,P,M
10/22/97	FMETL	ND	ND	ND	ND	ND	51100	260	297	7.0	V,S,P,M
01/08/98	FMETL	ND	ND	ND	ND	ND	1484	3.7	163	ND	V,S,P,M
04/07/98	FMETL	ND	ND	ND	ND	22	19280	287	ND	ND	V,S,P,M

SOURCE: MW32

Sampling Dates:
04/24/97 - 04/07/98

NOTES:

Page 1 of 2.

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 3 of 4




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Silanol, trimethyl-
(ug/l)




bis(2-Ethylhexyl)phthalate
(ug/l)




Hexadecanoic Acid
(ug/l)




(E)-3-Chloro-2-methyl-2-pentenal
(ug/l)




2-Pentanone,4-hydroxy-4-methyl
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)



Aluminum
(ug/l)



Lead
(ug/l)



SOURCE: MW32

Sampling Dates:
04/24/97 - 04/07/98

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Depth to Water									Notes
Units:	-	Feet									-
NJDEP Criteria:	-	-									-
04/24/97	FMETL	6.65									V,S,P,M
07/10/97	FMETL	7.20									V,S,P,M
10/22/97	FMETL	7.70									V,S,P,M
01/06/98	FMETL	4.50									V,S,P,M
04/07/98	FMETL	6.81									V,S,P,M

SOURCE: MW32

Sampling Dates:
04/24/97 - 04/07/98

NOTES:
Page 2 of 2.


FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4

U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

**Depth to Water
(Feet)**



SOURCE: MW32

Sampling Dates:
04/24/97 - 04/07/98

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4, Graph



**U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV**

	Lab	Silanol, (E)-3-Chloro-2-methyl-2-pentenal	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water	Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ugl	Feet	-
NJDEP Criteria:	-	NLE	NLE	300	50	200	8	10	-
04/24/97	FMETL	30	41	88600	424	-	-	8.95	V,S,P,M
07/10/97	FMETL	ND	ND	10260	519	2.1	1.0	ND	V,S,P,M
10/22/97	FMETL	ND	ND	26800	151	94	ND	4.0	V,S,P,M
01/08/98	FMETL	ND	ND	104700	342	217	6.0	4.0	V,S,P,M
04/07/98	FMETL	ND	ND	19780	110	119	3.4	ND	V,S,P,M

SOURCE: MW33

Sampling Dates:
04/24/97 - 04/07/98

NOTES:

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 4 of 4




**U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV**


Silanol, trimethyl-
(ug/l)




(E)-3-Chloro-2-methyl-2-pentenal
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ugl)



Depth to Water
(Feet)



SOURCE: MW33

Sampling Dates:
04/24/97 - 04/07/98

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-PW-EV

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-3484

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
3723.03	MW-30	29-32594	07/14/98
3723.04	MW-31	29-32595	07/14/98
3723.05	MW-32	29-32596	07/14/98
3723.06	MW-33	29-32597	07/14/98

NJDEP Laboratory Certification # 13461

 11/5/98
Daniel Wright Date:
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608

Fort Monmouth Environmental Testing Laboratory


Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (732)532-4359 Fax (732)532-3484 EMail:appleby@doim6.monmouth.army.mil

NJDEP Certification #13461


Chain of Custody Record

Customer: <u>J. Fallon</u>				Project No:		Analysis Parameters								Comments:		
Phone #: <u>826223</u>				Location: <u>CW-2 (2700) MWs</u>		VOA+15	BNA+25	Pest/PCB	TAL Metals					HNO Reading	HCl/HNO ₃ /K ⁺	
(V)DERA ()OMA ()Other: _____																
Samplers Name / Company: <u>Corey McCormack, TVS</u>				Sample #											Remarks / Preservation Method	
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles											
3723.01	Trip Blank	7/14/98	0710	Ag	2	✓										
.02	Field Blank		0945		5	✓	✓	✓	✓						well ID #	
.03	MW-30		1110		5	✓	✓	✓	✓				✓	0.0 ppm	29-32594	
.04	MW-31		1041		5	✓	✓	✓	✓				✓	1.6 ppm	29-32593	
.05	MW-32		1028		5	✓	✓	✓	✓				✓	3 ppm	29-32596	
.06	MW-33		1154		5	✓	✓	✓	✓				✓	1.3 ppm	29-32597	
.07	Field Dupe				5	✓	✓	✓	✓							
														Depth to water		
														2700 M ₁ -C ₁ : 2700.2		
														MW-01		
														13.57 ft		
Relinquished by (signature): <u>Corey McCormack</u>		Date/Time: <u>7/14/98 1300</u>		Received by (signature): <u>J. Verghna</u>		Relinquished by (signature):		Date/Time:		Received by (signature):						
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):						
Report Type: () Full, () Reduced, (X) Standard, () Screen / non-certified						Remarks:										
Turnaround time: (X) Standard 4 wks, () Rush Days, () ASAP Verbal Hrs.																



CW1_2.DGN

Fort Monmouth, Main Post
FIGURE 4.3-3
ACID NEUTRALIZATION LINE PITS (MW-25 AND MW-33)
SAMPLING LOCATIONS



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 7 / 14 / 98
WEATHER: SUNNY, WARM, BREEZY

ELEV. OF CASING SURVEY MARK: 51.71 ft
DEPTH TO WATER: 6.89 ft
DEPTH OF WELL: 17.91 ft
HEIGHT OF WATER: 11.02 ft
(11.02) X .65 X 3 = 21.48
GALLONS OF H2O TO BE PURGED: 22 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.19 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 0919
pH 6.57 su TEMP 20.9 °C
DISSOLVED O2 4.06 ppm SPECIFIC CONDUCTIVITY 80 us/cm

PURGE END TIME: 1110
pH 6.16 su TEMP 18.3 °C
DISSOLVED O2 3.66 ppm SPECIFIC CONDUCTIVITY 80 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.91 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ®
BAILER)

TOTAL VOLUME PURGED: 22 gal

pH 6.32 su TEMP 18.0 °C
DISSOLVED O2 3.26 ppm SPECIFIC CONDUCTIVITY 80 us/cm

COMMENTS: DUPE HERE. DARK TINGE TO WATER.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 7 / 14 / 98
WEATHER: SUNNY, WARM, BREEZY

ELEV. OF CASING SURVEY MARK: 51.58 ft
DEPTH TO WATER: 6.71 ft
DEPTH OF WELL: 16.86 ft
HEIGHT OF WATER: 10.15 ft
(10.15) X .65 X 3 = 19.79
GALLONS OF H2O TO BE PURGED: 20 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.22 gpm
Hnu READING: 1.6 ppm

PURGE START TIME: 0911
pH 6.08 su TEMP 19.8 °C
DISSOLVED O2 3.66 ppm SPECIFIC CONDUCTIVITY 80 us/cm

PURGE END TIME: 1041
pH 6.24 su TEMP 19.4 °C
DISSOLVED O2 3.26 ppm SPECIFIC CONDUCTIVITY 79 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 10.37 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ®
BAILER)

TOTAL VOLUME PURGED: 20 gal

pH 6.14 su TEMP 19.2 °C
DISSOLVED O2 3.26 ppm SPECIFIC CONDUCTIVITY 79 us/cm

COMMENTS: RUSTY COLOR

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 7 / 14 / 98
WEATHER: SUNNY, WARM, BREEZY

ELEV. OF CASING SURVEY MARK: 51.38 ft
DEPTH TO WATER: 7.06 ft
DEPTH OF WELL: 16.86 ft
HEIGHT OF WATER: 9.80 ft
(9.80) X .65 X 3 = 19.11
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.22 gpm
Hnu READING: 0.3 ppm

PURGE START TIME: 0902

pH	6.32	su	TEMP	20.2	°C		
DISSOLVED O2	3.86	ppm	SPECIFIC CONDUCTIVITY	79	us/cm		

PURGE END TIME: 1028

pH	6.14	su	TEMP	19.8	°C		
DISSOLVED O2	3.56	ppm	SPECIFIC CONDUCTIVITY	78	us/cm		

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 12.39 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ®
BAILER)

TOTAL VOLUME PURGED: 19 gal

pH	6.06	su	TEMP	19.6	°C		
DISSOLVED O2	3.56	ppm	SPECIFIC CONDUCTIVITY	79	us/cm		

COMMENTS: LIGHT RUST TINGE

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 33
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 7 / 14 / 98
WEATHER: SUNNY, WARM, BREEZY

ELEV. OF CASING SURVEY MARK: 51.09 ft
DEPTH TO WATER: 9.09 ft
DEPTH OF WELL: 16.04 ft
HEIGHT OF WATER: 6.95 ft
(6.95) X .65 X 3 = 13.55
GALLONS OF H2O TO BE PURGED: 14 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.07 gpm
Hnu READING: 1.3 ppm

PURGE START TIME: 0845
pH 5.21 su TEMP 20.4 °C
DISSOLVED O2 3.66 ppm SPECIFIC CONDUCTIVITY 80 us/cm

PURGE END TIME:
pH 5.98 su TEMP 19.7 °C
DISSOLVED O2 3.36 ppm SPECIFIC CONDUCTIVITY 80 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.17 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ®
BAILER)

TOTAL VOLUME PURGED: 14 gal

pH 5.92 su TEMP 19.3 °C
DISSOLVED O2 3.26 ppm SPECIFIC CONDUCTIVITY 80 us/cm

COMMENTS:

CASE NARRATIVE

Site: Bldg. CW-2
Lab ID: 3723

The duplicate analysis was performed on MW-30 (3723.03).

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit

J : Compound identified below detection limit

B : Compound in both sample and blank

D : Results from dilution of sample

U : Compound searched for but not detected

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00964.d
 Operator Skelton
 Date Acquired 17 Jul 1998 11:22 am

Sample Name VBLK27
 Field ID VBLK27
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	6.25 ug/L	
107131	Acrylonitrile			not detected	50	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethan			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00983.d
 Operator Skelton
 Date Acquired 18 Jul 1998 1:59 am

Sample Name 3723.01
 Field ID Trip Blank
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	6.25 ug/L	
107131	Acrylonitrile			not detected	50	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethan			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00984.d
 Operator Skelton
 Date Acquired 18 Jul 1998 2:43 am

Sample Name 3723.02
 Field ID Field Blank
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	6.25 ug/L	
107131	Acrylonitrile			not detected	50	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethan			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00985.d
 Operator Skelton
 Date Acquired 18 Jul 1998 3:28 am

Sample Name 3723.03
 Field ID MW30
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	6.25 ug/L	
107131	Acrylonitrile			not detected	50	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethan			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone	10.51	48170	9.84 ug/L	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00986.d
 Operator Skelton
 Date Acquired 18 Jul 1998 4:12 am

Sample Name 3723.04
 Field ID MW31
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	6.25 ug/L	
107131	Acrylonitrile			not detected	50	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00987.d
 Operator Skelton
 Date Acquired 18 Jul 1998 4:56 am

Sample Name 3723.05
 Field ID MW32
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	6.25 ug/L	
107131	Acrylonitrile			not detected	50	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone	10.50	33445	7.02 ug/L	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb00988.d
 Operator Skelton
 Date Acquired 18 Jul 1998 5:40 am

Sample Name 3723.06
 Field ID MW33
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	6.25 ug/L	
107131	Acrylonitrile			not detected	50	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone			not detected	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam VB00989.D
 Operator Skelton
 Date Acquired 18 Jul 1998 6:25 am

Sample Name 3723.07
 Field ID Field Dupe
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	6.25 ug/L	
107131	Acrylonitrile			not detected	50	6.25 ug/L	
75650	tert-Butyl alcohol			not detected	nle	12.50 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	2.50 ug/L	
108203	Di-isopropyl ether			not detected	nle	1.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	3.63 ug/L	
74-87-3	Chloromethane			not detected	30	0.79 ug/L	
75-01-4	Vinyl Chloride			not detected	5	2.61 ug/L	
74-83-9	Bromomethane			not detected	10	1.45 ug/L	
75-00-3	Chloroethane			not detected	nle	2.20 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	1.31 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.74 ug/L	
67-64-1	Acetone	10.54	33767	7.42 ug/L	700	1.57 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.54 ug/L	
75-09-2	Methylene Chloride			not detected	2	1.66 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.50 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.83 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	2.07 ug/L	
78-93-3	2-Butanone			not detected	300	2.06 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.65 ug/L	
67-66-3	Chloroform			not detected	6	0.43 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.81 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	1.20 ug/L	
71-43-2	Benzene			not detected	1	0.51 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	1.27 ug/L	
79-01-6	Trichloroethene			not detected	1	0.94 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.78 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.77 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	1.05 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.60 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	1.33 ug/L	
108-88-3	Toluene			not detected	1000	0.73 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	1.43 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	1.49 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.92 ug/L	
591-78-6	2-Hexanone			not detected	nle	1.12 ug/L	
126-48-1	Dibromochloromethane			not detected	10	1.36 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.66 ug/L	
100-41-4	Ethylbenzene			not detected	700	1.14 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	2.53 ug/L	
1330-20-7	o-Xylene			not detected	nle	1.92 ug/L	
100-42-5	Styrene			not detected	100	1.57 ug/L	
75-25-2	Bromoform			not detected	4	1.68 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	1.71 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.51 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	3.08 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.75 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

VBLK27

Lab Name: FMETL Project _____
NJDEP# 13461 Case No.: 3723 SDG No _____ Location CW-2
Matrix: (soil/water) WATER Lab Sample ID: VBLK27
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00964.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: not dec. _____ Date Analyzed: 07/17/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Trip Blank

Lab Name: FMETL Project _____
NJDEP# 13461 Case No.: 3723 SDG No _____ Location CW-2
Matrix: (soil/water) WATER Lab Sample ID: 3723.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00983.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: not dec. _____ Date Analyzed: 07/18/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Project _____
NJDEP# 13461 Case No.: 3723 SDG No _____ Location CW-2
Matrix: (soil/water) WATER Lab Sample ID: 3723.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00984.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: not dec. _____ Date Analyzed: 07/18/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW-30

Lab Name: FMETL Project _____
NJDEP# 13461 Case No.: 3723 SDG No _____ Location CW-2
Matrix: (soil/water) WATER Lab Sample ID: 3723.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00985.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: not dec. _____ Date Analyzed: 07/18/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0

(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW-31

Lab Name: FMETL Project _____
NJDEP# 13461 Case No.: 3723 SDG No _____ Location CW-2
Matrix: (soil/water) WATER Lab Sample ID: 3723.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00986.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: not dec. _____ Date Analyzed: 07/18/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW-32

Lab Name: FMETL Project _____
NJDEP# 13461 Case No.: 3723 SDG No _____ Location CW-2
Matrix: (soil/water) WATER Lab Sample ID: 3723.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00987.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: not dec. _____ Date Analyzed: 07/18/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW-33

Lab Name: FMETL Project _____
NJDEP# 13461 Case No.: 3723 SDG No _____ Location CW-2
Matrix: (soil/water) WATER Lab Sample ID: 3723.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00988.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: not dec. _____ Date Analyzed: 07/18/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Dupe

Lab Name: FMETL Project _____

NJDEP# 13461 Case No.: 3723 SDG No _____ Location CW-2

Matrix: (soil/water) WATER Lab Sample ID: 3723.07

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB00989.D

Level: (low/med) LOW Date Received: 07/14/98

% Moisture: not dec. _____ Date Analyzed: 07/18/98

GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn2093.d**
 Operator **FITZPATRICK**
 Date Acquired **17 Jul 98 7:35 pm**

Sample Name **SBLK 104**
 Misc Info **SBLK 104**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn2093.d**
 Operator **FITZPATRICK**
 Date Acquired **17 Jul 98 7:35 pm**

Sample Name **SBLK 104**
 Misc Info **SBLK 104**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	1.22	ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68	ug/L	
86-73-7	Fluorene			not detected	300	1.93	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73	ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88	ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55	ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67	ug/L	
120-12-7	Anthracene			not detected	2000	1.79	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83	ug/L	
206-44-0	Fluoranthene			not detected	300	1.85	ug/L	
92-87-5	Benzidine			not detected	50	4.11	ug/L	
129-00-0	Pyrene			not detected	200	1.02	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28	ug/L	
218-01-9	Chrysene			not detected	20	2.32	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn2095.d**
 Operator **FITZPATRICK**
 Date Acquired **17 Jul 98 9:15 pm**

Sample Name **3723.02**
 Misc Info **FIELD BLANK**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn2095.d**
 Operator **FITZPATRICK**
 Date Acquired **17 Jul 98 9:15 pm**

Sample Name **3723.02**
 Misc Info **FIELD BLANK**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	1.22 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68 ug/L	
86-73-7	Fluorene			not detected	300	1.93 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88 ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67 ug/L	
120-12-7	Anthracene			not detected	2000	1.79 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benzidine			not detected	50	4.11 ug/L	
129-00-0	Pyrene			not detected	200	1.02 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28 ug/L	
218-01-9	Chrysene			not detected	20	2.32 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13 ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn2096.d**
 Operator **FITZPATRICK**
 Date Acquired **17 Jul 98 10:04 pm**

Sample Name **3723.03**
 Misc Info **MW-30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bn2096.d
Operator FITZPATRICK
Date Acquired 17 Jul 98 10:04 pm

Sample Name 3723.03
Misc Info MW-30
Sample Multiplier 1

121-14-2	2,4-Dinitrotoluene			not detected	10	1.22	ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68	ug/L	
86-73-7	Fluorene			not detected	300	1.93	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73	ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88	ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55	ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67	ug/L	
120-12-7	Anthracene			not detected	2000	1.79	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83	ug/L	
206-44-0	Fluoranthene			not detected	300	1.85	ug/L	
92-87-5	Benzidine			not detected	50	4.11	ug/L	
129-00-0	Pyrene			not detected	200	1.02	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28	ug/L	
218-01-9	Chrysene			not detected	20	2.32	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13	ug/L	

Qualifiers

E = Value exceeded linear range
D = Value from dilution
B = Compound in related blank
MDL = Method Detection Limit
NLE = No Limit Established
R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn2097.d**
 Operator **FITZPATRICK**
 Date Acquired **17 Jul 98 10:53 pm**

Sample Name **3723.04**
 Misc Info **MW-31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bm2097.d
 Operator FITZPATRICK
 Date Acquired 17 Jul 98 10:53 pm

Sample Name 3723.04
 Misc Info MW-31
 Sample Multiplier 1

121-14-2	2,4-Dinitrotoluene			not detected	10	1.22	ug/L
84-66-2	Diethylphthalate			not detected	5000	1.68	ug/L
86-73-7	Fluorene			not detected	300	1.93	ug/L
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53	ug/L
100-01-6	4-Nitroaniline			not detected	NLE	2.70	ug/L
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58	ug/L
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73	ug/L
103-33-3	Azobenzene			not detected	NLE	1.92	ug/L
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54	ug/L
118-74-1	Hexachlorobenzene			not detected	10	1.88	ug/L
87-86-5	Pentachlorophenol			not detected	1	0.55	ug/L
85-01-8	Phenanthrene			not detected	NLE	1.67	ug/L
120-12-7	Anthracene			not detected	2000	1.79	ug/L
84-74-2	Di-n-butylphthalate			not detected	900	1.83	ug/L
206-44-0	Fluoranthene			not detected	300	1.85	ug/L
92-87-5	Benzidine			not detected	50	4.11	ug/L
129-00-0	Pyrene			not detected	200	1.02	ug/L
85-68-7	Butylbenzylphthalate			not detected	100	1.15	ug/L
56-55-3	Benzo[a]anthracene			not detected	10	1.57	ug/L
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28	ug/L
218-01-9	Chrysene			not detected	20	2.32	ug/L
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29	ug/L
117-84-0	Di-n-octylphthalate			not detected	100	1.30	ug/L
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31	ug/L
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57	ug/L
50-32-8	Benzo[a]pyrene			not detected	20	1.36	ug/L
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22	ug/L
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12	ug/L
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13	ug/L

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **bn2098.d**
 Operator **FITZPATRICK**
 Date Acquired **17 Jul 98 11:42 pm**

Sample Name **3723.05**
 Misc Info **MW-32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn2098.d**
 Operator **FITZPATRICK**
 Date Acquired **17 Jul 98 11:42 pm**

Sample Name **3723.05**
 Misc Info **MW-32**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	1.22	ug/L
84-66-2	Diethylphthalate			not detected	5000	1.68	ug/L
86-73-7	Fluorene			not detected	300	1.93	ug/L
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53	ug/L
100-01-6	4-Nitroaniline			not detected	NLE	2.70	ug/L
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58	ug/L
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73	ug/L
103-33-3	Azobenzene			not detected	NLE	1.92	ug/L
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54	ug/L
118-74-1	Hexachlorobenzene			not detected	10	1.88	ug/L
87-86-5	Pentachlorophenol			not detected	1	0.55	ug/L
85-01-8	Phenanthrene			not detected	NLE	1.67	ug/L
120-12-7	Anthracene			not detected	2000	1.79	ug/L
84-74-2	Di-n-butylphthalate			not detected	900	1.83	ug/L
206-44-0	Fluoranthene			not detected	300	1.85	ug/L
92-87-5	Benzidine			not detected	50	4.11	ug/L
129-00-0	Pyrene			not detected	200	1.02	ug/L
85-68-7	Butylbenzylphthalate			not detected	100	1.15	ug/L
56-55-3	Benzo[a]anthracene			not detected	10	1.57	ug/L
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28	ug/L
218-01-9	Chrysene			not detected	20	2.32	ug/L
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29	ug/L
117-84-0	Di-n-octylphthalate			not detected	100	1.30	ug/L
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31	ug/L
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57	ug/L
50-32-8	Benzo[a]pyrene			not detected	20	1.36	ug/L
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22	ug/L
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12	ug/L
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13	ug/L

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name bm2099.d
 Operator FITZPATRICK
 Date Acquired 18 Jul 98 12:30 am

Sample Name 3723.06
 Misc Info MW-33
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **bn2099.d**
 Operator **FITZPATRICK**
 Date Acquired **18 Jul 98 12:30 am**

Sample Name **3723.06**
 Misc Info **MW-33**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	1.22	ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68	ug/L	
86-73-7	Fluorene			not detected	300	1.93	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73	ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88	ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55	ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67	ug/L	
120-12-7	Anthracene			not detected	2000	1.79	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83	ug/L	
206-44-0	Fluoranthene			not detected	300	1.85	ug/L	
92-87-5	Benzidine			not detected	50	4.11	ug/L	
129-00-0	Pyrene			not detected	200	1.02	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28	ug/L	
218-01-9	Chrysene			not detected	20	2.32	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN2100.D**
 Operator **FITZPATRICK**
 Date Acquired **18 Jul 98 1:19 am**

Sample Name **3723.07**
 Misc Info **FIELD DUP**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	GW Criteria	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN2100.D**
 Operator **FITZPATRICK**
 Date Acquired **18 Jul 98 1:19 am**

Sample Name **3723.07**
 Misc Info **FIELD DUP**
 Sample Multiplier **1**

121-14-2	2,4-Dinitrotoluene			not detected	10	1.22	ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68	ug/L	
86-73-7	Fluorene			not detected	300	1.93	ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53	ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70	ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58	ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73	ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92	ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54	ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88	ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55	ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67	ug/L	
120-12-7	Anthracene			not detected	2000	1.79	ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83	ug/L	
206-44-0	Fluoranthene			not detected	300	1.85	ug/L	
92-87-5	Benzidine			not detected	50	4.11	ug/L	
129-00-0	Pyrene			not detected	200	1.02	ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15	ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57	ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28	ug/L	
218-01-9	Chrysene			not detected	20	2.32	ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29	ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30	ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31	ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57	ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36	ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22	ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12	ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13	ug/L	

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

SBLK 104

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 3723 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: SBLK 104
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN2093.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: _____ decanted: (Y/N) N Date Extracted: 07/15/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 07/17/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.29	9	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD BLANK

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 3723 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3723.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN2095.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: _____ decanted: (Y/N) N Date Extracted: 07/15/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 07/17/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.29	8	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

MW-30

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3723 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3723.03

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN2096.D

Level: (low/med) LOW Date Received: 07/14/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 07/15/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 07/17/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.29	12	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

MW-31

Lab Name: FMETL Lab Code 13461
Project _____ Case No.: 3723 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 3723.04
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN2097.D
Level: (low/med) LOW Date Received: 07/14/98
% Moisture: _____ decanted: (Y/N) N Date Extracted: 07/15/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 07/17/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
 SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
 TENTATIVELY IDENTIFIED COMPOUNDS

MW-32

Lab Name: FMETL Lab Code 13461
 Project _____ Case No.: 3723 Location CW-2 SDG No.: _____
 Matrix: (soil/water) WATER Lab Sample ID: 3723.05
 Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN2098.D
 Level: (low/med) LOW Date Received: 07/14/98
 % Moisture: _____ decanted: (Y/N) N Date Extracted: 07/15/98
 Concentrated Extract Volume: 1000 (uL) Date Analyzed: 07/17/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

MW-33

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3723 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3723.06

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN2099.D

Level: (low/med) LOW Date Received: 07/14/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 07/15/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 07/18/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD DUP

Lab Name: FMETL Lab Code 13461

Project _____ Case No.: 3723 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 3723.07

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN2100.D

Level: (low/med) LOW Date Received: 07/14/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 07/15/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 07/18/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	BLK145
	DPW, SELFM-PW-EV	Date Rec'd:	
	Bldg. 173	Extraction Date:	7/15/98
	Ft. Monmouth, NJ 07703	Analysis Date:	8/19/98

Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3723.02
	DPW, SELFM-PW-EV	Date Rec'd:	7/14/98
	Bldg. 173	Extraction Date:	7/15/98
	Ft. Monmouth, NJ 07703	Analysis Date:	8/19/98

Analysis:	EPA Method 608	Location :	CW-2 (2700) MWS
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	Field Blank
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3723.03
	DPW, SELFM-PW-EV	Date Rec'd:	7/14/98
	Bldg. 173	Extraction Date:	7/15/98
	Ft. Monmouth, NJ 07703	Analysis Date:	8/19/98

Analysis:	EPA Method 608	Location :	CW-2 (2700) MWS
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-30
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected	Column-Primary:	Rtx-CLPesticides 30m/.32 mm ID/.25
MDL = Method Detection Limit	Column-Confirmation:	Rtx-CLPesticides2 30m/.32 mm ID/.25
NLE = No Limit Established		
PQL = Practical Quantitation Limit		

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 3723.04
Date Rec'd: 7/14/98
Extraction Date: 7/15/98
Analysis Date: 8/19/98

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: D. Wright
Ext. Meth: Sep. Funnel

Location : CW-2 (2700) MWS
Field ID: MW-31

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3723.05
	DPW, SELFM-PW-EV	Date Rec'd:	7/14/98
	Bldg. 173	Extraction Date:	7/15/98
	Ft. Monmouth, NJ 07703	Analysis Date:	8/19/98

Analysis:	EPA Method 608	Location :	CW-2 (2700) MWS
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-32
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

Column-Primary: Rtx-CLPesticides 30m/.32 mm ID/.25

MDL = Method Detection Limit

Column-Confirmation: Rtx-CLPesticides2 30m/.32 mm ID/.25

NLE = No Limit Established

PQL = Practical Quantitation Limit

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3723.06
	DPW, SELFM-PW-EV	Date Rec'd:	7/14/98
	Bldg. 173	Extraction Date:	7/15/98
	Ft. Monmouth, NJ 07703	Analysis Date:	8/19/98

Analysis:	EPA Method 608	Location :	CW-2 (2700) MW'S
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-33
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Column-Confirmation:

Rtx-CLPesticides 30m/.32 mm ID/.25

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	3723.07
	DPW, SELFM-PW-EV	Date Rec'd:	7/14/98
	Bldg. 173	Extraction Date:	7/15/98
	Ft. Monmouth, NJ 07703	Analysis Date:	8/19/98

Analysis:	EPA Method 608	Location :	CW-2 (2700) MWS
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	Field Dup
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3723
 Sample Preparation: 07/24/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

METHOD BLANK SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/24/98	145	200	10.0
Antimony	07/24/98	5.0	20	2.0
Arsenic	07/24/98	ND	8	2.0
Barium	07/24/98	2.5	2000	0.5
Beryllium	07/24/98	0.7	20	0.5
Cadmium	08/04/98	ND	4	0.5
Calcium	07/24/98	243	NLE	20.0
Chromium	07/24/98	ND	100	0.5
Cobalt	07/24/98	ND	NLE	0.5
Copper	07/24/98	ND	1000	3.0
Iron	07/24/98	30	300	10.0
Lead	07/24/98	4.0	10	2.0
Magnesium	07/24/98	100	NLE	20.0
Manganese	07/24/98	ND	50	0.5
Mercury	07/24/98	ND	2	0.2
Nickel	07/24/98	ND	100	0.5
Potassium	07/24/98	ND	NLE	20.0
Selenium	07/24/98	ND	50	3.0
Silver	07/24/98	ND	20	3.0
Sodium	07/24/98	ND	50000	20.0
Thallium	07/24/98	ND	10	3.0
Vanadium	07/24/98	ND	NLE	1.0
Zinc	07/24/98	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3723.02
 Sample Received: 07/14/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/24/98	ND	200	10.0
Antimony	07/24/98	ND	20	2.0
Arsenic	07/24/98	ND	8	2.0
Barium	07/24/98	ND	2000	0.5
Beryllium	07/24/98	ND	20	0.5
Cadmium	08/04/98	ND	4	0.5
Calcium	07/24/98	149	NLE	20.0
Chromium	07/24/98	ND	100	0.5
Cobalt	07/24/98	ND	NLE	0.5
Copper	07/24/98	4.41	1000	3.0
Iron	07/24/98	117	300	10.0
Lead	07/24/98	ND	10	2.0
Magnesium	07/24/98	ND	NLE	20.0
Manganese	07/24/98	ND	50	0.5
Mercury	07/24/98	ND	2	0.2
Nickel	07/24/98	ND	100	0.5
Potassium	07/24/98	ND	NLE	20.0
Selenium	07/24/98	ND	50	3.0
Silver	07/24/98	ND	20	3.0
Sodium	07/24/98	ND	50000	20.0
Thallium	07/24/98	ND	10	3.0
Vanadium	07/24/98	ND	NLE	1.0
Zinc	07/24/98	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3723.03
 Sample Received: 07/14/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/24/98	65.7	200	10.0
Antimony	07/24/98	3.50	20	2.0
Arsenic	07/24/98	ND	8	2.0
Barium	07/24/98	85.5	2000	0.5
Beryllium	07/24/98	ND	20	0.5
Cadmium	08/04/98	ND	4	0.5
Calcium	07/24/98	75000	NLE	20.0
Chromium	07/24/98	ND	100	0.5
Cobalt	07/24/98	ND	NLE	0.5
Copper	07/24/98	4.37	1000	3.0
Iron	07/24/98	10900	300	10.0
Lead	07/24/98	ND	10	2.0
Magnesium	07/24/98	5270	NLE	20.0
Manganese	07/24/98	57.8	50	0.5
Mercury	07/24/98	ND	2	0.2
Nickel	07/24/98	0.630	100	0.5
Potassium	07/24/98	13800	NLE	20.0
Selenium	07/24/98	ND	50	3.0
Silver	07/24/98	ND	20	3.0
Sodium	07/24/98	14300	50000	20.0
Thallium	07/24/98	ND	10	3.0
Vanadium	07/24/98	1.22	NLE	1.0
Zinc	07/24/98	21.4	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3723.04
 Sample Received: 07/14/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/24/98	390	200	10.0
Antimony	07/24/98	3.67	20	2.0
Arsenic	07/24/98	ND	8	2.0
Barium	07/24/98	295	2000	0.5
Beryllium	07/24/98	ND	20	0.5
Cadmium	08/04/98	ND	4	0.5
Calcium	07/24/98	58800	NLE	20.0
Chromium	07/24/98	ND	100	0.5
Cobalt	07/24/98	ND	NLE	0.5
Copper	07/24/98	34.5	1000	3.0
Iron	07/24/98	83600	300	10.0
Lead	07/24/98	4.85	10	2.0
Magnesium	07/24/98	6500	NLE	20.0
Manganese	07/24/98	311	50	0.5
Mercury	07/24/98	ND	2	0.2
Nickel	07/24/98	ND	100	0.5
Potassium	07/24/98	12800	NLE	20.0
Selenium	07/24/98	ND	50	3.0
Silver	07/24/98	ND	20	3.0
Sodium	07/24/98	8970	50000	20.0
Thallium	07/24/98	ND	10	3.0
Vanadium	07/24/98	ND	NLE	1.0
Zinc	07/24/98	26.2	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3723.05
 Sample Received: 07/14/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/24/98	78.1	200	10.0
Antimony	07/24/98	2.27	20	2.0
Arsenic	07/24/98	2.51	8	2.0
Barium	07/24/98	203	2000	0.5
Beryllium	07/24/98	ND	20	0.5
Cadmium	08/04/98	ND	4	0.5
Calcium	07/24/98	88700	NLE	20.0
Chromium	07/24/98	ND	100	0.5
Cobalt	07/24/98	ND	NLE	0.5
Copper	07/24/98	31.1	1000	3.0
Iron	07/24/98	67500	300	10.0
Lead	07/24/98	3.99	10	2.0
Magnesium	07/24/98	8570	NLE	20.0
Manganese	07/24/98	287	50	0.5
Mercury	07/24/98	ND	2	0.2
Nickel	07/24/98	2.03	100	0.5
Potassium	07/24/98	10200	NLE	20.0
Selenium	07/24/98	ND	50	3.0
Silver	07/24/98	ND	20	3.0
Sodium	07/24/98	10700	50000	20.0
Thallium	07/24/98	ND	10	3.0
Vanadium	07/24/98	ND	NLE	1.0
Zinc	07/24/98	145	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3723.06
 Sample Received: 07/14/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/24/98	411	200	10.0
Antimony	07/24/98	ND	20	2.0
Arsenic	07/24/98	ND	8	2.0
Barium	07/24/98	144	2000	0.5
Beryllium	07/24/98	ND	20	0.5
Cadmium	08/04/98	ND	4	0.5
Calcium	07/24/98	27500	NLE	20.0
Chromium	07/24/98	ND	100	0.5
Cobalt	07/24/98	ND	NLE	0.5
Copper	07/24/98	19.5	1000	3.0
Iron	07/24/98	35900	300	10.0
Lead	07/24/98	4.19	10	2.0
Magnesium	07/24/98	3790	NLE	20.0
Manganese	07/24/98	130	50	0.5
Mercury	07/24/98	ND	2	0.2
Nickel	07/24/98	1.86	100	0.5
Potassium	07/24/98	8300	NLE	20.0
Selenium	07/24/98	ND	50	3.0
Silver	07/24/98	ND	20	3.0
Sodium	07/24/98	15600	50000	20.0
Thallium	07/24/98	ND	10	3.0
Vanadium	07/24/98	2.60	NLE	1.0
Zinc	07/24/98	55.0	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 3723.07
 Sample Received: 07/14/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Dup.

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/24/98	126	200	10.0
Antimony	07/24/98	3.73	20	2.0
Arsenic	07/24/98	ND	8	2.0
Barium	07/24/98	84.8	2000	0.5
Beryllium	07/24/98	ND	20	0.5
Cadmium	08/04/98	ND	4	0.5
Calcium	07/24/98	72700	NLE	20.0
Chromium	07/24/98	ND	100	0.5
Cobalt	07/24/98	ND	NLE	0.5
Copper	07/24/98	4.38	1000	3.0
Iron	07/24/98	13200	300	10.0
Lead	07/24/98	ND	10	2.0
Magnesium	07/24/98	5210	NLE	20.0
Manganese	07/24/98	65.1	50	0.5
Mercury	07/24/98	ND	2	0.2
Nickel	07/24/98	0.872	100	0.5
Potassium	07/24/98	14800	NLE	20.0
Selenium	07/24/98	ND	50	3.0
Silver	07/24/98	ND	20	3.0
Sodium	07/24/98	15400	50000	20.0
Thallium	07/24/98	ND	10	3.0
Vanadium	07/24/98	1.52	NLE	1.0
Zinc	07/24/98	22.0	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

	Lab	Silanol, trimethyl-	Hexadeca noic Acid	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water		Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ugl	Feet		-
NJDEP Criteria:	-	NLE	NLE	300	50	200	8	10	-		-
04/24/97	FMETL	31	9	9100	69	-	-	-	6.45		V,S,P,M
07/10/97	FMETL	ND	ND	12590	73	25	5.0	ND	7.05		V,S,P,M
10/22/97	FMETL	ND	ND	34800	171	175	5.0	5.0	7.60		V,S,P,M
01/08/98	FMETL	ND	ND	2795	5.0	204	ND	4.0	5.20		V,S,P,M
04/07/98	FMETL	ND	ND	3504	39.3	196	5.6	ND	6.56		V,S,P,M
07/14/98	FMETL	ND	ND	10900	57.8	65.7	ND	ND	6.89		V,S,P,M

SOURCE: MW30

Sampling Dates:
04/24/97 - 07/14/98

NOTES:

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 1 of 4




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Silanol, trimethyl-
(ug/l)




Hexadecanoic Acid
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ugl)



Depth to Water
(Feet)



SOURCE: MW30

Sampling Dates:
04/24/97 - 07/14/98

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Silanol, trimethyl-	Benzene-1, 2,3,4,-d4,5, 6-dichloro	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water		Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ugl	Feet		-
NJDEP Criteria:	-	NLE	NLE	300	50	200	8	10	-		-
04/24/97	FMETL	12	35	59900	277	-	-	-	6.38		V,S,P,M
07/10/97	FMETL	ND	ND	11830	267	ND	1.0	ND	7.00		V,S,P,M
10/22/97	FMETL	ND	ND	52300	243	93	ND	6.0	7.50		V,S,P,M
01/08/98	FMETL	ND	ND	68450	240	129	ND	25	6.30		V,S,P,M
04/07/98	FMETL	ND	ND	115100	266	ND	ND	ND	6.35		V,S,P,M
07/14/98	FMETL	ND	ND	83600	311	390	ND	4.85	6.71		V,S,P,M

SOURCE: MW31

Sampling Dates:
04/24/97 - 07/14/98

NOTES:


FORT MONMOUTH

GW MONITORING
Bldg CW-2


Well 1 of 1

 U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Silanol, trimethyl-
(ug/l)




Benzene-1,2,3,4-d4-5,6-dichloro
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ugl)



Depth to Water
(Feet)



SOURCE: MW31

Sampling Dates:
04/24/97 - 07/14/98

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 1 of 1, Graph




U.S. ARMY
FORT MONMOUTH
SELFM-PW-EV


Silanol, trimethyl-
(ug/l)




(E)-3-Chloro-2-methyl-2-pentenal
(ug/l)




2-Pentanone,4-hydroxy-4-methyl
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: MW32

Sampling Dates:
04/24/97 - 07/14/98

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Silanol, trimethyl-	(E)-3-Chloro-2-methyl-2-pentenal	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water		Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ugl	Feet		-
NJDEP Criteria:	-	NLE	NLE	300	50	200	8	10	-		-
04/24/97	FMETL	30	41	88600	424	-	-	-	8.95		V,S,P,M
07/10/97	FMETL	ND	ND	10260	519	2.1	1.0	ND	9.10		V,S,P,M
10/22/97	FMETL	ND	ND	26800	151	94	ND	4.0	9.10		V,S,P,M
01/08/98	FMETL	ND	ND	104700	342	217	6.0	4.0	9.00		V,S,P,M
04/07/98	FMETL	ND	ND	19780	110	119	3.4	ND	9.50		V,S,P,M
07/14/98	FMETL	ND	ND	35900	130	411	ND	4.19	9.09		V,S,P,M

SOURCE: MW33

Sampling Dates:
04/24/97 - 07/14/98

NOTES:


FORT MONMOUTH

GW MONITORING
Bldg CW-2


Well 1 of 1

 U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Silanol, trimethyl-
(ug/l)




(E)-3-Chloro-2-methyl-2-pentenal
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ugl)



Depth to Water
(Feet)



SOURCE: MW33

Sampling Dates:
04/24/97 - 07/14/98

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 1, Graph



U.S. ARMY
FORT MONMOUTH
SELF-PW-EV

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-3484

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT

FOR

Directorate of Public Works

Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
4083.03	MW-30	29-32594	11/24/98
4083.04	MW-31	29-32595	11/24/98
4083.05	MW-32	29-32596	11/24/98
4083.06	MW-33	29-32597	11/24/98

NJDEP Laboratory Certification # 13461

Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608



Fort Monmouth Environmental Testing Laboratory


Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (732)532-4359 Fax (732)532-3484 EMail:appleby@doim6.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: Joe Fallon		Project No:		Analysis Parameters								Comments:					
Phone #: 126223		Location: CW-2 mws 4th Qtr '98										HCL/HNO ₃ /4°C Remarks / Preservation Method					
() DERA () OMA () Other:																	
Samplers Name / Company: Corey McCormick, TUS		Sample #															
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles	VOATIS	BNATIS	Pest/PCB	TAL MTLs								
4083-.01	Trip	11/24/98	0835	AQ	2	✓											
.02	Field Blank		0850		5	✓	✓	✓	✓								
.03	MW-30		1023		5	✓	✓	✓	✓					✓	0.0 ppm		
.04	MW-31 *	12/25/98	1021		5	✓	✓	✓	✓					✓	0.0 ppm		
.05	MW-32		1021		5	✓	✓	✓	✓					✓	0.0 ppm		
.06	MW-33		1012		5	✓	✓	✓	✓					✓	0.0 ppm		
.07	Dupe	✓	—	↓	5	✓	✓	✓	✓								
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):	
Corey McCormick		11/24/98 1445		[Signature]													
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):	
Report Type: () Full, () Reduced, (x) Standard, () Screen / non-certified						Remarks:											
Turnaround time: (x) Standard 4 wks, () Rush _____ Days, () ASAP Verbal _____ Hrs.						Shms Dge/Trip/Blank w/ 290 of same date Tide: Out/Low											



LEGEND

● Soil Boring/Monitor Well	▬ Road (paved)	▬ Road/Track (unpaved)	▬ Site
▬ Fence	▬ Tree/Bush	▬ Base Boundary	▬ Wooded Area
▬ Building	▬ Light Pole	▬ Utility Area	▬ Approximate Boundary
▬ Utility Pole			

Fort Monmouth, Main Post

FIGURE 4.3-3

ACID NEUTRALIZATION LINE PITS (ANL-26 AND ANL-29)

SAMPLING LOCATIONS

SCALE IN FEET

0 50 100

50' 100'

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 30
NJDEP ID #: 2932594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 11/24/98
WEATHER: Cool/Clear.
TIDE: Out/Low

ELEV. OF CASING SURVEY MARK: 51.71ft
DEPTH TO WATER: 7.86 ft
DEPTH OF WELL: 17.95 ft
HEIGHT OF WATER: 10.09 ft
 $10.09 \times .65 \times 3 = 19.68$
GALLONS OF H₂O TO BE PURGED: 20 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.00 ppm

PURGE START TIME: 08:58
pH: 6.69su TEMP: 17.5 °C
DISSOLVED O₂: 8.08 ppm SPECIFIC CONDUCTIVITY: 929 us/cm

PURGE END TIME: 10:23
pH: 6.64su TEMP: 16.4 °C
DISSOLVED O₂: 8.17 ppm SPECIFIC CONDUCTIVITY: 924 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 12.27ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 20.00 gal

pH: 6.63su TEMP: 16.2 °C
DISSOLVED O₂: 8.26 ppm SPECIFIC CONDUCTIVITY: 926 us/cm

COMMENTS:

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 31
NJDEP ID #: 2932595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 11/24/98
WEATHER: Cool/Clear.
TIDE: Out/Low

ELEV. OF CASING SURVEY MARK: 51.58ft
DEPTH TO WATER: 7.78 ft
DEPTH OF WELL: 16.90 ft
HEIGHT OF WATER: 9.12 ft
9.12 X .65 X 3 = 17.78
GALLONS OF H2O TO BE PURGED: 18 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.00 ppm

PURGE START TIME: 11:02
pH: 6.83su TEMP: 17.9 °C
DISSOLVED O2: 8.23 ppm SPECIFIC CONDUCTIVITY: 734 us/cm

PURGE END TIME: 12:20
pH: 6.79su TEMP: 16.4 °C
DISSOLVED O2: 8.70 ppm SPECIFIC CONDUCTIVITY: 735 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 11.05ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 18.00 gal

pH: 6.77su TEMP: 16.1 °C
DISSOLVED O2: 8.72 ppm SPECIFIC CONDUCTIVITY: 733 us/cm

COMMENTS: Dup Here.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 32
NJDEP ID #: 2932596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 11/24/98
WEATHER: Cool/Clear.
TIDE: Out/Low

ELEV. OF CASING SURVEY MARK: 51.38ft
DEPTH TO WATER: 7.94 ft
DEPTH OF WELL: 16.89 ft
HEIGHT OF WATER: 8.95 ft
 $8.95 \times .65 \times 3 = 17.45$
GALLONS OF H2O TO BE PURGED: 17 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.22 gpm
Hnu READING: 0.00 ppm

PURGE START TIME: 09:07
pH: 6.77su TEMP: 17.7 °C
DISSOLVED O2: 8.98 ppm SPECIFIC CONDUCTIVITY: 889 us/cm

PURGE END TIME: 10:21
pH: 6.72su TEMP: 16.5 °C
DISSOLVED O2: 9.10 ppm SPECIFIC CONDUCTIVITY: 890 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 15.86ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 17.00 gal

pH: 6.74su TEMP: 16.3 °C
DISSOLVED O2: 9.17 ppm SPECIFIC CONDUCTIVITY: 894 us/cm

COMMENTS: Orange tinge/Particles.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 33
NJDEP ID #: 2932597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 11/24/98
WEATHER: Cool/Clear.
TIDE: Low/Out

ELEV. OF CASING SURVEY MARK: 51.09ft
DEPTH TO WATER: 9.13 ft
DEPTH OF WELL: 16.10 ft
HEIGHT OF WATER: 6.97 ft
 $6.97 \times .65 \times 3 = 13.59$
GALLONS OF H₂O TO BE PURGED: 14 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.00 ppm

PURGE START TIME: 09:11
pH: 6.81su TEMP: 17.2 °C
DISSOLVED O₂: 8.42 ppm SPECIFIC CONDUCTIVITY: 569 us/cm

PURGE END TIME: 10:12
pH: 6.80su TEMP: 16.6 °C
DISSOLVED O₂: 8.63 ppm SPECIFIC CONDUCTIVITY: 580 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 9.39ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 14.00 gal

pH: 6.82su TEMP: 16.3 °C
DISSOLVED O₂: 8.59 ppm SPECIFIC CONDUCTIVITY: 578 us/cm

COMMENTS: Orange tinge/Particles.

CASE NARRATIVE

Site: CW-2

Lab ID: 4083

The duplicate analysis was performed on MW-31 (4083.04).

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit

J : Compound identified below detection limit

B : Compound in both sample and blank

D : Results from dilution of sample

U : Compound searched for but not detected

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam **vb02245.d**
 Operator **Skelton**
 Date Acquired **30 Nov 98 10:20 am**

Sample Name **Vblk67**
 Field ID **Vblk67**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Vblk67

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4083 SDG No Location CW2
Matrix: (soil/water) WATER Lab Sample ID: Vblk67
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02245.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: not dec. Date Analyzed: 11/30/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb02255.d
 Operator Skelton
 Date Acquired 30 Nov 98 6:24 pm

Sample Name 4083.01
 Field ID Trip Blank
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Trip Blank

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4083 SDG No Location CW2
Matrix: (soil/water) WATER Lab Sample ID: 4083.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02255.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: not dec. Date Analyzed: 11/30/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb02256.d
 Operator Skelton
 Date Acquired 30 Nov 98 7:09 pm

Sample Name 4083.02
 Field ID Field Blank
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4083 SDG No Location CW2
Matrix: (soil/water) WATER Lab Sample ID: 4083.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02256.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: not dec. Date Analyzed: 11/30/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb02257.d
 Operator Skelton
 Date Acquired 30 Nov 98 7:54 pm

Sample Name 4083.03
 Field ID MW30
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW30

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4083 SDG No Location CW2
Matrix: (soil/water) WATER Lab Sample ID: 4083.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02257.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: not dec. Date Analyzed: 11/30/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb02258.d
 Operator Skelton
 Date Acquired 30 Nov 98 8:38 pm

Sample Name 4083.04
 Field ID MW31
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW31

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4083 SDG No Location CW2
Matrix: (soil/water) WATER Lab Sample ID: 4083.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02258.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: not dec. Date Analyzed: 11/30/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb02259.d
 Operator Skelton
 Date Acquired 30 Nov 98 9:23 pm

Sample Name 4083.05
 Field ID MW32
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW32

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4083 SDG No Location CW2
Matrix: (soil/water) WATER Lab Sample ID: 4083.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02259.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: not dec. Date Analyzed: 11/30/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb02260.d
 Operator Skelton
 Date Acquired 30 Nov 98 10:08 pm

Sample Name 4083.06
 Field ID MW33
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW33

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4083 SDG No Location CW2
Matrix: (soil/water) WATER Lab Sample ID: 4083.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02260.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: not dec. Date Analyzed: 11/30/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Nam vb02261.d
 Operator Skelton
 Date Acquired 1 Dec 98 7:37 am

Sample Name 4083.07
 Field ID Dupe
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ethe			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloroprope			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethan			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Dupe

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4083 SDG No Location CW2
Matrix: (soil/water) WATER Lab Sample ID: 4083.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02261.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: not dec. Date Analyzed: 12/01/98
GC Column: HP5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA01477.D**
 Operator **Skelton**
 Date Acquired **2 Dec 1998 3:32 pm**

Sample Name **Sblk172**
 Misc Info **Sblk172 A 981130**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BNA01477.D
 Operator Skelton
 Date Acquired 2 Dec 1998 3:32 pm

Sample Name Sblk172
 Misc Info Sblk172 A 981130
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.22 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68 ug/L	
86-73-7	Fluorene			not detected	300	1.93 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88 ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67 ug/L	
120-12-7	Anthracene			not detected	2000	1.79 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benzidine			not detected	50	4.11 ug/L	
129-00-0	Pyrene			not detected	200	1.02 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28 ug/L	
218-01-9	Chrysene			not detected	20	2.32 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Sblk172

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4083 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Sblk172
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA01477.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/30/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 12/02/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name bna01481.d
 Operator Skelton
 Date Acquired 2 Dec 1998 6:23 pm

Sample Name 4083.02
 Misc Info Field Blank
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bna01481.d
 Operator Skelton
 Date Acquired 2 Dec 1998 6:23 pm

Sample Name 4083.02
 Misc Info Field Blank
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.22 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68 ug/L	
86-73-7	Fluorene			not detected	300	1.93 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88 ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67 ug/L	
120-12-7	Anthracene			not detected	2000	1.79 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benazidine			not detected	50	4.11 ug/L	
129-00-0	Pyrene			not detected	200	1.02 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28 ug/L	
218-01-9	Chrysene			not detected	20	2.32 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6

Qualifiers

E = Value exceded linear range
 D = Value from dilution
 B = Compound in related blank
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4083 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4083.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA01481.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/30/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 12/02/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name bna01482.d
 Operator Skelton
 Date Acquired 2 Dec 1998 7:05 pm

Sample Name 4083.03
 Misc Info MW30
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bna01482.d
 Operator Skelton
 Date Acquired 2 Dec 1998 7:05 pm

Sample Name 4083.03
 Misc Info MW30
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.22 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68 ug/L	
86-73-7	Fluorene			not detected	300	1.93 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88 ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67 ug/L	
120-12-7	Anthracene			not detected	2000	1.79 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benazidine			not detected	50	4.11 ug/L	
129-00-0	Pyrene			not detected	200	1.02 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28 ug/L	
218-01-9	Chrysene			not detected	20	2.32 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW30

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4083 Location CW-2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4083.03
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA01482.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/30/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 12/02/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name bna01483.d
 Operator Skelton
 Date Acquired 2 Dec 1998 7:47 pm

Sample Name 4083.04
 Misc Info MW31
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bna01483.d
 Operator Skelton
 Date Acquired 2 Dec 1998 7:47 pm

Sample Name 4083.04
 Misc Info MW31
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.22 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68 ug/L	
86-73-7	Fluorene			not detected	300	1.93 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88 ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67 ug/L	
120-12-7	Anthracene			not detected	2000	1.79 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benazidine			not detected	50	4.11 ug/L	
129-00-0	Pyrene			not detected	200	1.02 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28 ug/L	
218-01-9	Chrysene			not detected	20	2.32 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW31

Lab Name: FMETL Lab Code 13461

Project LTM Case No.: 4083 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 4083.04

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA01483.D

Level: (low/med) LOW Date Received: 11/24/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/30/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 12/02/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name bna01484.d
 Operator Skelton
 Date Acquired 2 Dec 1998 8:30 pm

Sample Name 4083.05
 Misc Info MW32
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bna01484.d
Operator Skelton
Date Acquired 2 Dec 1998 8:30 pm

Sample Name 4083.05
Misc Info MW32
Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.22 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68 ug/L	
86-73-7	Fluorene			not detected	300	1.93 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88 ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67 ug/L	
120-12-7	Anthracene			not detected	2000	1.79 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benzidine			not detected	50	4.11 ug/L	
129-00-0	Pyrene			not detected	200	1.02 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28 ug/L	
218-01-9	Chrysene			not detected	20	2.32 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6

Qualifiers

E = Value exceeded linear range
D = Value from dilution
B = Compound in related blank
PQL = Practical Quantitation Limit

MDL = Method Detection Limit
NLE = No Limit Established
R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

MW32

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4083 Location CW-2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4083.05
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA01484.D
Level: (low/med) LOW Date Received: 11/24/98
% Moisture: decanted: (Y/N) N Date Extracted: 11/30/98
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 12/02/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name bna01485.d
 Operator Skelton
 Date Acquired 2 Dec 1998 9:13 pm

Sample Name 4083.06
 Misc Info MW33
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bna01485.d
 Operator Skelton
 Date Acquired 2 Dec 1998 9:13 pm

Sample Name 4083.06
 Misc Info MW33
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.22 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68 ug/L	
86-73-7	Fluorene			not detected	300	1.93 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88 ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67 ug/L	
120-12-7	Anthracene			not detected	2000	1.79 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benzidine			not detected	50	4.11 ug/L	
129-00-0	Pyrene			not detected	200	1.02 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28 ug/L	
218-01-9	Chrysene			not detected	20	2.32 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6

Qualifiers

E = Value exceeded linear range
 D = Value from dilution
 B = Compound in related blank
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

MW33

Lab Name: FMETL Lab Code 13461

Project LTM Case No.: 4083 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 4083.06

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA01485.D

Level: (low/med) LOW Date Received: 11/24/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/30/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 12/02/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 4 (ug/L or ug/Kg) UG/L _____

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000144-19-4	1,3-Pentanediol, 2,2,4-trimethyl-	9.80	42	JN
2.	unknown	12.63	17	J
3. 074367-34-3	Propanoic acid, 2-methyl-, 3-hydr	12.92	13	JN
4.	unknown	14.47	8	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name bna01486.d
 Operator Skelton
 Date Acquired 2 Dec 1998 9:56 pm

Sample Name 4083.07
 Misc Info Dupe
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.52 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	2.64 ug/L	
62-53-3	Aniline			not detected	NLE	2.90 ug/L	
108-95-2	Phenol			not detected	4000	1.11 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	2.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	1.92 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	2.65 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	2.50 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	2.09 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	2.44 ug/L	
	2-Methylphenol			not detected	NLE	2.09 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	2.96 ug/L	
	4-Methylphenol			not detected	NLE	1.72 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	2.22 ug/L	
67-72-1	Hexachloroethane			not detected	10	2.59 ug/L	
98-95-3	Nitrobenzene			not detected	10	2.45 ug/L	
78-59-1	Isophorone			not detected	100	2.31 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.72 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.42 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	2.54 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.79 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.71 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	2.58 ug/L	
91-20-3	Naphthalene			not detected	NLE	3.03 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	2.55 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.64 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.46 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	2.49 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.59 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.66 ug/L	
	2,4,5-Trichlorophenol			not detected	700	1.63 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	2.15 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.62 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	2.74 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	2.35 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	1.54 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.62 ug/L	
83-32-9	Acenaphthene			not detected	400	1.98 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.65 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	2.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.31 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name bna01486.d
Operator Skelton
Date Acquired 2 Dec 1998 9:56 pm

Sample Name 4083.07
Misc Info Dupe
Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.22 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.68 ug/L	
86-73-7	Fluorene			not detected	300	1.93 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.53 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.70 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.58 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.73 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.92 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.54 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.88 ug/L	
87-86-5	Pentachlorophenol			not detected	1	0.55 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.67 ug/L	
120-12-7	Anthracene			not detected	2000	1.79 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.83 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benzidine			not detected	50	4.11 ug/L	
129-00-0	Pyrene			not detected	200	1.02 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.15 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.57 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.28 ug/L	
218-01-9	Chrysene			not detected	20	2.32 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.29 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.30 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.31 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.57 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.36 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	1.22 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	3.12 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	1.13 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6

Qualifiers

E = Value exceeded linear range
D = Value from dilution
B = Compound in related blank
PQL = Practical Quantitation Limit

MDL = Method Detection Limit
NLE = No Limit Established
R.T. = Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET FIELD ID
TENTATIVELY IDENTIFIED COMPOUNDS

Dupe

Lab Name: FMETL Lab Code 13461

Project LTM Case No.: 4083 Location CW-2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 4083.07

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA01486.D

Level: (low/med) LOW Date Received: 11/24/98

% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/30/98

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 12/02/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	BLK253
	DPW, SELFM-PW-EV	Date Rec'd:	
	Bldg. 173	Extraction Date:	11/25/98
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/98
Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4083.02
	DPW, SELFM-PW-EV	Date Rec'd:	11/24/98
	Bldg. 173	Extraction Date:	11/25/98
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/98
Analysis:	EPA Method 608	Location :	CW-2 MW
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	Field Blank
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4083.03
	DPW, SELFM-PW-EV	Date Rec'd:	11/24/98
	Bldg. 173	Extraction Date:	11/25/98
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/98

Analysis:	EPA Method 608	Location :	CW-2 MW
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-30
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4083.04
	DPW, SELFM-PW-EV	Date Rec'd:	11/24/98
	Bldg. 173	Extraction Date:	11/25/98
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/98
Analysis:	EPA Method 608	Location :	CW-2 MW
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-31
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4083.05
	DPW, SELFM-PW-EV	Date Rec'd:	11/24/98
	Bldg. 173	Extraction Date:	11/25/98
	Ft. Monmouth, NJ 07703	Analysis Date:	12/2/98

Analysis:	EPA Method 608	Location :	CW-2 MW
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-32
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4083.06
	DPW, SELFM-PW-EV	Date Rec'd:	11/24/98
	Bldg. 173	Extraction Date:	11/25/98
	Ft. Monmouth, NJ 07703	Analysis Date:	12/3/98

Analysis:	EPA Method 608	Location :	CW-2 MW
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	MW-33
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 4083.07
DPW, SELFM-PW-EV Date Rec'd: 11/24/98
Bldg. 173 Extraction Date: 11/25/98
Ft. Monmouth, NJ 07703 Analysis Date: 12/3/98

Analysis: EPA Method 608 Location : CW-2 MW
Matrix: Aqueous
Analyst: D. Wright Field ID: Dupe
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary:

Rtx-CLPesticides 30m/.32 mm ID/.25

Column-Confirmation:

Rtx-CLPesticides2 30m/.32 mm ID/.25

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4083
 Sample Prepared: 12/16/98

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	12/17/98	32.7	200	10.0
Antimony	12/17/98	4.31	20	2.0
Arsenic	12/17/98	ND	8	2.0
Barium	12/17/98	1.94	2000	0.5
Beryllium	12/17/98	ND	20	0.5
Cadmium	12/17/98	ND	4	0.5
Calcium	12/17/98	71.0	NLE	20.0
Chromium	12/17/98	ND	100	0.5
Cobalt	12/17/98	ND	NLE	0.5
Copper	12/17/98	ND	1000	3.0
Iron	12/17/98	ND	300	10.0
Lead	12/17/98	ND	10	2.0
Magnesium	12/17/98	55.5	NLE	20.0
Manganese	12/17/98	ND	50	0.5
Mercury	12/14/98	ND	2	0.1
Nickel	12/17/98	1.28	100	0.5
Potassium	12/17/98	269	NLE	20.0
Selenium	12/17/98	ND	50	3.0
Silver	12/17/98	ND	20	3.0
Sodium	12/17/98	199	50000	20.0
Thallium	12/17/98	ND	10	3.0
Vanadium	12/17/98	ND	NLE	1.0
Zinc	12/17/98	2.17	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4083.02
 Sample Received: 11/24/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	12/17/98	ND	200	10.0
Antimony	12/17/98	ND	20	2.0
Arsenic	12/17/98	ND	8	2.0
Barium	12/17/98	0.6	2000	0.5
Beryllium	12/17/98	ND	20	0.5
Cadmium	12/17/98	ND	4	0.5
Calcium	12/17/98	ND	NLE	20.0
Chromium	12/17/98	ND	100	0.5
Cobalt	12/17/98	ND	NLE	0.5
Copper	12/17/98	ND	1000	3.0
Iron	12/17/98	ND	300	10.0
Lead	12/17/98	ND	10	2.0
Magnesium	12/17/98	ND	NLE	20.0
Manganese	12/17/98	ND	50	0.5
Mercury	12/14/98	0.2	2	0.1
Nickel	12/17/98	0.9	100	0.5
Potassium	12/17/98	87	NLE	20.0
Selenium	12/17/98	3.5	50	3.0
Silver	12/17/98	ND	20	3.0
Sodium	12/17/98	92	50000	20.0
Thallium	12/17/98	ND	10	3.0
Vanadium	12/17/98	ND	NLE	1.0
Zinc	12/17/98	9.2	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 4083.03
Sample Received: 11/24/98
Sample Matrix: Aqueous

Site: CW-2
Ft. Monmouth, New Jersey

Field ID#: MW-30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	12/17/98	ND	200	10.0
Antimony	12/17/98	3.99	20	2.0
Arsenic	12/17/98	11.5	8	2.0
Barium	12/17/98	250	2000	0.5
Beryllium	12/17/98	ND	20	0.5
Cadmium	12/17/98	ND	4	0.5
Calcium	12/17/98	109000	NLE	20.0
Chromium	12/17/98	3.75	100	0.5
Cobalt	12/17/98	ND	NLE	0.5
Copper	12/17/98	4.28	1000	3.0
Iron	12/17/98	27500	300	10.0
Lead	12/17/98	3.15	10	2.0
Magnesium	12/17/98	9310	NLE	20.0
Manganese	12/17/98	182	50	0.5
Mercury	12/14/98	2.3	2	0.1
Nickel	12/17/98	1.59	100	0.5
Potassium	12/17/98	12500	NLE	20.0
Selenium	12/17/98	5.27	50	3.0
Silver	12/17/98	ND	20	3.0
Sodium	12/17/98	17400	50000	20.0
Thallium	12/17/98	ND	10	3.0
Vanadium	12/17/98	1.45	NLE	1.0
Zinc	12/17/98	3.33	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 4083.04
Sample Received: 11/24/98
Sample Matrix: Aqueous

Site: CW-2
Ft. Monmouth, New Jersey

Field ID#: MW-31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	12/17/98	ND	200	10.0
Antimony	12/17/98	3.03	20	2.0
Arsenic	12/17/98	ND	8	2.0
Barium	12/17/98	275	2000	0.5
Beryllium	12/17/98	ND	20	0.5
Cadmium	12/17/98	ND	4	0.5
Calcium	12/17/98	56700	NLE	20.0
Chromium	12/17/98	3.33	100	0.5
Cobalt	12/17/98	ND	NLE	0.5
Copper	12/17/98	ND	1000	3.0
Iron	12/17/98	72800	300	10.0
Lead	12/17/98	2.33	10	2.0
Magnesium	12/17/98	6800	NLE	20.0
Manganese	12/17/98	322	50	0.5
Mercury	12/14/98	0.3	2	0.1
Nickel	12/17/98	ND	100	0.5
Potassium	12/17/98	11500	NLE	20.0
Selenium	12/17/98	4.14	50	3.0
Silver	12/17/98	ND	20	3.0
Sodium	12/17/98	9900	50000	20.0
Thallium	12/17/98	ND	10	3.0
Vanadium	12/17/98	ND	NLE	1.0
Zinc	12/17/98	6.51	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4083.05
 Sample Received: 11/24/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: MW-32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	12/17/98	166	200	10.0
Antimony	12/17/98	3.33	20	2.0
Arsenic	12/17/98	9.32	8	2.0
Barium	12/17/98	230	2000	0.5
Beryllium	12/17/98	ND	20	0.5
Cadmium	12/17/98	ND	4	0.5
Calcium	12/17/98	66900	NLE	20.0
Chromium	12/17/98	4.60	100	0.5
Cobalt	12/17/98	ND	NLE	0.5
Copper	12/17/98	38.3	1000	3.0
Iron	12/17/98	106000	300	10.0
Lead	12/17/98	4.08	10	2.0
Magnesium	12/17/98	7650	NLE	20.0
Manganese	12/17/98	342	50	0.5
Mercury	12/14/98	0.3	2	0.1
Nickel	12/17/98	1.22	100	0.5
Potassium	12/17/98	12100	NLE	20.0
Selenium	12/17/98	4.04	50	3.0
Silver	12/17/98	ND	20	3.0
Sodium	12/17/98	11200	50000	20.0
Thallium	12/17/98	ND	10	3.0
Vanadium	12/17/98	11.0	NLE	1.0
Zinc	12/17/98	127	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 4083.06
Sample Received: 11/24/98
Sample Matrix: Aqueous

Site: CW-2
Ft. Monmouth, New Jersey

Field ID#: MW-33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	12/17/98	125	200	10.0
Antimony	12/17/98	2.82	20	2.0
Arsenic	12/17/98	ND	8	2.0
Barium	12/17/98	119	2000	0.5
Beryllium	12/17/98	ND	20	0.5
Cadmium	12/17/98	ND	4	0.5
Calcium	12/17/98	32000	NLE	20.0
Chromium	12/17/98	4.87	100	0.5
Cobalt	12/17/98	ND	NLE	0.5
Copper	12/17/98	3.71	1000	3.0
Iron	12/17/98	26400	300	10.0
Lead	12/17/98	ND	10	2.0
Magnesium	12/17/98	5360	NLE	20.0
Manganese	12/17/98	87.8	50	0.5
Mercury	12/14/98	0.4	2	0.1
Nickel	12/17/98	1.61	100	0.5
Potassium	12/17/98	5250	NLE	20.0
Selenium	12/17/98	ND	50	3.0
Silver	12/17/98	ND	20	3.0
Sodium	12/17/98	17800	50000	20.0
Thallium	12/17/98	ND	10	3.0
Vanadium	12/17/98	1.40	NLE	1.0
Zinc	12/17/98	13.5	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4083.07
 Sample Received: 11/24/98
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	GW Criteria (ug/L)	MDL (ug/L)
Aluminum	12/17/98	ND	200	10.0
Antimony	12/17/98	2.67	20	2.0
Arsenic	12/17/98	ND	8	2.0
Barium	12/17/98	270	2000	0.5
Beryllium	12/17/98	ND	20	0.5
Cadmium	12/17/98	ND	4	0.5
Calcium	12/17/98	57700	NLE	20.0
Chromium	12/17/98	3.35	100	0.5
Cobalt	12/17/98	ND	NLE	0.5
Copper	12/17/98	ND	1000	3.0
Iron	12/17/98	70300	300	10.0
Lead	12/17/98	2.25	10	2.0
Magnesium	12/17/98	6810	NLE	20.0
Manganese	12/17/98	324	50	0.5
Mercury	12/14/98	0.3	2	0.1
Nickel	12/17/98	ND	100	0.5
Potassium	12/17/98	11700	NLE	20.0
Selenium	12/17/98	ND	50	3.0
Silver	12/17/98	ND	20	3.0
Sodium	12/17/98	10000	50000	20.0
Thallium	12/17/98	ND	10	3.0
Vanadium	12/17/98	ND	NLE	1.0
Zinc	12/17/98	11.6	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	9100	69	-	-	-	6.45				V,S,P,M
07/10/97	FMETL	12590	73	25	5.0	ND	7.05				V,S,P,M
10/22/97	FMETL	34800	171	175	5.0	5.0	7.60				V,S,P,M
01/08/98	FMETL	2795	5.0	204	ND	4.0	5.20				V,S,P,M
04/07/98	FMETL	3504	39.3	196	5.6	ND	6.56				V,S,P,M
07/14/98	FMETL	10900	57.8	65.7	ND	ND	6.89				V,S,P,M
11/24/98	FMETL	27500	182	ND	11.5	3.15	7.86				V,S,P,M

SOURCE: MW30

Sampling Dates:
04/24/97 - 11/24/98







NOTES:

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4

 U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: MW30

Sampling Dates:
04/24/97 - 11/24/98

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4, Graph



**U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV**

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	59900	277	-	-	-	6.38				V,S,P,M
07/10/97	FMETL	11830	267	ND	1.0	ND	7.00				V,S,P,M
10/22/97	FMETL	52300	243	93	ND	6.0	7.50				V,S,P,M
01/08/98	FMETL	68450	240	129	ND	25	6.30				V,S,P,M
04/07/98	FMETL	115100	266	ND	ND	ND	6.35				V,S,P,M
07/14/98	FMETL	83600	311	390	ND	4.85	6.71				V,S,P,M
11/24/98	FMETL	72800	322	ND	ND	2.33	7.78				V,S,P,M

SOURCE: MW31

Sampling Dates:
04/24/97 - 11/24/98

NOTES:

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4

 U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

SOURCE: MW31

Sampling Dates:
04/24/97 - 11/24/98

LEGEND:

PARAMETER

○ = Date
Sampled

NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 2 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	18400	125	-	-	-	6.65				V,S,P,M
07/10/97	FMETL	270	181	595	ND	ND	7.20				V,S,P,M
10/22/97	FMETL	51100	260	297	ND	7.0	7.70				V,S,P,M
01/08/98	FMETL	1484	3.7	163	ND	ND	4.50				V,S,P,M
04/07/98	FMETL	19280	287	ND	ND	ND	6.81				V,S,P,M
07/14/98	FMETL	67500	287	78.1	2.51	3.99	7.06				V,S,P,M
11/24/98	FMETL	106000	342	166	9.32	4.08	7.94				V,S,P,M

SOURCE: MW32

Sampling Dates:
04/24/97 - 11/24/98

NOTES:

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4

 U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

SOURCE: MW32

Sampling Dates:
04/24/97 - 11/24/98

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 3 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELFM-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug)



Depth to Water
(Feet)



	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	88600	424	-	-	-	8.95				V,S,P,M
07/10/97	FMETL	10260	519	2.1	1.0	ND	9.10				V,S,P,M
10/22/97	FMETL	26800	151	94	ND	4.0	9.10				V,S,P,M
01/08/98	FMETL	104700	342	217	6.0	4.0	9.00				V,S,P,M
04/07/98	FMETL	19780	110	119	3.4	ND	9.50				V,S,P,M
07/14/98	FMETL	35900	130	411	ND	4.19	9.09				V,S,P,M
11/24/98	FMETL	26400	87.8	125	ND	ND	9.13				V,S,P,M

SOURCE: MW33

Sampling Dates:
04/24/97 - 11/24/98

NOTES:

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

SOURCE: MW33

Sampling Dates:
04/24/97 - 11/24/98

LEGEND:

PARAMETER

○ = Date
Sampled

◊ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 4 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703


PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
4271.01	0CW2MW30	29-32594	02/11/99
4271.02	0CW2MW31	29-32595	02/11/99
4271.03	0CW2MW32	29-32596	02/11/99
4271.04	0CW2MW33	29-32597	02/11/99

NJDEP Laboratory Certification # 13461


 4-5-99

Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608



LEGEND

- Soil Boring/Monitor Well
- ▬ Road (asphalt)
- ▬ Road/Grass (unpaved)
- ⬆ Fence
- ▭ Building
- ▭ Site
- ▭ Wooded Area
- ▭ Tree/Rock
- ▭ Light Pole
- ▭ Utility Pole
- ▭ Rock Boundary
- ▭ Murky Area
- ▭ Approximate Boundary

Scale in Feet

0 50 100

Fort Monmouth, Main Post

FIGURE 4.3-3

ACID NEUTRALIZATION LINE (AL) ITS (CW-1 AND CW-2) SAMPLING LOCATIONS

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 02/11/99
WEATHER: Calm, Clear.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.71 ft
DEPTH TO WATER: 7.24 ft
DEPTH OF WELL: 17.95 ft
HEIGHT OF WATER: 10.71 ft
(10.71) X .65 X 3 = 20.88
GALLONS OF H2O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:09

pH	6.63	su	TEMP	10.9	°C		
DISSOLVED O2	6.78	ppm	SPECIFIC CONDUCTIVITY	540	us/c		

PURGE END TIME: 10:40

pH	6.60	su	TEMP	10.2	°C		
DISSOLVED O2	3.07	ppm	SPECIFIC CONDUCTIVITY	540	us/cm		

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 11.80 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON @
BAILER)

TOTAL VOLUME PURGED: 21 gal

pH	6.57	su	TEMP	9.9	°C		
DISSOLVED O2	3.11	ppm	SPECIFIC CONDUCTIVITY	539	us/cm		

COMMENTS:

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 02/11/99
WEATHER: Calm, Clear.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.58 ft
DEPTH TO WATER: 7.07 ft
DEPTH OF WELL: 16.90 ft
HEIGHT OF WATER: 9.83 ft
(9.83) X .65 X 3 = 19.16
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:17
pH 6.43 su TEMP 10.9 °C
DISSOLVED O2 10.62 ppm SPECIFIC CONDUCTIVITY 704 us/cm

PURGE END TIME: 10:39
pH 6.45 su TEMP 10.1 °C
DISSOLVED O2 2.94 ppm SPECIFIC CONDUCTIVITY 700 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.73 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ®
BAILER)

TOTAL VOLUME PURGED: 19 gal

pH 6.42 su TEMP 9.8 °C
DISSOLVED O2 2.91 ppm SPECIFIC CONDUCTIVITY 707 us/cm

COMMENTS: Orange tinge, cloudy.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 02/11/99
WEATHER: Calm, Clear.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.38 ft
DEPTH TO WATER: 7.33 ft
DEPTH OF WELL: 16.89 ft
HEIGHT OF WATER: 9.56 ft
(9.56) X .65 X 3 = 18.64
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:21
pH 7.03 su TEMP 11.4 °C
DISSOLVED O2 14.57 ppm SPECIFIC CONDUCTIVITY 723 us/cm

PURGE END TIME: 10:43
pH 7.04 su TEMP 10.4 °C
DISSOLVED O2 3.11 ppm SPECIFIC CONDUCTIVITY 723 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 8.89 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ®
BAILER)

TOTAL VOLUME PURGED: 19 gal

pH 7.04 su TEMP 10.3 °C
DISSOLVED O2 3.04 ppm SPECIFIC CONDUCTIVITY 722 us/cm

COMMENTS: Orange tinge.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW33
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 02/11/99
WEATHER: Calm, Clear.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.09 ft
DEPTH TO WATER: 8.13 ft
DEPTH OF WELL: 16.10 ft
HEIGHT OF WATER: 7.97 ft
(7.97) X .65 X 3 = 15.54
GALLONS OF H2O TO BE PURGED: 16 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:26

pH	6.73	su	TEMP	10.5	°C
DISSOLVED O2	10.29	ppm	SPECIFIC CONDUCTIVITY	429	us/cm

PURGE END TIME: 10:35

pH	6.70	su	TEMP	9.9	°C
DISSOLVED O2	4.25	ppm	SPECIFIC CONDUCTIVITY	429	us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.37 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ®
BAILER)

TOTAL VOLUME PURGED: 16 gal

pH	6.71	su	TEMP	9.7	°C
DISSOLVED O2	4.21	ppm	SPECIFIC CONDUCTIVITY	428	us/cm

COMMENTS: Cloudy, orange tinge.

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit

J : Compound identified below detection limit

B : Compound in both sample and blank

D : Results from dilution of sample

U : Compound searched for but not detected

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **V05824.D**
 Operator **Skelton**
 Date Acquired **19 Feb 1999 1:44 pm**

Sample Name **Vblk157**
 Field ID **Vblk157**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Vb1k157

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4271 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: Vb1k157
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V05824.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: not dec. Date Analyzed: 2/19/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
1. 000110-54-3	Hexane	14.25	13	JN

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB02748.D**
 Operator **Skelton**
 Date Acquired **23-Feb-99**

Sample Name **Vblk84**
 Field ID **Vblk84**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Vblk84

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4272 SDG No Location 2700
Matrix: (soil/water) WATER Lab Sample ID: Vblk84
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02748.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: not dec. Date Analyzed: 2/23/99
GC Column: Rtx5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB02756.D**
 Operator **Skelton**
 Date Acquired **23-Feb-99**

Sample Name **4272.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Trip Blank

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4272 SDG No Location 2700
Matrix: (soil/water) WATER Lab Sample ID: 4272.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02756.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: not dec. Date Analyzed: 2/23/99
GC Column: Rtx5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File VB02757.D
 Operator Skelton
 Date Acquired 23-Feb-99

Sample Name 4272.02
 Field ID Field Blank
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Project LTM
NJDEP# 13461 Case No.: 4272 SDG No Location 2700
Matrix: (soil/water) WATER Lab Sample ID: 4272.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB02757.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: not dec. Date Analyzed: 2/23/99
GC Column: Rtx5MS ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **V05836.D**
 Operator **Skelton**
 Date Acquired **19 Feb 1999 10:24 pm**

Sample Name **4271.01**
 Field ID **0CW2MW30**
 Sample Multiple **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW30

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4271 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4271.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V05836.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: not dec. _____ Date Analyzed: 2/19/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **V05837.D**
 Operator **Skelton**
 Date Acquired **19 Feb 1999 11:07 pm**

Sample Name **4271.02**
 Field ID **0CW2MW31**
 Sample Multiple **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW31

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4271 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4271.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V05837.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: not dec. _____ Date Analyzed: 2/19/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **V05838.D**
 Operator **Skelton**
 Date Acquired **19 Feb 1999 11:50 pm**

Sample Name **4271.03**
 Field ID **0CW2MW32**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW32

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4271 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4271.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V05838.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: not dec. _____ Date Analyzed: 2/19/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **V05839.D**
 Operator **Skelton**
 Date Acquired **20 Feb 1999 12:34 am**

Sample Name **4271.04**
 Field ID **0CW2MW33**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW33

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4271 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4271.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V05839.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: not dec. Date Analyzed: 2/20/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name BN02825.D

Operator Bhaskar

Date Acquired 16-Feb-99

Sample Name Sblk206

Misc Info Sblk206 A 990216

Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BN02825.D
Operator Bhaskar
Date Acquired 16-Feb-99

Sample Name Sblk206
Misc Info Sblk206 A 990216
Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
D= Value from dilution
B= Compound in Related Blank
PQL= Practical Quantitation Limit

MDL= Method Detection Limit
NLE= No Limit Established
R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

SbIk206

Lab Name: FMETL Lab Cod 13461

Project: LTM Case No.: 4271 Location: CW-2 SDG No:

Matrix: (soil/water) WATER Lab Sample ID: SbIk206

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN02825.D

Level: (low/med) LOW Date Received: 2/11/99

% Moisture: decanted: (Y/N) N Date Extracted: 2/16/99

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/16/99

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	29.18	80	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN02833.D**
 Operator **Bhaskar**
 Date Acquired **17-Feb-99**

Sample Name **4272.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN02833.D**
Operator **Bhaskar**
Date Acquired **17-Feb-99**

Sample Name **4272.02**
Misc Info **Field Blank**
Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
D= Value from dilution
B= Compound in Related Blank
PQL= Practical Quantitation Limit

MDL= Method Detection Limit
NLE= No Limit Established
R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

Field Blank

Lab Name: FMETL Lab Cod 13461
Project: LTM Case No.: 4272 Location: 2700 M SDG No: _____
Matrix: (soil/water) WATER Lab Sample ID: 4272.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN02833.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: _____ decanted: (Y/N) N Date Extracted: 2/16/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/17/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	29.16	75	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN02829.D**
 Operator **Bhaskar**
 Date Acquired **16-Feb-99**

Sample Name **4271.01**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN02829.D**
 Operator **Bhaskar**
 Date Acquired **16-Feb-99**

Sample Name **4271.01**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Ben-zidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

0CW2MW30

Lab Name: FMETL Lab Cod 13461
Project: LTM Case No.: 4271 Location: CW-2 SDG No: _____
Matrix: (soil/water) WATER Lab Sample ID: 4271.01
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN02829.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: _____ decanted: (Y/N) N Date Extracted: 2/16/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/16/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	23.29	13	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN02830.D**
 Operator **Bhaskar**
 Date Acquired **16-Feb-99**

Sample Name **4271.02**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN02830.D**
 Operator **Bhaskar**
 Date Acquired **16-Feb-99**

Sample Name **4271.02**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

0CW2MW31

Lab Name: FMETL Lab Cod 13461
Project: LTM Case No.: 4271 Location: CW-2 SDG No: _____
Matrix: (soil/water) WATER Lab Sample ID: 4271.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN02830.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: _____ decanted: (Y/N) N Date Extracted: 2/16/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/16/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	23.28	10	J
2.	unknown	29.11	34	J

Semi-Volatile Analysis Report

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification #13461

Data File Name BN02831.D

Operator Bhaskar

Date Acquired 17-Feb-99

Sample Name 4271.03

Misc Info 0CW2MW32

Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN02831.D**
 Operator **Bhaskar**
 Date Acquired **17-Feb-99**

Sample Name **4271.03**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

0CW2MW32

Lab Name: FMETL Lab Cod 13461
Project: LTM Case No.: 4271 Location: CW-2 SDG No:
Matrix: (soil/water) WATER Lab Sample ID: 4271.03
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN02831.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: decanted: (Y/N) N Date Extracted: 2/16/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/17/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN02832.D**
 Operator **Bhaskar**
 Date Acquired **17-Feb-99**

Sample Name **4271.04**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN02832.D**
 Operator **Bhaskar**
 Date Acquired **17-Feb-99**

Sample Name **4271.04**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

0CW2MW33

Lab Name: FMETL Lab Cod 13461
Project: LTM Case No.: 4271 Location: CW-2 SDG No:
Matrix: (soil/water) WATER Lab Sample ID: 4271.04
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN02832.D
Level: (low/med) LOW Date Received: 2/11/99
% Moisture: decanted: (Y/N) N Date Extracted: 2/16/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/17/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	23.29	9	J
2.	unknown	29.11	32	J

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	BLK287
	DPW, SELFM-PW-EV	Date Rec'd:	
	Bldg. 173	Extraction Date:	2/12/99
	Ft. Monmouth, NJ 07703	Analysis Date:	2/27/99

Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	BLK288
	DPW, SELFM-PW-EV	Date Rec'd:	
	Bldg. 173	Extraction Date:	2/12/99
	Ft. Monmouth, NJ 07703	Analysis Date:	2/27/99
Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7-9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4272.02
	DPW, SELFM-PW-EV	Date Rec'd:	2/11/99
	Bldg. 173	Extraction Date:	2/12/99
	Ft. Monmouth, NJ 07703	Analysis Date:	2/27/99

Analysis:	EPA Method 608	Location :	2700 Myer MWs
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	Field Blank
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected
MDL = Method Detection Limit
NLE = No Limit Established
PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um
Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4271.01
	DPW, SELFM-PW-EV	Date Rec'd:	2/11/99
	Bldg. 173	Extraction Date:	2/12/99
	Ft. Monmouth, NJ 07703	Analysis Date:	2/27/99
Analysis:	EPA Method 608	Location :	CW-2 MWs
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	0CW2MW30
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4271.02
	DPW, SELFM-PW-EV	Date Rec'd:	2/11/99
	Bldg. 173	Extraction Date:	2/12/99
	Ft. Monmouth, NJ 07703	Analysis Date:	2/27/99
Analysis:	EPA Method 608	Location :	CW-2 MWs
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	0CW2MW31
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4271.03
	DPW, SELFM-PW-EV	Date Rec'd:	2/11/99
	Bldg. 173	Extraction Date:	2/12/99
	Ft. Monmouth, NJ 07703	Analysis Date:	2/27/99
Analysis:	EPA Method 608	Location :	CW-2 MWs
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	0CW2MW32
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7-9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4271.04
	DPW, SELFM-PW-EV	Date Rec'd:	2/11/99
	Bldg. 173	Extraction Date:	2/12/99
	Ft. Monmouth, NJ 07703	Analysis Date:	2/27/99
Analysis:	EPA Method 608	Location :	CW-2 MWs
Matrix:	Aqueous		
Analyst:	D. Wright	Field ID:	0CW2MW33
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

MDL = Method Detection Limit

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

NLE = No Limit Established

PQL = Practical Quantitation Limit

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4272
 Sample Prepared: 02/19/99

Site:
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	02/22/99	ND	200	10.0
Antimony	02/22/99	3.96	20	2.0
Arsenic	02/22/99	ND	8	2.0
Barium	02/22/99	2.10	2000	0.5
Beryllium	02/22/99	ND	20	0.5
Cadmium	02/22/99	ND	4	0.5
Calcium	02/22/99	67.0	NLE	20.0
Chromium	02/22/99	ND	100	0.5
Cobalt	02/22/99	0.7	NLE	0.5
Copper	02/22/99	49.0	1000	3.0
Iron	02/22/99	60.0	300	10.0
Lead	02/22/99	ND	10	2.0
Magnesium	02/22/99	93.0	NLE	20.0
Manganese	02/22/99	0.6	50	0.5
Mercury	02/23/99	ND	2	0.1
Nickel	02/22/99	4.0	100	0.5
Potassium	02/22/99	ND	NLE	20.0
Selenium	02/22/99	ND	50	3.0
Silver	02/22/99	ND	20	3.0
Sodium	02/22/99	ND	50000	20.0
Thallium	02/22/99	ND	10	3.0
Vanadium	02/22/99	ND	NLE	1.0
Zinc	02/22/99	7.00	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4272.02
 Sample Received: 02/11/99
 Sample Matrix: Aqueous

Site: Bldg. 2700
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	02/22/99	ND	200	10.0
Antimony	02/22/99	ND	20	2.0
Arsenic	02/22/99	ND	8	2.0
Barium	02/22/99	ND	2000	0.5
Beryllium	02/22/99	ND	20	0.5
Cadmium	02/22/99	ND	4	0.5
Calcium	02/22/99	90.4	NLE	20.0
Chromium	02/22/99	ND	100	0.5
Cobalt	02/22/99	ND	NLE	0.5
Copper	02/22/99	26.7	1000	3.0
Iron	02/22/99	16.9	300	10.0
Lead	02/22/99	ND	10	2.0
Magnesium	02/22/99	ND	NLE	20.0
Manganese	02/22/99	1.07	50	0.5
Mercury	02/23/99	0.11	2	0.1
Nickel	02/22/99	2.27	100	0.5
Potassium	02/22/99	ND	NLE	20.0
Selenium	02/22/99	ND	50	3.0
Silver	02/22/99	ND	20	3.0
Sodium	02/22/99	90.6	50000	20.0
Thallium	02/22/99	ND	10	3.0
Vanadium	02/22/99	ND	NLE	1.0
Zinc	02/22/99	7.69	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4271.01
 Sample Received: 02/11/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	02/22/99	505	200	10.0
Antimony	02/22/99	ND	20	2.0
Arsenic	02/22/99	8.30	8	2.0
Barium	02/22/99	80.4	2000	0.5
Beryllium	02/22/99	ND	20	0.5
Cadmium	02/22/99	0.721	4	0.5
Calcium	02/22/99	66600	NLE	20.0
Chromium	02/22/99	5.85	100	0.5
Cobalt	02/22/99	0.646	NLE	0.5
Copper	02/22/99	9.50	1000	3.0
Iron	02/22/99	11000	300	10.0
Lead	02/22/99	ND	10	2.0
Magnesium	02/22/99	5290	NLE	20.0
Manganese	02/22/99	100.0	50	0.5
Mercury	02/23/99	ND	2	0.1
Nickel	02/22/99	8.79	100	0.5
Potassium	02/22/99	6930	NLE	20.0
Selenium	02/22/99	5.17	50	3.0
Silver	02/22/99	ND	20	3.0
Sodium	02/22/99	32400	50000	20.0
Thallium	02/22/99	ND	10	3.0
Vanadium	02/22/99	3.76	NLE	1.0
Zinc	02/22/99	16.6	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established
 * Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4271.02
 Sample Received: 02/11/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	02/22/99	ND	200	10.0
Antimony	02/22/99	4.22	20	2.0
Arsenic	02/22/99	ND	8	2.0
Barium	02/22/99	273	2000	0.5
Beryllium	02/22/99	ND	20	0.5
Cadmium	02/22/99	1.65	4	0.5
Calcium	02/22/99	56500	NLE	20.0
Chromium	02/22/99	3.40	100	0.5
Cobalt	02/22/99	ND	NLE	0.5
Copper	02/22/99	28.3	1000	3.0
Iron	02/22/99	71900	300	10.0
Lead	02/22/99	ND	10	2.0
Magnesium	02/22/99	6740	NLE	20.0
Manganese	02/22/99	316	50	0.5
Mercury	02/23/99	ND	2	0.1
Nickel	02/22/99	0.595	100	0.5
Potassium	02/22/99	10100	NLE	20.0
Selenium	02/22/99	3.93	50	3.0
Silver	02/22/99	ND	20	3.0
Sodium	02/22/99	14600	50000	20.0
Thallium	02/22/99	ND	10	3.0
Vanadium	02/22/99	ND	NLE	1.0
Zinc	02/22/99	6.67	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4271.03
 Sample Received: 02/11/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	02/22/99	137	200	10.0
Antimony	02/22/99	3.81	20	2.0
Arsenic	02/22/99	ND	8	2.0
Barium	02/22/99	42.5	2000	0.5
Beryllium	02/22/99	ND	20	0.5
Cadmium	02/22/99	1.07	4	0.5
Calcium	02/22/99	104000	NLE	20.0
Chromium	02/22/99	3.79	100	0.5
Cobalt	02/22/99	ND	NLE	0.5
Copper	02/22/99	92.7	1000	3.0
Iron	02/22/99	4480	300	10.0
Lead	02/22/99	ND	10	2.0
Magnesium	02/22/99	10100	NLE	20.0
Manganese	02/22/99	7.02	50	0.5
Mercury	02/23/99	ND	2	0.1
Nickel	02/22/99	5.03	100	0.5
Potassium	02/22/99	3670	NLE	20.0
Selenium	02/22/99	5.27	50	3.0
Silver	02/22/99	ND	20	3.0
Sodium	02/22/99	35700	50000	20.0
Thallium	02/22/99	ND	10	3.0
Vanadium	02/22/99	1.95	NLE	1.0
Zinc	02/22/99	59.4	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4271.04
 Sample Received: 02/11/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33

TAL-METALS RESULTS SUMMARY (ug/L)


Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	02/22/99	67.8	200	10.0
Antimony	02/22/99	2.49	20	2.0
Arsenic	02/22/99	ND	8	2.0
Barium	02/22/99	72.9	2000	0.5
Beryllium	02/22/99	ND	20	0.5
Cadmium	02/22/99	1.04	4	0.5
Calcium	02/22/99	32100	NLE	20.0
Chromium	02/22/99	2.40	100	0.5
Cobalt	02/22/99	ND	NLE	0.5
Copper	02/22/99	17.3	1000	3.0
Iron	02/22/99	11300	300	10.0
Lead	02/22/99	ND	10	2.0
Magnesium	02/22/99	6010	NLE	20.0
Manganese	02/22/99	81.2	50	0.5
Mercury	02/23/99	0.13	2	0.1
Nickel	02/22/99	3.15	100	0.5
Potassium	02/22/99	4770	NLE	20.0
Selenium	02/22/99	ND	50	3.0
Silver	02/22/99	ND	20	3.0
Sodium	02/22/99	37000	50000	20.0
Thallium	02/22/99	ND	10	3.0
Vanadium	02/22/99	ND	NLE	1.0
Zinc	02/22/99	11.1	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established


* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

04-01-1999 c:\mtech46\fm\2700-cw2\gw\cw2.wsf


Hexadecanoic Acid
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW30

Sampling Dates:
04/24/97 - 02/11/99

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	59900	277	-	-	-	6.38				V,S,P,M
07/10/97	FMETL	11830	267	ND	1.0	ND	7.00				V,S,P,M
10/22/97	FMETL	52300	243	93	ND	6.0	7.50				V,S,P,M
01/08/98	FMETL	68450	240	129	ND	25	6.30				V,S,P,M
04/07/98	FMETL	115100	266	ND	ND	ND	6.35				V,S,P,M
07/14/98	FMETL	83600	311	390	ND	4.85	6.71				V,S,P,M
11/24/98	FMETL	72800	322	ND	ND	2.33	7.78				V,S,P,M
02/11/99	FMETL	71900	316	ND	ND	ND	7.07				V,S,P,M

SOURCE: 0CW2MW31

Sampling Dates:
04/24/97 - 02/11/99

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 2 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)




Depth to Water
(Feet)




04-01-1999 c:\mtech46\fm\2700-cw2\gw\cw2.wsf


Hexadecanoic Acid
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW32

Sampling Dates:
04/24/97 - 02/11/99

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH







GW MONITORING
Bldg CW-2

Well 3 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	88600	424	-	-	-	8.95				V,S,P,M
07/10/97	FMETL	10260	519	2.1	1.0	ND	9.10				V,S,P,M
10/22/97	FMETL	26800	151	94	ND	4.0	9.10				V,S,P,M
01/08/98	FMETL	104700	342	217	6.0	4.0	9.00				V,S,P,M
04/07/98	FMETL	19780	110	119	3.4	ND	9.50				V,S,P,M
07/14/98	FMETL	35900	130	411	ND	4.19	9.09				V,S,P,M
11/24/98	FMETL	25400	87.8	125	ND	ND	9.13				V,S,P,M
02/11/99	FMETL	11300	81.2	67.8	ND	ND	8.13				V,S,P,M
</											



SOURCE: 0CW2MW33

Sampling Dates:
04/24/97 - 02/11/99

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
4539.03	0CW2MW30	29-32594	06/09/99
4539.04	0CW2MW31	29-32595	06/09/99
4539.05	0CW2MW32	29-32596	06/09/99
4539.06	0CW2MW33	29-32597	06/09/99

NJDEP Laboratory Certification # 13461

 7-19-99

Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY



PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608

Tel (732)532-4359 Fax (732)532-6263 EMail:appleby@mail1.monmouth.army.mil

Chain of Custody Record

print legibly



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 06/09/99
WEATHER: Sunny, warm.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 57.71 ft
DEPTH TO WATER: 7.21 ft
DEPTH OF WELL: 17.95 ft
HEIGHT OF WATER: 10.74 ft
(10.74) X .65 X 3 = 20.94
GALLONS OF H2O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) : PERISTALIC
PURGE RATE: 0.23 GPM
Hnu READING: 0.0 PPM

PURGE START TIME: 09:50
pH: 6.51 su
DISSOLVED O2: 8.17 PPM

TEMP: 13.7 °C
SPECIFIC CONDUCTIVITY: 615 us/cm

PURGE END TIME: 11:21
pH: 6.54 su
DISSOLVED O2: 5.10 PPM

TEMP: 13.1 °C
SPECIFIC CONDUCTIVITY: 614 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 10.02 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 21 gal

pH: 6.53 su
DISSOLVED O2: 5.07 PPM

TEMP: 13.1 °C
SPECIFIC CONDUCTIVITY: 613 us/cm

COMMENTS: Dup here.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 06/09/99
WEATHER: Sunny, warm.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.58 ft
DEPTH TO WATER: 7.15 ft
DEPTH OF WELL: 16.90 ft
HEIGHT OF WATER: 9.75 ft
(9.75) X .65 X 3 = 19.01
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) : PERISTALIC
PURGE RATE: 0.23 GPM
Hnu READING: 0.0 PPM

PURGE START TIME: 09:45
pH: 6.50 su
DISSOLVED O2: 8.31 PPM
TEMP: 13.7 °C
SPECIFIC CONDUCTIVITY: 548 us/cm

PURGE END TIME: 11:07
pH: 6.50 su
DISSOLVED O2: 5.32 PPM
TEMP: 13.2 °C
SPECIFIC CONDUCTIVITY: 549 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 8.41 ft
(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 19 gal

pH: 6.51 su
DISSOLVED O2: 5.27 PPM
TEMP: 13.2 °C
SPECIFIC CONDUCTIVITY: 547 us/cm

COMMENTS: Orange tinge w/particles.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 06/09/99
WEATHER: Sunny, warm.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.38 ft
DEPTH TO WATER: 7.49 ft
DEPTH OF WELL: 16.89 ft
HEIGHT OF WATER: 9.40 ft
 $(9.40) \times .65 \times 3 = 18.33$
GALLONS OF H₂O TO BE PURGED: 18 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) : PERISTALIC
PURGE RATE: 0.23 GPM
Hnu READING: 0.0 PPM

PURGE START TIME: 09:35

pH: 6.14 su

DISSOLVED O₂: 8.44 PPM

TEMP: 13.9 °C

SPECIFIC CONDUCTIVITY: 589 us/cm

PURGE END TIME: 10:53

pH: 6.16 su

DISSOLVED O₂: 5.55 PPM

TEMP: 13.3 °C

SPECIFIC CONDUCTIVITY: 589 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 11.76 ft

(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 18 gal

pH: 6.15 su

DISSOLVED O₂: 5.51 PPM

TEMP: 13.1 °C

SPECIFIC CONDUCTIVITY: 587 us/cm

COMMENTS: Slight Orange tinge.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW33
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 06/09/99
WEATHER: Sunny, warm.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.09 ft
DEPTH TO WATER: 9.13 ft
DEPTH OF WELL: 16.10 ft
HEIGHT OF WATER: 6.97 ft
 $(6.97) \times .65 \times 3 = 13.59$
GALLONS OF H2O TO BE PURGED: 14 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM) : PERISTALIC
PURGE RATE: 0.23 GPM
Hnu READING: 0.0 PPM

PURGE START TIME: 09:30

pH: 6.21 su

DISSOLVED O2: 8.13 PPM

TEMP: 13.9 °C

SPECIFIC CONDUCTIVITY: 707 us/cm

PURGE END TIME: 10:31

pH: 6.17 su

DISSOLVED O2: 5.17 PPM

TEMP: 13.3 °C

SPECIFIC CONDUCTIVITY: 710 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.43 ft

(SAMPLING METHOD: DEDICATED(LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 14 gal

pH: 6.15 su

DISSOLVED O2: 5.11 PPM

TEMP: 13.2 °C

SPECIFIC CONDUCTIVITY: 709 us/cm

COMMENTS: Orange tinge w/particles.

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit

J : Compound identified below detection limit

B : Compound in both sample and blank

D : Results from dilution of sample

U : Compound searched for but not detected

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VA006672.D**
 Operator **Deinhardt**
 Date Acquired **15 Jun 1999 9:48 am**

Sample Name **Vblk195**
 Field ID **Vblk195**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Vblk195

Lab Name: FMETL Project LTM

NJDEP # 13461 Case No.: 4539 Location CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: Vblk195

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VA006672.D

Level: (low/med) LOW Date Received: 6/9/99

% Moisture: not dec. _____ Date Analyzed: 6/15/99

GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 1

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
1. 000110-54-3	Hexane	10.03	10	JN

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VA006690.D**
 Operator **Deinhardt**
 Date Acquired **15 Jun 1999 8:30 pm**

Sample Name **4539.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Trip Blank

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4539 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4539.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VA006690.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: not dec. _____ Date Analyzed: 6/15/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 1

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
1. 000110-54-3	Hexane	10.03	6	JN

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VA006691.D**
 Operator **Deinhardt**
 Date Acquired **15 Jun 1999 9:04 pm**

Sample Name **4539.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6.2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4539 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4539.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VA006691.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: not dec. _____ Date Analyzed: 6/15/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 1

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
1. 000110-54-3	Hexane	10.03	7	JN

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VA006692.D**
 Operator **Deinhardt**
 Date Acquired **15 Jun 1999 9:39 pm**

Sample Name **4539.03**
 Field ID **OCW2MW30**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone	7.87	32242	8.09 ug/L	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW30

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4539 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4539.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VA006692.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: not dec. _____ Date Analyzed: 6/15/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
1. 000110-54-3	Hexane	10.00	7	JN

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VA006693.D**
 Operator **Deinhardt**
 Date Acquired **15 Jun 1999 10:13 pm**

Sample Name **4539.04**
 Field ID **OCW2MW31**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

OCW2MW31

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4539 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4539.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VA006693.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: not dec. _____ Date Analyzed: 6/15/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VA006694.D**
 Operator **Deinhardt**
 Date Acquired **15 Jun 1999 10:48 pm**

Sample Name **4539.05**
 Field ID **OCW2MW32**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6.2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW32

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4539 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4539.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VA006694.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: not dec. _____ Date Analyzed: 6/15/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VA006695.D**
 Operator **Deinhardt**
 Date Acquired **15 Jun 1999 11:22 pm**

Sample Name **4539.06**
 Field ID **OCW2MW33**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW33

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4539 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4539.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VA006695.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: not dec. _____ Date Analyzed: 6/15/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
1. 000110-54-3	Hexane	10.00	8	JN

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VA006696.D**
 Operator **Deinhardt**
 Date Acquired **15 Jun 1999 11:56 pm**

Sample Name **4539.07**
 Field ID **Dupe**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Dupe

Lab Name: FMETL Project LTM
NJDEP # 13461 Case No.: 4539 Location CW2 SDG No.: _____
Matrix: (soil/water): WATER Lab Sample ID: 4539.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VA006696.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: not dec. _____ Date Analyzed: 6/15/99
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA02740.D**
 Operator **Bhaskar**
 Date Acquired **11-Jun-99**

Sample Name **Sblk263**
 Misc Info **Sblk263 A 990610**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol	8.40	87727	1.52 ug/L	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA02740.D**
 Operator **Bhaskar**
 Date Acquired **11-Jun-99**

Sample Name **Sblk263**
 Misc Info **Sblk263 A 990610**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Sblk263

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4539 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: Sblk263
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA02740.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: decanted: (Y/N) N Date Extracted: 6/10/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 6/11/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA02746.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA02746.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4539 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4539.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA02746.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: decanted: (Y/N) N Date Extracted: 6/10/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 6/12/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA02747.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.03**
 Misc Info **OCW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA02747.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.03**
 Misc Info **OCW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW30

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4539 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4539.03
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA02747.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: decanted: (Y/N) N Date Extracted: 6/10/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 6/12/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA02748.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.04**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BNA02748.D
 Operator Bhaskar
 Date Acquired 12-Jun-99

Sample Name 4539.04
 Misc Info 0CW2MW31
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW31

Lab Name: FMETL Lab Code 13461

Project LTM Case No.: 4539 Location CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 4539.04

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA02748.D

Level: (low/med) LOW Date Received: 6/9/99

% Moisture: _____ decanted: (Y/N) N Date Extracted: 6/10/99

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 6/12/99

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA02749.D**

Operator **Bhaskar**

Date Acquired **12-Jun-99**

Sample Name **4539.05**

Misc Info **0CW2MW32**

Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA02749.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.05**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW32

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4539 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4539.05
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA02749.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: decanted: (Y/N) N Date Extracted: 6/10/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 6/12/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA02750.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.06**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA02750.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.06**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW33

Lab Name: FMETL Lab Code 13461

Project LTM Case No.: 4539 Location CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 4539.06

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA02750.D

Level: (low/med) LOW Date Received: 6/9/99

% Moisture: _____ decanted: (Y/N) N Date Extracted: 6/10/99

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 6/12/99

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA02751.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.07**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	5.00 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.94 ug/L	
62-53-3	Aniline			not detected	NLE	0.15 ug/L	
108-95-2	Phenol			not detected	4000	0.47 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.48 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.18 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.15 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.23 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.18 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.16 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.14 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.61 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.14 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.36 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.33 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.46 ug/L	
78-59-1	Isophorone			not detected	100	0.35 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.23 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.27 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.46 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.12 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	0.26 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.25 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.25 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	0.19 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.38 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.18 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.16 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.50 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.42 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.31 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.32 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.21 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	0.18 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.19 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.31 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.26 ug/L	
83-32-9	Acenaphthene			not detected	400	0.26 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	0.69 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.32 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	0.27 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA02751.D**
 Operator **Bhaskar**
 Date Acquired **12-Jun-99**

Sample Name **4539.07**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.36 ug/L	
84-66-2	Diethylphthalate			not detected	5000	0.82 ug/L	
86-73-7	Fluorene			not detected	300	0.29 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.31 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	0.90 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	0.44 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	0.23 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.80 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.55 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.82 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.08 ug/L	
85-01-8	Phenanthrene			not detected	NLE	0.18 ug/L	
120-12-7	Anthracene			not detected	2000	0.19 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	0.23 ug/L	
206-44-0	Fluoranthene			not detected	300	0.41 ug/L	
92-87-5	Benzidine			not detected	50	1.45 ug/L	
129-00-0	Pyrene			not detected	200	0.32 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	0.47 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	0.22 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	0.46 ug/L	
218-01-9	Chrysene			not detected	20	0.20 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	0.51 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	0.82 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	0.37 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	0.32 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	0.31 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.79 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.28 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.40 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Dupe

Lab Name: FMETL Lab Code 13461
Project LTM Case No.: 4539 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4539.07
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA02751.D
Level: (low/med) LOW Date Received: 6/9/99
% Moisture: decanted: (Y/N) N Date Extracted: 6/10/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 6/12/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	BLK350
	DPW, SELFM-PW-EV	Date Rec'd:	
	Bldg. 173	Extraction Date:	6/10/99
	Ft. Monmouth, NJ 07703	Analysis Date:	6/12/99

Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4539.02
	DPW, SELFM-PW-EV	Date Rec'd:	6/9/99
	Bldg. 173	Extraction Date:	6/10/99
	Ft. Monmouth, NJ 07703	Analysis Date:	6/12/99

Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	Field Blank
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides 2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 4539.03
Date Rec'd: 6/9/99
Extraction Date: 6/10/99
Analysis Date: 6/12/99

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: OCW2MW30

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 4539.04
DPW, SELFM-PW-EV Date Rec'd: 6/9/99
Bldg. 173 Extraction Date: 6/10/99
Ft. Monmouth, NJ 07703 Analysis Date: 6/12/99

Analysis: EPA Method 608 Location : CW2
Matrix: Aqueous
Analyst: T. Frankovich Field ID: OCW2MW31
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4539.05
	DPW, SELFM-PW-EV	Date Rec'd:	6/9/99
	Bldg. 173	Extraction Date:	6/10/99
	Ft. Monmouth, NJ 07703	Analysis Date:	6/12/99

Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	OCW2MW32
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4539.06
	DPW, SELFM-PW-EV	Date Rec'd:	6/9/99
	Bldg. 173	Extraction Date:	6/10/99
	Ft. Monmouth, NJ 07703	Analysis Date:	6/12/99

Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	OCW2MW33
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	4539.07
	DPW, SELFM-PW-EV	Date Rec'd:	6/9/99
	Bldg. 173	Extraction Date:	6/10/99
	Ft. Monmouth, NJ 07703	Analysis Date:	6/12/99

Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	Dupe
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4539
 Sample Prepared: 07/01/99

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/01/99	61.0	200	10.0
Antimony	07/01/99	5.85	20	2.0
Arsenic	07/01/99	ND	8	2.0
Barium	07/01/99	ND	2000	0.5
Beryllium	07/01/99	ND	20	0.5
Cadmium	07/01/99	20.7	4	0.5
Calcium	07/01/99	204	NLE	20.0
Chromium	07/01/99	1.14	100	0.5
Cobalt	07/01/99	ND	NLE	0.5
Copper	07/01/99	193	1000	3.0
Iron	07/01/99	65.0	300	10.0
Lead	07/01/99	ND	10	2.0
Magnesium	07/01/99	178	NLE	20.0
Manganese	07/01/99	1.78	50	0.5
Mercury	07/02/99	ND	2	0.1
Nickel	07/01/99	2.35	100	0.5
Potassium	07/01/99	31.0	NLE	20.0
Selenium	07/01/99	ND	50	3.0
Silver	07/01/99	ND	20	3.0
Sodium	07/01/99	181	50000	20.0
Thallium	07/01/99	ND	10	3.0
Vanadium	07/01/99	ND	NLE	1.0
Zinc	07/01/99	6.00	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4539.02
 Sample Received: 06/09/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/01/99	ND	200	10.0
Antimony	07/01/99	ND	20	2.0
Arsenic	07/01/99	ND	8	2.0
Barium	07/01/99	0.952	2000	0.5
Beryllium	07/01/99	ND	20	0.5
Cadmium	07/01/99	2.57	4	0.5
Calcium	07/01/99	107	NLE	20.0
Chromium	07/01/99	ND	100	0.5
Cobalt	07/01/99	ND	NLE	0.5
Copper	07/01/99	51.9	1000	3.0
Iron	07/01/99	ND	300	10.0
Lead	07/01/99	ND	10	2.0
Magnesium	07/01/99	39.8	NLE	20.0
Manganese	07/01/99	1.34	50	0.5
Mercury	07/02/99	ND	2	0.1
Nickel	07/01/99	1.12	100	0.5
Potassium	07/01/99	ND	NLE	20.0
Selenium	07/01/99	ND	50	3.0
Silver	07/01/99	ND	20	3.0
Sodium	07/01/99	157	50000	20.0
Thallium	07/01/99	6.34	10	3.0
Vanadium	07/01/99	ND	NLE	1.0
Zinc	07/01/99	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4539.03
 Sample Received: 06/09/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/01/99	521	200	10.0
Antimony	07/01/99	2.58	20	2.0
Arsenic	07/01/99	6.33	8	2.0
Barium	07/01/99	111	2000	0.5
Beryllium	07/01/99	ND	20	0.5
Cadmium	07/01/99	1.08	4	0.5
Calcium	07/01/99	87400	NLE	20.0
Chromium	07/01/99	5.43	100	0.5
Cobalt	07/01/99	0.675	NLE	0.5
Copper	07/01/99	51.5	1000	3.0
Iron	07/01/99	8210	300	10.0
Lead	07/01/99	ND	10	2.0
Magnesium	07/01/99	6800	NLE	20.0
Manganese	07/01/99	145	50	0.5
Mercury	07/02/99	ND	2	0.1
Nickel	07/01/99	1.60	100	0.5
Potassium	07/01/99	12700	NLE	20.0
Selenium	07/01/99	ND	50	3.0
Silver	07/01/99	ND	20	3.0
Sodium	07/01/99	25700	50000	20.0
Thallium	07/01/99	ND	10	3.0
Vanadium	07/01/99	3.65	NLE	1.0
Zinc	07/01/99	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4539.04
 Sample Received: 06/09/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/01/99	27.9	200	10.0
Antimony	07/01/99	ND	20	2.0
Arsenic	07/01/99	ND	8	2.0
Barium	07/01/99	348	2000	0.5
Beryllium	07/01/99	ND	20	0.5
Cadmium	07/01/99	3.50	4	0.5
Calcium	07/01/99	60100	NLE	20.0
Chromium	07/01/99	ND	100	0.5
Cobalt	07/01/99	ND	NLE	0.5
Copper	07/01/99	15.7	1000	3.0
Iron	07/01/99	104000	300	10.0
Lead	07/01/99	ND	10	2.0
Magnesium	07/01/99	7070	NLE	20.0
Manganese	07/01/99	326	50	0.5
Mercury	07/02/99	ND	2	0.1
Nickel	07/01/99	ND	100	0.5
Potassium	07/01/99	11200	NLE	20.0
Selenium	07/01/99	ND	50	3.0
Silver	07/01/99	ND	20	3.0
Sodium	07/01/99	13000	50000	20.0
Thallium	07/01/99	ND	10	3.0
Vanadium	07/01/99	4.23	NLE	1.0
Zinc	07/01/99	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4539.05
 Sample Received: 06/09/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/01/99	59.5	200	10.0
Antimony	07/01/99	ND	20	2.0
Arsenic	07/01/99	ND	8	2.0
Barium	07/01/99	202	2000	0.5
Beryllium	07/01/99	ND	20	0.5
Cadmium	07/01/99	2.06	4	0.5
Calcium	07/01/99	70700	NLE	20.0
Chromium	07/01/99	0.572	100	0.5
Cobalt	07/01/99	0.857	NLE	0.5
Copper	07/01/99	28.6	1000	3.0
Iron	07/01/99	64300	300	10.0
Lead	07/01/99	ND	10	2.0
Magnesium	07/01/99	7880	NLE	20.0
Manganese	07/01/99	310	50	0.5
Mercury	07/02/99	ND	2	0.1
Nickel	07/01/99	ND	100	0.5
Potassium	07/01/99	10700	NLE	20.0
Selenium	07/01/99	ND	50	3.0
Silver	07/01/99	ND	20	3.0
Sodium	07/01/99	15500	50000	20.0
Thallium	07/01/99	ND	10	3.0
Vanadium	07/01/99	5.48	NLE	1.0
Zinc	07/01/99	18.7	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4539.06
 Sample Received: 06/09/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/01/99	336	200	10.0
Antimony	07/01/99	ND	20	2.0
Arsenic	07/01/99	5.82	8	2.0
Barium	07/01/99	212	2000	0.5
Beryllium	07/01/99	ND	20	0.5
Cadmium	07/01/99	2.06	4	0.5
Calcium	07/01/99	42100	NLE	20.0
Chromium	07/01/99	2.07	100	0.5
Cobalt	07/01/99	0.768	NLE	0.5
Copper	07/01/99	6.04	1000	3.0
Iron	07/01/99	69600	300	10.0
Lead	07/01/99	ND	10	2.0
Magnesium	07/01/99	4990	NLE	20.0
Manganese	07/01/99	214	50	0.5
Mercury	07/02/99	ND	2	0.1
Nickel	07/01/99	ND	100	0.5
Potassium	07/01/99	8140	NLE	20.0
Selenium	07/01/99	ND	50	3.0
Silver	07/01/99	ND	20	3.0
Sodium	07/01/99	19000	50000	20.0
Thallium	07/01/99	ND	10	3.0
Vanadium	07/01/99	4.91	NLE	1.0
Zinc	07/01/99	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4539.07
 Sample Received: 06/09/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	07/01/99	238	200	10.0
Antimony	07/01/99	ND	20	2.0
Arsenic	07/01/99	5.79	8	2.0
Barium	07/01/99	113	2000	0.5
Beryllium	07/01/99	ND	20	0.5
Cadmium	07/01/99	ND	4	0.5
Calcium	07/01/99	89200	NLE	20.0
Chromium	07/01/99	3.26	100	0.5
Cobalt	07/01/99	ND	NLE	0.5
Copper	07/01/99	13.3	1000	3.0
Iron	07/01/99	5920	300	10.0
Lead	07/01/99	ND	10	2.0
Magnesium	07/01/99	6770	NLE	20.0
Manganese	07/01/99	148	50	0.5
Mercury	07/02/99	ND	2	0.1
Nickel	07/01/99	ND	100	0.5
Potassium	07/01/99	13100	NLE	20.0
Selenium	07/01/99	ND	50	3.0
Silver	07/01/99	ND	20	3.0
Sodium	07/01/99	25900	50000	20.0
Thallium	07/01/99	ND	10	3.0
Vanadium	07/01/99	2.64	NLE	1.0
Zinc	07/01/99	1.97	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

	Lab	Silanol, trimethyl-	Hexadeca noic Acid	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water		Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ugl	Feet		-
NJDEP Criteria:	-	NLE	NLE	300	50	200	8	10	-		-
04/24/97	FMETL	31	9	9100	69	-	-	-	6.45		V,S,P,M
07/10/97	FMETL	ND	ND	12590	73	25	5.0	ND	7.05		V,S,P,M
10/22/97	FMETL	ND	ND	34800	171	175	5.0	5.0	7.60		V,S,P,M
01/08/98	FMETL	ND	ND	2795	5.0	204	ND	4.0	5.20		V,S,P,M
04/07/98	FMETL	ND	ND	3504	39.3	196	5.6	ND	6.56		V,S,P,M
07/14/98	FMETL	ND	ND	10900	57.8	65.7	ND	ND	6.89		V,S,P,M
11/24/98	FMETL	ND	ND	27500	182	ND	11.5	3.15	7.86		V,S,P,M
02/11/99	FMETL	ND	ND	11000	100	505	8.3	ND	7.24		V,S,P,M
06/09/99	FMETL	ND	ND	8210	145	521	6.33	ND	7.21		V,S,P,M

SOURCE: 0CW2MW30

Sampling Dates:
04/24/97 - 06/09/99

NOTES:


FORT MONMOUTH

GW MONITORING
Bldg CW-2


Well 1 of 4

 U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Silanol, trimethyl-
(ug/l)




Hexadecanoic Acid
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW30

Sampling Dates:
04/24/97 - 06/09/99

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 1 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Silanol, trimethyl-
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW31

Sampling Dates:
04/24/97 - 06/09/99

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Silanol, trimethyl-	2-Pentanone 4-hydroxy- 4-methyl	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water		Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ugl	Feet		-
NJDEP Criteria:	-	NLE	NLE	300	50	200	8	10	-		-
04/24/97	FMETL	4	440	18400	125	-	-	-	6.65		V,S,P,M
07/10/97	FMETL	ND	ND	270	181	595	ND	ND	7.20		V,S,P,M
10/22/97	FMETL	ND	ND	51100	260	297	ND	7.0	7.70		V,S,P,M
01/08/98	FMETL	ND	ND	1484	3.7	163	ND	ND	4.50		V,S,P,M
04/07/98	FMETL	ND	22	19280	287	ND	ND	ND	6.81		V,S,P,M
07/14/98	FMETL	ND	ND	67500	287	78.1	2.51	3.99	7.06		V,S,P,M
11/24/98	FMETL	ND	ND	106000	342	166	9.32	4.08	7.94		V,S,P,M
02/11/99	FMETL	ND	ND	4480	7.02	137	ND	ND	7.33		V,S,P,M
06/09/99	FMETL	ND	ND	64300	310	59.5	ND	ND	7.49		V,S,P,M

SOURCE: 0CW2MW32

Sampling Dates:
04/24/97 - 06/09/99

NOTES:

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 3 of 4




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Silanol, trimethyl-
(ug/l)




2-Pentanone,4-hydroxy-4-methyl
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ugl)



Depth to Water
(Feet)



SOURCE: 0CW2MW32

Sampling Dates:
04/24/97 - 06/09/99

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 3 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Silanol, trimethyl-
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW33

Sampling Dates:
04/24/97 - 06/09/99

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703


PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
4686.04	0CW2MW30	29-32594	08/04/99
4686.05	0CW2MW31	29-32595	08/04/99
4686.06	0CW2MW32	29-32596	08/04/99
4686.07	0CW2MW33	29-32597	08/04/99

NJDEP Laboratory Certification # 13461

 9-9-99
Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY


PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608

Tel (732)532-4359 Fax (732)532-6263 EMail:appleby@mail1.monmouth.army.mil

Chain of Custody Record

print legibly



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: CW2MW030
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 08/04/99
WEATHER: Sunny, Hot.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.71 ft
DEPTH TO WATER: 7.43 ft
DEPTH OF WELL: 17.95 ft
HEIGHT OF WATER: 10.52 ft
 $(10.52) \times .65 \times 3 = 20.51$
GALLONS OF H₂O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM): PERISTALIC
PURGE RATE: 0.23 GPM
Hnu READING: 0.0 PPM

PURGE START TIME: 11:20

pH 6.87 su

DISSOLVED O₂ 6.21 PPM

TEMP 12.9 °C

SPECIFIC CONDUCTIVITY 530 us/cm

PURGE END TIME: 12:52

pH 6.87 su

DISSOLVED O₂ 4.11 PPM

TEMP 12.6 °C

SPECIFIC CONDUCTIVITY 531 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 10.83 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 21 gal

pH 6.82 su

DISSOLVED O₂ 4.07 PPM

TEMP 12.6 °C

SPECIFIC CONDUCTIVITY 530 us/cm

COMMENTS: No phases.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: CW2MW031
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 08/04/99
WEATHER: Sunny, Hot.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.58 ft
DEPTH TO WATER: 7.65 ft
DEPTH OF WELL: 16.91 ft
HEIGHT OF WATER: 9.26 ft
 $(9.26) \times .65 \times 3 = 18.05$
GALLONS OF H₂O TO BE PURGED: 18 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM): PERISTALTIC
PURGE RATE: 0.23 GPM
Hnu READING: 0.0 PPM

PURGE START TIME: 11:35

pH 6.61 su

DISSOLVED O₂ 6.22 PPM

TEMP 12.9 °C

SPECIFIC CONDUCTIVITY 395 us/cm

PURGE END TIME: 12:54

pH 6.59 su

DISSOLVED O₂ 4.29 PPM

TEMP 12.5 °C

SPECIFIC CONDUCTIVITY 395 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 9.71 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 18 gal

pH 6.57 su

DISSOLVED O₂ 4.27 PPM

TEMP 12.6 °C

SPECIFIC CONDUCTIVITY 395 us/cm

COMMENTS: No phases.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: CW2MW032
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 08/04/99
WEATHER: Sunny, Hot.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.38 ft
DEPTH TO WATER: 7.85 ft
DEPTH OF WELL: 16.89 ft
HEIGHT OF WATER: 9.04 ft
(9.04 X .65 X 3 = 17.62
GALLONS OF H₂O TO BE PURGED: 18 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM): PERISTALIC
PURGE RATE: 0.23 GPM
Hnu READING: 0.0 PPM

PURGE START TIME: 11:45

pH 7.27 su

DISSOLVED O₂ 6.07 PPM

TEMP 12.8 °C

SPECIFIC CONDUCTIVITY 450 us/cm

PURGE END TIME: 13:04

pH 7.23 su

DISSOLVED O₂ 4.04 PPM

TEMP 12.5 °C

SPECIFIC CONDUCTIVITY 448 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 13.33 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 18 gal

pH 7.01 su

DISSOLVED O₂ 3.99 PPM

TEMP 12.5 °C

SPECIFIC CONDUCTIVITY 449 us/cm

COMMENTS: DUP. Here. No phases.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: CW2MW033
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 08/04/99
WEATHER: Sunny, Hot.
TIDE: N/A

ELEV. OF CASING SURVEY MARK: 51.09 ft
DEPTH TO WATER: 9.15 ft
DEPTH OF WELL: 16.10 ft
HEIGHT OF WATER: 6.95 ft
 $(6.95 \times .65 \times 3 = 13.55)$
GALLONS OF H₂O TO BE PURGED: 14 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 GPM): PERISTALTIC
PURGE RATE: 0.23 GPM
Hnu READING: 0.0 PPM

PURGE START TIME: 11:55

pH 7.22 su

DISSOLVED O₂ 6.17 PPM

TEMP 12.7 °C

SPECIFIC CONDUCTIVITY 376 us/cm

PURGE END TIME: 12:55

pH 7.25 su

DISSOLVED O₂ 4.17 PPM

TEMP 12.6 °C

SPECIFIC CONDUCTIVITY 375 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 9.46 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 14 gal

pH 7.24 su

DISSOLVED O₂ 4.14 PPM

TEMP 12.7 °C

SPECIFIC CONDUCTIVITY 374 us/cm

COMMENTS: No phases.

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit

J : Compound identified below detection limit

B : Compound in both sample and blank

D : Results from dilution of sample

U : Compound searched for but not detected

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC000646.D**
 Operator **Skelton**
 Date Acquired **11 Aug 1999 11:06 am**

Sample Name **Vblk20**
 Field ID **Vblk20**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Vbik20

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 4686 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Vbik20
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC000646.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: not dec. _____ Date Analyzed: 8/11/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC000648.D**
 Operator **Skelton**
 Date Acquired **11 Aug 1999 1:29 pm**

Sample Name **4686.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Trip Blank

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 4686 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4686.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC000648.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: not dec. Date Analyzed: 8/11/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 1

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
1. 000091-20-3	Naphthalene	30.86	14	JN

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC000649.D**
 Operator **Skelton**
 Date Acquired **11 Aug 1999 2:11 pm**

Sample Name **4686.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m-p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Field Blank

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 4686 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4686.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC000649.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: not dec. _____ Date Analyzed: 8/11/99
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC000650.D**
 Operator **Skelton**
 Date Acquired **11 Aug 1999 2:54 pm**

Sample Name **4686.03**
 Field ID **Duplicate**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Dupe

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 4686 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4686.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC000650.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: not dec. Date Analyzed: 8/11/99
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC000651.D**
 Operator **Skelton**
 Date Acquired **11 Aug 1999 3:35 pm**

Sample Name **4686.04**
 Field ID **0CW2MW30**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

0CW2MW30

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 4686 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4686.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC000651.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: not dec. Date Analyzed: 8/11/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC000652.D**
 Operator **Skelton**
 Date Acquired **11 Aug 1999 4:17 pm**

Sample Name **4686.05**
 Field ID **0CW2MW31**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

0CW2MW31

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 4686 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4686.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC000652.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: not dec. Date Analyzed: 8/11/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC000653.D**
 Operator **Skelton**
 Date Acquired **11 Aug 1999 4:59 pm**

Sample Name **4686.06**
 Field ID **0CW2MW32**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m-p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7-9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

0CW2MW32

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 4686 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 4686.06

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC000653.D

Level: (low/med) LOW Date Received: 8/4/99

% Moisture: not dec. _____ Date Analyzed: 8/11/99

GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC000654.D**
 Operator **Skelton**
 Date Acquired **11 Aug 1999 5:41 pm**

Sample Name **4686.07**
 Field ID **0CW2MW33**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	nle	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

0CW2MW33

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 4686 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4686.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC000654.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: not dec. Date Analyzed: 8/11/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03137.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **Sblk283**
 Misc Info **Sblk283 A 990805**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03137.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **Sblk283**
 Misc Info **Sblk283 A 990805**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzydine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Sblk283

Lab Name: FMETL Lab Code 13461

Project 98-0211 Case No.: 4686 Location CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: Sblk283

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03137.D

Level: (low/med) LOW Date Received: 8/4/99

% Moisture: _____ decanted: (Y/N) N Date Extracted: 8/5/99

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/6/99

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.27	18	J
2.	unknown	9.12	30	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03139.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03139.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Lab Code 13461
Project 98-0211 Case No.: 4686 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4686.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03139.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: decanted: (Y/N) N Date Extracted: 8/5/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/6/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) . UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.26	21	J
2.	unknown	9.11	28	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03140.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.03**
 Misc Info **Dupe**
 Sample Multiplier **1.15**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.10 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	1.05 ug/L	
62-53-3	Aniline			not detected	NLE	1.87 ug/L	
108-95-2	Phenol			not detected	4000	0.94 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.47 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.30 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.39 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.37 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.17 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.30 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.35 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.60 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.40 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.92 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.73 ug/L	
98-95-3	Nitrobenzene			not detected	10	1.12 ug/L	
78-59-1	Isophorone			not detected	100	1.16 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	2.21 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	3.01 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.39 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.53 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	2.01 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.40 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.46 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.25 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.82 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.60 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.24 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.52 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	2.05 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.47 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.16 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.10 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.75 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	1.10 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.93 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.91 ug/L	
83-32-9	Acenaphthene			not detected	400	1.27 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.66 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.15 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.22 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03140.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.03**
 Misc Info **Dupe**
 Sample Multiplier **1.15**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.00 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.86 ug/L	
86-73-7	Fluorene			not detected	300	1.14 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.27 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.21 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.28 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.16 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.77 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.87 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.63 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.41 ug/L	
120-12-7	Anthracene			not detected	2000	1.29 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.96 ug/L	
206-44-0	Fluoranthene			not detected	300	1.89 ug/L	
92-87-5	Benzdine			not detected	50	4.81 ug/L	
129-00-0	Pyrene			not detected	200	1.44 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.21 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.37 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.01 ug/L	
218-01-9	Chrysene			not detected	20	1.59 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	2.00 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.66 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.44 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.48 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.21 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.95 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.74 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.97 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Dupe

Lab Name: FMETL Lab Code 13461
Project 98-0211 Case No.: 4686 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4686.03
Sample wt/vol: 870 (g/ml) ML Lab File ID: BNA03140.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: decanted: (Y/N) N Date Extracted: 8/5/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/6/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03141.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1.12**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.05 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	1.02 ug/L	
62-53-3	Aniline			not detected	NLE	1.83 ug/L	
108-95-2	Phenol			not detected	4000	0.92 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.43 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.24 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.36 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.33 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.14 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.27 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.31 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.56 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.39 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.90 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.68 ug/L	
98-95-3	Nitrobenzene			not detected	10	1.09 ug/L	
78-59-1	Isophorone			not detected	100	1.13 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	2.15 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.36 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.49 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.96 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.37 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.42 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.22 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.80 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.56 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.21 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.48 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.99 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.43 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.13 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.08 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.70 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	1.08 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.91 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.88 ug/L	
83-32-9	Acenaphthene			not detected	400	1.23 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.61 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.12 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.19 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03141.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1.12**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.97 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.81 ug/L	
86-73-7	Fluorene			not detected	300	1.11 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.23 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.18 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.22 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.13 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.75 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.85 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.05 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.59 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.38 ug/L	
120-12-7	Anthracene			not detected	2000	1.25 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.90 ug/L	
206-44-0	Fluoranthene			not detected	300	1.84 ug/L	
92-87-5	Benidine			not detected	50	4.68 ug/L	
129-00-0	Pyrene			not detected	200	1.40 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.18 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.33 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.96 ug/L	
218-01-9	Chrysene			not detected	20	1.55 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.95 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.61 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.40 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.44 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.18 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.93 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.72 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.94 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW30

Lab Name: FMETL Lab Code 13461

Project 98-0211 Case No.: 4686 Location CW2 SDG No.:

Matrix: (soil/water) WATER Lab Sample ID: 4686.04

Sample wt/vol: 892 (g/ml) ML Lab File ID: BNA03141.D

Level: (low/med) LOW Date Received: 8/4/99

% Moisture: decanted: (Y/N) N Date Extracted: 8/5/99

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/6/99

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.27	32	J
2.	unknown	9.11	35	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03142.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1.13**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.07 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	1.03 ug/L	
62-53-3	Aniline			not detected	NLE	1.84 ug/L	
108-95-2	Phenol			not detected	4000	0.93 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.45 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.26 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.37 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.34 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.15 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.28 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.32 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.40 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.90 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.70 ug/L	
98-95-3	Nitrobenzene			not detected	10	1.10 ug/L	
78-59-1	Isophorone			not detected	100	1.14 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	2.17 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.96 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.37 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.50 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.98 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.38 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.44 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.23 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.80 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.57 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.22 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.49 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	2.01 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.45 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.14 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.08 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.72 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	1.08 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.89 ug/L	
83-32-9	Acenaphthene			not detected	400	1.24 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.63 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.13 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.20 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03142.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1.13**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.98 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.83 ug/L	
86-73-7	Fluorene			not detected	300	1.12 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.24 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.19 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.24 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.14 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.76 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.86 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.06 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.60 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.39 ug/L	
120-12-7	Anthracene			not detected	2000	1.27 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.92 ug/L	
206-44-0	Fluoranthene			not detected	300	1.85 ug/L	
92-87-5	Benzidine			not detected	50	4.72 ug/L	
129-00-0	Pyrene			not detected	200	1.41 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.19 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.34 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.98 ug/L	
218-01-9	Chrysene			not detected	20	1.56 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.97 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.63 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.41 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.46 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.19 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.94 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.72 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.95 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW31

Lab Name: FMETL Lab Code 13461
Project 98-0211 Case No.: 4686 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4686.05
Sample wt/vol: 885 (g/ml) ML Lab File ID: BNA03142.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: _____ decanted: (Y/N) N Date Extracted: 8/5/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/6/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.28	41	J
2.	unknown	9.12	33	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03143.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1.17**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	2.14 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	1.06 ug/L	
62-53-3	Aniline			not detected	NLE	1.91 ug/L	
108-95-2	Phenol			not detected	4000	0.96 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.50 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.34 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.42 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.39 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.19 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.32 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.37 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.63 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.41 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.94 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.76 ug/L	
98-95-3	Nitrobenzene			not detected	10	1.13 ug/L	
78-59-1	Isophorone			not detected	100	1.18 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	2.25 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	3.07 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.42 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.56 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	2.05 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.43 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.49 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.28 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.83 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.63 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.26 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.54 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	2.08 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.50 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.18 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.12 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.78 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	1.12 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.95 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.92 ug/L	
83-32-9	Acenaphthene			not detected	400	1.29 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.68 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.17 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.24 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03143.D**
 Operator **Bhaskar**
 Date Acquired **6-Ang-99**

Sample Name **4686.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1.17**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.02 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.90 ug/L	
86-73-7	Fluorene			not detected	300	1.16 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.29 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.23 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.32 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.18 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.78 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.89 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.10 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.66 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.44 ug/L	
120-12-7	Anthracene			not detected	2000	1.31 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.99 ug/L	
206-44-0	Fluoranthene			not detected	300	1.92 ug/L	
92-87-5	Benzidine			not detected	50	4.89 ug/L	
129-00-0	Pyrene			not detected	200	1.46 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.23 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.39 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	2.05 ug/L	
218-01-9	Chrysene			not detected	20	1.61 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	2.04 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.68 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.46 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.51 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.23 ug/L	
193-39-5	Indenof[1,2,3-cd]pyrene			not detected	20	0.97 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.75 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.98 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW32

Lab Name: FMETL Lab Code 13461

Project 98-0211 Case No.: 4686 Location CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 4686.06

Sample wt/vol: 858 (g/ml) ML Lab File ID: BNA03143.D

Level: (low/med) LOW Date Received: 8/4/99

% Moisture: _____ decanted: (Y/N) N Date Extracted: 8/5/99

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/6/99

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.28	35	J
2.	unknown	9.11	33	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03144.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03144.D**
 Operator **Bhaskar**
 Date Acquired **6-Aug-99**

Sample Name **4686.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW33

Lab Name: FMETL Lab Code 13461
Project 98-0211 Case No.: 4686 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4686.07
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03144.D
Level: (low/med) LOW Date Received: 8/4/99
% Moisture: decanted: (Y/N) N Date Extracted: 8/5/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/6/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.27	33	J
2.	unknown	9.12	32	J

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : BLK374
Date Rec'd:
Extraction Date: 8/10/99
Analysis Date: 8/12/99

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location :

Field ID:

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 4686.02
Date Rec'd: 8/4/99
Extraction Date: 8/10/99
Analysis Date: 8/12/99

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: Field Blank

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army DPW, SELFM-PW-EV Bldg. 173 Ft. Monmouth, NJ 07703	Lab. ID # :	4686.03
		Date Rec'd:	8/4/99
		Extraction Date:	8/10/99
		Analysis Date:	8/12/99
Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	Dupe
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 4686.04
Date Rec'd: 8/4/99
Extraction Date: 8/10/99
Analysis Date: 8/13/99

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: 0CW2MW30

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army DPW, SELFM-PW-EV Bldg. 173 Ft. Monmouth, NJ 07703	Lab. ID # :	4686.05
		Date Rec'd:	8/4/99
		Extraction Date:	8/10/99
		Analysis Date:	8/13/99

Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	0CW2MW31
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

PQL = Practical Quantitation Limit

PQL = Practical Quantitation Limit

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4686
 Sample Prepared: 08/19/99

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/20/99	ND	200	10.0
Antimony	08/20/99	ND	20	2.0
Arsenic	08/20/99	ND	8	2.0
Barium	08/20/99	1.06	2000	0.5
Beryllium	08/20/99	ND	20	0.5
Cadmium	08/20/99	0.771	4	0.5
Calcium	08/20/99	76.1	NLE	20.0
Chromium	08/20/99	ND	100	0.5
Cobalt	08/20/99	ND	NLE	0.5
Copper	08/20/99	49.5	1000	3.0
Iron	08/20/99	ND	300	10.0
Lead	08/20/99	4.20	10	2.0
Magnesium	08/20/99	ND	NLE	20.0
Manganese	08/20/99	1.12	50	0.5
Mercury	08/24/99	ND	2	0.1
Nickel	08/20/99	5.75	100	0.5
Potassium	08/20/99	1290	NLE	20.0
Selenium	08/20/99	ND	50	3.0
Silver	08/20/99	ND	20	3.0
Sodium	08/20/99	303	50000	20.0
Thallium	08/20/99	ND	10	3.0
Vanadium	08/20/99	ND	NLE	1.0
Zinc	08/20/99	41.3	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4686.02
 Sample Received: 08/04/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/20/99	ND	200	10.0
Antimony	08/20/99	ND	20	2.0
Arsenic	08/20/99	ND	8	2.0
Barium	08/20/99	0.588	2000	0.5
Beryllium	08/20/99	ND	20	0.5
Cadmium	08/20/99	ND	4	0.5
Calcium	08/20/99	356	NLE	20.0
Chromium	08/20/99	ND	100	0.5
Cobalt	08/20/99	ND	NLE	0.5
Copper	08/20/99	3.55	1000	3.0
Iron	08/20/99	40.5	300	10.0
Lead	08/20/99	ND	10	2.0
Magnesium	08/20/99	48.4	NLE	20.0
Manganese	08/20/99	1.06	50	0.5
Mercury	08/24/99	ND	2	0.1
Nickel	08/20/99	0.928	100	0.5
Potassium	08/20/99	99.2	NLE	20.0
Selenium	08/20/99	ND	50	3.0
Silver	08/20/99	ND	20	3.0
Sodium	08/20/99	419	50000	20.0
Thallium	08/20/99	ND	10	3.0
Vanadium	08/20/99	ND	NLE	1.0
Zinc	08/20/99	4.25	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4686.03
 Sample Received: 08/04/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/20/99	90.3	200	10.0
Antimony	08/20/99	ND	20	2.0
Arsenic	08/20/99	ND	8	2.0
Barium	08/20/99	249	2000	0.5
Beryllium	08/20/99	ND	20	0.5
Cadmium	08/20/99	1.19	4	0.5
Calcium	08/20/99	72000	NLE	20.0
Chromium	08/20/99	ND	100	0.5
Cobalt	08/20/99	ND	NLE	0.5
Copper	08/20/99	5.52	1000	3.0
Iron	08/20/99	76200	300	10.0
Lead	08/20/99	ND	10	2.0
Magnesium	08/20/99	8280	NLE	20.0
Manganese	08/20/99	368	50	0.5
Mercury	08/24/99	0.3	2	0.1
Nickel	08/20/99	1.32	100	0.5
Potassium	08/20/99	11900	NLE	20.0
Selenium	08/20/99	ND	50	3.0
Silver	08/20/99	ND	20	3.0
Sodium	08/20/99	15000	50000	20.0
Thallium	08/20/99	ND	10	3.0
Vanadium	08/20/99	2.50	NLE	1.0
Zinc	08/20/99	24.8	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4686.04
 Sample Received: 08/04/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/20/99	304	200	10.0
Antimony	08/20/99	ND	20	2.0
Arsenic	08/20/99	9.05	8	2.0
Barium	08/20/99	127	2000	0.5
Beryllium	08/20/99	ND	20	0.5
Cadmium	08/20/99	2.06	4	0.5
Calcium	08/20/99	83300	NLE	20.0
Chromium	08/20/99	3.82	100	0.5
Cobalt	08/20/99	ND	NLE	0.5
Copper	08/20/99	77.7	1000	3.0
Iron	08/20/99	44800	300	10.0
Lead	08/20/99	6.02	10	2.0
Magnesium	08/20/99	7890	NLE	20.0
Manganese	08/20/99	212	50	0.5
Mercury	08/24/99	ND	2	0.1
Nickel	08/20/99	8.53	100	0.5
Potassium	08/20/99	10800	NLE	20.0
Selenium	08/20/99	ND	50	3.0
Silver	08/20/99	ND	20	3.0
Sodium	08/20/99	47200	50000	20.0
Thallium	08/20/99	ND	10	3.0
Vanadium	08/20/99	3.02	NLE	1.0
Zinc	08/20/99	56.6	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4686.05
 Sample Received: 08/04/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/20/99	ND	200	10.0
Antimony	08/20/99	ND	20	2.0
Arsenic	08/20/99	ND	8	2.0
Barium	08/20/99	361	2000	0.5
Beryllium	08/20/99	ND	20	0.5
Cadmium	08/20/99	1.06	4	0.5
Calcium	08/20/99	59600	NLE	20.0
Chromium	08/20/99	ND	100	0.5
Cobalt	08/20/99	ND	NLE	0.5
Copper	08/20/99	ND	1000	3.0
Iron	08/20/99	77500	300	10.0
Lead	08/20/99	ND	10	2.0
Magnesium	08/20/99	7120	NLE	20.0
Manganese	08/20/99	347	50	0.5
Mercury	08/24/99	ND	2	0.1
Nickel	08/20/99	1.11	100	0.5
Potassium	08/20/99	11600	NLE	20.0
Selenium	08/20/99	ND	50	3.0
Silver	08/20/99	ND	20	3.0
Sodium	08/20/99	12900	50000	20.0
Thallium	08/20/99	ND	10	3.0
Vanadium	08/20/99	2.40	NLE	1.0
Zinc	08/20/99	6.86	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4686.06
 Sample Received: 08/04/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/20/99	67.4	200	10.0
Antimony	08/20/99	ND	20	2.0
Arsenic	08/20/99	ND	8	2.0
Barium	08/20/99	247	2000	0.5
Beryllium	08/20/99	ND	20	0.5
Cadmium	08/20/99	2.25	4	0.5
Calcium	08/20/99	71700	NLE	20.0
Chromium	08/20/99	ND	100	0.5
Cobalt	08/20/99	ND	NLE	0.5
Copper	08/20/99	6.23	1000	3.0
Iron	08/20/99	76000	300	10.0
Lead	08/20/99	ND	10	2.0
Magnesium	08/20/99	8270	NLE	20.0
Manganese	08/20/99	369	50	0.5
Mercury	08/24/99	ND	2	0.1
Nickel	08/20/99	1.70	100	0.5
Potassium	08/20/99	11900	NLE	20.0
Selenium	08/20/99	ND	50	3.0
Silver	08/20/99	ND	20	3.0
Sodium	08/20/99	14800	50000	20.0
Thallium	08/20/99	ND	10	3.0
Vanadium	08/20/99	2.84	NLE	1.0
Zinc	08/20/99	24.8	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4686.07
 Sample Received: 08/04/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33


TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/20/99	69.8	200	10.0
Antimony	08/20/99	ND	20	2.0
Arsenic	08/20/99	3.25	8	2.0
Barium	08/20/99	158	2000	0.5
Beryllium	08/20/99	ND	20	0.5
Cadmium	08/20/99	0.561	4	0.5
Calcium	08/20/99	35100	NLE	20.0
Chromium	08/20/99	0.700	100	0.5
Cobalt	08/20/99	ND	NLE	0.5
Copper	08/20/99	ND	1000	3.0
Iron	08/20/99	35900	300	10.0
Lead	08/20/99	ND	10	2.0
Magnesium	08/20/99	5360	NLE	20.0
Manganese	08/20/99	149	50	0.5
Mercury	08/24/99	ND	2	0.1
Nickel	08/20/99	1.27	100	0.5
Potassium	08/20/99	7690	NLE	20.0
Selenium	08/20/99	ND	50	3.0
Silver	08/20/99	ND	20	3.0
Sodium	08/20/99	16100	50000	20.0
Thallium	08/20/99	ND	10	3.0
Vanadium	08/20/99	ND	NLE	1.0
Zinc	08/20/99	7.30	5000	1.0


ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6


Silanol, trimethyl-
(ug/l)




Hexadecanoic Acid
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ugl)



Depth to Water
(Feet)



SOURCE: 0CW2MW30

Sampling Dates:
04/24/97 - 08/04/99

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 1 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

Silanol, trimethyl-
(ug/l)



	Lab	Silanol, trimethyl-	Hexadeca noic Acid	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water		Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ugl	Feet		-
NJDEP Criteria:	-	NLE	NLE	300	50	200	8	10	-		-
04/24/97	FMETL	4	18	18400	125	-	-	-	6.65		V,S,P,M
07/10/97	FMETL	ND	ND	270	181	595	ND	ND	7.20		V,S,P,M
10/22/97	FMETL	ND	ND	51100	260	297	ND	7.0	7.70		V,S,P,M
01/08/98	FMETL	ND	ND	1484	3.7	163	ND	ND	4.50		V,S,P,M
04/07/98	FMETL	ND	ND	19280	287	ND	ND	ND	6.81		V,S,P,M
07/14/98	FMETL	ND	ND	67500	287	78.1	2.51	3.99	7.06		V,S,P,M
11/24/98	FMETL	ND	ND	106000	342	166	9.32	4.08	7.94		V,S,P,M
02/11/99	FMETL	ND	ND	4480	7.02	137	ND	ND	7.33		V,S,P,M
06/09/99	FMETL	ND	ND	64300	310	59.5	ND	ND	7.49		V,S,P,M
08/04/99	FMETL	ND	ND	76000	369	67.4	ND	ND	7.85		V,S,P,M

SOURCE: 0CW2MW32

Sampling Dates:
04/24/97 - 08/04/99

NOTES:

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 3 of 4




**U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV**


Silanol, trimethyl-
(ug/l)




Hexadecanoic Acid
(ug/l)




Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW32

Sampling Dates:
04/24/97 - 08/04/99

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
4911.04	0CW2MW30	29-32594	11/03/99
4911.05	0CW2MW31	29-32595	11/03/99
4911.06	0CW2MW32	29-32596	11/03/99
4911.07	0CW2MW33	29-32597	11/03/99

NJDEP Laboratory Certification # 13461


Daniel Wright/Date: 12-8-99
Laboratory Director

METHODOLOGY SUMMARY


PARAMETER	REFERENCE
TARGET ANALYTE LIST METALS	Standard Methods, 18th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B

PARAMETER	REFERENCE
TARGET COMPOUND LIST ORGANICS	Federal Register 40 CFR Part 136 Appendix A
Base/Neutral and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticide and PCB by GC	608

Tel (732)532-4359 Fax (732)532-6263 EMail:appleby@mail1.monmouth.army.mil

Chain of Custody Record

print legibly



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 11/03/99
WEATHER: Sunny, cold, windy.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.71 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.02 ft
DEPTH OF WELL: 17.95 ft
DEPTH TO TOP OF SCREEN: 6.00 ft
HEIGHT OF WATER: 10.93 ft
 $(10.93) \times .65 \times 3 = 21.31$
GALLONS OF H₂O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:55

pH 7.18 su

DISSOLVED O₂ 6.81 ppm

TEMP 13.5 °C

SPECIFIC CONDUCTIVITY 134 us/cm

PURGE END TIME: 10:26

pH 7.20 su

DISSOLVED O₂ 5.62 ppm

TEMP 13.3 °C

SPECIFIC CONDUCTIVITY 134 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 12.12 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 21 gal

SAMPLE START TIME: 10:27

pH 7.21 su

DISSOLVED O₂ 5.60 ppm

TEMP 13.3 °C

SPECIFIC CONDUCTIVITY 134 us/cm

SAMPLE END TIME: 10:34

COMMENTS:

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 11/03/99
WEATHER: Sunny, cold, windy.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.58 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.18 ft
DEPTH OF WELL: 16.41 ft
DEPTH TO TOP OF SCREEN: 5.00 ft
HEIGHT OF WATER: 9.73 ft
 $(9.73) \times .65 \times 3 = 18.97$
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:00

pH 7.35 su

DISSOLVED O2 6.71 ppm

TEMP 13.4 °C

SPECIFIC CONDUCTIVITY 193 us/cm

PURGE END TIME: 10:22

pH 7.36 su

DISSOLVED O2 5.70 ppm

TEMP 13.2 °C

SPECIFIC CONDUCTIVITY 193 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.42 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 10:23

pH 7.35 su

DISSOLVED O2 5.68 ppm

TEMP 13.2 °C

SPECIFIC CONDUCTIVITY 192 us/cm

SAMPLE END TIME: 10:26

COMMENTS: Orange tinge. Particles.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 11/03/99
WEATHER: Sunny, cold, windy.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.38 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 6.53 ft
DEPTH OF WELL: 16.88 ft
DEPTH TO TOP OF SCREEN: 5.00 ft
HEIGHT OF WATER: 10.36 ft
 $(10.36) \times .65 \times 3 = 20.20$
GALLONS OF H2O TO BE PURGED: 20 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:10

pH 7.21 su

DISSOLVED O2 6.91 ppm

TEMP 13.5 °C

SPECIFIC CONDUCTIVITY 155 us/cm

PURGE END TIME: 10:37

pH 7.22 su

DISSOLVED O2 5.81 ppm

TEMP 13.4 °C

SPECIFIC CONDUCTIVITY 155 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 11.52 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON @ BAILER)

TOTAL VOLUME PURGED: 20 gal

SAMPLE START TIME: 10:38

pH 7.21 su

DISSOLVED O2 5.80 ppm

TEMP 13.3 °C

SPECIFIC CONDUCTIVITY 156 us/cm

SAMPLE END TIME: 10:43

COMMENTS: Orange tinge. DUP. Here.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW33
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 11/03/99
WEATHER: Sunny, cold, windy.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.09 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 6.14 ft
DEPTH OF WELL: 16.10 ft
DEPTH TO TOP OF SCREEN: 5.00 ft
HEIGHT OF WATER: 9.96 ft
(9.96) X .65 X 3 = 19.42
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:15

pH 6.83 su

DISSOLVED O2 6.67 ppm

TEMP 13.5 °C

SPECIFIC CONDUCTIVITY 117 us/cm

PURGE END TIME: 10:37

pH 6.84 su

DISSOLVED O2 5.31 ppm

TEMP 13.3 °C

SPECIFIC CONDUCTIVITY 117 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 10.02 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 10:44

pH 6.81 su

DISSOLVED O2 5.31 ppm

TEMP 13.3 °C

SPECIFIC CONDUCTIVITY 117 us/cm

SAMPLE END TIME: 10:50

COMMENTS: Orange tinge, heavier while bailing. MS/MSD here.

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit
J : Compound identified below detection limit
B : Compound in both sample and blank
D : Results from dilution of sample
U : Compound searched for but not detected
E : Compound exceeds calibration limit

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB004723.D**
 Operator **Skelton**
 Date Acquired **8 Nov 1999 5:50 pm**

Sample Name **Vblk145**
 Field ID **Vblk145**
 Sample Multiple **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Vblk145

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Vblk145
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004723.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. _____ Date Analyzed: 11/8/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB004756.D**
 Operator **Skelton**
 Date Acquired **12 Nov 1999 1:08 pm**

Sample Name **Vblk146**
 Field ID **Vblk146**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6.2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Vblk146

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Vblk146
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004756.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. _____ Date Analyzed: 11/12/99
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File VB004737.D
 Operator Skelton
 Date Acquired 9 Nov 1999 2:52 am

Sample Name 4911.01
 Field ID Trip Blank
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Trip Blank

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004737.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. _____ Date Analyzed: 11/9/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB004738.D**
 Operator **Skelton**
 Date Acquired **9 Nov 1999 3:32 am**

Sample Name **4911.02**
 Field ID **Field Blank**
 Sample Multiple **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Field Blank

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004738.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. _____ Date Analyzed: 11/9/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File VB004740.D
 Operator Skelton
 Date Acquired 9 Nov 1999 4:50 am

Sample Name 4911.04
 Field ID 0CW2MW30
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6.2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW30

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004740.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. _____ Date Analyzed: 11/9/99
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB004773.D**
 Operator **Skelton**
 Date Acquired **13 Nov 1999 12:21 am**

Sample Name **4911.05**
 Field ID **0CW2MW31**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW31

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004773.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. _____ Date Analyzed: 11/13/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB004742.D**
 Operator **Skelton**
 Date Acquired **9 Nov 1999 6:07 am**

Sample Name **4911.06**
 Field ID **0CW2MW32**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW32

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004742.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. _____ Date Analyzed: 11/9/99
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB004743.D**
 Operator **Skelton**
 Date Acquired **9 Nov 1999 6:46 am**

Sample Name **4911.07**
 Field ID **0CW2MW33**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6.2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW33

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004743.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. _____ Date Analyzed: 11/9/99
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB004772.D**
 Operator **Skelton**
 Date Acquired **12 Nov 1999 11:42 pm**

Sample Name **4911.03**
 Field ID **Dupe**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Dupe

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 4911 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 4911.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB004772.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: not dec. Date Analyzed: 11/12/99
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN04028.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **Sblk317**
 Misc Info **Sblk317 A 991108**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.79 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN04028.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **Sblk317**
 Misc Info **Sblk317 A 991108**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

Sblk317

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 4911 Location: CW2 SDG No: _____
Matrix: (soil/water) WATER Lab Sample ID: Sblk317
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN04028.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/8/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 11/8/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification #13461

Data File Name BN04032.D

Operator Bhaskar

Date Acquired 8-Nov-99

Sample Name 4911.02

Misc Info Field Blank

Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.79 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN04032.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **4911.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate	23.84	145664	4.72 ug/L	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

Field Blank

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 4911 Location: CW2 SDG No:
Matrix: (soil/water) WATER Lab Sample ID: 4911.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN04032.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: decanted: (Y/N) N Date Extracted: 11/8/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 11/8/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	28.01	160	J
2.	unknown	29.15	23	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN04034.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **4911.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.79 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN04034.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **4911.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

OCW2MW30

Lab Name: FMETL Lab Code 13461

Project: LTM Case No.: 4911 Location: CW2 SDG No: _____

Matrix: (soil/water) WATER Lab Sample ID: 4911.04

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN04034.D

Level: (low/med) LOW Date Received: 11/3/99

% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/8/99

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 11/8/99

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 5 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	9.33	13	J
2.	unknown	15.03	6	J
3. 000057-10-3	Hexadecanoic acid	19.53	6	JN
4.	unknown	28.87	38	J
5.	unknown	29.14	18	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN04035.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **4911.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.79 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BN04035.D
 Operator Bhaskar
 Date Acquired 8-Nov-99

Sample Name 4911.05
 Misc Info 0CW2MW31
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

0CW2MW31

Lab Name: FMETL Lab Code 13461

Project: LTM Case No.: 4911 Location: CW2 SDG No: _____

Matrix: (soil/water) WATER Lab Sample ID: 4911.05

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN04035.D

Level: (low/med) LOW Date Received: 11/3/99

% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/8/99

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 11/8/99

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 5 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	5.88	5	J
2. 000057-10-3	Hexadecanoic acid	19.52	5	JN
3.	unknown	25.89	16	J
4.	unknown	27.94	180	J
5.	unknown	29.15	96	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN04036.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **4911.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.79 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN04036.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **4911.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benztidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

0CW2MW32

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 4911 Location: CW2 SDG No: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.06
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN04036.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/8/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 11/8/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000057-10-3	Hexadecanoic acid	19.53	4	JN
2.	unknown	27.97	58	J
3.	unknown	28.78	8	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name BN04037.D
 Operator Bhaskar
 Date Acquired 9-Nov-99

Sample Name 4911.07
 Misc Info 0CW2MW33
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.79 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BN04037.D**
 Operator **Bhaskar**
 Date Acquired **9-Nov-99**

Sample Name **4911.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

0CW2MW33

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 4911 Location: CW2 SDG No: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.07
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN04037.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/8/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 11/9/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000057-10-3	Hexadecanoic acid	19.53	5	JN
2.	unknown	28.90	42	J
3.	unknown	29.14	15	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BN04033.D**
 Operator **Bhaskar**
 Date Acquired **8-Nov-99**

Sample Name **4911.03**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.79 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BN04033.D

Operator Bhaskar

Date Acquired 8-Nov-99

Sample Name 4911.03

Misc Info Dupe

Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
D= Value from dilution
B= Compound in Related Blank
PQL= Practical Quantitation Limit

MDL= Method Detection Limit
NLE= No Limit Established
R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field ID:

Dupe

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 4911 Location: CW2 SDG No: _____
Matrix: (soil/water) WATER Lab Sample ID: 4911.03
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BN04033.D
Level: (low/med) LOW Date Received: 11/3/99
% Moisture: _____ decanted: (Y/N) N Date Extracted: 11/8/99
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 11/8/99
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000057-10-3	Hexadecanoic acid	19.53	5	JN
2.	unknown	27.95	53	J
3.	unknown	28.99	150	J

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : BLK430
Date Rec'd:
Extraction Date: 11/4/99
Analysis Date: 11/22/99

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location :

Field ID:

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

MDL = Method Detection Limit

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

NLE = No Limit Established

PQL = Practical Quantitation Limit

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army DPW, SELFM-PW-EV Bldg. 173 Ft. Monmouth, NJ 07703	Lab. ID # :	4911.02
		Date Rec'd:	11/3/99
		Extraction Date:	11/4/99
		Analysis Date:	11/22/99
Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous.		
Analyst:	T. Frankovich	Field ID:	Field Blank
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army DPW, SELFM-PW-EV Bldg. 173 Ft. Monmouth, NJ 07703	Lab. ID # :	4911.04
		Date Rec'd:	11/3/99
		Extraction Date:	11/4/99
		Analysis Date:	11/22/99
Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous T. Frankovich	Field ID:	0CW2MW30
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 4911.05
Date Rec'd: 11/3/99
Extraction Date: 11/4/99
Analysis Date: 11/22/99

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: 0CW2MW31

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 4911.06
Date Rec'd: 11/3/99
Extraction Date: 11/4/99
Analysis Date: 11/22/99

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: 0CW2MW32

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 4911.07
Date Rec'd: 11/3/99
Extraction Date: 11/4/99
Analysis Date: 11/22/99

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: 0CW2MW33

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army DPW, SELFM-PW-EV Bldg. 173 Ft. Monmouth, NJ 07703	Lab. ID # :	4911.03
		Date Rec'd:	11/3/99
		Extraction Date:	11/4/99
		Analysis Date:	11/22/99
Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	Dupe
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides 2 30m/.32mm ID/.25um

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4911
 Sample Prepared: 11/30/99

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	12/01/99	43.9	200	10.0
Antimony	12/01/99	5.65	20	2.0
Arsenic	12/01/99	ND	8	2.0
Barium	12/01/99	ND	2000	0.5
Beryllium	12/01/99	ND	20	0.5
Cadmium	12/01/99	ND	4	0.5
Calcium	12/01/99	118	NLE	20.0
Chromium	12/01/99	2.78	100	0.5
Cobalt	12/01/99	ND	NLE	0.5
Copper	12/01/99	216	1000	3.0
Iron	12/01/99	42.1	300	10.0
Lead	12/01/99	ND	10	2.0
Magnesium	12/01/99	106	NLE	20.0
Manganese	12/01/99	ND	50	0.5
Mercury	11/19/99	ND	2	0.1
Nickel	12/01/99	3.60	100	0.5
Potassium	12/01/99	838	NLE	20.0
Selenium	12/01/99	ND	50	3.0
Silver	12/01/99	ND	20	3.0
Sodium	12/01/99	369	50000	20.0
Thallium	12/01/99	ND	10	3.0
Vanadium	12/01/99	ND	NLE	1.0
Zinc	12/01/99	22.2	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4911.02
 Sample Received: 11/03/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	12/01/99	ND	200	10.0
Antimony	12/01/99	ND	20	2.0
Arsenic	12/01/99	ND	8	2.0
Barium	12/01/99	ND	2000	0.5
Beryllium	12/01/99	ND	20	0.5
Cadmium	12/01/99	ND	4	0.5
Calcium	12/01/99	65.2	NLE	20.0
Chromium	12/01/99	0.521	100	0.5
Cobalt	12/01/99	ND	NLE	0.5
Copper	12/01/99	ND	1000	3.0
Iron	12/01/99	ND	300	10.0
Lead	12/01/99	ND	10	2.0
Magnesium	12/01/99	ND	NLE	20.0
Manganese	12/01/99	ND	50	0.5
Mercury	11/19/99	ND	2	0.1
Nickel	12/01/99	ND	100	0.5
Potassium	12/01/99	ND	NLE	20.0
Selenium	12/01/99	ND	50	3.0
Silver	12/01/99	ND	20	3.0
Sodium	12/01/99	551	50000	20.0
Thallium	12/01/99	ND	10	3.0
Vanadium	12/01/99	ND	NLE	1.0
Zinc	12/01/99	15.4	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4911.04
 Sample Received: 11/03/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	12/01/99	92.7	200	10.0
Antimony	12/01/99	ND	20	2.0
Arsenic	12/01/99	6.06	8	2.0
Barium	12/01/99	72.7	2000	0.5
Beryllium	12/01/99	ND	20	0.5
Cadmium	12/01/99	ND	4	0.5
Calcium	12/01/99	55300	NLE	20.0
Chromium	12/01/99	2.38	100	0.5
Cobalt	12/01/99	ND	NLE	0.5
Copper	12/01/99	12.4	1000	3.0
Iron	12/01/99	6540	300	10.0
Lead	12/01/99	ND	10	2.0
Magnesium	12/01/99	4300	NLE	20.0
Manganese	12/01/99	36.3	50	0.5
Mercury	11/19/99	0.2	2	0.1
Nickel	12/01/99	2.24	100	0.5
Potassium	12/01/99	8930	NLE	20.0
Selenium	12/01/99	4.01	50	3.0
Silver	12/01/99	ND	20	3.0
Sodium	12/01/99	15400	50000	20.0
Thallium	12/01/99	ND	10	3.0
Vanadium	12/01/99	2.19	NLE	1.0
Zinc	12/01/99	2.24	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4911.05
 Sample Received: 11/03/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	12/01/99	14.9	200	10.0
Antimony	12/01/99	ND	20	2.0
Arsenic	12/01/99	ND	8	2.0
Barium	12/01/99	265	2000	0.5
Beryllium	12/01/99	ND	20	0.5
Cadmium	12/01/99	1.45	4	0.5
Calcium	12/01/99	53400	NLE	20.0
Chromium	12/01/99	ND	100	0.5
Cobalt	12/01/99	ND	NLE	0.5
Copper	12/01/99	3.69	1000	3.0
Iron	12/01/99	64600	300	10.0
Lead	12/01/99	ND	10	2.0
Magnesium	12/01/99	6610	NLE	20.0
Manganese	12/01/99	309	50	0.5
Mercury	11/19/99	ND	2	0.1
Nickel	12/01/99	4.98	100	0.5
Potassium	12/01/99	11600	NLE	20.0
Selenium	12/01/99	ND	50	3.0
Silver	12/01/99	ND	20	3.0
Sodium	12/01/99	12500	50000	20.0
Thallium	12/01/99	ND	10	3.0
Vanadium	12/01/99	ND	NLE	1.0
Zinc	12/01/99	35.5	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4911.06
 Sample Received: 11/03/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	12/01/99	162	200	10.0
Antimony	12/01/99	ND	20	2.0
Arsenic	12/01/99	4.09	8	2.0
Barium	12/01/99	61.7	2000	0.5
Beryllium	12/01/99	ND	20	0.5
Cadmium	12/01/99	0.837	4	0.5
Calcium	12/01/99	95100	NLE	20.0
Chromium	12/01/99	3.64	100	0.5
Cobalt	12/01/99	ND	NLE	0.5
Copper	12/01/99	44.9	1000	3.0
Iron	12/01/99	11500	300	10.0
Lead	12/01/99	ND	10	2.0
Magnesium	12/01/99	9380	NLE	20.0
Manganese	12/01/99	27.0	50	0.5
Mercury	11/19/99	ND	2	0.1
Nickel	12/01/99	4.57	100	0.5
Potassium	12/01/99	4990	NLE	20.0
Selenium	12/01/99	5.66	50	3.0
Silver	12/01/99	ND	20	3.0
Sodium	12/01/99	21000	50000	20.0
Thallium	12/01/99	ND	10	3.0
Vanadium	12/01/99	4.91	NLE	1.0
Zinc	12/01/99	41.1	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4911.07
 Sample Received: 11/03/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	12/01/99	52.8	200	10.0
Antimony	12/01/99	ND	20	2.0
Arsenic	12/01/99	ND	8	2.0
Barium	12/01/99	46.7	2000	0.5
Beryllium	12/01/99	ND	20	0.5
Cadmium	12/01/99	1.38	4	0.5
Calcium	12/01/99	18100	NLE	20.0
Chromium	12/01/99	1.30	100	0.5
Cobalt	12/01/99	ND	NLE	0.5
Copper	12/01/99	3.98	1000	3.0
Iron	12/01/99	19500	300	10.0
Lead	12/01/99	ND	10	2.0
Magnesium	12/01/99	3260	NLE	20.0
Manganese	12/01/99	47.2	50	0.5
Mercury	11/19/99	ND	2	0.1
Nickel	12/01/99	2.75	100	0.5
Potassium	12/01/99	3490	NLE	20.0
Selenium	12/01/99	ND	50	3.0
Silver	12/01/99	ND	20	3.0
Sodium	12/01/99	8950	50000	20.0
Thallium	12/01/99	ND	10	3.0
Vanadium	12/01/99	ND	NLE	1.0
Zinc	12/01/99	20.8	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established
 * Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 4911.03
 Sample Received: 11/03/99
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	12/01/99	157	200	10.0
Antimony	12/01/99	ND	20	2.0
Arsenic	12/01/99	3.19	8	2.0
Barium	12/01/99	56.1	2000	0.5
Beryllium	12/01/99	ND	20	0.5
Cadmium	12/01/99	0.601	4	0.5
Calcium	12/01/99	92500	NLE	20.0
Chromium	12/01/99	3.27	100	0.5
Cobalt	12/01/99	ND	NLE	0.5
Copper	12/01/99	47.9	1000	3.0
Iron	12/01/99	8980	300	10.0
Lead	12/01/99	ND	10	2.0
Magnesium	12/01/99	9280	NLE	20.0
Manganese	12/01/99	21.0	50	0.5
Mercury	11/19/99	ND	2	0.1
Nickel	12/01/99	3.13	100	0.5
Potassium	12/01/99	4750	NLE	20.0
Selenium	12/01/99	5.69	50	3.0
Silver	12/01/99	ND	20	3.0
Sodium	12/01/99	20900	50000	20.0
Thallium	12/01/99	ND	10	3.0
Vanadium	12/01/99	4.28	NLE	1.0
Zinc	12/01/99	29.4	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	9100	69	-	-	-	6.45				V,S,P,M
07/10/97	FMETL	12590	73	25	5.0	ND	7.05				V,S,P,M
10/22/97	FMETL	34800	171	175	5.0	5.0	7.60				V,S,P,M
01/08/98	FMETL	2795	5.0	204	ND	4.0	5.20				V,S,P,M
04/07/98	FMETL	3504	39.3	196	5.6	ND	6.56				V,S,P,M
07/14/98	FMETL	10900	57.8	65.7	ND	ND	6.89				V,S,P,M
11/24/98	FMETL	27500	182	ND	11.5	3.15	7.86				V,S,P,M
02/11/99	FMETL	11000	100	505	8.3	ND	7.24				V,S,P,M
06/09/99	FMETL	8210	145	521	6.33	ND	7.21				V,S,P,M
08/04/99	FMETL	44800	212	304	9.05	6.02	7.43				V,S,P,M
11/03/99	FMETL	6540	36.3	92.7	6.06	ND	7.02				V,S,P,M

SOURCE: 0CW2MW30

Sampling Dates:
04/24/97 - 11/03/99

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW30

Sampling Dates:
04/24/97 - 11/03/99

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	59900	277	-	-	-	6.38				V,S,P,M
07/10/97	FMETL	11830	267	ND	1.0	ND	7.00				V,S,P,M
10/22/97	FMETL	52300	243	93	ND	6.0	7.50				V,S,P,M
01/08/98	FMETL	68450	240	129	ND	25	6.30				V,S,P,M
04/07/98	FMETL	115100	266	ND	ND	ND	6.35				V,S,P,M
07/14/98	FMETL	83600	311	390	ND	4.85	6.71				V,S,P,M
11/24/98	FMETL	72800	322	ND	ND	2.33	7.78				V,S,P,M
02/11/99	FMETL	71900	316	ND	ND	ND	7.07				V,S,P,M
06/09/99	FMETL	104000	326	27.9	ND	ND	7.15				V,S,P,M
08/04/99	FMETL	77500	347	ND	ND	ND	7.65				V,S,P,M
11/03/99	FMETL	64600	309	14.9	ND	ND	7.18				V,S,P,M

SOURCE: 0CW2MW31

Sampling Dates:
04/24/97 - 11/03/99

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW31

Sampling Dates:
04/24/97 - 11/03/99

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	18400	125	-	-	-	6.65				V,S,P,M
07/10/97	FMETL	270	181	595	ND	ND	7.20				V,S,P,M
10/22/97	FMETL	51100	260	297	ND	7.0	7.70				V,S,P,M
01/08/98	FMETL	1484	3.7	163	ND	ND	4.50				V,S,P,M
04/07/98	FMETL	19280	287	ND	ND	ND	6.81				V,S,P,M
07/14/98	FMETL	67500	287	78.1	2.51	3.99	7.06				V,S,P,M
11/24/98	FMETL	106000	342	166	9.32	4.08	7.94				V,S,P,M
02/11/99	FMETL	4480	7.02	137	ND	ND	7.33				V,S,P,M
06/09/99	FMETL	64300	310	59.5	ND	ND	7.49				V,S,P,M
08/04/99	FMETL	76000	369	67.4	ND	ND	7.85				V,S,P,M
11/03/99	FMETL	11500	27	162	4.09	ND	6.53				V,S,P,M

SOURCE: 0CW2MW32

Sampling Dates:
04/24/97 - 11/03/99

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW32

Sampling Dates:
04/24/97 - 11/03/99

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/97	FMETL	88600	424	-	-	-	8.95				V,S,P,M
07/10/97	FMETL	10260	519	2.1	1.0	ND	9.10				V,S,P,M
10/22/97	FMETL	26800	151	94	ND	4.0	9.10				V,S,P,M
01/08/98	FMETL	104700	342	217	6.0	4.0	9.00				V,S,P,M
04/07/98	FMETL	19780	110	119	3.4	ND	9.50				V,S,P,M
07/14/98	FMETL	35900	130	411	ND	4.19	9.09				V,S,P,M
11/24/98	FMETL	25400	87.8	125	ND	ND	9.13				V,S,P,M
02/11/99	FMETL	11300	81.2	67.8	ND	ND	8.13				V,S,P,M
06/09/99	FMETL	69600	214	336	5.82	ND	9.13				V,S,P,M
08/04/99	FMETL	35900	149	69	8	3.25	9.15				V,S,P,M
11/03/99	FMETL	19500	47.2	52.8	ND	ND	6.14				V,S,P,M

SOURCE: 0CW2MW33

Sampling Dates:
04/24/97 - 11/03/99

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW33

Sampling Dates:
04/24/97 - 11/03/99

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works

Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
5175.04	0CW2MW30	29-32594	02/15/00
5175.05	0CW2MW31	29-32595	02/15/00
5175.06	0CW2MW32	29-32596	02/15/00
5175.07	0CW2MW33	29-32597	02/15/00

NJDEP Laboratory Certification # 13461


Daniel Wright/Date. 4-6-00
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST	Standard Methods, 18 th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B
TARGET COMPOUND LIST	Federal Register 40 CFR Part 136 Appendix A
Base/Neutrals and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticides and PCB's by GC	608



Fort Monmouth Environmental Testing Laboratory


Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (732)532-4359 Fax (732)532-6263 EMail:appleby@mail1.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: <u>J. Fallon</u>		Project No:		Analysis Parameters								Comments:		
Phone #: <u>X26223</u>		Location: <u>CW2 wells</u>										<u>HCL/HNO₃/24°C</u>		
X)DERA ()OMA ()Other:		<u>1st Qtr '00</u>												
Samplers Name / Company: <u>Corey McCormack, TVS</u>				Sample #									Remarks / Preservation Method	
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles	VOTIS	Pest/PAH	BNA+PS	TALMTIS					
<u>5175.01</u>	<u>Trip</u>	<u>2/15/00</u>	<u>0731</u>	<u>AQ</u>	<u>2</u>	<u>✓</u>							<u>—</u>	
<u>.02</u>	<u>Field Blank</u>		<u>0915</u>		<u>5</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>				<u>—</u>	
<u>.03</u>	<u>Dupe</u>		<u>—</u>		<u>5</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>				<u>—</u>	
<u>.04</u>	<u>OCW2 MW 30</u>		<u>1101</u>		<u>9</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>—</u>				<u>0.0</u>	<u>29-32594</u>
<u>.05</u>	<u>OCW2 MW 30</u>		<u>0950</u>		<u>5</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>—</u>				<u>0.0</u>	<u>29-32595</u>
<u>.06</u>	<u>OCW2 MW 32</u>		<u>0949</u>		<u>5</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>—</u>				<u>0.0</u>	<u>29-32596</u>
<u>.07</u>	<u>OCW2 MW 33</u>	<u>✓</u>	<u>0924</u>	<u>✓</u>	<u>5</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>—</u>				<u>0.0</u>	<u>29-32597</u>
Relinquished by (signature): <u>Corey McCormack</u> Date/Time: <u>2/15/00 1430</u> Received by (signature): <u>J. Appleby</u> Relinquished by (signature): Date/Time: Received by (signature):														
Relinquished by (signature): Date/Time: Received by (signature): Relinquished by (signature): Date/Time: Received by (signature):														
Report Type: () Full, () Reduced, <u>X</u> Standard, () Screen / non-certified														
Turnaround time: <u>X</u> Standard 3 wks, () Rush Days, () ASAP Verbal Hrs.														
Remarks: <u>Shows Trip/FB/Dupe w/ CW34 See date, cpm</u> <u>Tide: N/A</u>														



2337MW1

CORREGIDOR

2525

2543

2542-A

2542

2536

2702

2610
2611
2612
2613
2614
2615
2616
2617
2618
2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630
2631
2632
2633
2634
2635
2636
2637
2638
2639
2640
2641
2642
2643
2644
2645
2646
2647
2648
2649
2650
2651
2652
2653
2654
2655
2656
2657
2658
2659
2660
2661
2662
2663
2664
2665
2666
2667
2668
2669
2670
2671
2672
2673
2674
2675
2676
2677
2678
2679
2680
2681
2682
2683
2684
2685
2686
2687
2688
2689
2690
2691
2692
2693
2694
2695
2696
2697
2698
2699
2700
2701
2702
2703
2704
2705
2706
2707
2708
2709
2710
2711
2712
2713
2714
2715
2716
2717
2718
2719
2720
2721
2722
2723
2724
2725
2726
2727
2728
2729
2730
2731
2732
2733
2734
2735
2736
2737
2738
2739
2740
2741
2742
2743
2744
2745
2746
2747
2748
2749
2750
2751
2752
2753
2754
2755
2756
2757
2758
2759
2760
2761
2762
2763
2764
2765
2766
2767
2768
2769
2770
2771
2772
2773
2774
2775
2776
2777
2778
2779
2780
2781
2782
2783
2784
2785
2786
2787
2788
2789
2790
2791
2792
2793
2794
2795
2796
2797
2798
2799
2800

2700.216

2700

2700

2706

2700.4

2715

2610
2611
2612
2613
2614
2615
2616
2617
2618
2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630
2631
2632
2633
2634
2635
2636
2637
2638
2639
2640
2641
2642
2643
2644
2645
2646
2647
2648
2649
2650
2651
2652
2653
2654
2655
2656
2657
2658
2659
2660
2661
2662
2663
2664
2665
2666
2667
2668
2669
2670
2671
2672
2673
2674
2675
2676
2677
2678
2679
2680
2681
2682
2683
2684
2685
2686
2687
2688
2689
2690
2691
2692
2693
2694
2695
2696
2697
2698
2699
2700
2701
2702
2703
2704
2705
2706
2707
2708
2709
2710
2711
2712
2713
2714
2715
2716
2717
2718
2719
2720
2721
2722
2723
2724
2725
2726
2727
2728
2729
2730
2731
2732
2733
2734
2735
2736
2737
2738
2739
2740
2741
2742
2743
2744
2745
2746
2747
2748
2749
2750
2751
2752
2753
2754
2755
2756
2757
2758
2759
2760
2761
2762
2763
2764
2765
2766
2767
2768
2769
2770
2771
2772
2773
2774
2775
2776
2777
2778
2779
2780
2781
2782
2783
2784
2785
2786
2787
2788
2789
2790
2791
2792
2793
2794
2795
2796
2797
2798
2799
2800

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 02/15/00
WEATHER: Sunny, cold.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.71 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.02 ft
DEPTH OF WELL: 17.95 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 10.93 ft
(10.93) X .65 X 3 = 21.31
GALLONS OF H2O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:29

pH 6.81 su

DISSOLVED O2 5.89 ppm

TEMP 12.7 °C

SPECIFIC CONDUCTIVITY 113 us/cm

PURGE END TIME: 11:00

pH 6.83 su

DISSOLVED O2 5.04 ppm

TEMP 12.6 °C

SPECIFIC CONDUCTIVITY 113 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.27 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 21 gal

SAMPLE START TIME: 11:01

pH 6.83 su

DISSOLVED O2 5.02 ppm

TEMP 12.6 °C

SPECIFIC CONDUCTIVITY 113 us/cm

SAMPLE END TIME: 11:05

COMMENTS: MS/MSD here.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 02/15/00
WEATHER: Sunny, cold.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.88 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.03 ft
DEPTH OF WELL: 16.91 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 9.88 ft
(9.88) X .65 X 3 = 19.26
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:26

pH 6.79 su

DISSOLVED O2 6.01 ppm

TEMP 12.7 °C

SPECIFIC CONDUCTIVITY 95 us/cm

PURGE END TIME: 09:49

pH 6.83 su

DISSOLVED O2 5.31 ppm

TEMP 12.5 °C

SPECIFIC CONDUCTIVITY 96 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 8.34 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 09:50

pH 6.84 su

DISSOLVED O2 5.30 ppm

TEMP 12.5 °C

SPECIFIC CONDUCTIVITY 96 us/cm

SAMPLE END TIME: 09:55

COMMENTS: DUP. Here. Orange tinge, particles increased while bailing.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 02/15/00
WEATHER: Sunny, cold.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.38 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 6.54 ft
DEPTH OF WELL: 16.89 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 10.35 ft
(10.35) X .65 X 3 = 20.18
GALLONS OF H2O TO BE PURGED: 20 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:15

pH 6.79 su

DISSOLVED O2 5.98 ppm

TEMP 12.5 °C

SPECIFIC CONDUCTIVITY 100 us/cm

PURGE END TIME: 09:48

pH 6.80 su

DISSOLVED O2 5.03 ppm

TEMP 12.4 °C

SPECIFIC CONDUCTIVITY 98 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 10.96 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 20 gal

SAMPLE START TIME: 09:49

pH 6.82 su

DISSOLVED O2 5.03 ppm

TEMP 12.4 °C

SPECIFIC CONDUCTIVITY 99 us/cm

SAMPLE END TIME: 09:55

COMMENTS: DUP. Here. Orange tinge, particles.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW33
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 02/15/00
WEATHER: Sunny, cold.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.09 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 9.09 ft
DEPTH OF WELL: 16.10 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 7.01 ft
(7.01) X .65 X 3 = 13.66
GALLONS OF H2O TO BE PURGED: 14 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:22
pH 6.77 su
DISSOLVED O2 6.11 ppm
TEMP 12.7 °C
SPECIFIC CONDUCTIVITY 111 us/cm

PURGE END TIME: 09:23
pH 6.76 su
DISSOLVED O2 5.23 ppm
TEMP 12.6 °C
SPECIFIC CONDUCTIVITY 110 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.49 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 14 gal

SAMPLE START TIME: 09:24
pH 6.74 su
DISSOLVED O2 5.21 ppm
TEMP 12.4 °C
SPECIFIC CONDUCTIVITY 111 us/cm

SAMPLE END TIME: 09:28

COMMENTS: DUP. Here. Orange tinge, particles while bailing.

**US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEP CERTIFICATION # 13461**

Definition of Qualifiers

MDL : Method Detection Limit
J : Compound Identified Below Detection Limit
B : Compound is in Both Sample and Blank
D : Results are from a Dilution of the Sample
U : Compound Searched for but not Detected
E : Compound Exceeds Calibration Limit

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC002129.D**
 Operator **Skelton**
 Date Acquired **16 Feb 2000 1:34 pm**

Sample Name **Vblk58**
 Field ID **Vblk58**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75343	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156594	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Vblk58

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 5175 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: Vblk58

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC002129.D

Level: (low/med) LOW Date Received: 2/15/00

% Moisture: not dec. _____ Date Analyzed: 2/16/00

GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC002146.D**
 Operator **Skelton**
 Date Acquired **17 Feb 2000 2:02 am**

Sample Name **5175.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75343	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156594	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform	16.22	122541	3.06 ug/L	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Trip Blank

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 5175 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5175.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC002146.D
Level: (low/med) LOW Date Received: 2/15/00
% Moisture: not dec. _____ Date Analyzed: 2/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC002147.D**
 Operator **Skelton**
 Date Acquired **17 Feb 2000 2:42 am**

Sample Name **5175.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75343	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156594	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform	16.22	121037	3.01 ug/L	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Field Blank

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 5175 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5175.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC002147.D
Level: (low/med) LOW Date Received: 2/15/00
% Moisture: not dec. _____ Date Analyzed: 2/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC002148.D**
 Operator **Skelton**
 Date Acquired **17 Feb 2000 3:23 am**

Sample Name **5175.03**
 Field ID **Dupe**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75343	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156594	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Dupe

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 5175 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5175.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC002148.D
Level: (low/med) LOW Date Received: 2/15/00
% Moisture: not dec. _____ Date Analyzed: 2/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File VC002149.D
 Operator Skelton
 Date Acquired 17 Feb 2000 4:04 am

Sample Name 5175.04
 Field ID 0CW2MW30
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75343	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156594	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

0CW2MW30

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 5175 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5175.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC002149.D
Level: (low/med) LOW Date Received: 2/15/00
% Moisture: not dec. _____ Date Analyzed: 2/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File VC002150.D
 Operator Skelton
 Date Acquired 17 Feb 2000 4:45 am

Sample Name 5175.05
 Field ID 0CW2MW31
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75343	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156594	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range -
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

0CW2MW31

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 5175 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5175.05

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC002150.D

Level: (low/med) LOW Date Received: 2/15/00

% Moisture: not dec. _____ Date Analyzed: 2/17/00

GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC002151.D**
 Operator **Skelton**
 Date Acquired **17 Feb 2000 5:26 am**

Sample Name **5175.06**
 Field ID **0CW2MW32**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75343	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156594	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

0CW2MW32

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 5175 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5175.06

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC002151.D

Level: (low/med) LOW Date Received: 2/15/00

% Moisture: not dec. _____ Date Analyzed: 2/17/00

GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VC002152.D**
 Operator **Skelton**
 Date Acquired **17 Feb 2000 6:07 am**

Sample Name **5175.07**
 Field ID **0CW2MW33**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75343	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone	8.86	143659	9.26 ug/L	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156594	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-35-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

0CW2MW33

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 5175 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5175.07

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC002152.D

Level: (low/med) LOW Date Received: 2/15/00

% Moisture: not dec. _____ Date Analyzed: 2/17/00

GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03639.D**
 Operator **Bhaskar**
 Date Acquired **18-Feb-00**

Sample Name **Sblk344**
 Misc Info **Sblk344**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03639.D**
 Operator **Bhaskar**
 Date Acquired **18-Feb-00**

Sample Name **Sblk344**
 Misc Info **Sblk344**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Sblk344

Lab Name: FMETL Lab Code 13461

Project 100004 Case No.: 5175 Location CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: Sblk344

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03639.D

Level: (low/med) LOW Date Received: 2/15/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 2/17/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/18/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.07	4	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03641.D**
 Operator **Bhaskar**
 Date Acquired **18-Feb-00**

Sample Name **5175.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03641.D**
 Operator **Bhaskar**
 Date Acquired **18-Feb-00**

Sample Name **5175.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Field Blank

Lab Name: FMETL Lab Code 13461

Project 100004 Case No.: 5175 Location CW2 SDG No.:

Matrix: (soil/water) WATER Lab Sample ID: 5175.02

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03641.D

Level: (low/med) LOW Date Received: 2/15/00

% Moisture: decanted: (Y/N) N Date Extracted: 2/17/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/18/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.07	4	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03642.D**
 Operator **Bhaskar**
 Date Acquired **18-Feb-00**

Sample Name **5175.03**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BNA03642.D
Operator Bhaskar
Date Acquired 18-Feb-00

Sample Name 5175.03
Misc Info Dupe
Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzof[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
D= Value from dilution
B= Compound in Related Blank
PQL= Practical Quantitation Limit

MDL= Method Detection Limit
NLE= No Limit Established
R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

Dupe

Lab Name: FMETL Lab Code 13461

Project 100004 Case No.: 5175 Location CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5175.03

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03642.D

Level: (low/med) LOW Date Received: 2/15/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 2/17/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/18/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.07	5	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03643.D**
 Operator **Bhaskar**
 Date Acquired **18-Feb-00**

Sample Name **5175.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03643.D**
 Operator **Bhaskar**
 Date Acquired **18-Feb-00**

Sample Name **5175.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW30

Lab Name: FMETL Lab Code 13461

Project 100004 Case No.: 5175 Location CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5175.04

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03643.D

Level: (low/med) LOW Date Received: 2/15/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 2/17/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/18/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.07	5	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03646.D**
 Operator **Bhaskar**
 Date Acquired **19-Feb-00**

Sample Name **5175.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03646.D**
Operator **Bhaskar**
Date Acquired **19-Feb-00**

Sample Name **5175.05**
Misc Info **0CW2MW31**
Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
D= Value from dilution
B= Compound in Related Blank
PQL= Practical Quantitation Limit

MDL= Method Detection Limit
NLE= No Limit Established
R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW31

Lab Name: FMETL Lab Code 13461
Project 100004 Case No.: 5175 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5175.05
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03646.D
Level: (low/med) LOW Date Received: 2/15/00
% Moisture: decanted: (Y/N) N Date Extracted: 2/17/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/19/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.07	4	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03647.D**
 Operator **Bhaskar**
 Date Acquired **19-Feb-00**

Sample Name **5175.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03647.D**
 Operator **Bhaskar**
 Date Acquired **19-Feb-00**

Sample Name **5175.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW32

Lab Name: FMETL Lab Code 13461
Project 100004 Case No.: 5175 Location CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5175.06
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03647.D
Level: (low/med) LOW Date Received: 2/15/00
% Moisture: decanted: (Y/N) N Date Extracted: 2/17/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/19/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.07	5	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03648.D**
 Operator **Bhaskar**
 Date Acquired **19-Feb-00**

Sample Name **5175.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03648.D**
 Operator **Bhaskar**
 Date Acquired **19-Feb-00**

Sample Name **5175.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID

0CW2MW33

Lab Name: FMETL Lab Code 13461
Project 100004 Case No.: 5175 Location CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5175.07
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03648.D
Level: (low/med) LOW Date Received: 2/15/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 2/17/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 2/19/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.07	5	J
2.	unknown	8.39	10	J
3.	unknown	11.94	4	J

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : BLK472
Date Rec'd:
Extraction Date: 2/18/00
Analysis Date: 2/29/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location :

Field ID:

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

PQL = Practical Quantitation Limit

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg: 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5175.03
Date Rec'd: 2/15/00
Extraction Date: 2/18/00
Analysis Date: 2/29/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 Wells
Field ID: Dupe

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	5175.04
	DPW. SELFM-PW-EV	Date Rec'd:	2/15/00
	Bldg. 173	Extraction Date:	2/18/00
	Ft. Monmouth, NJ 07703	Analysis Date:	2/29/00

Analysis:	EPA Method 608	Location :	CW2 Wells
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	0CW2MW30
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army Lab. ID # : 5175.06
DPW, SELFM-PW-EV Date Rec'd: 2/15/00
Bldg. 173 Extraction Date: 2/18/00
Ft. Monmouth, NJ 07703 Analysis Date: 2/29/00

Analysis: EPA Method 608 Location : CW2 Wells
Matrix: Aqueous
Analyst: T. Frankovich Field ID: 0CW2MW32
Ext. Meth: Sep. Funnel

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides 2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg: 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5175.07
Date Rec'd: 2/15/00
Extraction Date: 2/18/00
Analysis Date: 2/29/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 Wells
Field ID: 0CW2MW33

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0030	ND
beta-BHC	1		0.20	0.0024	ND
gamma-BHC	1		0.20	0.0015	ND
delta-BHC	1		NLE	0.0019	ND
Heptachlor	1		0.40	0.0020	ND
Aldrin	1		0.04	0.0010	ND
Heptachlor Epoxide	1		0.20	0.0009	ND
Endosulfan I	1		0.40	0.0057	ND
4,4'-DDE	1		0.10	0.0009	ND
Dieldrin	1		0.03	0.0016	ND
Endrin	1		2.00	0.0020	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0033	ND
4,4'-DDD	1		0.10	0.0022	ND
4,4'-DDT	1		0.10	0.0013	ND
Endosulfan-Sulfate	1		0.40	0.0027	ND
Methoxychlor	1		40.00	0.0038	ND
Alpha-chlordane	1		0.50	0.0011	ND
Gamma-chlordane	1		0.50	0.0009	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0640	ND
Arochlor 1221	1		0.50	0.0500	ND
Arochlor 1232	1		0.50	0.0500	ND
Arochlor 1242	1		0.50	0.0280	ND
Arochlor 1248	1		0.50	0.0500	ND
Arochlor 1254	1		0.50	0.0500	ND
Arochlor 1260	1		0.50	0.0680	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

MDL = Method Detection Limit

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

NLE = No Limit Established

PQL = Practical Quantitation Limit

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5175
 Sample Prepared: 03/28/00

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	03/29/00	ND	200	10.0
Antimony	03/29/00	ND	20	2.0
Arsenic	03/29/00	ND	8	2.0
Barium	03/29/00	ND	2000	0.5
Beryllium	03/29/00	ND	20	0.5
Cadmium	03/29/00	ND	4	0.5
Calcium	03/29/00	80.1	NLE	20.0
Chromium	03/29/00	ND	100	0.5
Cobalt	03/29/00	ND	NLE	0.5
Copper	03/29/00	ND	1000	3.0
Iron	03/29/00	23.3	300	10.0
Lead	03/29/00	ND	10	2.0
Magnesium	03/29/00	28.3	NLE	20.0
Manganese	03/29/00	ND	50	0.5
Mercury	02/23/00	ND	2	0.1
Nickel	03/29/00	ND	100	0.5
Potassium	03/29/00	171	NLE	20.0
Selenium	03/29/00	ND	50	3.0
Silver	03/29/00	ND	20	3.0
Sodium	03/29/00	1030	50000	20.0
Thallium	03/29/00	ND	10	3.0
Vanadium	03/29/00	ND	NLE	1.0
Zinc	03/29/00	55.3	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5175.02
 Sample Received: 02/15/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	03/29/00	ND	200	10.0
Antimony	03/29/00	ND	20	2.0
Arsenic	03/29/00	ND	8	2.0
Barium	03/29/00	ND	2000	0.5
Beryllium	03/29/00	ND	20	0.5
Cadmium	03/29/00	ND	4	0.5
Calcium	03/29/00	ND	NLE	20.0
Chromium	03/29/00	ND	100	0.5
Cobalt	03/29/00	ND	NLE	0.5
Copper	03/29/00	ND	1000	3.0
Iron	03/29/00	ND	300	10.0
Lead	03/29/00	ND	10	2.0
Magnesium	03/29/00	ND	NLE	20.0
Manganese	03/29/00	ND	50	0.5
Mercury	02/23/00	ND	2	0.1
Nickel	03/29/00	ND	100	0.5
Potassium	03/29/00	20.5	NLE	20.0
Selenium	03/29/00	ND	50	3.0
Silver	03/29/00	ND	20	3.0
Sodium	03/29/00	152	50000	20.0
Thallium	03/29/00	ND	10	3.0
Vanadium	03/29/00	ND	NLE	1.0
Zinc	03/29/00	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5175.03
 Sample Received: 02/15/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	03/29/00	53.1	200	10.0
Antimony	03/29/00	ND	20	2.0
Arsenic	03/29/00	ND	8	2.0
Barium	03/29/00	268	2000	0.5
Beryllium	03/29/00	ND	20	0.5
Cadmium	03/29/00	ND	4	0.5
Calcium	03/29/00	52800	NLE	20.0
Chromium	03/29/00	ND	100	0.5
Cobalt	03/29/00	ND	NLE	0.5
Copper	03/29/00	ND	1000	3.0
Iron	03/29/00	112000	300	10.0
Lead	03/29/00	ND	10	2.0
Magnesium	03/29/00	6550	NLE	20.0
Manganese	03/29/00	297	50	0.5
Mercury	02/23/00	0.3	2	0.1
Nickel	03/29/00	ND	100	0.5
Potassium	03/29/00	9270	NLE	20.0
Selenium	03/29/00	ND	50	3.0
Silver	03/29/00	ND	20	3.0
Sodium	03/29/00	11700	50000	20.0
Thallium	03/29/00	ND	10	3.0
Vanadium	03/29/00	ND	NLE	1.0
Zinc	03/29/00	21.9	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5175.04
 Sample Received: 02/15/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	03/29/00	20.4	200	10.0
Antimony	03/29/00	ND	20	2.0
Arsenic	03/29/00	ND	8	2.0
Barium	03/29/00	24.3	2000	0.5
Beryllium	03/29/00	ND	20	0.5
Cadmium	03/29/00	ND	4	0.5
Calcium	03/29/00	28700	NLE	20.0
Chromium	03/29/00	ND	100	0.5
Cobalt	03/29/00	ND	NLE	0.5
Copper	03/29/00	7.24	1000	3.0
Iron	03/29/00	1840	300	10.0
Lead	03/29/00	ND	10	2.0
Magnesium	03/29/00	2480	NLE	20.0
Manganese	03/29/00	2.69	50	0.5
Mercury	02/23/00	0.3	2	0.1
Nickel	03/29/00	0.599	100	0.5
Potassium	03/29/00	5440	NLE	20.0
Selenium	03/29/00	ND	50	3.0
Silver	03/29/00	ND	20	3.0
Sodium	03/29/00	15700	50000	20.0
Thallium	03/29/00	ND	10	3.0
Vanadium	03/29/00	1.58	NLE	1.0
Zinc	03/29/00	5.75	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5175.05
 Sample Received: 02/15/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	03/29/00	11.7	200	10.0
Antimony	03/29/00	ND	20	2.0
Arsenic	03/29/00	ND	8	2.0
Barium	03/29/00	264	2000	0.5
Beryllium	03/29/00	ND	20	0.5
Cadmium	03/29/00	ND	4	0.5
Calcium	03/29/00	53600	NLE	20.0
Chromium	03/29/00	1.08	100	0.5
Cobalt	03/29/00	ND	NLE	0.5
Copper	03/29/00	14.0	1000	3.0
Iron	03/29/00	111000	300	10.0
Lead	03/29/00	ND	10	2.0
Magnesium	03/29/00	6660	NLE	20.0
Manganese	03/29/00	301	50	0.5
Mercury	02/23/00	0.4	2	0.1
Nickel	03/29/00	ND	100	0.5
Potassium	03/29/00	9400	NLE	20.0
Selenium	03/29/00	ND	50	3.0
Silver	03/29/00	ND	20	3.0
Sodium	03/29/00	12100	50000	20.0
Thallium	03/29/00	ND	10	3.0
Vanadium	03/29/00	ND	NLE	1.0
Zinc	03/29/00	10.8	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5175.06
 Sample Received: 02/15/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	03/29/00	95.7	200	10.0
Antimony	03/29/00	ND	20	2.0
Arsenic	03/29/00	ND	8	2.0
Barium	03/29/00	70.0	2000	0.5
Beryllium	03/29/00	ND	20	0.5
Cadmium	03/29/00	ND	4	0.5
Calcium	03/29/00	76600	NLE	20.0
Chromium	03/29/00	1.98	100	0.5
Cobalt	03/29/00	ND	NLE	0.5
Copper	03/29/00	25.5	1000	3.0
Iron	03/29/00	11300	300	10.0
Lead	03/29/00	ND	10	2.0
Magnesium	03/29/00	8120	NLE	20.0
Manganese	03/29/00	53.9	50	0.5
Mercury	02/23/00	0.2	2	0.1
Nickel	03/29/00	2.21	100	0.5
Potassium	03/29/00	6220	NLE	20.0
Selenium	03/29/00	3.74	50	3.0
Silver	03/29/00	ND	20	3.0
Sodium	03/29/00	27500	50000	20.0
Thallium	03/29/00	ND	10	3.0
Vanadium	03/29/00	3.69	NLE	1.0
Zinc	03/29/00	29.2	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5175.07
 Sample Received: 02/15/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	03/29/00	96.2	200	10.0
Antimony	03/29/00	ND	20	2.0
Arsenic	03/29/00	2.67	8	2.0
Barium	03/29/00	159	2000	0.5
Beryllium	03/29/00	ND	20	0.5
Cadmium	03/29/00	ND	4	0.5
Calcium	03/29/00	45500	NLE	20.0
Chromium	03/29/00	1.45	100	0.5
Cobalt	03/29/00	ND	NLE	0.5
Copper	03/29/00	ND	1000	3.0
Iron	03/29/00	54400	300	10.0
Lead	03/29/00	3.77	10	2.0
Magnesium	03/29/00	5340	NLE	20.0
Manganese	03/29/00	201	50	0.5
Mercury	02/23/00	ND	2	0.1
Nickel	03/29/00	1.80	100	0.5
Potassium	03/29/00	8500	NLE	20.0
Selenium	03/29/00	ND	50	3.0
Silver	03/29/00	ND	20	3.0
Sodium	03/29/00	14800	50000	20.0
Thallium	03/29/00	ND	10	3.0
Vanadium	03/29/00	ND	NLE	1.0
Zinc	03/29/00	11.5	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	9100	69	ND	ND	ND	6.45				V,S,P,M
07/10/1997	FMETL	12590	73	25	5.0	ND	7.05				V,S,P,M
10/22/1997	FMETL	34800	171	175	5.0	5.0	7.60				V,S,P,M
01/08/1998	FMETL	2795	5.0	204	ND	4.0	5.20				V,S,P,M
04/07/1998	FMETL	3504	39.3	196	5.6	ND	6.56				V,S,P,M
07/14/1998	FMETL	10900	57.8	65.7	ND	ND	6.89				V,S,P,M
11/24/1998	FMETL	27500	182	ND	11.5	3.15	7.86				V,S,P,M
02/11/1999	FMETL	11000	100	505	8.3	ND	7.24				V,S,P,M
06/09/1999	FMETL	8210	145	521	6.33	ND	7.21				V,S,P,M
08/04/1999	FMETL	44800	212	304	9.05	6.02	7.43				V,S,P,M
11/03/1999	FMETL	6540	36.3	92.7	6.06	ND	7.02				V,S,P,M
02/15/2000	FMETL	1840	2.69	20.4	ND	ND	7.02				V,S,P,M

SOURCE: 0CW2MW30

Sampling Dates:
04/24/1997 - 02/15/2000

NOTES:

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4

 U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

SOURCE: 0CW2MW30

Sampling Dates:
04/24/1997 - 02/15/2000

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 1 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)









Lead
(ug/l)



Depth to Water
(Feet)





SOURCE: 0CW2MW31

Sampling Dates:
04/24/1997 - 02/15/2000

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	18400	125	ND	ND	ND	6.65				V,S,P,M
07/10/1997	FMETL	270	181	595	ND	ND	7.20				V,S,P,M
10/22/1997	FMETL	51100	260	297	ND	7.0	7.70				V,S,P,M
01/08/1998	FMETL	1484	3.7	163	ND	ND	4.50				V,S,P,M
04/07/1998	FMETL	19280	287	ND	ND	ND	6.81				V,S,P,M
07/14/1998	FMETL	67500	287	78.1	2.51	3.99	7.06				V,S,P,M
11/24/1998	FMETL	106000	342	166	9.32	4.08	7.94				V,S,P,M
02/11/1999	FMETL	4480	7.02	137	ND	ND	7.33				V,S,P,M
06/09/1999	FMETL	64300	310	59.5	ND	ND	7.49				V,S,P,M
08/04/1999	FMETL	76000	369	67.4	ND	ND	7.85				V,S,P,M
11/03/1999	FMETL	11500	27	162	4.09	ND	6.53				V,S,P,M
02/15/2000	FMETL	11300	53.9	95.7	ND	ND	6.54				V,S,P,M
02/15/2000D	FMETL	112000	297	53.1	ND	ND	6.54				V,S,P,M

SOURCE: 0CW2MW32

Sampling Dates:
04/24/1997 - 02/15/2000

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW32

Sampling Dates:
04/24/1997 - 02/15/2000

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	88600	424	ND	ND	ND	8.95				V,S,P,M
07/10/1997	FMETL	10260	519	2.1	1.0	ND	9.10				V,S,P,M
10/22/1997	FMETL	26800	151	94	ND	4.0	9.10				V,S,P,M
01/08/1998	FMETL	104700	342	217	6.0	4.0	9.00				V,S,P,M
04/07/1998	FMETL	19780	110	119	3.4	ND	9.50				V,S,P,M
07/14/1998	FMETL	35900	130	411	ND	4.19	9.09				V,S,P,M
11/24/1998	FMETL	25400	87.8	125	ND	ND	9.13				V,S,P,M
02/11/1999	FMETL	11300	81.2	67.8	ND	ND	8.13				V,S,P,M
06/09/1999	FMETL	69600	214	336	5.82	ND	9.13				V,S,P,M
08/04/1999	FMETL	35900	149	69	8	3.25	9.15				V,S,P,M
11/03/1999	FMETL	19500	47.2	52.8	ND	ND	6.14				V,S,P,M
02/15/2000	FMETL	54400	201	96.2	2.67	3.77	9.09				V,S,P,M

SOURCE: 0CW2MW33

Sampling Dates:
04/24/1997 - 02/15/2000

NOTES:

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4

 U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

SOURCE: 0CW2MW33

Sampling Dates:
04/24/1997 - 02/15/2000

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 4 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)




FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
5401.04	0CW2MW30	29-32594	05/08/00
5401.05	0CW2MW31	29-32595	05/08/00
5401.06	0CW2MW32	29-32596	05/08/00
5401.07	0CW2MW33	29-32597	05/08/00

NJDEP Laboratory Certification # 13461

Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST	Standard Methods, 18 th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B
TARGET COMPOUND LIST	Federal Register 40 CFR Part 136 Appendix A
Base/Neutrals and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticides and PCB's by GC	608



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (732)532-4359 Fax (732)532-6263 EMail:wrightd@mail1.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: J. Fallon		Project No:		Analysis Parameters								Comments:			
Phone #: 201-223		Location: CW2 wells										HCL/HNO ₃ /64°C			
X IDERA () OMA () Other:		2nd Qtr '00													
Samplers Name / Company: Corey McCormack, TKS				Sample #									Remarks / Preservation Method		
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles	VO+IS	TALPTES	Pest/PCB	DNA 725						
5401.01	Trip	5/8/00	0745	AQ	2	✓									
.02	Field Blank		0945		5	✓	✓	✓	✓						
.03	Dupe		—		5	✓	✓	✓	✓						
.04	OCW2 MW30		1032		5	✓	✓	✓	✓				0.0	29-32594	
.05	OCW2 MW31		1018		5	✓	✓	✓	✓				0.0	29-32595	
.06	OCW2 MW32		1010		5	✓	✓	✓	✓				0.0	29-32596	
.07	OCW2 MW33		0956	✓	5	✓	✓	✓	✓				0.0	29-32597	
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):					
Corey McCormack		5/8/00 1505		J. Wright											
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):					
Report Type: () Full () Reduced (X) Standard () Screen / non-certified () EDD						Remarks: Shuss Trip/FB/Dupe w/ 2603 + 2700 Sun det. CSm									
Turnaround time: (X) Standard 3 wks () Rush Days () ASAP Verbal Hrs.						Tide: N/A									

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 05/08/00
WEATHER: Sunny, Hot.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.71 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.15 ft
DEPTH OF WELL: 17.95 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 10.80 ft
(10.80) X .65 X 3 = 21.06
GALLONS OF H2O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:00

pH 6.85 su

DISSOLVED O2 5.70 ppm

TEMP 12.9 °C

SPECIFIC CONDUCTIVITY 110 us/cm

PURGE END TIME: 10:31

pH 6.85 su

DISSOLVED O2 5.24 ppm

TEMP 12.8 °C

SPECIFIC CONDUCTIVITY 111 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 10.91 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 21 gal

SAMPLE START TIME: 10:32

~~pH 6.85 su~~

DISSOLVED O2 5.19 ppm

~~TEMP 12.9 °C~~

SPECIFIC CONDUCTIVITY 111 us/cm

SAMPLE END TIME: 10:37

COMMENTS: DUP. Here.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 05/08/00
WEATHER: Sunny, hot.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.88 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 6.96 ft
DEPTH OF WELL: 16.91 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 9.95 ft
(9.95) X .65 X 3 =19.40
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:55

pH 6.84 su
DISSOLVED O2 5.76 ppm

TEMP 13.1 °C
SPECIFIC CONDUCTIVITY 98 us/cm

PURGE END TIME: 10:17

pH 6.85 su
DISSOLVED O2 5.23 ppm

TEMP 12.9 °C
SPECIFIC CONDUCTIVITY 100 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 10:05 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 10:18

pH 6.85 su
DISSOLVED O2 5.19 ppm

TEMP 12.9 °C
SPECIFIC CONDUCTIVITY 100 us/cm

SAMPLE END TIME: 10:24

COMMENTS:

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 05/08/00
WEATHER: Sunny, hot.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.38 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.29 ft
DEPTH OF WELL: 16.89 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 9.60 ft
(9.60) X .65 X 3 = 18.72
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:47

pH 6.83 su

DISSOLVED O2 5.76 ppm

TEMP 12.7 °C

SPECIFIC CONDUCTIVITY 97 us/cm

PURGE END TIME: 10:09

pH 6.84 su

DISSOLVED O2 5.21 ppm

TEMP 12.7 °C

SPECIFIC CONDUCTIVITY 100 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 14.13 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 10:10

pH 6.83 su

DISSOLVED O2 5.17 ppm

10:15:55

TEMP 12.7 °C

SPECIFIC CONDUCTIVITY 101 us/cm

COMMENTS:

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW33
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 05/08/00
WEATHER: Sunny, hot.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.09 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 8.13 ft
DEPTH OF WELL: 16.10 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 7.97 ft
(7.97) X .65 X 3 =15.54
GALLONS OF H2O TO BE PURGED: 16 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm): PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:45
pH 6.79 su
DISSOLVED O2 5.71 ppm

TEMP 12.9 °C
SPECIFIC CONDUCTIVITY 114 us/cm

PURGE END TIME: 09:55
pH 6.83 su
DISSOLVED O2 5.10 ppm

TEMP 12.8 °C
SPECIFIC CONDUCTIVITY 111 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.63 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 16 gal

SAMPLE START TIME: 09:56
~~pH 6.82 su~~
DISSOLVED O2 5.04 ppm

~~TEMP 12.9 °C~~
SPECIFIC CONDUCTIVITY 112 us/cm

SAMPLE END TIME: 10:00

COMMENTS:

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit
J : Compound identified below detection limit
B : Compound in both sample and blank
D : Results from dilution of sample
U : Compound searched for but not detected
E : Compound exceeds calibration limit

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB006815.D**
 Operator **Skelton**
 Date Acquired **9 May 2000 2:30 pm**

Sample Name **Vblk208**
 Field ID **Vblk208**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Vblk208

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5401 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: Vblk208
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB006815.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: not dec. Date Analyzed: 5/9/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB006830.D**
 Operator **Skelton**
 Date Acquired **10 May 2000 12:37 am**

Sample Name **5401.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Trip Blank

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5401 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5401.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB006830.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: not dec. _____ Date Analyzed: 5/10/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB006831.D**
 Operator **Skelton**
 Date Acquired **10 May 2000 1:17 am**

Sample Name **5401.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Field Blank

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5401 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5401.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB006831.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: not dec. _____ Date Analyzed: 5/10/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB006832.D**
 Operator **Skelton**
 Date Acquired **10 May 2000 1:57 am**

Sample Name **5401.03**
 Field ID **Dupe**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Dupe

Lab Name: FMETLProject: LTMNJDEP#: 13461Case No.: 5401Location: CW2

SDG No.: _____

Matrix: (soil/water) WATERLab Sample ID: 5401.03Sample wt/vol: 5.0 (g/ml) MLLab File ID: VB006832.DLevel: (low/med) LOWDate Received: 5/8/00

% Moisture: not dec. _____

Date Analyzed: 5/10/00GC Column: RTX502 ID: 0.25 (mm)Dilution Factor: 1.0

Soil Extract Volume: _____ (uL)

Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB006833.D**
 Operator **Skelton**
 Date Acquired **10 May 2000 2:36 am**

Sample Name **5401.04**
 Field ID **0CW2MW30**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW30

Lab Name: FMETL Project: LTM

NJDEP#: 13461 Case No.: 5401 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5401.04

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB006833.D

Level: (low/med) LOW Date Received: 5/8/00

% Moisture: not dec. _____ Date Analyzed: 5/10/00

GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB006834.D**
 Operator **Skelton**
 Date Acquired **10 May 2000 3:16 am**

Sample Name **5401.05**
 Field ID **0CW2MW31**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW31

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5401 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5401.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB006834.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: not dec. _____ Date Analyzed: 5/10/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File VB006835.D
 Operator Skelton
 Date Acquired 10 May 2000 3:55 am

Sample Name 5401.06
 Field ID 0CW2MW32
 Sample Multiplier 1

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW32

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5401 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5401.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB006835.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: not dec. Date Analyzed: 5/10/00
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB006836.D**
 Operator **Skelton**
 Date Acquired **10 May 2000 4:35 am**

Sample Name **5401.07**
 Field ID **0CW2MW33**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifiers
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6.2-Sept-97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW33

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5401 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5401.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB006836.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: not dec. Date Analyzed: 5/10/00
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03933.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **Sbik368**
 Misc Info **Sbik368 A 000510**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BNA03933.D
 Operator Bhaskar
 Date Acquired 26-May-00

Sample Name Sblk368
 Misc Info Sblk368 A 000510
 Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Sblk368

Lab Name: FMETL Lab Code: 13461

Project: 100004 Case No.: 5401 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: Sblk368

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03933.D

Level: (low/med) LOW Date Received: 5/8/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 5/10/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 5/26/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.97	9	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03935.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03935.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Field Blank

Lab Name: FMETL Lab Code 13461
Project: 100004 Case No.: 5401 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5401.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03935.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 5/10/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 5/26/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.97	9	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03936.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.03**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03936.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.03**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Dupe

Lab Name: FMETL Lab Code 13461
Project: 100004 Case No.: 5401 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5401.03
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03936.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: decanted: (Y/N) N Date Extracted: 5/10/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 5/26/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.97	12	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03937.D**

Operator **Bhaskar**

Date Acquired **26-May-00**

Sample Name **5401.04**

Misc Info **0CW2MW30**

Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BNA03937.D
Operator Bhaskar
Date Acquired 26-May-00

Sample Name 5401.04
Misc Info 0CW2MW30
Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
D= Value from dilution
B= Compound in Related Blank
PQL= Practical Quantitation Limit

MDL= Method Detection Limit
NLE= No Limit Established
R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW30

Lab Name: FMETL Lab Code 13461
Project: 100004 Case No.: 5401 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5401.04
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03937.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 5/10/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 5/26/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.97	12	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03938.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03938.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW31

Lab Name: FMETL Lab Code 13461
Project: 100004 Case No.: 5401 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5401.05
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03938.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 5/10/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 5/26/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.97	12	J
2. 077899-10-6	(Z)14-Tricosenyl formate	32.50	10	JN

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03939.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03939.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW32

Lab Name: FMETL Lab Code 13461

Project: 100004 Case No.: 5401 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5401.06

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03939.D

Level: (low/med) LOW Date Received: 5/8/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 5/10/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 5/26/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
<u>1.</u>	<u>unknown</u>	<u>6.97</u>	<u>11</u>	<u>J</u>

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA03940.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.83 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.91 ug/L	
62-53-3	Aniline			not detected	NLE	1.63 ug/L	
108-95-2	Phenol			not detected	4000	0.82 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	1.28 ug/L	
95-57-8	2-Chlorophenol			not detected	40	2.00 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	1.21 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	1.19 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	1.02 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	1.13 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	1.17 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	1.39 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.35 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.80 ug/L	
67-72-1	Hexachloroethane			not detected	10	1.50 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.97 ug/L	
78-59-1	Isophorone			not detected	100	1.01 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	1.92 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	2.62 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	1.21 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	1.33 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.75 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	1.22 ug/L	
91-20-3	Naphthalene			not detected	NLE	1.27 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.09 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.71 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	1.39 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	1.08 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	1.32 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	1.78 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	1.28 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	1.01 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	0.96 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.52 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.96 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.81 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	0.79 ug/L	
83-32-9	Acenaphthene			not detected	400	1.10 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.44 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	1.00 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.06 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA03940.D**
 Operator **Bhaskar**
 Date Acquired **26-May-00**

Sample Name **5401.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	0.87 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.62 ug/L	
86-73-7	Fluorene			not detected	300	0.99 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	1.10 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	1.05 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	1.98 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.01 ug/L	
103-33-3	Azobenzene			not detected	NLE	0.67 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	0.76 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	0.94 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.42 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.23 ug/L	
120-12-7	Anthracene			not detected	2000	1.12 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	1.70 ug/L	
206-44-0	Fluoranthene			not detected	300	1.64 ug/L	
92-87-5	Benzidine			not detected	50	4.18 ug/L	
129-00-0	Pyrene			not detected	200	1.25 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.05 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	1.19 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.75 ug/L	
218-01-9	Chrysene			not detected	20	1.38 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.74 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.25 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.29 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	1.05 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	0.83 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	0.64 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	0.84 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW33

Lab Name: FMETL Lab Code 13461
Project: 100004 Case No.: 5401 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5401.07
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA03940.D
Level: (low/med) LOW Date Received: 5/8/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 5/10/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 5/26/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.98	13	J

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID #: PBLK520
Date Rec'd:
Extraction Date: 5/9/00
Analysis Date: 5/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location :

Field ID:

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0007	ND
beta-BHC	1		0.20	0.0014	ND
gamma-BHC	1		0.20	0.0012	ND
delta-BHC	1		NLE	0.0021	ND
Heptachlor	1		0.40	0.0016	ND
Aldrin	1		0.04	0.0014	ND
Heptachlor Epoxide	1		0.20	0.0008	ND
Endosulfan I	1		0.40	0.0014	ND
4,4'-DDE	1		0.10	0.0014	ND
Dieldrin	1		0.03	0.0011	ND
Endrin	1		2.00	0.0012	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0006	ND
4,4'-DDD	1		0.10	0.0012	ND
4,4'-DDT	1		0.10	0.0019	ND
Endosulfan-Sulfate	1		0.40	0.0018	ND
Methoxychlor	1		40.00	0.0022	ND
Alpha-chlordane	1		0.50	0.0007	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5401.02
Date Rec'd: 5/8/00
Extraction Date: 5/9/00
Analysis Date: 5/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: Field Blank

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0007	ND
beta-BHC	1		0.20	0.0014	ND
gamma-BHC	1		0.20	0.0012	ND
delta-BHC	1		NLE	0.0021	ND
Heptachlor	1		0.40	0.0016	ND
Aldrin	1		0.04	0.0014	ND
Heptachlor Epoxide	1		0.20	0.0008	ND
Endosulfan I	1		0.40	0.0014	ND
4,4'-DDE	1		0.10	0.0014	ND
Dieldrin	1		0.03	0.0011	ND
Endrin	1		2.00	0.0012	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0006	ND
4,4'-DDD	1		0.10	0.0012	ND
4,4'-DDT	1		0.10	0.0019	ND
Endosulfan-Sulfate	1		0.40	0.0018	ND
Methoxychlor	1		40.00	0.0022	ND
Alpha-chlordane	1		0.50	0.0007	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5401.03
Date Rec'd: 5/8/00
Extraction Date: 5/9/00
Analysis Date: 5/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: Dupe

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0007	ND
beta-BHC	1		0.20	0.0014	ND
gamma-BHC	1		0.20	0.0012	ND
delta-BHC	1		NLE	0.0021	ND
Heptachlor	1		0.40	0.0016	ND
Aldrin	1		0.04	0.0014	ND
Heptachlor Epoxide	1		0.20	0.0008	ND
Endosulfan I	1		0.40	0.0014	ND
4,4'-DDE	1		0.10	0.0014	ND
Dieldrin	1		0.03	0.0011	ND
Endrin	1		2.00	0.0012	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0006	ND
4,4'-DDD	1		0.10	0.0012	ND
4,4'-DDT	1		0.10	0.0019	ND
Endosulfan-Sulfate	1		0.40	0.0018	ND
Methoxychlor	1		40.00	0.0022	ND
Alpha-chlordane	1		0.50	0.0007	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5401.04
Date Rec'd: 5/8/00
Extraction Date: 5/9/00
Analysis Date: 5/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: 00W2MW30

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0007	ND
beta-BHC	1		0.20	0.0014	ND
gamma-BHC	1		0.20	0.0012	ND
delta-BHC	1		NLE	0.0021	ND
Heptachlor	1		0.40	0.0016	ND
Aldrin	1		0.04	0.0014	ND
Heptachlor Epoxide	1		0.20	0.0008	ND
Endosulfan I	1		0.40	0.0014	ND
4,4'-DDE	1		0.10	0.0014	ND
Dieldrin	1		0.03	0.0011	ND
Endrin	1		2.00	0.0012	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0006	ND
4,4'-DDD	1		0.10	0.0012	ND
4,4'-DDT	1		0.10	0.0019	ND
Endosulfan-Sulfate	1		0.40	0.0018	ND
Methoxychlor	1		40.00	0.0022	ND
Alpha-chlordane	1		0.50	0.0007	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg: 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5401.05
Date Rec'd: 5/8/00
Extraction Date: 5/9/00
Analysis Date: 5/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: 00W2MW31

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0007	ND
beta-BHC	1		0.20	0.0014	ND
gamma-BHC	1		0.20	0.0012	ND
delta-BHC	1		NLE	0.0021	ND
Heptachlor	1		0.40	0.0016	ND
Aldrin	1		0.04	0.0014	ND
Heptachlor Epoxide	1		0.20	0.0008	ND
Endosulfan I	1		0.40	0.0014	ND
4,4'-DDE	1		0.10	0.0014	ND
Dieldrin	1		0.03	0.0011	ND
Endrin	1		2.00	0.0012	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0006	ND
4,4'-DDD	1		0.10	0.0012	ND
4,4'-DDT	1		0.10	0.0019	ND
Endosulfan-Sulfate	1		0.40	0.0018	ND
Methoxychlor	1		40.00	0.0022	ND
Alpha-chlordane	1		0.50	0.0007	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5401.06
Date Rec'd: 5/8/00
Extraction Date: 5/9/00
Analysis Date: 5/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: 00W2MW32

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0007	ND
beta-BHC	1		0.20	0.0014	ND
gamma-BHC	1		0.20	0.0012	ND
delta-BHC	1		NLE	0.0021	ND
Heptachlor	1		0.40	0.0016	ND
Aldrin	1		0.04	0.0014	ND
Heptachlor Epoxide	1		0.20	0.0008	ND
Endosulfan I	1		0.40	0.0014	ND
4,4'-DDE	1		0.10	0.0014	ND
Dieldrin	1		0.03	0.0011	ND
Endrin	1		2.00	0.0012	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0006	ND
4,4'-DDD	1		0.10	0.0012	ND
4,4'-DDT	1		0.10	0.0019	ND
Endosulfan-Sulfate	1		0.40	0.0018	ND
Methoxychlor	1		40.00	0.0022	ND
Alpha-chlordane	1		0.50	0.0007	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides 2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5401.07
Date Rec'd: 5/8/00
Extraction Date: 5/9/00
Analysis Date: 5/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: 00W2MW33

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0007	ND
beta-BHC	1		0.20	0.0014	ND
gamma-BHC	1		0.20	0.0012	ND
delta-BHC	1		NLE	0.0021	ND
Heptachlor	1		0.40	0.0016	ND
Aldrin	1		0.04	0.0014	ND
Heptachlor Epoxide	1		0.20	0.0008	ND
Endosulfan I	1		0.40	0.0014	ND
4,4'-DDE	1		0.10	0.0014	ND
Dieldrin	1		0.03	0.0011	ND
Endrin	1		2.00	0.0012	ND
Endrin Ketone	1		NLE	0.0012	ND
Endosulfan II	1		0.40	0.0006	ND
4,4'-DDD	1		0.10	0.0012	ND
4,4'-DDT	1		0.10	0.0019	ND
Endosulfan-Sulfate	1		0.40	0.0018	ND
Methoxychlor	1		40.00	0.0022	ND
Alpha-chlordane	1		0.50	0.0007	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.0273	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

MDL = Method Detection Limit

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

NLE = No Limit Established

PQL = Practical Quantitation Limit

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5401
 Sample Prepared: 06/01/00

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	06/01/00	15.3	200	10.0
Antimony	06/01/00	ND	20	2.0
Arsenic	06/01/00	ND	8	2.0
Barium	06/01/00	ND	2000	0.5
Beryllium	06/01/00	ND	20	0.5
Cadmium	06/01/00	ND	4	0.5
Calcium	06/01/00	189	NLE	20.0
Chromium	06/01/00	ND	100	0.5
Cobalt	06/01/00	ND	NLE	0.5
Copper	06/01/00	ND	1000	3.0
Iron	06/01/00	25.4	300	10.0
Lead	06/01/00	ND	10	2.0
Magnesium	06/01/00	25.6	NLE	20.0
Manganese	06/01/00	0.661	50	0.5
Mercury	05/15/00	ND	2	0.1
Nickel	06/01/00	ND	100	0.5
Potassium	06/01/00	ND	NLE	20.0
Selenium	06/01/00	ND	50	3.0
Silver	06/01/00	ND	20	3.0
Sodium	06/01/00	43.1	50000	20.0
Thallium	06/05/00	ND	10	1.0
Vanadium	06/01/00	ND	NLE	1.0
Zinc	06/01/00	3.20	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5401.02
 Sample Received 05/08/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	06/01/00	ND	200	10.0
Antimony	06/01/00	ND	20	2.0
Arsenic	06/01/00	ND	8	2.0
Barium	06/01/00	ND	2000	0.5
Beryllium	06/01/00	ND	20	0.5
Cadmium	06/01/00	ND	4	0.5
Calcium	06/01/00	ND	NLE	20.0
Chromium	06/01/00	ND	100	0.5
Cobalt	06/01/00	ND	NLE	0.5
Copper	06/01/00	ND	1000	3.0
Iron	06/01/00	ND	300	10.0
Lead	06/01/00	ND	10	2.0
Magnesium	06/01/00	ND	NLE	20.0
Manganese	06/01/00	ND	50	0.5
Mercury	05/15/00	ND	2	0.1
Nickel	06/01/00	ND	100	0.5
Potassium	06/01/00	ND	NLE	20.0
Selenium	06/01/00	ND	50	3.0
Silver	06/01/00	ND	20	3.0
Sodium	06/01/00	ND	50000	20.0
Thallium	06/05/00	ND	10	1.0
Vanadium	06/01/00	ND	NLE	1.0
Zinc	06/01/00	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5401.03
 Sample Received: 05/08/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	06/01/00	133	200	10.0
Antimony	06/01/00	ND	20	2.0
Arsenic	06/01/00	ND	8	2.0
Barium	06/01/00	61.4	2000	0.5
Beryllium	06/01/00	ND	20	0.5
Cadmium	06/01/00	ND	4	0.5
Calcium	06/01/00	59000	NLE	20.0
Chromium	06/01/00	4.96	100	0.5
Cobalt	06/01/00	ND	NLE	0.5
Copper	06/01/00	101	1000	3.0
Iron	06/01/00	8090	300	10.0
Lead	06/01/00	13.7	10	2.0
Magnesium	06/01/00	4900	NLE	20.0
Manganese	06/01/00	74.9	50	0.5
Mercury	05/15/00	ND	2	0.1
Nickel	06/01/00	7.58	100	0.5
Potassium	06/01/00	7500	NLE	20.0
Selenium	06/01/00	ND	50	3.0
Silver	06/01/00	ND	20	3.0
Sodium	06/01/00	25200	50000	20.0
Thallium	06/05/00	ND	10	1.0
Vanadium	06/01/00	3.02	NLE	1.0
Zinc	06/01/00	158	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5401.04
 Sample Received: 05/08/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	06/01/00	105	200	10.0
Antimony	06/01/00	ND	20	2.0
Arsenic	06/01/00	ND	8	2.0
Barium	06/01/00	61.7	2000	0.5
Beryllium	06/01/00	ND	20	0.5
Cadmium	06/01/00	0.787	4	0.5
Calcium	06/01/00	59800	NLE	20.0
Chromium	06/01/00	7.19	100	0.5
Cobalt	06/01/00	0.822	NLE	0.5
Copper	06/01/00	327	1000	3.0
Iron	06/01/00	7410	300	10.0
Lead	06/01/00	46.6	10	2.0
Magnesium	06/01/00	4910	NLE	20.0
Manganese	06/01/00	73.1	50	0.5
Mercury	05/15/00	ND	2	0.1
Nickel	06/01/00	17.6	100	0.5
Potassium	06/01/00	7670	NLE	20.0
Selenium	06/01/00	ND	50	3.0
Silver	06/01/00	ND	20	3.0
Sodium	06/01/00	24500	50000	20.0
Thallium	06/05/00	ND	10	1.0
Vanadium	06/01/00	3.17	NLE	1.0
Zinc	06/01/00	429	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5401.05
 Sample Received: 05/08/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	06/01/00	ND	200	10.0
Antimony	06/01/00	ND	20	2.0
Arsenic	06/01/00	ND	8	2.0
Barium	06/01/00	305	2000	0.5
Beryllium	06/01/00	ND	20	0.5
Cadmium	06/01/00	ND	4	0.5
Calcium	06/01/00	52500	NLE	20.0
Chromium	06/01/00	1.57	100	0.5
Cobalt	06/01/00	ND	NLE	0.5
Copper	06/01/00	ND	1000	3.0
Iron	06/01/00	86000	300	10.0
Lead	06/01/00	ND	10	2.0
Magnesium	06/01/00	6650	NLE	20.0
Manganese	06/01/00	343	50	0.5
Mercury	05/15/00	ND	2	0.1
Nickel	06/01/00	ND	100	0.5
Potassium	06/01/00	10200	NLE	20.0
Selenium	06/01/00	ND	50	3.0
Silver	06/01/00	ND	20	3.0
Sodium	06/01/00	12600	50000	20.0
Thallium	06/01/00	ND	10	3.0
Vanadium	06/01/00	2.08	NLE	1.0
Zinc	06/01/00	15.2	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5401.06
 Sample Received: 05/08/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	06/01/00	51.4	200	10.0
Antimony	06/01/00	ND	20	2.0
Arsenic	06/01/00	ND	8	2.0
Barium	06/01/00	193	2000	0.5
Beryllium	06/01/00	ND	20	0.5
Cadmium	06/01/00	0.585	4	0.5
Calcium	06/01/00	71800	NLE	20.0
Chromium	06/01/00	2.63	100	0.5
Cobalt	06/01/00	ND	NLE	0.5
Copper	06/01/00	27.9	1000	3.0
Iron	06/01/00	55700	300	10.0
Lead	06/01/00	ND	10	2.0
Magnesium	06/01/00	8300	NLE	20.0
Manganese	06/01/00	382	50	0.5
Mercury	05/15/00	ND	2	0.1
Nickel	06/01/00	3.00	100	0.5
Potassium	06/01/00	9220	NLE	20.0
Selenium	06/01/00	ND	50	3.0
Silver	06/01/00	ND	20	3.0
Sodium	06/01/00	15600	50000	20.0
Thallium	06/01/00	ND	10	3.0
Vanadium	06/01/00	6.80	NLE	1.0
Zinc	06/01/00	79.9	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5401.07
 Sample Received: 05/08/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	06/01/00	29.3	200	10.0
Antimony	06/01/00	ND	20	2.0
Arsenic	06/01/00	ND	8	2.0
Barium	06/01/00	121	2000	0.5
Beryllium	06/01/00	ND	20	0.5
Cadmium	06/01/00	ND	4	0.5
Calcium	06/01/00	36100	NLE	20.0
Chromium	06/01/00	0.845	100	0.5
Cobalt	06/01/00	0.770	NLE	0.5
Copper	06/01/00	ND	1000	3.0
Iron	06/01/00	36500	300	10.0
Lead	06/01/00	ND	10	2.0
Magnesium	06/01/00	5870	NLE	20.0
Manganese	06/01/00	242	50	0.5
Mercury	05/15/00	ND	2	0.1
Nickel	06/01/00	0.949	100	0.5
Potassium	06/01/00	7120	NLE	20.0
Selenium	06/01/00	ND	50	3.0
Silver	06/01/00	ND	20	3.0
Sodium	06/01/00	19900	50000	20.0
Thallium	06/01/00	ND	10	3.0
Vanadium	06/01/00	1.78	NLE	1.0
Zinc	06/01/00	6.37	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	9100	69	ND	ND	ND	6.45				V,S,P,M
07/10/1997	FMETL	12590	73	25	5.0	ND	7.05				V,S,P,M
10/22/1997	FMETL	34800	171	175	5.0	5.0	7.60				V,S,P,M
01/08/1998	FMETL	2795	5.0	204	ND	4.0	5.20				V,S,P,M
04/07/1998	FMETL	3504	39.3	196	5.6	ND	6.56				V,S,P,M
07/14/1998	FMETL	10900	57.8	65.7	ND	ND	6.89				V,S,P,M
11/24/1998	FMETL	27500	182	ND	11.5	3.15	7.86				V,S,P,M
02/11/1999	FMETL	11000	100	505	8.3	ND	7.24				V,S,P,M
06/09/1999	FMETL	8210	145	521	6.33	ND	7.21				V,S,P,M
08/04/1999	FMETL	44800	212	304	9.05	6.02	7.43				V,S,P,M
11/03/1999	FMETL	6540	36.3	92.7	6.06	ND	7.02				V,S,P,M
02/15/2000	FMETL	1840	2.69	20.4	ND	ND	7.02				V,S,P,M
05/08/2000	FMETL	7410	73.1	105	ND	46.6	7.15				V,S,P,M
05/08/2000D	FMETL	8090	74.9	133	ND	13.7	7.15				V,S,P,M

SOURCE: 0CW2MW30

Sampling Dates:
04/24/1997 - 05/08/2000

NOTES:

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 1 of 4



U.S. ARMY
FORT MONMOUTH
SELFM-PW-EV

SOURCE: 0CW2MW30

Sampling Dates:
04/24/1997 - 05/08/2000

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 1 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)









Depth to Water
(Feet)



SOURCE: 0CW2MW31

Sampling Dates:
04/24/1997 - 05/08/2000



LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria








FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 2 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW32

Sampling Dates:
04/24/1997 - 05/08/2000

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 3 of 4, Graph



	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	88600	424	ND	ND	ND	8.95				V,S,P,M
07/10/1997	FMETL	10260	519	2.1	1.0	ND	9.10				V,S,P,M
10/22/1997	FMETL	26800	151	94	ND	4.0	9.10				V,S,P,M
01/08/1998	FMETL	104700	342	217	6.0	4.0	9.00				V,S,P,M
04/07/1998	FMETL	19780	110	119	3.4	ND	9.50				V,S,P,M
07/14/1998	FMETL	35900	130	411	ND	4.19	9.09				V,S,P,M
11/24/1998	FMETL	25400	87.8	125	ND	ND	9.13				V,S,P,M
02/11/1999	FMETL	11300	81.2	67.8	ND	ND	8.13				V,S,P,M
06/09/1999	FMETL	69600	214	336	5.82	ND	9.13				V,S,P,M
08/04/1999	FMETL	35900	149	69	8	3.25	9.15				V,S,P,M
11/03/1999	FMETL	19500	47.2	52.8	ND	ND	6.14				V,S,P,M
02/15/2000	FMETL	54400	201	96.2	2.67	3.77	9.09				V,S,P,M
05/08/2000	FMETL	36500	242	29.3	ND	ND	8.13				V,S,P,M

SOURCE: 0CW2MW33

Sampling Dates:
04/24/1997 - 05/08/2000

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4



U.S. ARMY
FORT MONMOUTH
SELFM-PW-EV



SOURCE: 0CW2MW33

Sampling Dates:
04/24/1997 - 05/08/2000

LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Well 4 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
5591.04	0CW2MW30	29-32594	08/02/00
5591.05	0CW2MW31	29-32595	08/02/00
5591.06	0CW2MW32	29-32596	08/02/00
5591.07	0CW2MW33	29-32597	08/02/00

NJDEP Laboratory Certification # 13461

 8-31-00
Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST	Standard Methods, 18 th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B
TARGET COMPOUND LIST	Federal Register 40 CFR Part 136 Appendix A
Base/Neutrals and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticides and PCB's by GC	608



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (732)532-4359 Fax (732)532-6263 EMail:wrightd@mail1.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: <u>J. Fallon</u>		Project No:		Analysis Parameters								Comments:			
Phone #: <u>X26223</u>		Location: <u>CW2 wells</u>										<u>HCL/HNO₃/24h</u>			
() DERA () OMA () Other:		<u>3rd Qtr '00</u>													
Samplers Name / Company: <u>Corey McCormick, TVS</u>				Sample #									Remarks / Preservation Method		
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles	VD+IS	TALMTLS	Pist/PB	BNATSS						
<u>5591</u>	<u>.01 Trip</u>	<u>8/2/00</u>	<u>0940</u>	<u>AQ</u>	<u>2</u>	<u>✓</u>								<u>1</u>	
	<u>.02 Field Blank</u>		<u>1000</u>		<u>5</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>					<u>1</u>	
	<u>.03 Dope</u>		<u>—</u>		<u>5</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>					<u>1</u>	
	<u>.04 OCW2 mw30</u>		<u>1116</u>		<u>5</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>					<u>0.0</u>	<u>29-32594</u>
	<u>.05 OCW2 mw31</u>		<u>1109</u>		<u>1</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>					<u>0.0</u>	<u>29-32595</u>
	<u>.06 OCW2 mw32 *</u>		<u>1124</u>		<u>1</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>					<u>0.0</u>	<u>29-32596</u>
	<u>.07 OCW2 mw33</u>	<u>✓</u>	<u>1047</u>	<u>✓</u>	<u>1</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>					<u>0.0</u>	<u>29-32597</u>
Relinquished by (signature): <u>Corey McCormick</u>		Date/Time: <u>8/2/00 1515</u>		Received by (signature): <u>J. Fallon</u>		Relinquished by (signature):		Date/Time:		Received by (signature):					
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):					
Report Type: () Full, () Reduced, (X) Standard, () Screen / non-certified, () EDD						Remarks: <u>Shoes T/FB/D w/ 2562 and 2700 Sm det, cm, cfm</u>									
Turnaround time: (X) Standard 3 wks, () Rush Days, () ASAP Verbal Hrs.						Tide: <u>N/A</u>									

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 08/02/00
WEATHER: Overcast, hot, humid.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.71 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 6.86 ft
DEPTH OF WELL: 17.95 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 11.09 ft
 $(11.09) \times .65 \times 3 = 21.62$
GALLONS OF H₂O TO BE PURGED: 22 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:40

pH 6.55 su

DISSOLVED O₂ 5.87 ppm

TEMP 23.3 °C

SPECIFIC CONDUCTIVITY 263 us/cm

PURGE END TIME: 11:15

pH 6.50 su

DISSOLVED O₂ 4.10 ppm

TEMP 22.9 °C

SPECIFIC CONDUCTIVITY 260 us/cm

DEPTH TO H₂O AFTER PURGE AND BEFORE SAMPLING: 10.22 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 22 gal

SAMPLE START TIME: 11:16

pH 6.49 su

DISSOLVED O₂ 4.07 ppm

TEMP 22.8 °C

SPECIFIC CONDUCTIVITY 259 us/cm

SAMPLE END TIME: 11:23

COMMENTS: Cloudy.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 08/02/00
WEATHER: Overcast, hot, humid.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.88 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 6.73 ft
DEPTH OF WELL: 16.91 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 10.18 ft
 $(10.18) \times .65 \times 3 = 19.85$
GALLONS OF H2O TO BE PURGED: 20 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:41
pH 6.66 su
DISSOLVED O2 5.91 ppm
TEMP 21.3 °C
SPECIFIC CONDUCTIVITY 309 us/cm

PURGE END TIME: 11:08
pH 6.52 su
DISSOLVED O2 4.17 ppm
TEMP 20.9 °C
SPECIFIC CONDUCTIVITY 305 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.63 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 20 gal

SAMPLE START TIME: 11:09
pH 6.51 su
DISSOLVED O2 4.11 ppm
TEMP 20.8 °C
SPECIFIC CONDUCTIVITY 304 us/cm

SAMPLE END TIME: 11:14

COMMENTS: Cloudy, orange.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 08/02/00
WEATHER: Overcast, hot, humid.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.38 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 5.93 ft
DEPTH OF WELL: 16.89 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 10.96 ft
(10.96) X .65 X 3 = 21.37
GALLONS OF H2O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 09:45
pH 6.97 su
DISSOLVED O2 5.99 ppm
TEMP 22.4 °C
SPECIFIC CONDUCTIVITY 359 us/cm

PURGE END TIME: 11:16
pH 6.95 su
DISSOLVED O2 4.01 ppm
TEMP 21.4 °C
SPECIFIC CONDUCTIVITY 356 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 10.26 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 21 gal

SAMPLE START TIME: 11:24
pH 6.94su
DISSOLVED O2 3.97 ppm
TEMP 21.3 °C
SPECIFIC CONDUCTIVITY 356 us/cm

SAMPLE END TIME: 11:28

COMMENTS: Cloudy, DUP. Here.

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

Definition of Qualifiers

MDL : Method Detection Limit
J : Compound identified below detection limit
B : Compound in both sample and blank
D : Results from dilution of sample
U : Compound searched for but not detected
E : Compound exceeds calibration limit

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB007832.D**
 Operator **Skelton**
 Date Acquired **11 Aug 2000 10:18 am**

Sample Name **Vblk234**
 Field ID **Vblk234**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

VbIk234

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: VbIk234
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB007832.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: not dec. _____ Date Analyzed: 8/11/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB007843.D**
 Operator **Skelton**
 Date Acquired **11 Aug 2000 6:02 pm**

Sample Name **5591.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform	16.40	91330	1.70 ug/L	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Trip Blank

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5591.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB007843.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: not dec. _____ Date Analyzed: 8/11/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB007844.D**
 Operator **Skelton**
 Date Acquired **11 Aug 2000 6:43 pm**

Sample Name **5591.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform	16.40	89010	1.76 ug/L	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB007845.D**
 Operator **Skelton**
 Date Acquired **11 Aug 2000 7:23 pm**

Sample Name **5591.03**
 Field ID **Dupe**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Dupe

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5591.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB007845.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: not dec. _____ Date Analyzed: 8/11/00
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB007846.D**
 Operator **Skelton**
 Date Acquired **11 Aug 2000 8:04 pm**

Sample Name **5591.04**
 Field ID **0CW2MW30**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW30

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5591.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB007846.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: not dec. _____ Date Analyzed: 8/11/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB007847.D**
 Operator **Skelton**
 Date Acquired **11 Aug 2000 8:44 pm**

Sample Name **5591.05**
 Field ID **0CW2MW31**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW31

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5591.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB007847.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: not dec. _____ Date Analyzed: 8/11/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB007848.D**
 Operator **Skelton**
 Date Acquired **11 Aug 2000 9:25 pm**

Sample Name **5591.06**
 Field ID **0CW2MW32**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW32

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5591.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB007848.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: not dec. _____ Date Analyzed: 8/11/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB007849.D**
 Operator **Skelton**
 Date Acquired **11 Aug 2000 10:06 pm**

Sample Name **5591.07**
 Field ID **0CW2MW33**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW33

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5591 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5591.07
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB007849.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: not dec. Date Analyzed: 8/11/00
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04331.D**
 Operator **Bhaskar**
 Date Acquired **8-Aug-00**

Sample Name **Sblk404**
 Misc Info **Sblk404 A 000807**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04331.D**
 Operator **Bhaskar**
 Date Acquired **8-Aug-00**

Sample Name **Sblk404**
 Misc Info **Sblk404 A 000807**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04316.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04316.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzydine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04317.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.03**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04317.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.03**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04318.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04318.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04319.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04319.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04320.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04320.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04321.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04321.D**
 Operator **Bhaskar**
 Date Acquired **7-Aug-00**

Sample Name **5591.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Sblk404

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Sblk404
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04331.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 8/7/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/8/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Field Blank

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5591.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04316.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 8/7/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/7/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Dupe

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 5591 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5591.03
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04317.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: decanted: (Y/N) N Date Extracted: 8/7/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/7/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 000105-60-2	Caprolactam	14.20	6	JN

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW30

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5591.04
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04318.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 8/7/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/7/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	33.04	28	J

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW31

Lab Name: FMETL Lab Code 13461

Project: LTM Case No.: 5591 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5591.05

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04319.D

Level: (low/med) LOW Date Received: 8/2/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 8/7/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/7/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.89	4	J
2. 000105-60-2	Caprolactam	14.20	5	JN
3. 022393-98-2	9-Hexadecenoic acid, 9-octadece	33.04	29	JN

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW32

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 5591 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5591.06
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04320.D
Level: (low/med) LOW Date Received: 8/2/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 8/7/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/7/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.89	5	J
2. 000105-60-2	Caprolactam	14.21	8	JN

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW33

Lab Name: FMETL Lab Code 13461

Project: LTM Case No.: 5591 Location: CW2 SDG No.:

Matrix: (soil/water) WATER Lab Sample ID: 5591.07

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04321.D

Level: (low/med) LOW Date Received: 8/2/00

% Moisture: decanted: (Y/N) N Date Extracted: 8/7/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 8/7/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.89	5	J
2. 000105-60-2	Caprolactam	14.21	4	JN
3. 003687-45-4	9-Octadecenoic acid (Z)-, 9-octad	33.05	39	JN

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : PBLK559
Date Rec'd:
Extraction Date: 8/8/00
Analysis Date: 8/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location :

Field ID:

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5591.02
Date Rec'd: 8/2/00
Extraction Date: 8/8/00
Analysis Date: 8/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: Field Blank

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

MDL = Method Detection Limit

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

NLE = No Limit Established

PQL = Practical Quantitation Limit

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5591.04
Date Rec'd: 8/2/00
Extraction Date: 8/8/00
Analysis Date: 8/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: 0CW2MW30

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5591.05
Date Rec'd: 8/2/00
Extraction Date: 8/8/00
Analysis Date: 8/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: 0CW2MW31

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5591.06
Date Rec'd: 8/2/00
Extraction Date: 8/8/00
Analysis Date: 8/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: 0CW2MW32

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5591.07
Date Rec'd: 8/2/00
Extraction Date: 8/8/00
Analysis Date: 8/11/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: 0CW2MW33

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5591
 Sample Prepared: 08/30/00

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/30/00	ND	200	10.0
Antimony	08/30/00	3.86	20	2.0
Arsenic	08/30/00	ND	8	2.0
Barium	08/30/00	ND	2000	0.5
Beryllium	08/30/00	ND	20	0.5
Cadmium	08/30/00	ND	4	0.5
Calcium	08/30/00	ND	NLE	20.0
Chromium	08/30/00	ND	100	0.5
Cobalt	08/30/00	ND	NLE	0.5
Copper	08/30/00	ND	1000	2.0
Iron	08/30/00	ND	300	2.0
Lead	08/30/00	ND	10	1.0
Magnesium	08/30/00	ND	NLE	10.0
Manganese	08/30/00	ND	50	0.5
Mercury	08/15/00	ND	2	0.1
Nickel	08/30/00	ND	100	1.0
Potassium	08/30/00	ND	NLE	40.0
Selenium	08/30/00	ND	50	3.0
Silver	08/30/00	ND	20	1.0
Sodium	08/30/00	109	50000	20.0
Thallium	08/30/00	ND	10	2.0
Vanadium	08/30/00	ND	NLE	0.5
Zinc	08/30/00	8.85	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5591.02
 Sample Received: 08/02/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/30/00	ND	200	10.0
Antimony	08/30/00	ND	20	2.0
Arsenic	08/30/00	ND	8	2.0
Barium	08/30/00	0.687	2000	0.5
Beryllium	08/30/00	ND	20	0.5
Cadmium	08/30/00	ND	4	0.5
Calcium	08/30/00	ND	NLE	20.0
Chromium	08/30/00	ND	100	0.5
Cobalt	08/30/00	ND	NLE	0.5
Copper	08/30/00	ND	1000	2.0
Iron	08/30/00	ND	300	2.0
Lead	08/30/00	ND	10	1.0
Magnesium	08/30/00	ND	NLE	10.0
Manganese	08/30/00	ND	50	0.5
Mercury	08/15/00	ND	2	0.1
Nickel	08/30/00	ND	100	1.0
Potassium	08/30/00	53.4	NLE	40.0
Selenium	08/30/00	ND	50	3.0
Silver	08/30/00	ND	20	1.0
Sodium	08/30/00	ND	50000	20.0
Thallium	08/30/00	ND	10	2.0
Vanadium	08/30/00	ND	NLE	0.5
Zinc	08/30/00	ND	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5591.03
 Sample Received: 08/02/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/30/00	28.1	200	10.0
Antimony	08/30/00	4.47	20	2.0
Arsenic	08/30/00	ND	8	2.0
Barium	08/30/00	48.2	2000	0.5
Beryllium	08/30/00	ND	20	0.5
Cadmium	08/30/00	ND	4	0.5
Calcium	08/30/00	114000	NLE	20.0
Chromium	08/30/00	2.36	100	0.5
Cobalt	08/30/00	0.583	NLE	0.5
Copper	08/30/00	224	1000	2.0
Iron	08/30/00	4130	300	2.0
Lead	08/30/00	38.3	10	1.0
Magnesium	08/30/00	10900	NLE	10.0
Manganese	08/30/00	7.99	50	0.5
Mercury	08/15/00	ND	2	0.1
Nickel	08/30/00	10.4	100	1.0
Potassium	08/30/00	5430	NLE	40.0
Selenium	08/30/00	5.90	50	3.0
Silver	08/30/00	ND	20	1.0
Sodium	08/30/00	17900	50000	20.0
Thallium	08/30/00	ND	10	2.0
Vanadium	08/30/00	3.04	NLE	0.5
Zinc	08/30/00	326	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5591.04
 Sample Received: 08/02/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/30/00	ND	200	10.0
Antimony	08/30/00	4.50	20	2.0
Arsenic	08/30/00	ND	8	2.0
Barium	08/30/00	60.2	2000	0.5
Beryllium	08/30/00	ND	20	0.5
Cadmium	08/30/00	ND	4	0.5
Calcium	08/30/00	68100	NLE	20.0
Chromium	08/30/00	1.50	100	0.5
Cobalt	08/30/00	ND	NLE	0.5
Copper	08/30/00	72.1	1000	2.0
Iron	08/30/00	2040	300	2.0
Lead	08/30/00	21.8	10	1.0
Magnesium	08/30/00	4670	NLE	10.0
Manganese	08/30/00	15.2	50	0.5
Mercury	08/15/00	ND	2	0.1
Nickel	08/30/00	6.54	100	1.0
Potassium	08/30/00	11300	NLE	40.0
Selenium	08/30/00	ND	50	3.0
Silver	08/30/00	ND	20	1.0
Sodium	08/30/00	7280	50000	20.0
Thallium	08/30/00	ND	10	2.0
Vanadium	08/30/00	1.63	NLE	0.5
Zinc	08/30/00	164	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5591.05
 Sample Received: 08/02/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/30/00	14.7	200	10.0
Antimony	08/30/00	5.66	20	2.0
Arsenic	08/30/00	ND	8	2.0
Barium	08/30/00	326	2000	0.5
Beryllium	08/30/00	ND	20	0.5
Cadmium	08/30/00	ND	4	0.5
Calcium	08/30/00	53700	NLE	20.0
Chromium	08/30/00	1.37	100	0.5
Cobalt	08/30/00	ND	NLE	0.5
Copper	08/30/00	ND	1000	2.0
Iron	08/30/00	68900	300	2.0
Lead	08/30/00	2.44	10	1.0
Magnesium	08/30/00	6610	NLE	10.0
Manganese	08/30/00	294	50	0.5
Mercury	08/15/00	ND	2	0.1
Nickel	08/30/00	ND	100	1.0
Potassium	08/30/00	10400	NLE	40.0
Selenium	08/30/00	ND	50	3.0
Silver	08/30/00	ND	20	1.0
Sodium	08/30/00	8200	50000	20.0
Thallium	08/30/00	ND	10	2.0
Vanadium	08/30/00	0.655	NLE	0.5
Zinc	08/30/00	13.0	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5591.06
 Sample Received: 08/02/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/30/00	21.8	200	10.0
Antimony	08/30/00	5.58	20	2.0
Arsenic	08/30/00	4.14	8	2.0
Barium	08/30/00	51.3	2000	0.5
Beryllium	08/30/00	ND	20	0.5
Cadmium	08/30/00	ND	4	0.5
Calcium	08/30/00	114000	NLE	20.0
Chromium	08/30/00	1.90	100	0.5
Cobalt	08/30/00	0.583	NLE	0.5
Copper	08/30/00	ND	1000	2.0
Iron	08/30/00	4700	300	2.0
Lead	08/30/00	2.96	10	1.0
Magnesium	08/30/00	10600	NLE	10.0
Manganese	08/30/00	8.74	50	0.5
Mercury	08/15/00	ND	2	0.1
Nickel	08/30/00	2.71	100	1.0
Potassium	08/30/00	5340	NLE	40.0
Selenium	08/30/00	ND	50	3.0
Silver	08/30/00	ND	20	1.0
Sodium	08/30/00	17900	50000	20.0
Thallium	08/30/00	ND	10	2.0
Vanadium	08/30/00	3.25	NLE	0.5
Zinc	08/30/00	29.6	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5591.07
 Sample Received: 08/02/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	08/30/00	38.2	200	10.0
Antimony	08/30/00	4.04	20	2.0
Arsenic	08/30/00	ND	8	2.0
Barium	08/30/00	83.6	2000	0.5
Beryllium	08/30/00	ND	20	0.5
Cadmium	08/30/00	ND	4	0.5
Calcium	08/30/00	23900	NLE	20.0
Chromium	08/30/00	ND	100	0.5
Cobalt	08/30/00	ND	NLE	0.5
Copper	08/30/00	ND	1000	2.0
Iron	08/30/00	13400	300	2.0
Lead	08/30/00	1.50	10	1.0
Magnesium	08/30/00	2660	NLE	10.0
Manganese	08/30/00	81.4	50	0.5
Mercury	08/15/00	ND	2	0.1
Nickel	08/30/00	ND	100	1.0
Potassium	08/30/00	6080	NLE	40.0
Selenium	08/30/00	ND	50	3.0
Silver	08/30/00	ND	20	1.0
Sodium	08/30/00	5230	50000	20.0
Thallium	08/30/00	ND	10	2.0
Vanadium	08/30/00	0.821	NLE	0.5
Zinc	08/30/00	16.4	5000	1.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

SOURCE: 0CW2MW30

Sampling Dates:
04/24/1997 - 08/02/2000

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 1 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW31

Sampling Dates:
04/24/1997 - 08/02/2000

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 2 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW32

Sampling Dates:
04/24/1997 - 08/02/2000

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 3 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



SOURCE: 0CW2MW33

Sampling Dates:
04/24/1997 - 08/02/2000

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH


GW MONITORING
Bldg CW-2

Well 4 of 4, Graph




U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV


Iron
(ug/l)




Manganese
(ug/l)




Aluminum
(ug/l)




Arsenic
(ug/l)



Lead
(ug/l)



Depth to Water
(Feet)



FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT FOR

Directorate of Public Works
Fort Monmouth, NJ 07703

PROJECT : DERA/ Long Term Monitoring
Low Flow/Round I

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
5660.02	0CW2MW30	29-32594	08/24/00
5657.02	0CW2MW31	29-32595	08/23/00
5657.03	0CW2MW32	29-32596	08/23/00
5657.04	0CW2MW33	29-32597	08/23/00


NJDEP Laboratory Certification # 13461

 9/18/00
Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST	Standard Methods, 18 th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B
TARGET COMPOUND LIST	Federal Register 40 CFR Part 136 Appendix A
Base/Neutrals and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticides and PCB's by GC	608

SAMPLING



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (732)532-4359 Fax (732)532-6263 EMail:wrightd@mail1.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

[illegible]

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW2
MW#: 0CW2MW30
NJDEP ID#29-32594
NJDEP CERT # 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: David Sharpe
DATE: 08/24/00
WEATHER: Cloudy.
TIDE: N/A
WELL CONDITION: Good

Hnu Calibration: Span 2.8 w/ 100 ppm Isobutylene
Sonde Calibration:
pH: 7.00/10.00/4.00 Buffers
Sp Cond/Cond: 147.0 μ ohms/cm solution (KCl)
DO: % Humidity 760mm (Barometric Pressure)
Temp.: N/A

LNAPLs: N
DNAPLs: N
ELEV. OF INNER CASING SURVEY MARK: N/A ft
INNER CASING DIA: 4 INCH
DEPTH TO WATER: 7.1 ft

Before Purge Start: 7.1 ft Previous Day: 7.1 ft After Sampling: 8.3 ft
DEPTH OF WELL: 17.95 ft
DEPTH TO TOP OF SCREEN: N/A ft
DEPTH OF PUMP/TUBE INTAKE: 15.5 ft TUBING: Food grade Polyethylene 1/4"/Silicon
HEIGHT OF WATER: ft

() X .65 / X 3 = (.65 for 4", .163 for 2")
GALLONS OF H2O TO BE PURGED: Gal
PURGE METHOD: (FLOW at >100 TO <500 ml/Min): ~~2" REDIFLO 2~~ 2" REDIFLO 2 GRUNDFOS SUBMERSIBLE PUMP
Purged at 220ml/Min or Gal/Min. (ml to gal.: ml(.0002642)=gal)

PURGE RATE: gpm
Hnu READING: 0 ppm (Well)
Hnu READING: 0 ppm (Well Cap)

PURGE START TIME: 11:15
pH 6.58 su
DISSOLVED O₂ 0.00 mg/L

TEMP 21.17 °C
SPECIFIC CONDUCTIVITY 642.4 ms/cm

PURGE END TIME: 11:55
pH 6.58 su
DISSOLVED O₂ 0.00 mg/L

TEMP 20.53 °C
SPECIFIC CONDUCTIVITY 651.5 ms/cm

DEPTH TO H2O AFTER PURGE AND SAMPLING: 8.3 ft
(SAMPLING METHOD: Through pump, Tubing with flow cell disconnected.)

SAMPLE START TIME: 11:51
pH 6.58 su
DISSOLVED O₂ 0.00 mg/L

TEMP 20.77 °C
SPECIFIC CONDUCTIVITY 653.2 ms/cm

SAMPLE END TIME: 11:54
ANALYTES: TAL Metals
COMMENTS:

FIELD READINGS

MW:0CW2MW30

NJDEP ID#: 29-32594

DATE: 8/24/00

Time (Min.)	pH	Temp. (°C)	Cond.	Specific Cond.	Dissolved O ₂ (mg/L)	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/Min)	Notes
11:15	6.58	21.17	598.4	642.4	0.00	4.8	7.15	220	
11:20	6.57	20.38	582	638.3	0.00	4.7	7.15	220	
11:25	6.58	20.7	586.7	639.3	0.00	3.84	7.15	220	
11:30	6.58	20.57	587.2	641.4	0.00	3.18	7.15	220	
11:35	6.58	20.59	589.4	643.6	0.00	3.01	7.15	220	
11:40	6.58	20.51	591.4	647	0.00	3.22	8.0	220	
11:45	6.58	20.53	595.9	651.5	0.00	3.12	8.0	220	
11:50	6.58	20.77	600.5	653.2	0.00	3.12	8.3	220	

Time	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/min)
1115	4.80	7.15	220
1120	4.70	7.15	220
1125	3.84	7.15	220
1130	3.18	7.15	220
1135	3.01	7.15	220
1140	3.22	8	220
1145	3.12	8	220
1150	3.12	8.3	220

Cw2mw30
CW2MW30 Low Flow Data for
Temp., Sp. Cond., Cond., D.O., pH
-- Data Report --


=====

From 08/24/00 11:10 to 08/24/00 11:50
Number of samples: 9

08/24/00	Temp C	SpCond mS/cm	Cond mS/cm	DO	Conc mg/L	pH
08/24/00 11:10	20.08	999.99	999.00	0.00	999.99	6.58
08/24/00 11:15	21.17	642.400	595.400	0.00	0.00	6.58
08/24/00 11:20	20.38	638.300	582.000	0.00	0.00	6.57
08/24/00 11:25	20.70	639.300	586.700	0.00	0.00	6.58
08/24/00 11:30	20.57	641.400	587.200	0.00	0.00	6.58
08/24/00 11:35	20.59	643.600	589.400	0.00	0.00	6.58
08/24/00 11:40	20.51	647.000	591.400	0.00	0.00	6.58
08/24/00 11:45	20.53	651.500	595.900	0.00	0.00	6.58
08/24/00 11:50	20.77	653.200	600.500	0.00	0.00	6.58


CW2MW30 Low Flow Data for

Temp., Sp. Cond., Cond., D.O., pH




CW2MW30
Permit #: 29-32594
8/24/00

Turbidity




CW2MW30
Permit #: 29-32594
8/24/00

Depth to Water.



CW2MW30
Permit #: 29-32594
8/24/00

Flow Rate



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW2

MW#: 0CW2MW31

NJDEP ID#29-32595

NJDEP CERT # 13461

SAMPLING CONTRACTOR: TVS

SAMPLER: David Sharpe

DATE: 08/23/00

WEATHER: Clear.

TIDE: N/A

WELL CONDITION: Good

LNAPLs: N

DNAPLs: N

ELEV. OF INNER CASING SURVEY MARK: N/A ft

INNER CASING DIA: 4 INCH

DEPTH TO WATER: 6.6 ft

Before Purge Start: 6.6 ft

Previous Day: 6.7 ft

After Sampling: 6.6 ft

DEPTH OF WELL: 16.9 ft

DEPTH TO TOP OF SCREEN: N/A ft

DEPTH OF PUMP/TUBE INTAKE: 14 ft

TUBING: Food grade Polyethylene 1/4"/Silicon

HEIGHT OF WATER: ft

() X .65 / X 3 =

(.65 for 4", .163 for 2")

GALLONS OF H2O TO BE PURGED: Gal

PURGE METHOD:(FLOW at >100 TO <500 ml/Min): ~~REDIFLO 2~~ 2" REDIFLO 2 GRUNDFOS SUBMERSIBLE PUMP

Purged at 240 mL/Min or

Gal/Min. (ml to gal.: ml(.0002642)=gal)

PURGE RATE: gpm

Hnu READING: 0 ppm (Well)

Hnu READING: 0 ppm (Well Cap)

PURGE START TIME: 09:30

pH 6.59 su

DISSOLVED O₂ 0.00 mg/L

TEMP 19.99 °C

SPECIFIC CONDUCTIVITY 1430 ms/cm

PURGE END TIME: 11:21

pH 6.57 su

DISSOLVED O₂ 0.00 mg/L

TEMP 20.05 °C

SPECIFIC CONDUCTIVITY 1359 ms/cm

DEPTH TO H2O AFTER PURGE AND SAMPLING: 6.6 ft

(SAMPLING METHOD: Through pump, Tubing with flow cell disconnected.)

SAMPLE START TIME: 11:17

pH 6.57 su

DISSOLVED O₂ 0.00 mg/L

TEMP 20.17 °C

SPECIFIC CONDUCTIVITY 1358 ms/cm

SAMPLE END TIME: 11:20

ANALYTES: TAL Metals

COMMENTS:

FIELD READINGS

MW:0CW2MW31

NJDEP ID#: 29-32595

DATE: 8/23/00

Time (Min.)	pH	Temp. (°C)	Cond.	Specific Cond.	Dissolved O ₂ (mg/L)	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/Min)	Notes
9:30	6.59	19.99	1293	1430	0.00	25.5	6.7	240	
9:35	6.6	19.73	1284	1428	0.00	16.6	6.7	240	
9:40	6.6	19.78	1281	1423	0.00	17.2	6.7	240	
9:45	6.6	19.82	1276	1416	0.00	17.5	6.7	240	
9:50	6.6	19.88	1270	1408	0.00	16.1	6.7	240	
9:55	6.59	19.94	1266	1401	0.00	14.7	6.7	240	
10:00	6.59	19.81	1259	1398	0.00	13.8	6.7	240	
10:05	6.59	19.85	1257	1395	0.00	13	6.7	240	
10:10	6.59	19.85	1255	1392	0.00	13.2	6.7	240	
10:15	6.59	19.91	1253	1388	0.00	12.5	6.7	240	
10:20	6.59	19.99	1254	1386	0.00	11.5	6.7	240	
10:25	6.58	19.96	1250	1384	0.00	10.8	6.7	240	
10:30	6.58	20.07	1252	1383	0.00	9.7	6.7	240	
10:35	6.58	20.09	1250	1379	0.00	10.2	6.7	240	
10:40	6.58	10.1	1246	1375	0.00	10.4	6.7	240	
10:45	6.58	20.09	1245	1374	0.00	9.8	6.7	240	
10:50	6.58	20.18	1245	1371	0.00	9.1	6.7	240	
10:55	6.57	20.19	1243	1368	0.00	11	6.7	240	
11:00	6.57	20.15	1239	1365	0.00	10	6.7	240	
11:05	6.57	20.07	1236	1365	0.00	9.7	6.7	240	
11:10	6.57	20.05	1230	1359	0.00	9.6	6.7	240	
11:15	6.57	20.17	1232	1358	0.00	7.6	6.7	240	

Time	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (g/min)
930	25.50	6.7	240
935	16.60	6.7	240
940	17.20	6.7	240
945	17.50	6.7	240
950	16.10	6.7	240
955	14.70	6.7	240
1000	13.80	6.7	240
1005	13.00	6.7	240
1010	13.20	6.7	240
1015	12.50	6.7	240
1020	11.50	6.7	240
1025	10.80	6.7	240
1030	9.70	6.7	240
1035	10.20	6.7	240
1040	10.40	6.7	240
1045	9.80	6.7	240
1050	9.10	6.7	240
1055	11.00	6.7	240
1100	10.00	6.7	240
1105	9.70	6.7	240
1110	9.60	6.7	240
1115	7.60	6.7	240




Cwmw31
 CW2MW31 Low Flow Data For
 Temp., Sp. Cond., Cond., D.O., pH
 -- Data Report --

=====

From 08/23/00 09:30 to 08/23/00 11:15
 Number of samples: 22

08/23/00	Temp C	SpCond mS/cm	Cond mS/cm	DO mg/L	pH
08/23/00 09:30	19.99	1430.000	1293.000	0.00	6.59
08/23/00 09:35	19.73	1428.000	1284.000	0.00	6.60
08/23/00 09:40	19.78	1423.000	1281.000	0.00	6.60
08/23/00 09:45	19.82	1416.000	1276.000	0.00	6.60
08/23/00 09:50	19.88	1408.000	1270.000	0.00	6.60
08/23/00 09:55	19.94	1401.000	1266.000	0.00	6.59
08/23/00 10:00	19.81	1398.000	1259.000	0.00	6.59
08/23/00 10:05	19.85	1395.000	1257.000	0.00	6.59
08/23/00 10:10	19.85	1392.000	1255.000	0.00	6.59
08/23/00 10:15	19.91	1388.000	1253.000	0.00	6.59
08/23/00 10:20	19.99	1386.000	1254.000	0.00	6.59
08/23/00 10:25	19.96	1384.000	1250.000	0.00	6.58
08/23/00 10:30	20.07	1383.000	1252.000	0.00	6.58
08/23/00 10:35	20.09	1379.000	1250.000	0.00	6.59
08/23/00 10:40	20.10	1375.000	1246.000	0.00	6.58
08/23/00 10:45	20.09	1374.000	1245.000	0.00	6.58
08/23/00 10:50	20.18	1371.000	1245.000	0.00	6.58
08/23/00 10:55	20.19	1368.000	1243.000	0.00	6.57
08/23/00 11:00	20.15	1365.000	1239.000	0.00	6.57
08/23/00 11:05	20.07	1365.000	1236.000	0.00	6.57
08/23/00 11:10	20.05	1359.000	1230.000	0.00	6.57
08/23/00 11:15	20.17	1358.000	1232.000	0.00	6.57

CW2MW31.DAT



08/23/00

08/23/00

08/23/00

08/23/00


08/23/00

08/23/00

DateTime(M/D/Y)


CW2MW31
Permit #: 29-32595
8/23/00

Turbidity




CW2MW31
Permit #: 29-32595
8/23/00

Depth to Water.



CW2MW30
Permit #: 29-32595
8/23/00

Flow Rate



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW2

MW#: 0CW2MW32

NJDEP ID#29-32596

NJDEP CERT # 13461

SAMPLING CONTRACTOR: TVS

SAMPLER: David Sharpe

DATE: 08/23/00

WEATHER: Cloudy.

TIDE: N/A

WELL CONDITION: Good

LNAPLs: N

DNAPLs: N

ELEV. OF INNER CASING SURVEY MARK: N/A ft

INNER CASING DIA: 4 INCH

DEPTH TO WATER: 6.95 ft

Before Purge Start: 6.95 ft

Previous Day: 6.90 ft

After Sampling: 6.9 ft

DEPTH OF WELL: 16.89 ft

DEPTH TO TOP OF SCREEN: N/A ft

DEPTH OF PUMP/TUBE INTAKE: 14.5 ft

TUBING: Food grade Polyethylene 1/4"/Silicon

HEIGHT OF WATER: ft

() X .65 / X 3 =

(.65 for 4", .163 for 2")

GALLONS OF H2O TO BE PURGED: Gal

PURGE METHOD: (FLOW at >100 TO <500 ml/Min): ~~REDIFLO 2~~ 2" REDIFLO 2 GRUNDFOS SUBMERSIBLE PUMP

Purged at 280 mL/Min or

Gal/Min. (ml to gal.: ml(.0002642)=gal)

PURGE RATE: gpm

Hnu READING: 0 ppm (Well)

Hnu READING: 0 ppm (Well Cap)

PURGE START TIME: 12:00

pH 6.74 su

DISSOLVED O₂ 0.00 mg/L

TEMP 20.55 °C

SPECIFIC CONDUCTIVITY 1525 ms/cm

PURGE END TIME: 12:46

pH 6.73 su

DISSOLVED O₂ 0.00 mg/L

TEMP 21.29 °C

SPECIFIC CONDUCTIVITY 1516 ms/cm

DEPTH TO H2O AFTER PURGE AND SAMPLING: 6.9 ft

(SAMPLING METHOD: Through pump, Tubing with flow cell disconnected.)

SAMPLE START TIME: 12:41

pH 6.73 su

DISSOLVED O₂ 0.00 mg/L

TEMP 21.16 °C

SPECIFIC CONDUCTIVITY 1515 ms/cm

SAMPLE END TIME: 12:45

ANALYTES: TAL Metals

COMMENTS:

FIELD READINGS

MW:0CW2MW32

NJDEP ID#: 29-32596

DATE: 8/23/00

Time (Min.)	pH	Temp. (°C)	Cond.	Specific Cond.	Dissolved O ₂ (mg/L)	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/Min)	Notes
12:00	6.74	20.55	1396	1525	0.00	13.9	6.8	280	
12:05	6.74	20.72	1398	1523	0.00	8.4	6.8	280	
12:10	6.74	20.87	1403	1523	0.00	11.1	6.8	280	
12:15	6.74	21.03	1406	1521	0.00	8.2	6.8	280	
12:20	6.74	21.25	1412	1521	0.00	6.6	6.8	280	
12:25	6.74	21.27	1413	1521	0.00	7.4	6.8	280	
12:30	6.74	21.51	1418	1519	0.00	8.3	6.8	280	
12:35	6.73	21.29	1409	1516	0.00	8.7	6.8	280	
12:40	6.73	21.16	1404	1515	0.00	9.0	6.8	280	

Time	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/min)
1200	13.90	6.8	280
1205	8.40	6.8	280
1210	11.10	6.8	280
1215	8.20	6.8	280
1220	6.60	6.8	280
1225	7.40	6.8	280
1230	8.30	6.8	280
1235	8.70	6.8	280
1240	9.00	6.8	280

Cw2mw32
 CW2MW32 Low Flow Data For
 Temp., Sp. Cond., Cond., D.O., pH
 -- Data Report --




=====

From 08/23/00 12:00 to 08/23/00 12:40
 Number of samples: 9

08/23/00	Temp C	SpCond mS/cm	Cond mS/cm	D0	Conc mg/L	pH
08/23/00 12:00	20.55	1525.000	1396.000		0.00	6.74
08/23/00 12:05	20.72	1523.000	1398.000		0.00	6.74
08/23/00 12:10	20.87	1523.000	1403.000		0.00	6.74
08/23/00 12:15	21.03	1521.000	1406.000		0.00	6.74
08/23/00 12:20	21.25	1521.000	1412.000		0.00	6.74
08/23/00 12:25	21.27	1521.000	1413.000		0.00	6.74
08/23/00 12:30	21.51	1519.000	1418.000		0.00	6.74
08/23/00 12:35	21.29	1516.000	1409.000		0.00	6.73
08/23/00 12:40	21.16	1515.000	1404.000		0.00	6.73

CW2MW32 Low Flow Data For

Temp., Sp. Cond., Cond., D.O., pH



08/23/00

08/23/00

08/23/00

08/23/00


08/23/00

08/23/00

{08/23/00}


CW2MW32
Permit #: 29-32596
8/23/00

Turbidity




CW2MW32
Permit #: 29-32596
8/23/00

Depth to Water.



CW2MW32
Permit #: 29-32596
8/23/00

Flow Rate



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW2

MW#: 0CW2MW33

NJDEP ID#29-32597

NJDEP CERT # 13461

SAMPLING CONTRACTOR: TVS

SAMPLER: David Sharpe

DATE: 08/23/00

WEATHER: Cloudy.

TIDE: N/A

WELL CONDITION: Good

LNAPLs: N

DNAPLs: N

ELEV. OF INNER CASING SURVEY MARK: N/A ft

INNER CASING DIA: 4 INCH

DEPTH TO WATER: 8.7 ft

Before Purge Start: 8.7 ft

Previous Day: 8.8 ft

After Sampling: 8.7 ft

DEPTH OF WELL: 16.10 ft

DEPTH TO TOP OF SCREEN: N/A ft

DEPTH OF PUMP/TUBE INTAKE: 14 ft

TUBING: Food grade Polyethylene 1/4"/Silicon

HEIGHT OF WATER: ft

() X .65 / X 3 =

(.65 for 4", .163 for 2")

GALLONS OF H2O TO BE PURGED: Gal

PURGE METHOD: (FLOW at >100 TO <500 ml/Min): ~~REDIFLO 2~~ 2" REDIFLO 2 GRUNDFOS SUBMERSIBLE PUMP

Purged at 230 mL/Min or

Gal/Min. (ml to gal.: ml(.0002642)=gal)

PURGE RATE: gpm

Hnu READING: 0 ppm (Well)

Hnu READING: 0 ppm (Well Cap)

PURGE START TIME: 13:20

pH 6.33 su

DISSOLVED O₂ 0.00 mg/L

TEMP 19.07 °C

SPECIFIC CONDUCTIVITY 886.2 ms/cm

PURGE END TIME: 14:41

pH 6.26 su

DISSOLVED O₂ 0.00 mg/L

TEMP 18.80 °C

SPECIFIC CONDUCTIVITY 1162 ms/cm

DEPTH TO H2O AFTER PURGE AND SAMPLING: 8.7 ft

(SAMPLING METHOD: Through pump, Tubing with flow cell disconnected.)

SAMPLE START TIME: 14:36

pH 6.25 su

DISSOLVED O₂ 0.00 mg/L

TEMP 18.75 °C

SPECIFIC CONDUCTIVITY 1180 ms/cm

SAMPLE END TIME: 14:40

ANALYTES: TAL Metals

COMMENTS:

FIELD READINGS

MW:0CW2MW33

NJDEP ID#: 29-32597

DATE: 8/23/00

Time (Min.)	pH	Temp. (°C)	Cond.	Specific Cond.	Dissolved O ₂ (mg/L)	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/Min)	Notes
13:20	6.33	19.07	785.9	886.2	0.00	145	8.7	230	
13:25	6.32	18.96	785.3	887.7	0.00	85.6	8.7	230	
13:30	6.32	18.93	789.4	892.9	0.00	47.9	8.7	230	
13:35	6.32	19	799.7	903.2	0.00	44.2	8.7	230	
13:40	6.31	19.15	814.4	916.9	0.00	40.2	8.7	230	
13:45	6.31	19.08	821.8	926.5	0.00	34	8.7	230	
13:50	6.3	19	833.3	941.2	0.00	24.4	8.7	230	
13:55	6.3	19.02	844.8	953.9	0.00	20.1	8.7	230	
14:00	6.29	18.97	873.5	987.3	0.00	16.1	8.7	230	
14:05	6.28	18.84	907.4	1028	0.00	14.4	8.7	230	
14:10	6.28	18.9	939.7	1064	0.00	14.4	8.7	230	
14:15	6.27	18.84	968.6	1098	0.00	11.1	8.7	230	
14:20	6.26	18.82	992.9	1126	0.00	10.6	8.7	230	
14:25	6.26	18.81	1015	1151	0.00	9.58	8.7	230	
14:30	6.26	18.8	1025	1162	0.00	9.21	8.7	230	
14:35	6.25	18.75	1039	1180	0.00	7.4	8.7	230	

Time	Salinity (NTU)	Depth to Water (ft)	Flow Rate (ml/min)
1320	145.00	8.7	230
1325	85.60	8.7	230
1330	47.90	8.7	230
1335	44.20	8.7	230
1340	40.20	8.7	230
1345	34.00	8.7	230
1350	24.40	8.7	230
1355	20.10	8.7	230
1400	16.10	8.7	230
1405	14.40	8.7	230
1410	14.40	8.7	230
1415	11.10	8.7	230
1420	10.60	8.7	230
1425	9.68	8.7	230
1430	9.21	8.7	230
1435	7.40	8.7	230

Cw2mw33
 CW2MW33 Low Flow Data For
 Temp., Sp. Cond., Cond., D.O., pH
 -- Data Report --



=====

From 08/23/00 13:20 to 08/23/00 14:35
 Number of samples: 16

08/23/00	Temp C	SpCond mS/cm	Cond mS/cm	DO	Conc mg/L	pH
08/23/00 13:20	19.07	886.200	785.900		0.00	6.33
08/23/00 13:25	18.96	887.700	785.300		0.00	6.32
08/23/00 13:30	18.93	892.900	789.400		0.00	6.32
08/23/00 13:35	19.00	903.200	799.700		0.00	6.32
08/23/00 13:40	19.15	916.900	814.400		0.00	6.31
08/23/00 13:45	19.08	926.500	821.800		0.00	6.31
08/23/00 13:50	19.00	941.200	833.300		0.00	6.30
08/23/00 13:55	19.02	953.900	844.800		0.00	6.30
08/23/00 14:00	18.97	987.300	873.500		0.00	6.29
08/23/00 14:05	18.84	1028.000	907.400		0.00	6.28
08/23/00 14:10	18.90	1064.000	939.700		0.00	6.28
08/23/00 14:15	18.84	1098.000	968.600		0.00	6.27
08/23/00 14:20	18.82	1126.000	992.900		0.00	6.26
08/23/00 14:25	18.81	1151.000	1015.000		0.00	6.26
08/23/00 14:30	18.80	1162.000	1025.000		0.00	6.26
08/23/00 14:35	18.75	1180.000	1039.000		0.00	6.25

CW2MW33 Low Flow Data For

Temp., Sp. Cond., Cond., D.O., pH



08/23/00

08/23/00

08/23/00

08/23/00


08/23/00

08/23/00

(08/23/00)


CW2MW33
Permit #: 29-32597
8/23/00

Turbidity




CW2MW33
Permit #: 29-32597
8/23/00

Depth to Water.



CW2MW33
Permit #: 29-32597
8/23/00

Flow Rate



METALS

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5657
 Sample Prepared: 09/07/00

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	09/07/00	30	200	10.0
Antimony	09/07/00	ND	20	2.0
Arsenic	09/07/00	ND	8	2.0
Barium	09/07/00	ND	2000	0.5
Beryllium	09/07/00	ND	20	0.5
Cadmium	09/07/00	ND	4	0.5
Calcium	09/07/00	120	NLE	20.0
Chromium	09/07/00	ND	100	0.5
Cobalt	09/07/00	ND	NLE	0.5
Copper	09/07/00	ND	1000	2.0
Iron	09/07/00	15.0	300	10.0
Lead	09/07/00	ND	10	1.0
Magnesium	09/07/00	ND	NLE	10.0
Manganese	09/07/00	ND	50	0.5
Mercury	09/07/00	ND	2	0.1
Nickel	09/07/00	ND	100	1.0
Potassium	09/07/00	ND	NLE	40.0
Selenium	09/07/00	ND	50	3.0
Silver	09/07/00	ND	20	1.0
Sodium	09/07/00	890	50000	20.0
Thallium	09/07/00	ND	10	2.0
Vanadium	09/07/00	ND	NLE	0.5
Zinc	09/07/00	19.0	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5657.01
 Sample Received: 08/23/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	09/07/00	ND	200	10.0
Antimony	09/07/00	ND	20	2.0
Arsenic	09/07/00	ND	8	2.0
Barium	09/07/00	ND	2000	0.5
Beryllium	09/07/00	ND	20	0.5
Cadmium	09/07/00	ND	4	0.5
Calcium	09/07/00	ND	NLE	20.0
Chromium	09/07/00	ND	100	0.5
Cobalt	09/07/00	ND	NLE	0.5
Copper	09/07/00	ND	1000	2.0
Iron	09/07/00	ND	300	10.0
Lead	09/07/00	ND	10	1.0
Magnesium	09/07/00	ND	NLE	10.0
Manganese	09/07/00	ND	50	0.5
Mercury	09/07/00	ND	2	0.1
Nickel	09/07/00	ND	100	1.0
Potassium	09/07/00	47.8	NLE	40.0
Selenium	09/07/00	ND	50	3.0
Silver	09/07/00	ND	20	1.0
Sodium	09/07/00	ND	50000	20.0
Thallium	09/07/00	ND	10	2.0
Vanadium	09/07/00	ND	NLE	0.5
Zinc	09/07/00	ND	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5660.01
 Sample Received: 08/25/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	09/07/00	ND	200	10.0
Antimony	09/07/00	ND	20	2.0
Arsenic	09/07/00	ND	8	2.0
Barium	09/07/00	ND	2000	0.5
Beryllium	09/07/00	ND	20	0.5
Cadmium	09/07/00	ND	4	0.5
Calcium	09/07/00	ND	NLE	20.0
Chromium	09/07/00	ND	100	0.5
Cobalt	09/07/00	ND	NLE	0.5
Copper	09/07/00	ND	1000	2.0
Iron	09/07/00	ND	300	10.0
Lead	09/07/00	ND	10	1.0
Magnesium	09/07/00	ND	NLE	10.0
Manganese	09/07/00	ND	50	0.5
Mercury	09/07/00	ND	2	0.1
Nickel	09/07/00	ND	100	1.0
Potassium	09/07/00	ND	NLE	40.0
Selenium	09/07/00	ND	50	3.0
Silver	09/07/00	ND	20	1.0
Sodium	09/07/00	ND	50000	20.0
Thallium	09/07/00	ND	10	2.0
Vanadium	09/07/00	ND	NLE	0.5
Zinc	09/07/00	ND	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5657.05
 Sample Received: 08/23/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Dup

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	09/07/00	65.2	200	10.0
Antimony	09/07/00	ND	20	2.0
Arsenic	09/07/00	ND	8	2.0
Barium	09/07/00	250	2000	0.5
Beryllium	09/07/00	ND	20	0.5
Cadmium	09/07/00	ND	4	0.5
Calcium	09/07/00	55700	NLE	20.0
Chromium	09/07/00	ND	100	0.5
Cobalt	09/07/00	ND	NLE	0.5
Copper	09/07/00	ND	1000	2.0
Iron	09/07/00	70200	300	10.0
Lead	09/07/00	ND	10	1.0
Magnesium	09/07/00	6870	NLE	10.0
Manganese	09/07/00	308	50	0.5
Mercury	09/07/00	ND	2	0.1
Nickel	09/07/00	ND	100	1.0
Potassium	09/07/00	10500	NLE	40.0
Selenium	09/07/00	ND	50	3.0
Silver	09/07/00	ND	20	1.0
Sodium	09/07/00	14100	50000	20.0
Thallium	09/07/00	ND	10	2.0
Vanadium	09/07/00	ND	NLE	0.5
Zinc	09/07/00	38.8	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5660.02
 Sample Received: 08/25/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	09/07/00	65.2	200	10.0
Antimony	09/07/00	4.12	20	2.0
Arsenic	09/07/00	4.27	8	2.0
Barium	09/07/00	61.3	2000	0.5
Beryllium	09/07/00	ND	20	0.5
Cadmium	09/07/00	ND	4	0.5
Calcium	09/07/00	84600	NLE	20.0
Chromium	09/07/00	ND	100	0.5
Cobalt	09/07/00	ND	NLE	0.5
Copper	09/07/00	ND	1000	2.0
Iron	09/07/00	2180	300	10.0
Lead	09/07/00	ND	10	1.0
Magnesium	09/07/00	5950	NLE	10.0
Manganese	09/07/00	19.5	50	0.5
Mercury	09/07/00	ND	2	0.1
Nickel	09/07/00	ND	100	1.0
Potassium	09/07/00	9500	NLE	40.0
Selenium	09/07/00	ND	50	3.0
Silver	09/07/00	ND	20	1.0
Sodium	09/07/00	14200	50000	20.0
Thallium	09/07/00	ND	10	2.0
Vanadium	09/07/00	ND	NLE	0.5
Zinc	09/07/00	33.8	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5657.02
 Sample Received: 08/23/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	09/07/00	42.7	200	10.0
Antimony	09/07/00	2.74	20	2.0
Arsenic	09/07/00	ND	8	2.0
Barium	09/07/00	245	2000	0.5
Beryllium	09/07/00	ND	20	0.5
Cadmium	09/07/00	ND	4	0.5
Calcium	09/07/00	54000	NLE	20.0
Chromium	09/07/00	ND	100	0.5
Cobalt	09/07/00	ND	NLE	0.5
Copper	09/07/00	ND	1000	2.0
Iron	09/07/00	69000	300	10.0
Lead	09/07/00	ND	10	1.0
Magnesium	09/07/00	6610	NLE	10.0
Manganese	09/07/00	300	50	0.5
Mercury	09/07/00	ND	2	0.1
Nickel	09/07/00	ND	100	1.0
Potassium	09/07/00	10600	NLE	40.0
Selenium	09/07/00	ND	50	3.0
Silver	09/07/00	ND	20	1.0
Sodium	09/07/00	12700	50000	20.0
Thallium	09/07/00	ND	10	2.0
Vanadium	09/07/00	ND	NLE	0.5
Zinc	09/07/00	25.2	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5657.03
 Sample Received: 08/23/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	09/07/00	53.7	200	10.0
Antimony	09/07/00	2.36	20	2.0
Arsenic	09/07/00	ND	8	2.0
Barium	09/07/00	51.3	2000	0.5
Beryllium	09/07/00	ND	20	0.5
Cadmium	09/07/00	ND	4	0.5
Calcium	09/07/00	131000	NLE	20.0
Chromium	09/07/00	ND	100	0.5
Cobalt	09/07/00	ND	NLE	0.5
Copper	09/07/00	ND	1000	2.0
Iron	09/07/00	2100	300	10.0
Lead	09/07/00	1.73	10	1.0
Magnesium	09/07/00	12400	NLE	10.0
Manganese	09/07/00	3.61	50	0.5
Mercury	09/07/00	ND	2	0.1
Nickel	09/07/00	ND	100	1.0
Potassium	09/07/00	5600	NLE	40.0
Selenium	09/07/00	ND	50	3.0
Silver	09/07/00	ND	20	1.0
Sodium	09/07/00	25600	50000	20.0
Thallium	09/07/00	ND	10	2.0
Vanadium	09/07/00	ND	NLE	0.5
Zinc	09/07/00	56.8	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5657.04
 Sample Received: 08/23/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	09/07/00	623	200	10.0
Antimony	09/07/00	ND	20	2.0
Arsenic	09/07/00	ND	8	2.0
Barium	09/07/00	189	2000	0.5
Beryllium	09/07/00	ND	20	0.5
Cadmium	09/07/00	ND	4	0.5
Calcium	09/07/00	60800	NLE	20.0
Chromium	09/07/00	ND	100	0.5
Cobalt	09/07/00	ND	NLE	0.5
Copper	09/07/00	ND	1000	2.0
Iron	09/07/00	59800	300	10.0
Lead	09/07/00	2.44	10	1.0
Magnesium	09/07/00	8740	NLE	10.0
Manganese	09/07/00	281	50	0.5
Mercury	09/07/00	ND	2	0.1
Nickel	09/07/00	ND	100	1.0
Potassium	09/07/00	10200	NLE	40.0
Selenium	09/07/00	ND	50	3.0
Silver	09/07/00	ND	20	1.0
Sodium	09/07/00	84100	50000	20.0
Thallium	09/07/00	ND	10	2.0
Vanadium	09/07/00	ND	NLE	0.5
Zinc	09/07/00	29.5	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT

FOR

Directorate of Public Works

Fort Monmouth, NJ 07703


PROJECT: DERA/ Long Term Monitoring
Low Flow/Round II

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
5765.05	0CW2MW30	29-32594	10/03/00
5765.02	0CW2MW31	29-32595	10/03/00
5765.04	0CW2MW32	29-32596	10/03/00
5765.06	0CW2MW33	29-32597	10/03/00


NJDEP Laboratory Certification # 13461

 10-19-00
Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST	Standard Methods, 18 th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B
TARGET COMPOUND LIST	Federal Register 40 CFR Part 136 Appendix A
Base/Neutrals and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticides and PCB's by GC	608

SAMPLING



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (732)532-4359 Fax (732)532-6263 EMail:wrightd@mail1.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

[illegible]

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2 (2700)

MW#: 0CW2MW30

NJDEP ID#29-32594

NJDEP CERT # 13461

SAMPLING CONTRACTOR: TVS

SAMPLER: David Sharpe

DATE: 10/03/00

WEATHER: Sunny, Warm

TIDE: N/A

WELL CONDITION: Good

LNAPLs: N

DNAPLs: N

ELEV. OF INNER CASING SURVEY MARK: N/A ft

INNER CASING DIA: 4 INCH

DEPTH TO WATER: 6.73 ft

Before Purge Start: 6.73 ft

Previous Day: 6.80 ft

After Sampling: 8.86 ft

DEPTH OF WELL: 17.95 ft

DEPTH TO TOP OF SCREEN: N/A ft

DEPTH OF PUMP/TUBE INTAKE: 15.0 ft

TUBING: Food grade Polyethylene 1/4"/Silicon

HEIGHT OF WATER: 11.22 ft

11.22 X .65 X 3 = 21.88

(0.65 for 4", 0.163 for 2")

GALLONS OF H2O TO BE PURGED: 22 Gal

PURGE METHOD:(FLOW at >100 TO <500 ml/Min): PERISTALTIC PUMP

Purged at 300 mL/Min or Gal/Min. (mL to gal: mL (.0002642)=gal)

PURGE RATE: gpm

Hnu READING: 0 ppm (Well)

Hnu READING: 0 ppm (Well Cap)

PURGE START TIME: 13:40

pH 6.44 su

DISSOLVED O₂ 0.35 mg/L

TEMP 20.67 °C

SPECIFIC CONDUCTIVITY 154.8 ms/cm

PURGE END TIME: 14:30

pH 6.45 su

DISSOLVED O₂ 0.15 mg/L

TEMP 21.00 °C

SPECIFIC CONDUCTIVITY 143.4 ms/cm

DEPTH TO H₂O AFTER PURGE AND SAMPLING: 8.86 ft

(SAMPLING METHOD: Through pump, Tubing with flow cell disconnected.)

SAMPLE START TIME: 14:25

pH 6.64 su

DISSOLVED O₂ 0.17 mg/L

TEMP 20.87 °C

SPECIFIC CONDUCTIVITY 144.4 ms/cm

SAMPLE END TIME: 14:29

ANALYTES: TAL Metals

COMMENTS:

FIELD READINGS

MW: 0CW2MW30

NJDEP ID#: 29-32594




DATE: 10/03/00

Time (Min.)	pH	Temp. (°C)	Cond.	Specific Cond.	Dissolved O ₂ (mg/L)	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/Min)	Notes
13:30	6.44	20.67	142	154.8	0.35	23.6	6.73	300	
13:45	6.33	20.73	140.1	152.5	0.24	7.74	6.73	300	
13:50	6.35	20.63	137.9	150.5	0.21	5.91	6.73	300	
13:55	6.35	20.55	136	148.7	0.2	4.97	6.73	300	
14:00	6.38	20.73	134.4	146.4	0.18	4.03	6.73	300	
14:05	6.4	20.89	133.2	144.6	0.17	3.97	6.73	300	
14:10	6.42	20.84	132.1	143.5	0.12	4.4	6.73	300	
14:15	6.43	21.06	132.3	143	0.15	3.58	6.73	300	
14:20	6.45	21	132.4	143.4	0.15	2.93	6.73	300	
14:25	6.46	20.87	133.1	144.4	0.17	3.1	8.86	300	

Time	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/min)
1340	23.60	6.73	300
1345	7.74	6.89	300
1350	5.91	6.98	300
1355	4.97	7.15	300
1400	4.03	7.35	300
1405	3.97	7.57	300
1410	4.40	7.8	300
1415	3.58	7.94	300
1420	2.93	8.3	300
1425	3.10	8.86	300

CW2MW30-2 Low Flow Data For

Temp., Sp. Cond., Cond., D.O., pH



10/03/00

10/03/00

10/03/00

10/03/00

10/03/00

10/03/00

(10/02/00)

Cw2mw30-
 CW2MW30-2 Low Flow Data For
 Temp., Sp. Cond., Cond., D.O., pH
 -- Data Report --


=====

From 10/03/00 13:40 to 10/03/00 14:25
 Number of samples: 10

	Temp	SpCond	Cond	DO	Conc	pH
	C	mS/cm	mS/cm		mg/L	
10/02/00						
10/03/00 13:40	20.67	154.800	142.000		0.35	6.44
10/03/00 13:45	20.73	152.500	140.100		0.24	6.33
10/03/00 13:50	20.63	150.500	137.900		0.21	6.35
10/03/00 13:55	20.55	148.700	136.000		0.20	6.35
10/03/00 14:00	20.73	146.400	134.400		0.18	6.38
10/03/00 14:05	20.89	144.600	133.200		0.17	6.40
10/03/00 14:10	20.84	143.500	132.100		0.12	6.42
10/03/00 14:15	21.06	143.000	132.300		0.15	6.43
10/03/00 14:20	21.00	143.400	132.400		0.15	6.45
10/03/00 14:25	20.87	144.400	133.100		0.17	6.46


CW2MW30
Permit #: 29-32594
10/02/00

Turbidity




CW2MW30
Permit #: 29-32594
10/02/00

Depth to Water.



CW2MW30
Permit #: 29-32594
10/02/00

Flow Rate



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2 (2700)

MW#: 0CW2MW31

NJDEP ID#29-32595

NJDEP CERT # 13461

SAMPLING CONTRACTOR: TVS

SAMPLER: David Sharpe

DATE: 10/03/00

WEATHER: Sunny

TIDE: N/A

WELL CONDITION: Good

LNAPLs: N

DNAPLs: N

ELEV. OF INNER CASING SURVEY MARK: N/A ft

INNER CASING DIA: 4 INCH

DEPTH TO WATER: 7.65ft

Before Purge Start: 7.65 ft

Previous Day: 7.70 ft

After Sampling: 7.40 ft

DEPTH OF WELL: 16.91 ft

DEPTH TO TOP OF SCREEN: N/A ft

DEPTH OF PUMP/TUBE INTAKE: 14.0 ft

HEIGHT OF WATER: 9.26 ft

9.26 X .65 X 3 = 18.06

TUBING: Food grade Polyethylene 1/4"/Silicon

(0.65 for 4", 0.163 for 2")

GALLONS OF H₂O TO BE PURGED: 18 Gal

PURGE METHOD:(FLOW at >100 TO <500 ml/Min): PERISTALTIC PUMP

Purged at 290 mL/Min or Gal/Min. (mL to gal: mL (.0002642)=gal)

PURGE RATE: gpm

Hnu READING: 0 ppm (Well)

Hnu READING: 0 ppm (Well Cap)

PURGE START TIME: 8:45

pH 6.04 su

DISSOLVED O₂ 0.5 mg/L

TEMP 19.47 °C

SPECIFIC CONDUCTIVITY 266.8 ms/cm

PURGE END TIME: 10:50

pH 6.34 su

DISSOLVED O₂ 0.09 mg/L

TEMP 20.61 °C

SPECIFIC CONDUCTIVITY 249.9 ms/cm

DEPTH TO H₂O AFTER PURGE AND SAMPLING: 7.4 ft

(SAMPLING METHOD: Through pump, Tubing with flow cell disconnected.)

SAMPLE START TIME: 10:45

pH 6.34 su

DISSOLVED O₂ 0.09 mg/L

TEMP 20.68 °C

SPECIFIC CONDUCTIVITY 249.8 ms/cm

SAMPLE END TIME: 10:46

ANALYTES: TAL Metals

COMMENTS: Duplicate here.

FIELD READINGS

MW: 0CW2MW31

NJDEP ID#: 29-32595




DATE: 10/03/00

Time (Min.)	pH	Temp. (°C)	Cond.	Specific Cond.	Dissolved O ₂ (mg/L)	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/Min)	Notes
8:45	6.04	19.47	238.6	266.8	0.5	273	7.65	290	
8:50	6.2	19.18	230.2	259	0.17	69	7.65	290	
8:55	6.27	19.26	229.1	257.3	0.11	35	7.65	290	
9:00	6.3	19.25	228.2	256.3	0.11	47	7.65	290	
9:05	6.32	19.23	227.1	255.3	0.1	46.1	7.65	290	
9:10	6.33	19.58	228.7	255.1	0.07	60.8	7.65	290	
9:15	6.33	19.76	228.4	253.8	0.08	65.1	7.65	290	
9:20	6.33	19.87	228.7	253.6	0.09	65.7	7.65	290	
9:25	6.33	19.94	228.5	252.9	0.09	73.2	7.65	290	
9:30	6.33	20.03	228.4	252.4	0.09	71.1	7.65	290	
9:35	6.33	20.08	228.4	252.1	0.09	62.7	7.65	290	
9:40	6.33	20.11	228.4	251.9	0.09	60.5	7.65	290	
9:45	6.33	20.17	228.6	251.8	0.09	60.6	7.65	290	
9:50	6.33	20.22	228.5	251.5	0.07	51.5	7.65	290	
9:55	6.33	20.23	228.1	251	0.09	43.1	7.65	290	
10:00	6.33	20.27	228.7	251.4	0.09	43.6	7.65	290	
10:05	6.33	20.3	228.7	251.3	0.09	42.3	7.65	290	
10:10	6.34	20.29	227.6	250.1	0.09	38.9	7.65	290	
10:15	6.34	20.41	229	251	0.09	39	7.65	290	
10:20	6.34	20.47	228.8	250.5	0.09	35.9	7.65	290	
10:25	6.34	20.46	228.5	250.2	0.09	35	7.65	290	
10:30	6.34	20.52	229	250.4	0.09	33.3	7.65	290	
10:35	6.34	20.59	228.6	249.6	0.09	31.1	7.65	290	
10:40	6.34	20.61	228.9	249.9	0.09	27.7	7.65	290	
10:45	6.34	20.68	229.2	249.8	0.09	34.7	7.65	290	

Time	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/min)
845	273.00	7.65	290
850	69.00	7.65	290
855	35.00	7.65	290
900	47.00	7.65	290
905	46.10	7.65	290
910	60.80	7.65	290
915	65.10	7.65	290
920	65.70	7.65	290
925	73.20	7.65	290
930	71.10	7.65	290
935	62.70	7.65	290
940	60.50	7.65	290
945	60.60	7.6	290
950	51.50	7.6	290
955	43.10	7.6	290
1000	43.60	7.6	290
1005	42.30	7.6	290
1010	38.90	7.6	290
1015	39	7.55	290
1020	35.9	7.55	290
1025	35	7.55	290
1030	33.3	7.55	290
1035	31.1	7.5	290
1040	27.7	7.5	290
1045	34.7	7.4	290

CW2MW31-2 Low Flow Data For

Temp., Sp. Cond., Cond., D.O., pH



10/03/00

10/03/00

10/03/00

10/03/00

10/03/00

10/03/00

(10/02/00)

Cw2mw31-
 CW2MW31-2 Low Flow Data For
 Temp., Sp. Cond., Cond., D.O., pH
 -- Data Report --

=====


From 10/03/00 08:45 to 10/03/00 10:45

Number of samples: 25

	Temp	SpCond	Cond	DO	Conc	pH
10/02/00	C	mS/cm	mS/cm		mg/L	
10/03/00 08:45	19.47	266.800	238.600		0.50	6.04
10/03/00 08:50	19.18	259.000	230.200		0.17	6.20
10/03/00 08:55	19.26	257.300	229.100		0.11	6.27
10/03/00 09:00	19.25	256.300	228.200		0.11	6.30
10/03/00 09:05	19.23	255.300	227.100		0.10	6.32
10/03/00 09:10	19.58	255.100	228.700		0.07	6.33
10/03/00 09:15	19.76	253.800	228.400		0.08	6.33
10/03/00 09:20	19.87	253.600	228.700		0.09	6.33
10/03/00 09:25	19.94	252.900	228.500		0.09	6.33
10/03/00 09:30	20.03	252.400	228.400		0.09	6.33
10/03/00 09:35	20.08	252.100	228.400		0.09	6.33
10/03/00 09:40	20.11	251.900	228.400		0.09	6.33
10/03/00 09:45	20.17	251.800	228.600		0.09	6.33
10/03/00 09:50	20.22	251.500	228.500		0.07	6.33
10/03/00 09:55	20.23	251.000	228.100		0.09	6.33
10/03/00 10:00	20.27	251.400	228.700		0.09	6.33
10/03/00 10:05	20.30	251.300	228.700		0.09	6.33
10/03/00 10:10	20.29	250.100	227.600		0.09	6.34
10/03/00 10:15	20.41	251.000	229.000		0.09	6.34
10/03/00 10:20	20.47	250.500	228.800		0.09	6.34
10/03/00 10:25	20.46	250.200	228.500		0.09	6.34
10/03/00 10:30	20.52	250.400	229.000		0.09	6.34
10/03/00 10:35	20.59	249.600	228.600		0.09	6.34
10/03/00 10:40	20.61	249.900	228.900		0.09	6.34
10/03/00 10:45	20.68	249.800	229.200		0.09	6.34


CW2MW31
Permit #: 29-32595
10/02/00

Turbidity




CW2MW31
Permit #: 29-32595
10/02/00

Depth to Water.



CW2MW31
Permit #: 29-32595
10/02/00

Flow Rate



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2 (2700)

MW#: 0CW2MW32

NJDEP ID#29-32596

NJDEP CERT # 13461

SAMPLING CONTRACTOR: TVS

SAMPLER: David Sharpe

DATE: 10/03/00

WEATHER: Sunny, Warm

TIDE: N/A

WELL CONDITION: Good

LNAPLs: N

DNAPLs: N

ELEV. OF INNER CASING SURVEY MARK: N/A ft

INNER CASING DIA: 4 INCH

DEPTH TO WATER: 7.2ft

Before Purge Start: 7.2 ft

Previous Day: 7.25 ft

After Sampling: 9.14 ft

DEPTH OF WELL: 16.89 ft

DEPTH TO TOP OF SCREEN: N/A ft

DEPTH OF PUMP/TUBE INTAKE: 14.0 ft

TUBING: Food grade Polyethylene 1/4"/Silicon

HEIGHT OF WATER: 9.69 ft

9.69 X .65 X 3 = 18.90

(0.65 for 4", 0.163 for 2")

GALLONS OF H2O TO BE PURGED: 19 Gal

PURGE METHOD:(FLOW at >100 TO <500 ml/Min): PERISTALTIC PUMP

Purged at 290 mL/Min or Gal/Min. (mL to gal: mL (.0002642)=gal)

PURGE RATE: gpm

Hnu READING: 0 ppm (Well)

Hnu READING: 0 ppm (Well Cap)

PURGE START TIME: 11:20

pH 6.47 su

TEMP 20.49 °C

DISSOLVED O₂ 0.15 mg/L

SPECIFIC CONDUCTIVITY 268.3 ms/cm

PURGE END TIME: 12:50

pH 6.78 su

TEMP 21.43 °C

DISSOLVED O₂ 1.05 mg/L

SPECIFIC CONDUCTIVITY 231.5 ms/cm

DEPTH TO H₂O AFTER PURGE AND SAMPLING: 9.14 ft

(SAMPLING METHOD: Through pump, Tubing with flow cell disconnected.)

SAMPLE START TIME: 12:45

pH 6.78 su

TEMP 21.43 °C

DISSOLVED O₂ 1.01 mg/L

SPECIFIC CONDUCTIVITY 230.7 ms/cm

SAMPLE END TIME: 12:49

ANALYTES: TAL Metals

COMMENTS:

FIELD READINGS

MW: 0CW2MW32

NJDEP ID#: 29-32596




DATE: 10/03/00

Time (Min.)	pH	Temp. (°C)	Cond.	Specific Cond.	Dissolved O ₂ (mg/L)	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/Min)	Notes
11:20	6.47	20.49	245.2	268.3	0.15	35.3	7.2	290	
11:25	6.5	20.67	242.4	264.3	0.22	19.1	7.2	290	
11:30	6.55	20.8	233.9	254.3	0.36	18.4	7.2	290	
11:35	6.6	20.8	227.2	247	0.55	12.8	7.2	290	
11:40	6.67	20.97	222.1	246.6	0.77	12.1	7.2	290	
11:45	6.71	21.05	218.4	236.2	0.95	12	7.2	290	
11:50	6.74	21.03	217	234.9	1.08	11	7.2	290	
11:55	6.76	21.17	216.8	233.9	1.16	13.4	7.2	290	
12:00	6.77	21.19	216.5	233.5	1.13	10.4	7.2	290	
12:05	6.77	21.25	217.8	234.6	1.11	10.8	7.2	290	
12:10	6.77	21.27	217.7	234.4	1.12	11.7	7.2	290	
12:15	6.77	21.22	217.1	234	1.06	11.4	7.2	290	
12:20	6.77	21.32	217.3	233.7	1.08	10.1	7.2	290	
12:25	6.78	21.32	216.5	232.9	1.09	11.6	7.2	290	
12:30	6.78	21.35	215.9	232.1	1.1	10.5	7.2	290	
12:35	6.78	21.39	215.8	231.8	1.08	9.25	7.2	290	
12:40	6.78	21.43	215.7	231.5	1.05	9.29	7.2	290	
12:45	6.78	21.43	215	230.7	1.01	10.4	7.2	290	

Time	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/min)
1120	35.30	7.2	290
1125	19.10	7.3	290
1130	18.40	7.4	290
1135	12.80	7.65	290
1140	12.10	7.75	290
1145	12.00	7.9	290
1150	11.00	8.05	290
1155	13.40	8.2	290
1200	10.40	8.35	290
1205	10.80	8.48	290
1210	11.70	8.55	290
1215	11.40	8.65	290
1220	10.10	8.7	290
1225	11.60	8.9	290
1230	10.50	9	290
1235	9.25	9.05	290
1240	9.29	9.1	290
1245	10.40	9.14	290

CW2MW32-2 Low Flow Data For

Temp., Sp. Cond., Cond., D.O., pH



10/03/00

10/03/00

10/03/00

10/03/00

10/03/00

10/03/00

(10/02/00)

Cw2mw32-
 CW2MW32-2 Low Flow Data For
 Temp., Sp. Cond., Cond., D.O., pH
 -- Data Report --


=====

From 10/03/00 11:20 to 10/03/00 12:45
 Number of samples: 18

	Temp	SpCond	Cond	DO	Conc	pH
10/02/00	C	mS/cm	mS/cm		mg/L	
10/03/00 11:20	20.49	268.300	245.200		0.15	6.47
10/03/00 11:25	20.67	264.300	242.400		0.22	6.50
10/03/00 11:30	20.80	254.300	233.900		0.36	6.55
10/03/00 11:35	20.80	247.000	227.200		0.55	6.60
10/03/00 11:40	20.97	240.600	222.100		0.77	6.67
10/03/00 11:45	21.05	236.200	218.400		0.95	6.71
10/03/00 11:50	21.03	234.900	217.000		1.08	6.74
10/03/00 11:55	21.17	233.900	216.800		1.16	6.76
10/03/00 12:00	21.19	233.500	216.500		1.13	6.77
10/03/00 12:05	21.25	234.600	217.800		1.11	6.77
10/03/00 12:10	21.27	234.400	217.700		1.12	6.77
10/03/00 12:15	21.22	234.000	217.100		1.06	6.77
10/03/00 12:20	21.32	233.700	217.300		1.08	6.77
10/03/00 12:25	21.32	232.900	216.500		1.09	6.78
10/03/00 12:30	21.35	232.100	215.900		1.10	6.78
10/03/00 12:35	21.39	231.800	215.800		1.08	6.78
10/03/00 12:40	21.43	231.500	215.700		1.05	6.78
10/03/00 12:45	21.43	230.700	215.000		1.01	6.78


CW2MW32
Permit #: 29-32596
10/02/00

Turbidity




CW2MW32
Permit #: 29-32596
10/02/00

Depth to Water.



CW2MW32
Permit #: 29-32596
10/02/00

Flow Rate



U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2 (2700)

MW#: 0CW2MW33

NJDEP ID#29-32597

NJDEP CERT # 13461

SAMPLING CONTRACTOR: TVS

SAMPLER: David Sharpe

DATE: 10/03/00

WEATHER: Overcast, Warm

TIDE: N/A

WELL CONDITION: Good

LNAPLs: N

DNAPLs: N

ELEV. OF INNER CASING SURVEY MARK: N/A ft

INNER CASING DIA: 4 INCH

DEPTH TO WATER: 8.85ft

Before Purge Start: 8.85 ft

Previous Day: 8.90 ft

After Sampling: 8.90 ft

DEPTH OF WELL: 16.10 ft

DEPTH TO TOP OF SCREEN: N/A ft

DEPTH OF PUMP/TUBE INTAKE: ft

HEIGHT OF WATER: 7.25 ft

7.25 X .65 X 3 = 14.14

TUBING: Food grade Polyethylene 1/4"/Silicon

(0.65 for 4", 0.163 for 2")

GALLONS OF H₂O TO BE PURGED: 14 Gal

PURGE METHOD:(FLOW at >100 TO <500 ml/Min): PERISTALTIC PUMP

Purged at 380 mL/Min or Gal/Min. (mL to gal: mL (.0002642)=gal)

PURGE RATE: gpm

Hnu READING: 0 ppm (Well)

Hnu READING: 0 ppm (Well Cap)

PURGE START TIME: 14:50

pH 6.18 su

DISSOLVED O₂ 1.10 mg/L

TEMP 20.28 °C

SPECIFIC CONDUCTIVITY 153.9 ms/cm

PURGE END TIME: 15:55

pH 5.98 su

DISSOLVED O₂ 0.16 mg/L

TEMP 19.54 °C

SPECIFIC CONDUCTIVITY 207.9 ms/cm

DEPTH TO H₂O AFTER PURGE AND SAMPLING: 8.9 ft

(SAMPLING METHOD: Through pump, Tubing with flow cell disconnected.)

SAMPLE START TIME: 15:50

pH 5.98 su

DISSOLVED O₂ 0.15 mg/L

TEMP 19.55 °C

SPECIFIC CONDUCTIVITY 213.9 ms/cm

SAMPLE END TIME: 15:54

ANALYTES: TAL Metals

COMMENTS:

FIELD READINGS

MW: 0CW2MW33

NJDEP ID#: 29-32597




DATE: 10/03/00

Time (Min.)	pH	Temp. (°C)	Cond.	Specific Cond.	Dissolved O ₂ (mg/L)	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/Min)	Notes
14:50	6.18	20.28	140	153.9	1.1	353	8.85	380	
14:55	6.08	19.42	138.3	154.7	0.97	305	8.85	380	
15:00	6.03	19.32	139.6	156.6	0.53	195	8.85	380	
15:05	6.06	19.35	139.9	156.9	0.53	167	8.85	380	
15:10	6.04	19.35	142.8	160.2	0.48	137	8.85	380	
15:15	6.02	19.39	147.1	164.8	0.41	116	8.85	380	
15:20	6.01	19.35	152.4	170.8	0.35	89.9	8.85	380	
15:25	6	19.51	155.8	174	0.31	68.4	8.85	380	
15:30	6	19.69	162.6	180.9	0.22	49.4	8.85	380	
15:35	5.99	19.63	170.9	190.5	0.21	42.9	8.85	380	
15:40	5.99	19.57	178.4	199	0.19	37.1	8.85	380	
15:45	5.98	19.54	186.2	207.9	0.16	30.4	8.85	380	
15:50	5.98	19.55	191.6	213.9	0.15	27.9	8.85	380	

Time	Turbidity (NTU)	Depth to Water (ft)	Flow Rate (ml/min)
1450	353.00	8.85	380
1455	305.00	8.85	380
1500	195.00	8.85	380
1505	167.00	8.85	380
1510	137.00	8.85	380
1515	116.00	8.85	380
1520	89.90	8.85	380
1525	68.40	8.85	380
1530	49.40	8.85	380
1535	42.90	8.9	380
1540	37.10	8.9	380
1545	30.40	8.9	380
1550	27.90	8.9	380

CW2MW33-2 Low Flow Data For

Temp., Sp. Cond., Cond., D.O., pH



10/03/00

10/03/00

10/03/00

10/03/00

10/03/00

10/03/00

(10/02/00)

Cw2mw33-
CW2MW33-2 Low Flow Data For
Temp., Sp. Cond., Cond., D.O., pH
-- Data Report --

=====


From 10/03/00 14:50 to 10/03/00 15:50

Number of samples: 13

	Temp	SpCond	Cond	DO	Conc	pH
	C	mS/cm	mS/cm		mg/L	
10/02/00						
10/03/00 14:50	20.28	153.900	140.000		1.10	6.18
10/03/00 14:55	19.42	154.700	138.300		0.97	6.08
10/03/00 15:00	19.32	156.600	139.600		0.53	6.03
10/03/00 15:05	19.35	156.900	139.900		0.53	6.06
10/03/00 15:10	19.33	160.200	142.800		0.48	6.04
10/03/00 15:15	19.39	164.800	147.100		0.41	6.02
10/03/00 15:20	19.35	170.800	152.400		0.35	6.01
10/03/00 15:25	19.51	174.000	155.800		0.31	6.00
10/03/00 15:30	19.69	180.900	162.600		0.22	6.00
10/03/00 15:35	19.63	190.500	170.900		0.21	5.99
10/03/00 15:40	19.57	199.000	178.400		0.19	5.99
10/03/00 15:45	19.54	207.900	186.200		0.16	5.98
10/03/00 15:50	19.55	213.900	191.600		0.15	5.98


CW2MW33
Permit #: 29-32597
10/02/00

Turbidity




CW2MW33
Permit #: 29-32597
10/02/00

Depth to Water.



CW2MW33
Permit #: 29-32597
10/02/00

Flow Rate



METALS

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5765
 Sample Prepared: 10/04/00

Site: CW2

Field ID#: Method Blank

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/12/00	41.2	200	10.0
Antimony	10/12/00	ND	20	2.0
Arsenic	10/12/00	ND	8	2.0
Barium	10/12/00	ND	2000	0.5
Beryllium	10/12/00	ND	20	0.5
Cadmium	10/12/00	ND	4	0.5
Calcium	10/12/00	107	NLE	20.0
Chromium	10/12/00	0.616	100	0.5
Cobalt	10/12/00	ND	NLE	0.5
Copper	10/12/00	39.6	1000	2.0
Iron	10/12/00	ND	300	2.0
Lead	10/12/00	ND	10	1.0
Magnesium	10/12/00	45.2	NLE	10.0
Manganese	10/12/00	ND	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/12/00	3.84	100	1.0
Potassium	10/12/00	ND	NLE	40.0
Selenium	10/12/00	ND	50	3.0
Silver	10/12/00	ND	20	1.0
Sodium	10/12/00	708	50000	20.0
Thallium	10/12/00	ND	10	2.0
Vanadium	10/12/00	ND	NLE	0.5
Zinc	10/12/00	12.1	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5765.01
 Sample Received: 10/03/00
 Sample Matrix: Aqueous

Site: CW2

Field ID#: FB

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/12/00	ND	200	10.0
Antimony	10/12/00	ND	20	2.0
Arsenic	10/12/00	ND	8	2.0
Barium	10/12/00	ND	2000	0.5
Beryllium	10/12/00	ND	20	0.5
Cadmium	10/12/00	ND	4	0.5
Calcium	10/12/00	ND	NLE	20.0
Chromium	10/12/00	ND	100	0.5
Cobalt	10/12/00	ND	NLE	0.5
Copper	10/12/00	ND	1000	2.0
Iron	10/12/00	35.6	300	2.0
Lead	10/12/00	ND	10	1.0
Magnesium	10/12/00	ND	NLE	10.0
Manganese	10/12/00	ND	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/12/00	ND	100	1.0
Potassium	10/12/00	ND	NLE	40.0
Selenium	10/12/00	ND	50	3.0
Silver	10/12/00	ND	20	1.0
Sodium	10/12/00	ND	50000	20.0
Thallium	10/12/00	ND	10	2.0
Vanadium	10/12/00	ND	NLE	0.5
Zinc	10/12/00	ND	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5765.03
 Sample Received: 10/03/00
 Sample Matrix: Aqueous

Site: CW2

Field ID#: FD

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/12/00	26.5	200	10.0
Antimony	10/12/00	ND	20	2.0
Arsenic	10/12/00	ND	8	2.0
Barium	10/12/00	238	2000	0.5
Beryllium	10/12/00	ND	20	0.5
Cadmium	10/12/00	ND	4	0.5
Calcium	10/12/00	51600	NLE	20.0
Chromium	10/12/00	1.83	100	0.5
Cobalt	10/12/00	ND	NLE	0.5
Copper	10/12/00	65.4	1000	2.0
Iron	10/12/00	66500	300	2.0
Lead	10/12/00	ND	10	1.0
Magnesium	10/12/00	6360	NLE	10.0
Manganese	10/12/00	277	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/12/00	ND	100	1.0
Potassium	10/12/00	10400	NLE	40.0
Selenium	10/12/00	ND	50	3.0
Silver	10/12/00	ND	20	1.0
Sodium	10/12/00	12000	50000	20.0
Thallium	10/12/00	ND	10	2.0
Vanadium	10/12/00	1.46	NLE	0.5
Zinc	10/12/00	23.3	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5765.02
 Sample Received: 10/03/00
 Sample Matrix: Aqueous

Site: CW2

Field ID#: CW2MW31

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/12/00	38.5	200	10.0
Antimony	10/12/00	ND	20	2.0
Arsenic	10/12/00	ND	8	2.0
Barium	10/12/00	235	2000	0.5
Beryllium	10/12/00	ND	20	0.5
Cadmium	10/12/00	ND	4	0.5
Calcium	10/12/00	50500	NLE	20.0
Chromium	10/12/00	1.11	100	0.5
Cobalt	10/12/00	ND	NLE	0.5
Copper	10/12/00	11.8	1000	2.0
Iron	10/12/00	65000	300	2.0
Lead	10/12/00	ND	10	1.0
Magnesium	10/12/00	6230	NLE	10.0
Manganese	10/12/00	275	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/12/00	ND	100	1.0
Potassium	10/12/00	10100	NLE	40.0
Selenium	10/12/00	ND	50	3.0
Silver	10/12/00	ND	20	1.0
Sodium	10/12/00	11900	50000	20.0
Thallium	10/12/00	ND	10	2.0
Vanadium	10/12/00	1.65	NLE	0.5
Zinc	10/12/00	15.0	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5765.04
 Sample Received: 10/03/00
 Sample Matrix: Aqueous

Site: CW2

Field ID#: CW2MW32

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/12/00	35.1	200	10.0
Antimony	10/12/00	ND	20	2.0
Arsenic	10/12/00	ND	8	2.0
Barium	10/12/00	34.1	2000	0.5
Beryllium	10/12/00	ND	20	0.5
Cadmium	10/12/00	ND	4	0.5
Calcium	10/12/00	103000	NLE	20.0
Chromium	10/12/00	1.85	100	0.5
Cobalt	10/12/00	ND	NLE	0.5
Copper	10/12/00	59.3	1000	2.0
Iron	10/12/00	1630	300	2.0
Lead	10/12/00	ND	10	1.0
Magnesium	10/12/00	9530	NLE	10.0
Manganese	10/12/00	4.59	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/12/00	4.42	100	1.0
Potassium	10/12/00	4160	NLE	40.0
Selenium	10/12/00	ND	50	3.0
Silver	10/12/00	ND	20	1.0
Sodium	10/12/00	18100	50000	20.0
Thallium	10/12/00	ND	10	2.0
Vanadium	10/12/00	3.05	NLE	0.5
Zinc	10/12/00	72.8	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5765.05
 Sample Received: 10/03/00
 Sample Matrix: Aqueous

Site: CW2

Field ID#: CW2MW30

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/12/00	39.5	200	10.0
Antimony	10/12/00	ND	20	2.0
Arsenic	10/12/00	ND	8	2.0
Barium	10/12/00	51.9	2000	0.5
Beryllium	10/12/00	ND	20	0.5
Cadmium	10/12/00	ND	4	0.5
Calcium	10/12/00	64600	NLE	20.0
Chromium	10/12/00	2.06	100	0.5
Cobalt	10/12/00	ND	NLE	0.5
Copper	10/12/00	25.1	1000	2.0
Iron	10/12/00	834	300	2.0
Lead	10/12/00	ND	10	1.0
Magnesium	10/12/00	4540	NLE	10.0
Manganese	10/12/00	7.75	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/12/00	4.67	100	1.0
Potassium	10/12/00	9160	NLE	40.0
Selenium	10/12/00	ND	50	3.0
Silver	10/12/00	ND	20	1.0
Sodium	10/12/00	9420	50000	20.0
Thallium	10/12/00	ND	10	2.0
Vanadium	10/12/00	2.09	NLE	0.5
Zinc	10/12/00	18.7	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 5765.06
Sample Received: 10/03/00
Sample Matrix: Aqueous

Site: CW2

Field ID#: CW2MW33

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/12/00	31.9	200	10.0
Antimony	10/12/00	ND	20	2.0
Arsenic	10/12/00	ND	8	2.0
Barium	10/12/00	175	2000	0.5
Beryllium	10/12/00	ND	20	0.5
Cadmium	10/12/00	ND	4	0.5
Calcium	10/12/00	51600	NLE	20.0
Chromium	10/12/00	2.63	100	0.5
Cobalt	10/12/00	ND	NLE	0.5
Copper	10/12/00	28.9	1000	2.0
Iron	10/12/00	45500	300	2.0
Lead	10/12/00	ND	10	1.0
Magnesium	10/12/00	5490	NLE	10.0
Manganese	10/12/00	257	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/12/00	2.69	100	1.0
Potassium	10/12/00	10200	NLE	40.0
Selenium	10/12/00	ND	50	3.0
Silver	10/12/00	ND	20	1.0
Sodium	10/12/00	9890	50000	20.0
Thallium	10/12/00	ND	10	2.0
Vanadium	10/12/00	1.34	NLE	0.5
Zinc	10/12/00	36.8	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT

FOR

Directorate of Public Works

Fort Monmouth, NJ 07703


PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
5784.04	0CW2MW30	29-32594	10/12/00
5784.05	0CW2MW31	29-32595	10/12/00
5784.06	0CW2MW32	29-32596	10/12/00
5784.07	0CW2MW33	29-32597	10/12/00

NJDEP Laboratory Certification # 13461

 11-15-00
Daniel Wright/Date:
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST	Standard Methods, 18 th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B
TARGET COMPOUND LIST	Federal Register 40 CFR Part 136 Appendix A
Base/Neutrals and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticides and PCB's by GC	608

[illegible]

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 10/12/00
WEATHER: Sunny, cool.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.71 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.31 ft
DEPTH OF WELL: 17.95 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 10.64 ft
(10.64) X .65 X 3 = 20.74
GALLONS OF H2O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 07:50

pH 6.88 su

DISSOLVED O2 5.57 ppm

TEMP 19.7 °C

SPECIFIC CONDUCTIVITY 307 us/cm

PURGE END TIME: 08:21

pH 6.77 su

DISSOLVED O2 4.10 ppm

TEMP 19.2 °C

SPECIFIC CONDUCTIVITY 298 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 12.92 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 22 gal

SAMPLE START TIME: 09:22

pH 6.76 su

DISSOLVED O2 4.07 ppm

TEMP 19.2 °C

SPECIFIC CONDUCTIVITY 297 us/cm

SAMPLE END TIME: 09:29

COMMENTS:

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 10/12/00
WEATHER: Sunny, cool.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.88 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.16 ft
DEPTH OF WELL: 16.91 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 9.75 ft
(9.75) X .65 X 3 = 19.01
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 07:55

pH 6.67 su
DISSOLVED O2 5.31 ppm

TEMP 19.7 °C
SPECIFIC CONDUCTIVITY 407 us/cm

PURGE END TIME: 09:17

pH 6.56 su
DISSOLVED O2 4.12 ppm

TEMP 19.1 °C
SPECIFIC CONDUCTIVITY 397 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 10.07 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 09:18

pH 6.56 su
DISSOLVED O2 4.10 ppm

TEMP 19.2 °C
SPECIFIC CONDUCTIVITY 398 us/cm

SAMPLE END TIME: 09:22

COMMENTS: Cloudy, orange.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 10/12/00
WEATHER: Sunny, cool.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.38 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.35 ft
DEPTH OF WELL: 16.89 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 9.54 ft
(9.54) X .65 X 3 = 18.60
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:00

pH 6.79 su

DISSOLVED O2 5.48 ppm

TEMP 19.5 °C

SPECIFIC CONDUCTIVITY 304 us/cm

PURGE END TIME: 09:22

pH 6.73 su

DISSOLVED O2 4.13 ppm

TEMP 19.0 °C

SPECIFIC CONDUCTIVITY 294 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 15.62 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 09:30

pH 6.73 su

DISSOLVED O2 4.11 ppm

TEMP 19.1 °C

SPECIFIC CONDUCTIVITY 294 us/cm

SAMPLE END TIME: 09:39

COMMENTS: Large drain down, slow flow. Recovered slowly. Started clearing, became very cloudy and orange.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW33
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 10/12/00
WEATHER: Sunny, cool.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.09 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 9.11 ft
DEPTH OF WELL: 16.10 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 6.99 ft
(6.99) X .65 X 3 = 13.63
GALLONS OF H2O TO BE PURGED: 14 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 08:05

pH 6.99 su

DISSOLVED O2 5.11 ppm

TEMP 19.4 °C

SPECIFIC CONDUCTIVITY 404 us/cm

PURGE END TIME: 09:06

pH 6.91 su

DISSOLVED O2 4.10 ppm

TEMP 18.7 °C

SPECIFIC CONDUCTIVITY 399 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.98 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 14 gal

SAMPLE START TIME: 09:07

pH 6.90 su

DISSOLVED O2 4.07 ppm

TEMP 18.8 °C

SPECIFIC CONDUCTIVITY 398 us/cm

SAMPLE END TIME: 09:16

COMMENTS: Cloudy, orange tinge. DUP here.

**US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEP CERTIFICATION # 13461**

Definition of Qualifiers

MDL : Method Detection Limit
J : Compound Identified Below Detection Limit
B : Compound is in Both Sample and Blank
D : Results are from a Dilution of the Sample
U : Compound Searched for but not Detected
E : Compound Exceeds Calibration Limit

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB008507.D**
 Operator **Skelton**
 Date Acquired **17 Oct 2000 11:49 am**

Sample Name **Vblk249**
 Field ID **Vblk249**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Vblk249

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5784 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: Vblk249
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB008507.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: not dec. Date Analyzed: 10/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB008514.D**
 Operator **Skelton**
 Date Acquired **17 Oct 2000 5:35 pm**

Sample Name **5784.01**
 Field ID **Trip Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone	9.34	178997	7.29 ug/L	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Trip Blank

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5784 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5784.01
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB008514.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: not dec. _____ Date Analyzed: 10/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB008515.D**
 Operator **Skelton**
 Date Acquired **17 Oct 2000 6:15 pm**

Sample Name **5784.02**
 Field ID **Field Blank**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone	9.28	127641	5.32 ug/L	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Field Blank

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5784 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5784.02
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB008515.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: not dec. _____ Date Analyzed: 10/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB008516.D**
 Operator **Skelton**
 Date Acquired **17 Oct 2000 6:55 pm**

Sample Name **5784.03**
 Field ID **Dupe**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

Dupe

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5784 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5784.03
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB008516.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: not dec. _____ Date Analyzed: 10/17/00
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB008517.D**
 Operator **Skelton**
 Date Acquired **17 Oct 2000 7:35 pm**

Sample Name **5784.04**
 Field ID **0CW2MW30**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW30

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5784 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5784.04
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB008517.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: not dec. Date Analyzed: 10/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB008518.D**
 Operator **Skelton**
 Date Acquired **17 Oct 2000 8:15 pm**

Sample Name **5784.05**
 Field ID **0CW2MW31**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW31

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5784 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5784.05
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB008518.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: not dec. _____ Date Analyzed: 10/17/00
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB008519.D**
 Operator **Skelton**
 Date Acquired **17 Oct 2000 8:55 pm**

Sample Name **5784.06**
 Field ID **0CW2MW32**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW32

Lab Name: FMETL Project: LTM
NJDEP#: 13461 Case No.: 5784 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5784.06
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VB008519.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: not dec. _____ Date Analyzed: 10/17/00
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File **VB008520.D**
 Operator **Skelton**
 Date Acquired **17 Oct 2000 9:36 pm**

Sample Name **5784.07**
 Field ID **0CW2MW33**
 Sample Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/l)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156-59-4	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6 2-Sept-9

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Lab ID.

0CW2MW33

Lab Name: FMETLProject: LTMNJDEP#: 13461Case No.: 5784Location: CW2

SDG No.: _____

Matrix: (soil/water) WATERLab Sample ID: 5784.07Sample wt/vol: 5.0 (g/ml) MLLab File ID: VB008520.DLevel: (low/med) LOWDate Received: 10/12/00

% Moisture: not dec. _____

Date Analyzed: 10/17/00GC Column: RTX502 ID: 0.25 (mm)Dilution Factor: 1.0

Soil Extract Volume: _____ (uL)

Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04559.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **Sblk427**
 Misc Info **Sblk427 A 001013**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04559.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **Sblk427**
 Misc Info **Sblk427 A 001013**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Sblk427

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 5784 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: Sblk427
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04559.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/13/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/16/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04561.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04561.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.02**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Field Blank

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 5784 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 5784.02
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04561.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: decanted: (Y/N) N Date Extracted: 10/13/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/16/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
------------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04562.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.03**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04562.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.03**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Dupe

Lab Name: FMETL Lab Code 13461

Project: LTM Case No.: 5784 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5784.03

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04562.D

Level: (low/med) LOW Date Received: 10/12/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/13/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/16/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.81	6	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04563.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.04**
 Misc Info **0CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04563.D**

Operator **Bhaskar**

Date Acquired **16-Oct-00**

Sample Name **5784.04**

Misc Info **0CW2MW30**

Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
D= Value from dilution
B= Compound in Related Blank
PQL= Practical Quantitation Limit

MDL= Method Detection Limit
NLE= No Limit Established
R.T.=Retention Time

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW30

Lab Name: FMETL Lab Code 13461

Project: LTM Case No.: 5784 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5784.04

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04563.D

Level: (low/med) LOW Date Received: 10/12/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/13/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/16/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.81	6	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04564.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04564.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.05**
 Misc Info **0CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW31

Lab Name: FMETL Lab Code 13461

Project: LTM Case No.: 5784 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 5784.05

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04564.D

Level: (low/med) LOW Date Received: 10/12/00

% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/13/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/16/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.81	5	J
2. 003687-45-4	9-Octadecenoic acid (Z)-, 9-octad	32.71	23	JN

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04565.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04565.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.06**
 Misc Info **0CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW32

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 5784 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 5784.06
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04565.D
Level: (low/med) LOW Date Received: 10/12/00
% Moisture: _____ decanted: (Y/N) N Date Extracted: 10/13/00
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/16/00
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 2 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.80	7	J
2. 000105-60-2	Caprolactam	14.14	16	JN

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04568.D**
 Operator **Bhaskar**
 Date Acquired **16-Oct-00**

Sample Name **5784.07**
 Misc Info **0CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
108-60-1	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name BNA04568.D

Operator Bhaskar

Date Acquired 16-Oct-00

Sample Name 5784.07

Misc Info 0CW2MW33

Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate			not detected	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range

D= Value from dilution

B= Compound in Related Blank

PQL= Practical Quantitation Limit

MDL= Method Detection Limit

NLE= No Limit Established

R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

0CW2MW33

Lab Name: FMETL Lab Code 13461

Project: LTM Case No.: 5784 Location: CW2 SDG No.:

Matrix: (soil/water) WATER Lab Sample ID: 5784.07

Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04568.D

Level: (low/med) LOW Date Received: 10/12/00

% Moisture: decanted: (Y/N) N Date Extracted: 10/13/00

Concentrated Extract Volume: 1000 (uL) Date Analyzed: 10/16/00

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 3 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	6.80	7	J
2. 000112-92-5	1-Octadecanol	27.50	6	JN
3. 003687-45-4	9-Octadecenoic acid (Z)-, 9-octad	32.73	57	JN

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	PBLK606
	DPW, SELFM-PW-EV	Date Rec'd:	
	Bldg. 173	Extraction Date:	10/16/00
	Ft. Monmouth, NJ 07703	Analysis Date:	10/16/00
Analysis:	EPA Method 608	Location :	
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

MDL = Method Detection Limit

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

NLE = No Limit Established

PQL = Practical Quantitation Limit

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5784.02
Date Rec'd: 10/12/00
Extraction Date: 10/16/00
Analysis Date: 10/17/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: Field Blank

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	5784.03
	DPW, SELFM-PW-EV	Date Rec'd:	10/12/00
	Bldg. 173	Extraction Date:	10/16/00
	Ft. Monmouth, NJ 07703	Analysis Date:	10/17/00
Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	Dupe
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides 2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5784.04
Date Rec'd: 10/12/00
Extraction Date: 10/16/00
Analysis Date: 10/17/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: 0CW2MW30

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	5784.05
	DPW, SELFM-PW-EV	Date Rec'd:	10/12/00
	Bldg. 173	Extraction Date:	10/16/00
	Ft. Monmouth, NJ 07703	Analysis Date:	10/17/00
Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	C0CW2MW31
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	5784.06
	DPW, SELFM-PW-EV	Date Rec'd:	10/12/00
	Bldg. 173	Extraction Date:	10/16/00
	Ft. Monmouth, NJ 07703	Analysis Date:	10/17/00

Analysis:	EPA Method 608	Location :	CW2
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	0CW2MW32
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 5784.07
Date Rec'd: 10/12/00
Extraction Date: 10/16/00
Analysis Date: 10/17/00

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2
Field ID: 0CW2MW33

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5784
 Sample Prepared: 10/17/00

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Method Blank

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/19/00	12.2	200	10.0
Antimony	10/19/00	ND	20	2.0
Arsenic	10/19/00	ND	8	2.0
Barium	10/19/00	ND	2000	0.5
Beryllium	10/19/00	ND	20	0.5
Cadmium	10/19/00	ND	4	0.5
Calcium	10/19/00	85.3	NLE	20.0
Chromium	10/19/00	ND	100	0.5
Cobalt	10/19/00	ND	NLE	0.5
Copper	10/19/00	ND	1000	2.0
Iron	10/19/00	28.8	300	2.0
Lead	10/19/00	ND	10	1.0
Magnesium	10/19/00	ND	NLE	10.0
Manganese	10/19/00	ND	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/19/00	ND	100	1.0
Potassium	10/19/00	ND	NLE	40.0
Selenium	10/19/00	ND	50	3.0
Silver	10/19/00	ND	20	1.0
Sodium	10/19/00	171	50000	20.0
Thallium	10/19/00	ND	10	2.0
Vanadium	10/19/00	0.584	NLE	0.5
Zinc	10/19/00	12.5	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5784.02
 Sample Received: 10/12/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/19/00	30.8	200	10.0
Antimony	10/19/00	ND	20	2.0
Arsenic	10/19/00	ND	8	2.0
Barium	10/19/00	ND	2000	0.5
Beryllium	10/19/00	ND	20	0.5
Cadmium	10/19/00	ND	4	0.5
Calcium	10/19/00	126	NLE	20.0
Chromium	10/19/00	ND	100	0.5
Cobalt	10/19/00	ND	NLE	0.5
Copper	10/19/00	ND	1000	2.0
Iron	10/19/00	ND	300	2.0
Lead	10/19/00	ND	10	1.0
Magnesium	10/19/00	ND	NLE	10.0
Manganese	10/19/00	ND	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/19/00	ND	100	1.0
Potassium	10/19/00	ND	NLE	40.0
Selenium	10/19/00	ND	50	3.0
Silver	10/19/00	ND	20	1.0
Sodium	10/19/00	ND	50000	20.0
Thallium	10/19/00	ND	10	2.0
Vanadium	10/19/00	ND	NLE	0.5
Zinc	10/19/00	ND	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5784.03
 Sample Received: 10/12/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/19/00	110	200	10.0
Antimony	10/19/00	ND	20	2.0
Arsenic	10/19/00	2.43	8	2.0
Barium	10/19/00	146	2000	0.5
Beryllium	10/19/00	ND	20	0.5
Cadmium	10/19/00	ND	4	0.5
Calcium	10/19/00	36200	NLE	20.0
Chromium	10/19/00	1.63	100	0.5
Cobalt	10/19/00	ND	NLE	0.5
Copper	10/19/00	ND	1000	2.0
Iron	10/19/00	40900	300	2.0
Lead	10/19/00	ND	10	1.0
Magnesium	10/19/00	4680	NLE	10.0
Manganese	10/19/00	183	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/19/00	ND	100	1.0
Potassium	10/19/00	9490	NLE	40.0
Selenium	10/19/00	ND	50	3.0
Silver	10/19/00	ND	20	1.0
Sodium	10/19/00	20400	50000	20.0
Thallium	10/19/00	ND	10	2.0
Vanadium	10/19/00	1.52	NLE	0.5
Zinc	10/19/00	26.9	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5784.04
 Sample Received: 10/12/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/19/00	100	200	10.0
Antimony	10/19/00	ND	20	2.0
Arsenic	10/19/00	3.95	8	2.0
Barium	10/19/00	67.0	2000	0.5
Beryllium	10/19/00	ND	20	0.5
Cadmium	10/19/00	ND	4	0.5
Calcium	10/19/00	67000	NLE	20.0
Chromium	10/19/00	3.00	100	0.5
Cobalt	10/19/00	ND	NLE	0.5
Copper	10/19/00	35.4	1000	2.0
Iron	10/19/00	8150	300	2.0
Lead	10/19/00	ND	10	1.0
Magnesium	10/19/00	5060	NLE	10.0
Manganese	10/19/00	39.1	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/19/00	1.95	100	1.0
Potassium	10/19/00	8770	NLE	40.0
Selenium	10/19/00	ND	50	3.0
Silver	10/19/00	ND	20	1.0
Sodium	10/19/00	20200	50000	20.0
Thallium	10/19/00	ND	10	2.0
Vanadium	10/19/00	2.67	NLE	0.5
Zinc	10/19/00	38.1	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5784.05
 Sample Received: 10/12/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/19/00	20.6	200	10.0
Antimony	10/19/00	ND	20	2.0
Arsenic	10/19/00	ND	8	2.0
Barium	10/19/00	288	2000	0.5
Beryllium	10/19/00	ND	20	0.5
Cadmium	10/19/00	ND	4	0.5
Calcium	10/19/00	49800	NLE	20.0
Chromium	10/19/00	0.968	100	0.5
Cobalt	10/19/00	ND	NLE	0.5
Copper	10/19/00	6.12	1000	2.0
Iron	10/19/00	62100	300	2.0
Lead	10/19/00	ND	10	1.0
Magnesium	10/19/00	6170	NLE	10.0
Manganese	10/19/00	294	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/19/00	ND	100	1.0
Potassium	10/19/00	9980	NLE	40.0
Selenium	10/19/00	ND	50	3.0
Silver	10/19/00	ND	20	1.0
Sodium	10/19/00	11300	50000	20.0
Thallium	10/19/00	ND	10	2.0
Vanadium	10/19/00	ND	NLE	0.5
Zinc	10/19/00	27.3	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5784.06
 Sample Received: 10/12/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/19/00	238	200	10.0
Antimony	10/19/00	ND	20	2.0
Arsenic	10/19/00	4.55	8	2.0
Barium	10/19/00	166	2000	0.5
Beryllium	10/19/00	ND	20	0.5
Cadmium	10/19/00	ND	4	0.5
Calcium	10/19/00	73300	NLE	20.0
Chromium	10/19/00	3.05	100	0.5
Cobalt	10/19/00	ND	NLE	0.5
Copper	10/19/00	31.0	1000	2.0
Iron	10/19/00	39900	300	2.0
Lead	10/19/00	ND	10	1.0
Magnesium	10/19/00	7890	NLE	10.0
Manganese	10/19/00	326	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/19/00	2.71	100	1.0
Potassium	10/19/00	8360	NLE	40.0
Selenium	10/19/00	ND	50	3.0
Silver	10/19/00	ND	20	1.0
Sodium	10/19/00	14800	50000	20.0
Thallium	10/19/00	ND	10	2.0
Vanadium	10/19/00	6.87	NLE	0.5
Zinc	10/19/00	119	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 5784.07
 Sample Received: 10/12/00
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW33

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	10/19/00	109	200	10.0
Antimony	10/19/00	ND	20	2.0
Arsenic	10/19/00	3.69	8	2.0
Barium	10/19/00	144	2000	0.5
Beryllium	10/19/00	ND	20	0.5
Cadmium	10/19/00	ND	4	0.5
Calcium	10/19/00	37300	NLE	20.0
Chromium	10/19/00	1.17	100	0.5
Cobalt	10/19/00	ND	NLE	0.5
Copper	10/19/00	165	1000	2.0
Iron	10/19/00	38800	300	2.0
Lead	10/19/00	29.7	10	1.0
Magnesium	10/19/00	4720	NLE	10.0
Manganese	10/19/00	188	50	0.5
Mercury	10/17/00	ND	2	0.1
Nickel	10/19/00	4.79	100	1.0
Potassium	10/19/00	9320	NLE	40.0
Selenium	10/19/00	ND	50	3.0
Silver	10/19/00	ND	20	1.0
Sodium	10/19/00	19800	50000	20.0
Thallium	10/19/00	ND	10	2.0
Vanadium	10/19/00	1.40	NLE	0.5
Zinc	10/19/00	257	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	9100	69	ND	ND	ND	6.45				V,S,P,M
07/10/1997	FMETL	12590	73	25	5.0	ND	7.05				V,S,P,M
10/22/1997	FMETL	34800	171	175	5.0	5.0	7.60				V,S,P,M
01/08/1998	FMETL	2795	5.0	204	ND	4.0	5.20				V,S,P,M
04/07/1998	FMETL	3504	39.3	196	5.6	ND	6.56				V,S,P,M
07/14/1998	FMETL	10900	57.8	65.7	ND	ND	6.89				V,S,P,M
11/24/1998	FMETL	27500	182	ND	11.5	3.15	7.86				V,S,P,M
02/11/1999	FMETL	11000	100	505	8.3	ND	7.24				V,S,P,M
06/09/1999	FMETL	8210	145	521	6.33	ND	7.21				V,S,P,M
08/04/1999	FMETL	44800	212	304	9.05	6.02	7.43				V,S,P,M
11/03/1999	FMETL	6540	36.3	92.7	6.06	ND	7.02				V,S,P,M
02/15/2000	FMETL	1840	2.69	20.4	ND	ND	7.02				V,S,P,M
05/08/2000	FMETL	7410	73.1	105	ND	46.6	7.15				V,S,P,M
05/08/2000D	FMETL	8090	74.9	133	ND	13.7	7.15				V,S,P,M
08/02/2000	FMETL	2040	15.2	ND	ND	21.8	6.86				V,S,P,M
10/12/2000	FMETL	8150	39.4	100	3.95	ND	7.31				V,S,P,M

SOURCE: 0CW2MW30

Sampling Dates:

04/24/1997 - 10/12/2000

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 1 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW30

Sampling Dates:
04/24/1997 - 10/12/2000

LEGEND:

PARAMETER

- o = Date Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 1 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	59900	277	ND	ND	ND	6.38				V,S,P,M
07/10/1997	FMETL	11830	267	ND	1.0	ND	7.00				V,S,P,M
10/22/1997	FMETL	52300	243	93	ND	6.0	7.50				V,S,P,M
01/08/1998	FMETL	68450	240	129	ND	25	6.30				V,S,P,M
04/07/1998	FMETL	115100	266	ND	ND	ND	6.35				V,S,P,M
07/14/1998	FMETL	83600	311	390	ND	4.85	6.71				V,S,P,M
11/24/1998	FMETL	72800	322	ND	ND	2.33	7.78				V,S,P,M
02/11/1999	FMETL	71900	316	ND	ND	ND	7.07				V,S,P,M
06/09/1999	FMETL	104000	326	27.9	ND	ND	7.15				V,S,P,M
08/04/1999	FMETL	77500	347	ND	ND	ND	7.65				V,S,P,M
11/03/1999	FMETL	64600	309	14.9	ND	ND	7.18				V,S,P,M
02/15/2000	FMETL	111000	301	11.7	ND	ND	7.03				V,S,P,M
05/08/2000	FMETL	86000	343	ND	ND	ND	6.96				V,S,P,M
08/02/2000	FMETL	68900	294	14.7	ND	2.44	6.73				V,S,P,M
10/12/2000	FMETL	62100	294	20.6	ND	ND	7.16				V,S,P,M

SOURCE: 0CW2MW31

Sampling Dates:
04/24/1997 - 10/12/2000

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 2 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW31

Sampling Dates:

04/24/1997 - 10/12/2000

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 2 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	18400	125	ND	ND	ND	6.65				V,S,P,M
07/10/1997	FMETL	270	181	595	ND	ND	7.20				V,S,P,M
10/22/1997	FMETL	51100	260	297	ND	7.0	7.70				V,S,P,M
01/08/1998	FMETL	1484	3.7	163	ND	ND	4.50				V,S,P,M
04/07/1998	FMETL	19280	287	ND	ND	ND	6.81				V,S,P,M
07/14/1998	FMETL	67500	287	78.1	2.51	3.99	7.06				V,S,P,M
11/24/1998	FMETL	106000	342	166	9.32	4.08	7.94				V,S,P,M
02/11/1999	FMETL	4480	7.02	137	ND	ND	7.33				V,S,P,M
06/09/1999	FMETL	64300	310	59.5	ND	ND	7.49				V,S,P,M
08/04/1999	FMETL	76000	369	67.4	ND	ND	7.85				V,S,P,M
11/03/1999	FMETL	11500	27	162	4.09	ND	6.53				V,S,P,M
02/15/2000	FMETL	11300	53.9	95.7	ND	ND	6.54				V,S,P,M
02/15/2000D	FMETL	112000	297	53.1	ND	ND	6.54				V,S,P,M
05/08/2000	FMETL	55700	382	51.4	ND	ND	7.29				V,S,P,M
08/02/2000	FMETL	4700	8.74	21.8	4.14	2.96	5.93				V,S,P,M
08/02/2000D	FMETL	4130	7.99	28.1	ND	38.3	5.93				V,S,P,M
10/12/2000	FMETL	39900	326	238	4.55	ND	7.35				V,S,P,M

SOURCE: 0CW2MW32

Sampling Dates:

04/24/1997 - 10/12/2000

NOTES:




FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 3 of 4






U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW32

Sampling Dates:
04/24/1997 - 10/12/2000



LEGEND:

PARAMETER

o = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 3 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	88600	424	ND	ND	ND	8.95				V,S,P,M
07/10/1997	FMETL	10260	519	2.1	1.0	ND	9.10				V,S,P,M
10/22/1997	FMETL	26800	151	94	ND	4.0	9.10				V,S,P,M
01/08/1998	FMETL	104700	342	217	6.0	4.0	9.00				V,S,P,M
04/07/1998	FMETL	19780	110	119	3.4	ND	9.50				V,S,P,M
07/14/1998	FMETL	35900	130	411	ND	4.19	9.09				V,S,P,M
11/24/1998	FMETL	25400	87.8	125	ND	ND	9.13				V,S,P,M
02/11/1999	FMETL	11300	81.2	67.8	ND	ND	8.13				V,S,P,M
06/09/1999	FMETL	69600	214	336	5.82	ND	9.13				V,S,P,M
08/04/1999	FMETL	35900	149	69	8	3.25	9.15				V,S,P,M
11/03/1999	FMETL	19500	47.2	52.8	ND	ND	6.14				V,S,P,M
02/15/2000	FMETL	54400	201	96.2	2.67	3.77	9.09				V,S,P,M
05/08/2000	FMETL	36500	242	29.3	ND	ND	8.13				V,S,P,M
08/02/2000	FMETL	13400	81.4	38.2	ND	1.50	9.12				V,S,P,M
10/12/2000	FMETL	38800	188	109	3.69	29.7	9.11				V,S,P,M
10/12/2000D	FMETL	40900	183	110	2.43	ND	9.11				V,S,P,M

SOURCE: 0CW2MW33

Sampling Dates:
04/24/1997 - 10/12/2000

NOTES:

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 4 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732)532-6224 FAX: (732)532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING



ANALYTICAL DATA REPORT

FOR

Directorate of Public Works

Fort Monmouth, NJ 07703


PROJECT : DERA/ Long Term Monitoring

SAMPLE LOCATION AND IDENTIFICATION

SITE: CW-2

LABORATORY ID #	MONITOR WELL#	NJDEP WELL ID#	SAMPLE DATE
53/146	0CW2MW30	29-32594	01/11/01
54/147	0CW2MW31	29-32595	01/11/01
55/148	0CW2MW32	29-32596	01/11/01
56/149	0CW2MW33	29-32597	01/11/01

NJDEP Laboratory Certification # 13461


Daniel Wright/Date: 2-7-01
Laboratory Director

METHODOLOGY SUMMARY

PARAMETER	REFERENCE
TARGET ANALYTE LIST	Standard Methods, 18 th ed.
Aluminum	3120B
Antimony	3120B
Arsenic	3120B
Barium	3120B
Beryllium	3120B
Cadmium	3120B
Calcium	3120B
Chromium	3120B
Cobalt	3120B
Copper	3120B
Iron	3120B
Lead	3120B
Magnesium	3120B
Manganese	3120B
Mercury	3112B
Nickel	3120B
Potassium	3120B
Selenium	3120B
Silver	3120B
Sodium	3120B
Thallium	3120B
Vanadium	3120B
Zinc	3120B
TARGET COMPOUND LIST	Federal Register 40 CFR Part 136 Appendix A
Base/Neutrals and Acid Extractables by GC/MS	625
Purgeable Organics by GC/MS	624
Pesticides and PCB's by GC	608



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (732)532-4359 Fax (732)532-6263 EMail:wrightd@mail1.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

[illegible]

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW30
NJDEP ID #: 29-32594
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 01/11/01
WEATHER: Sunny, cold.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.71 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.32 ft
DEPTH OF WELL: 17.95 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 10.63 ft
 $(10.63) \times .65 \times 3 = 20.72$
GALLONS OF H2O TO BE PURGED: 21 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 11:45
pH 6.88 su
DISSOLVED O2 5.81 ppm
TEMP 12.5 °C
SPECIFIC CONDUCTIVITY 123 us/cm

PURGE END TIME: 13:16
pH 6.81 su
DISSOLVED O2 5.11 ppm
TEMP 12.1 °C
SPECIFIC CONDUCTIVITY 117 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 11.83 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 21 gal

SAMPLE START TIME: 13:17
pH 6.82 su
DISSOLVED O2 5.11 ppm
TEMP 12.2 °C
SPECIFIC CONDUCTIVITY 117 us/cm

SAMPLE END TIME: 13:20

COMMENTS:

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW31
NJDEP ID #: 29-32595
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 01/11/01
WEATHER: Sunny, cold.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.88 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 7.16 ft
DEPTH OF WELL: 16.91 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 9.75 ft
 $(9.75) \times .65 \times 3 = 19.01$
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 11:47

pH 6.89 su

DISSOLVED O2 5.84 ppm

TEMP 12.7 °C

SPECIFIC CONDUCTIVITY 111 us/cm

PURGE END TIME: 13:09

pH 6.81 su

DISSOLVED O2 5.10 ppm

TEMP 12.1 °C

SPECIFIC CONDUCTIVITY 107 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.35 ft

(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)

TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 13:10

pH 6.80 su

DISSOLVED O2 5.07 ppm

TEMP 12.2 °C

SPECIFIC CONDUCTIVITY 108 us/cm

SAMPLE END TIME: 13:14

COMMENTS: Cloudy, yellow.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW32
NJDEP ID #: 29-32596
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 01/11/01
WEATHER: Sunny, cold.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.38 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 6.98 ft
DEPTH OF WELL: 16.89 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 9.91 ft
 $(9.91) \times .65 \times 3 = 19.32$
GALLONS OF H2O TO BE PURGED: 19 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hmu READING: 0.0 ppm

PURGE START TIME: 11:49
pH 6.93 su
DISSOLVED O2 5.89 ppm
TEMP 12.4 °C
SPECIFIC CONDUCTIVITY 107 us/cm

PURGE END TIME: 13:11
pH 6.87 su
DISSOLVED O2 5.25 ppm
TEMP 12.0 °C
SPECIFIC CONDUCTIVITY 104 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 14.41 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 19 gal

SAMPLE START TIME: 13:15
pH 6.86 su
DISSOLVED O2 5.23 ppm
TEMP 12.0 °C
SPECIFIC CONDUCTIVITY 103 us/cm

SAMPLE END TIME: 13:17

COMMENTS: Large drain down. Slightly cloudy.

U.S. ARMY FORT MONMOUTH MONITORING WELL SAMPLING DATA

LOCATION: CW-2
MW#: 0CW2MW33
NJDEP ID #: 29-32597
NJDEP CERT #: 13461
SAMPLING CONTRACTOR: TVS
SAMPLER: Corey McCormack
DATE: 01/11/01
WEATHER: Sunny, cold.
TIDE: N/A

LNAPLs: N
DNAPLs N
ELEV. OF INNER CASING SURVEY MARK: 51.09 ft
INNER CASING DIA.: 4 INCH
DEPTH TO WATER: 9.14 ft
DEPTH OF WELL: 16.10 ft
DEPTH TO TOP OF SCREEN: N/A ft
HEIGHT OF WATER: 6.96 ft
 $(6.96) \times .65 \times 3 = 13.57$
GALLONS OF H2O TO BE PURGED: 14 gal
PURGE METHOD: (FLOW OF <0.5 TO >5.0 gpm) : PERISTALTIC
PURGE RATE: 0.23 gpm
Hnu READING: 0.0 ppm

PURGE START TIME: 11:50
pH 6.84 su
DISSOLVED O2 5.87 ppm
TEMP 12.7 °C
SPECIFIC CONDUCTIVITY 127 us/cm

PURGE END TIME: 12:51
pH 6.89 su
DISSOLVED O2 5.23 ppm
TEMP 12.2 °C
SPECIFIC CONDUCTIVITY 117 us/cm

DEPTH TO H2O AFTER PURGE AND BEFORE SAMPLING: 9.61 ft
(SAMPLING METHOD: DEDICATED (LAW NJDEP FSPM 1992) TEFLON ® BAILER)
TOTAL VOLUME PURGED: 14 gal

SAMPLE START TIME: 12:52
pH 6.90 su
DISSOLVED O2 5.21 ppm
TEMP 12.3 °C
SPECIFIC CONDUCTIVITY 116 us/cm

SAMPLE END TIME: 12:57

COMMENTS: Cloudy, orange particles. DUP. Here.

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEP CERTIFICATION # 13461

Definition of Qualifiers

MDL	:	Method Detection Limit
J	:	Compound identified below detection limit
B	:	Compound found in blank
D	:	Results are from a dilution of the sample
U	:	Compound searched for but not detected
E	:	Compound exceeds calibration limit
PQL	:	Practical Quantitation Limit
NLE	:	No limit established
RT	:	Retention time

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification Number #13461

Data File **VC004692.D**
 Operator **Skelton**
 Date Acquired **11-Jan-01**

Sample Name **MB 011101**
 Field ID **MB 011101**
 Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156594	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C., 7:9-6 2-Sept 97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

MB 011101

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 50-56 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: MB 011101
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC004692.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: not dec. _____ Date Analyzed: 1/11/01
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification Number #13461

Data File **VC004704.D**
 Operator **Skelton**
 Date Acquired **12-Jan-01**

Sample Name **50 143**
 Field ID **Trip Blank**
 Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride	11.17	128744	1.92 ug/L	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156594	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C., 7:9-6 2-Sept 97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Trip Blank

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 50-56 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 50 143

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC004704.D

Level: (low/med) LOW Date Received: 1/11/01

% Moisture: not dec. _____ Date Analyzed: 1/12/01

GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification Number #13461

Data File **VC004705.D**
 Operator **Skelton**
 Date Acquired **12-Jan-01**

Sample Name **51 144**
 Field ID **Field Blank**
 Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride	11.16	102745	1.66 ug/L	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156594	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C., 7:9-6 2-Sept 97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Field Blank

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 50-56 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 51 144
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC004705.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: not dec. Date Analyzed: 1/12/01
GC Column: RTX502 ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification Number #13461

Data File **VC004706.D**
 Operator **Skelton**
 Date Acquired **12-Jan-01**

Sample Name **52 145**
 Field ID **Dupe**
 Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156594	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C., 7-9-6 2-Sept 97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

Dupe

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 50-56 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 52 145
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC004706.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: not dec. Date Analyzed: 1/12/01
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification Number #13461

Data File **VC004707.D**
 Operator **Skelton**
 Date Acquired **12-Jan-01**

Sample Name **53 146**
 Field ID **CW2MW30**
 Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156594	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C., 7:9-6.2-Sept 97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

CW2MW030

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 50-56 Location: CW2 SDG No.:

Matrix: (soil/water) WATER Lab Sample ID: 53 146

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC004707.D

Level: (low/med) LOW Date Received: 1/11/01

% Moisture: not dec. Date Analyzed: 1/12/01

GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: (uL) Soil Aliquot Volume: (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification Number #13461

Data File **VC004708.D**
 Operator **Skelton**
 Date Aquired **12-Jan-01**

Sample Name **54 147**
 Field ID **CW2MW31**
 Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156594	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C., 7-9-6 2-Sept 97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

CW2MW031

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 50-56 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 54 147

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC004708.D

Level: (low/med) LOW Date Received: 1/11/01

% Moisture: not dec. _____ Date Analyzed: 1/12/01

GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification Number #13461

Data File **VC004709.D**
 Operator **Skelton**
 Date Acquired **12-Jan-01**

Sample Name **55 148**
 Field ID **CW2MW32**
 Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156594	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C., 7-9-6 2-Sept 97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

CW2MW032

Lab Name: FMETL NJDEP#: 13461
Project: LTM Case No.: 50-56 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 55 148
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC004709.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: not dec. _____ Date Analyzed: 1/12/01
GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0
Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification Number #13461

Data File **VC004710.D**
 Operator **Skelton**
 Date Acquired **12-Jan-01**

Sample Name **56 149**
 Field ID **CW2MW33**
 Multiplier **1**

CAS#	Compound Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifier
107028	Acrolein			not detected	50	1.85 ug/L	
107131	Acrylonitrile			not detected	50	2.78 ug/L	
75650	tert-Butyl alcohol			not detected	nle	8.52 ug/L	
1634044	Methyl-tert-Butyl ether			not detected	70	0.16 ug/L	
108203	Di-isopropyl ether			not detected	nle	0.25 ug/L	
75718	Dichlorodifluoromethane			not detected	nle	1.68 ug/L	
74-87-3	Chloromethane			not detected	30	1.16 ug/L	
75-01-4	Vinyl Chloride			not detected	5	1.06 ug/L	
74-83-9	Bromomethane			not detected	10	1.10 ug/L	
75-00-3	Chloroethane			not detected	nle	1.01 ug/L	
75-69-4	Trichlorofluoromethane			not detected	nle	0.50 ug/L	
75-35-4	1,1-Dichloroethene			not detected	2	0.24 ug/L	
67-64-1	Acetone			not detected	700	1.36 ug/L	
75-15-0	Carbon Disulfide			not detected	nle	0.46 ug/L	
75-09-2	Methylene Chloride			not detected	2	0.24 ug/L	
156-60-5	trans-1,2-Dichloroethene			not detected	100	0.16 ug/L	
75-34-3	1,1-Dichloroethane			not detected	70	0.12 ug/L	
108-05-4	Vinyl Acetate			not detected	nle	0.78 ug/L	
78-93-3	2-Butanone			not detected	300	0.62 ug/L	
156594	cis-1,2-Dichloroethene			not detected	10	0.17 ug/L	
67-66-3	Chloroform			not detected	6	0.30 ug/L	
75-55-6	1,1,1-Trichloroethane			not detected	30	0.23 ug/L	
56-23-5	Carbon Tetrachloride			not detected	2	0.47 ug/L	
71-43-2	Benzene			not detected	1	0.23 ug/L	
107-06-2	1,2-Dichloroethane			not detected	2	0.18 ug/L	
79-01-6	Trichloroethene			not detected	1	0.23 ug/L	
78-87-5	1,2-Dichloropropane			not detected	1	0.40 ug/L	
75-27-4	Bromodichloromethane			not detected	1	0.55 ug/L	
110-75-8	2-Chloroethyl vinyl ether			not detected	nle	0.65 ug/L	
10061-01-5	cis-1,3-Dichloropropene			not detected	nle	0.69 ug/L	
108-10-1	4-Methyl-2-Pentanone			not detected	400	0.59 ug/L	
108-88-3	Toluene			not detected	1000	0.37 ug/L	
10061-02-6	trans-1,3-Dichloropropene			not detected	nle	0.87 ug/L	
79-00-5	1,1,2-Trichloroethane			not detected	3	0.48 ug/L	
127-18-4	Tetrachloroethene			not detected	1	0.32 ug/L	
591-78-6	2-Hexanone			not detected	nle	0.71 ug/L	
126-48-1	Dibromochloromethane			not detected	10	0.86 ug/L	
108-90-7	Chlorobenzene			not detected	4	0.39 ug/L	
100-41-4	Ethylbenzene			not detected	700	0.65 ug/L	
1330-20-7	m+p-Xylenes			not detected	nle	1.14 ug/L	
1330-20-7	o-Xylene			not detected	nle	0.62 ug/L	
100-42-5	Styrene			not detected	100	0.56 ug/L	
75-25-2	Bromoform			not detected	4	0.70 ug/L	
79-34-5	1,1,2,2-Tetrachloroethane			not detected	2	0.47 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.55 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.57 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.64 ug/L	

*Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C., 7:9-6.2-Sept 97

Qualifiers

B = Compound found in related blank
 E = Value above linear range
 D = Value from dilution
 PQL = Practical Quantitation Limit

MDL = Method Detection Limit
 NLE = No Limit Established
 R.T. = Retention Time

1E

VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID:

CW2MW033

Lab Name: FMETL NJDEP#: 13461

Project: LTM Case No.: 50-56 Location: CW2 SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: 56 149

Sample wt/vol: 5.0 (g/ml) ML Lab File ID: VC004710.D

Level: (low/med) LOW Date Received: 1/11/01

% Moisture: not dec. _____ Date Analyzed: 1/12/01

GC Column: RTX502. ID: 0.25 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (uL) Soil Aliquot Volume: _____ (uL)

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/LNumber TICs found: 0

CAS NO.	COMPOUND NAME	RT	EST. CONC.	Q
---------	---------------	----	------------	---

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04844.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **MB-156**
 Misc Info **MB-156**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04844.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **MB-156**
 Misc Info **MB-156**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate	18.86	279212	9.18 ug/L	5000	1.54 ug/L	
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate	27.95	307979	9.31 ug/L	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

MB-156

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 144-149 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: MB-156
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04844.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: _____ decanted: (Y/N) N Date Extracted: 1/12/01
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 1/16/01
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.11	16	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04846.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **144**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04846.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **144**
 Misc Info **Field Blank**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate	18.86	146305	4.90 ug/L	5000	1.54 ug/L	B
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Field Blank

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 144-149 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 144
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04846.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: _____ decanted: (Y/N) N Date Extracted: 1/12/01
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 1/16/01
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.11	17	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04847.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **145**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04847.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **145**
 Misc Info **Dupe**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate	18.86	100858	3.57 ug/L	5000	1.54 ug/L	B
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

Dupe

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 144-149 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 145
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04847.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: _____ decanted: (Y/N) N Date Extracted: 1/12/01
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 1/16/01
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.11	19	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04848.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **146**
 Misc Info **CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04848.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **146**
 Misc Info **CW2MW30**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate	18.86	78692	2.84 ug/L	5000	1.54 ug/L	B
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzydine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

CW2MW30

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 144-149 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 146
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04848.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: _____ decanted: (Y/N) N Date Extracted: 1/12/01
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 1/16/01
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.11	18	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04849.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **147**
 Misc Info **CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04849.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **147**
 Misc Info **CW2MW31**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate	18.86	67081	2.37 ug/L	5000	1.54 ug/L	B
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

CW2MW31

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 144-149 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 147
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04849.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: decanted: (Y/N) N Date Extracted: 1/12/01
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 1/16/01
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.10	18	J

Semi-Volatile Analysis Report
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification #13461

Data File Name **BNA04850.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **148**
 Misc Info **CW2MW32**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04850.D**
Operator **Bhaskar**
Date Acquired **16-Jan-01**

Sample Name **148**
Misc Info **CW2MW32**
Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate	18.86	58452	2.05 ug/L	5000	1.54 ug/L	B
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzidine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
D= Value from dilution
B= Compound in Related Blank
PQL= Practical Quantitation Limit

MDL= Method Detection Limit
NLE= No Limit Established
R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

CW2MW32

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 144-149 Location: CW2 SDG No.:
Matrix: (soil/water) WATER Lab Sample ID: 148
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04850.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: decanted: (Y/N) N Date Extracted: 1/12/01
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 1/16/01
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH:

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.10	19	J

Semi-Volatile Analysis Report

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification #13461

Data File Name BNA04851.D

Operator Bhaskar

Date Acquired 16-Jan-01

Sample Name 149

Misc Info CW2MW33

Sample Multiplier 1

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
110-86-1	Pyridine			not detected	NLE	1.54 ug/L	
62-75-9	N-nitroso-dimethylamine			not detected	20	0.69 ug/L	
62-53-3	Aniline			not detected	NLE	1.85 ug/L	
108-95-2	Phenol			not detected	4000	0.52 ug/L	
111-44-4	bis(2-Chloroethyl)ether			not detected	10	0.63 ug/L	
95-57-8	2-Chlorophenol			not detected	40	0.61 ug/L	
541-73-1	1,3-Dichlorobenzene			not detected	600	0.62 ug/L	
106-46-7	1,4-Dichlorobenzene			not detected	75	0.58 ug/L	
100-51-6	Benzyl alcohol			not detected	NLE	0.62 ug/L	
95-50-1	1,2-Dichlorobenzene			not detected	600	0.65 ug/L	
95-48-7	2-Methylphenol			not detected	NLE	0.59 ug/L	
39638-32-9	bis(2-chloroisopropyl)ether			not detected	300	0.57 ug/L	
106-44-5	4-Methylphenol			not detected	NLE	0.48 ug/L	
621-64-7	n-Nitroso-di-n-propylamine			not detected	20	0.64 ug/L	
67-72-1	Hexachloroethane			not detected	10	0.34 ug/L	
98-95-3	Nitrobenzene			not detected	10	0.51 ug/L	
78-59-1	Isophorone			not detected	100	0.45 ug/L	
88-75-5	2-Nitrophenol			not detected	NLE	0.52 ug/L	
105-67-9	2,4-Dimethylphenol			not detected	100	0.93 ug/L	
111-91-1	bis(2-Chloroethoxy)methane			not detected	NLE	0.48 ug/L	
120-83-2	2,4-Dichlorophenol			not detected	20	0.39 ug/L	
65-85-0	Benzoic Acid			not detected	NLE	1.15 ug/L	
120-82-1	1,2,4-Trichlorobenzene			not detected	9	0.54 ug/L	
91-20-3	Naphthalene			not detected	NLE	0.72 ug/L	
106-47-8	4-Chloroaniline			not detected	NLE	1.78 ug/L	
87-68-3	Hexachlorobutadiene			not detected	1	0.43 ug/L	
59-50-7	4-Chloro-3-methylphenol			not detected	NLE	0.71 ug/L	
91-57-6	2-Methylnaphthalene			not detected	NLE	0.55 ug/L	
77-47-4	Hexachlorocyclopentadiene			not detected	50	0.76 ug/L	
88-06-2	2,4,6-Trichlorophenol			not detected	20	0.59 ug/L	
95-95-4	2,4,5-Trichlorophenol			not detected	700	0.96 ug/L	
91-58-7	2-Chloronaphthalene			not detected	NLE	0.53 ug/L	
88-74-4	2-Nitroaniline			not detected	NLE	1.04 ug/L	
131-11-3	Dimethylphthalate			not detected	7000	1.04 ug/L	
208-96-8	Acenaphthylene			not detected	NLE	0.70 ug/L	
606-20-2	2,6-Dinitrotoluene			not detected	NLE	0.92 ug/L	
99-09-2	3-Nitroaniline			not detected	NLE	1.93 ug/L	
83-32-9	Acenaphthene			not detected	400	0.62 ug/L	
51-28-5	2,4-Dinitrophenol			not detected	40	1.84 ug/L	
132-64-9	Dibenzofuran			not detected	NLE	0.73 ug/L	
100-02-7	4-Nitrophenol			not detected	NLE	1.41 ug/L	

Semi-Volatile Analysis Report

Page 2

Data File Name **BNA04851.D**
 Operator **Bhaskar**
 Date Acquired **16-Jan-01**

Sample Name **149**
 Misc Info **CW2MW33**
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Result	Regulatory Level (ug/L)*	MDL	Qualifiers
121-14-2	2,4-Dinitrotoluene			not detected	10	1.41 ug/L	
84-66-2	Diethylphthalate	18.86	50504	1.71 ug/L	5000	1.54 ug/L	B
86-73-7	Fluorene			not detected	300	0.98 ug/L	
7005-72-3	4-Chlorophenyl-phenylether			not detected	NLE	0.86 ug/L	
100-01-6	4-Nitroaniline			not detected	NLE	2.96 ug/L	
534-52-1	4,6-Dinitro-2-methylphenol			not detected	NLE	2.10 ug/L	
86-30-6	n-Nitrosodiphenylamine			not detected	20	1.44 ug/L	
103-33-3	Azobenzene			not detected	NLE	1.00 ug/L	
101-55-3	4-Bromophenyl-phenylether			not detected	NLE	1.28 ug/L	
118-74-1	Hexachlorobenzene			not detected	10	1.08 ug/L	
87-86-5	Pentachlorophenol			not detected	1	1.74 ug/L	
85-01-8	Phenanthrene			not detected	NLE	1.73 ug/L	
120-12-7	Anthracene			not detected	2000	1.85 ug/L	
84-74-2	Di-n-butylphthalate			not detected	900	2.49 ug/L	
206-44-0	Fluoranthene			not detected	300	1.48 ug/L	
92-87-5	Benzdine			not detected	50	2.15 ug/L	
129-00-0	Pyrene			not detected	200	1.53 ug/L	
85-68-7	Butylbenzylphthalate			not detected	100	1.24 ug/L	
56-55-3	Benzo[a]anthracene			not detected	10	2.68 ug/L	
91-94-1	3,3'-Dichlorobenzidine			not detected	60	1.60 ug/L	
218-01-9	Chrysene			not detected	20	1.14 ug/L	
117-81-7	bis(2-Ethylhexyl)phthalate			not detected	30	1.34 ug/L	
117-84-0	Di-n-octylphthalate			not detected	100	1.44 ug/L	
205-99-2	Benzo[b]fluoranthene			not detected	10	1.32 ug/L	
207-08-9	Benzo[k]fluoranthene			not detected	2	1.15 ug/L	
50-32-8	Benzo[a]pyrene			not detected	20	2.43 ug/L	
193-39-5	Indeno[1,2,3-cd]pyrene			not detected	20	2.24 ug/L	
53-70-3	Dibenz[a,h]anthracene			not detected	20	1.94 ug/L	
191-24-2	Benzo[g,h,i]perylene			not detected	NLE	2.04 ug/L	

* Higher of PQL's and Ground Water Criteria as per NJAC 7:9-6 2-Sept-97

Qualifiers

E= Value Exceeds Linear Range
 D= Value from dilution
 B= Compound in Related Blank
 PQL= Practical Quantitation Limit

MDL= Method Detection Limit
 NLE= No Limit Established
 R.T.=Retention Time

1F

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

Field Id:

CW2MW33

Lab Name: FMETL Lab Code 13461
Project: LTM Case No.: 144-149 Location: CW2 SDG No.: _____
Matrix: (soil/water) WATER Lab Sample ID: 149
Sample wt/vol: 1000 (g/ml) ML Lab File ID: BNA04851.D
Level: (low/med) LOW Date Received: 1/11/01
% Moisture: _____ decanted: (Y/N) N Date Extracted: 1/12/01
Concentrated Extract Volume: 1000 (uL) Date Analyzed: 1/16/01
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: _____

CONCENTRATION UNITS:

Number TICs found: 1 (ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	unknown	7.10	21	J

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : MB-154
Date Rec'd:
Extraction Date: 1/12/01
Analysis Date: 1/22/01

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location :
Field ID:

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 144
Date Rec'd: 1/11/01
Extraction Date: 1/12/01
Analysis Date: 1/22/01

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: Field Blank

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	145
	DPW, SELFM-PW-EV	Date Rec'd:	1/11/01
	Bldg. 173	Extraction Date:	1/12/01
	Ft. Monmouth, NJ 07703	Analysis Date:	1/22/01
Analysis:	EPA Method 608	Location :	CW2 wells
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	Dupe
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 146
Date Rec'd: 1/11/01
Extraction Date: 1/12/01
Analysis Date: 1/22/01

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: CW2MW30

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 147
Date Rec'd: 1/11/01
Extraction Date: 1/12/01
Analysis Date: 1/22/01

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: CW2MW31

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client :	U.S. Army	Lab. ID # :	148
	DPW, SELFM-PW-EV	Date Rec'd:	1/11/01
	Bldg. 173	Extraction Date:	1/12/01
	Ft. Monmouth, NJ 07703	Analysis Date:	1/22/01
Analysis:	EPA Method 608	Location :	CW2 wells
Matrix:	Aqueous		
Analyst:	T. Frankovich	Field ID:	CW2MW32
Ext. Meth:	Sep. Funnel		

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client : U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab. ID # : 149
Date Rec'd: 1/11/01
Extraction Date: 1/12/01
Analysis Date: 1/22/01

Analysis: EPA Method 608
Matrix: Aqueous
Analyst: T. Frankovich
Ext. Meth: Sep. Funnel

Location : CW2 wells
Field ID: CW2MW33

Pesticide/PCB	Dilution Factor	Retention Time	Regulatory Level * (ug/L)	MDL (ug/L)	Result (ug/L)
alpha-BHC	1		0.02	0.0011	ND
beta-BHC	1		0.20	0.0050	ND
gamma-BHC	1		0.20	0.0013	ND
delta-BHC	1		NLE	0.0016	ND
Heptachlor	1		0.40	0.0035	ND
Aldrin	1		0.04	0.0026	ND
Heptachlor Epoxide	1		0.20	0.0020	ND
Endosulfan I	1		0.40	0.0016	ND
4,4'-DDE	1		0.10	0.0021	ND
Dieldrin	1		0.03	0.0020	ND
Endrin	1		2.00	0.0032	ND
Endrin Ketone	1		NLE	0.0026	ND
Endosulfan II	1		0.40	0.0022	ND
4,4'-DDD	1		0.10	0.0020	ND
4,4'-DDT	1		0.10	0.0052	ND
Endosulfan-Sulfate	1		0.40	0.0026	ND
Alpha-chlordane	1		0.50	0.0036	ND
Gamma-chlordane	1		0.50	0.0007	ND
Toxaphene	1		3.00	0.1517	ND
Arochlor 1016	1		0.50	0.0683	ND
Arochlor 1221	1		0.50	0.0666	ND
Arochlor 1232	1		0.50	0.0648	ND
Arochlor 1242	1		0.50	0.0485	ND
Arochlor 1248	1		0.50	0.0544	ND
Arochlor 1254	1		0.50	0.0608	ND
Arochlor 1260	1		0.50	0.0732	ND

* Higher of PQL's and ground water criteria as per NJAC 7:9-6

ND = Not Detected

MDL = Method Detection Limit

NLE = No Limit Established

PQL = Practical Quantitation Limit

Column-Primary: Rtx-CLPesticides 30m/.32mm ID/.25um

Column-Confirmation: Rtx-CLPesticides2 30m/.32mm ID/.25um

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 144-149
Sample Prepared: 1/16/01

Site: CW-2
Ft. Monmouth, New Jersey

Field ID#: Method Blank

Method of Digestion: E.P.A SW-846, Method 3015A
Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	01/16/01	ND	200	10.0
Antimony	01/16/01	ND	20	2.0
Arsenic	01/16/01	ND	8	2.0
Barium	01/16/01	ND	2000	0.5
Beryllium	01/16/01	ND	20	0.5
Cadmium	01/16/01	ND	4	0.5
Calcium	01/16/01	98.3	NLE	20.0
Chromium	01/16/01	ND	100	0.5
Cobalt	01/16/01	ND	NLE	0.5
Copper	01/16/01	ND	1000	2.0
Iron	01/16/01	36.3	300	2.0
Lead	01/16/01	ND	10	1.0
Magnesium	01/16/01	ND	NLE	10.0
Manganese	01/16/01	ND	50	0.5
Mercury	01/17/01	ND	2	0.1
Nickel	01/16/01	ND	100	1.0
Potassium	01/16/01	ND	NLE	40.0
Selenium	01/16/01	ND	50	3.0
Silver	01/16/01	ND	20	1.0
Sodium	01/16/01	ND	50000	20.0
Thallium	01/16/01	ND	10	2.0
Vanadium	01/16/01	ND	NLE	0.5
Zinc	01/16/01	ND	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 144
 Sample Received: 01/11/01
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Field Blank

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	01/16/01	ND	200	10.0
Antimony	01/16/01	ND	20	2.0
Arsenic	01/16/01	ND	8	2.0
Barium	01/16/01	ND	2000	0.5
Beryllium	01/16/01	ND	20	0.5
Cadmium	01/16/01	ND	4	0.5
Calcium	01/16/01	ND	NLE	20.0
Chromium	01/16/01	ND	100	0.5
Cobalt	01/16/01	ND	NLE	0.5
Copper	01/16/01	ND	1000	2.0
Iron	01/16/01	ND	300	2.0
Lead	01/16/01	ND	10	1.0
Magnesium	01/16/01	64.4	NLE	10.0
Manganese	01/16/01	ND	50	0.5
Mercury	01/17/01	ND	2	0.1
Nickel	01/16/01	ND	100	1.0
Potassium	01/16/01	ND	NLE	40.0
Selenium	01/16/01	ND	50	3.0
Silver	01/16/01	ND	20	1.0
Sodium	01/16/01	ND	50000	20.0
Thallium	01/16/01	ND	10	2.0
Vanadium	01/16/01	ND	NLE	0.5
Zinc	01/16/01	ND	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 145
 Sample Received: 01/11/01
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: Dupe

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	01/16/01	282	200	10.0
Antimony	01/16/01	ND	20	2.0
Arsenic	01/16/01	5.88	8	2.0
Barium	01/16/01	207	2000	0.5
Beryllium	01/16/01	ND	20	0.5
Cadmium	01/16/01	ND	4	0.5
Calcium	01/16/01	50200	NLE	20.0
Chromium	01/16/01	2.39	100	0.5
Cobalt	01/16/01	ND	NLE	0.5
Copper	01/16/01	ND	1000	2.0
Iron	01/16/01	143000	300	2.0
Lead	01/16/01	2.10	10	1.0
Magnesium	01/16/01	5740	NLE	10.0
Manganese	01/16/01	253	50	0.5
Mercury	01/17/01	ND	2	0.1
Nickel	01/16/01	1.24	100	1.0
Potassium	01/16/01	9440	NLE	40.0
Selenium	01/16/01	ND	50	3.0
Silver	01/16/01	ND	20	1.0
Sodium	01/16/01	13400	50000	20.0
Thallium	01/16/01	ND	10	2.0
Vanadium	01/16/01	2.89	NLE	0.5
Zinc	01/16/01	46.6	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis
U.S. Army, Fort Monmouth Environmental Laboratory
NJDEP Certification # 13461

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Lab ID #: 146
Sample Received: 1/11/01
Sample Matrix: Aqueous

Site: CW-2
Ft. Monmouth, New Jersey

Field ID#: 0CW2MW30

Method of Digestion: E.P.A SW-846, Method 3015A
Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	01/16/01	38.1	200	10.0
Antimony	01/16/01	ND	20	2.0
Arsenic	01/16/01	3.48	8	2.0
Barium	01/16/01	62.1	2000	0.5
Beryllium	01/16/01	ND	20	0.5
Cadmium	01/16/01	ND	4	0.5
Calcium	01/16/01	59600	NLE	20.0
Chromium	01/16/01	1.29	100	0.5
Cobalt	01/16/01	ND	NLE	0.5
Copper	01/16/01	ND	1000	2.0
Iron	01/16/01	9730	300	2.0
Lead	01/16/01	ND	10	1.0
Magnesium	01/16/01	4690	NLE	10.0
Manganese	01/16/01	54.6	50	0.5
Mercury	01/17/01	0.2	2	0.1
Nickel	01/16/01	2.38	100	1.0
Potassium	01/16/01	7410	NLE	40.0
Selenium	01/16/01	7.20	50	3.0
Silver	01/16/01	ND	20	1.0
Sodium	01/16/01	22200	50000	20.0
Thallium	01/16/01	ND	10	2.0
Vanadium	01/16/01	1.25	NLE	0.5
Zinc	01/16/01	7.46	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 147
 Sample Received: 1/11/01
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW31

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	01/16/01	ND	200	10.0
Antimony	01/16/01	ND	20	2.0
Arsenic	01/16/01	ND	8	2.0
Barium	01/16/01	252	2000	0.5
Beryllium	01/16/01	ND	20	0.5
Cadmium	01/16/01	ND	4	0.5
Calcium	01/16/01	56600	NLE	20.0
Chromium	01/16/01	ND	100	0.5
Cobalt	01/16/01	ND	NLE	0.5
Copper	01/16/01	ND	1000	2.0
Iron	01/16/01	78800	300	2.0
Lead	01/16/01	ND	10	1.0
Magnesium	01/16/01	7030	NLE	10.0
Manganese	01/16/01	294	50	0.5
Mercury	01/17/01	0.2	2	0.1
Nickel	01/16/01	ND	100	1.0
Potassium	01/16/01	10600	NLE	40.0
Selenium	01/16/01	5.28	50	3.0
Silver	01/16/01	ND	20	1.0
Sodium	01/16/01	12600	50000	20.0
Thallium	01/16/01	ND	10	2.0
Vanadium	01/16/01	ND	NLE	0.5
Zinc	01/16/01	9.44	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 148
 Sample Received: 1/11/01
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: 0CW2MW32

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	01/16/01	63.2	200	10.0
Antimony	01/16/01	ND	20	2.0
Arsenic	01/16/01	5.59	8	2.0
Barium	01/16/01	49.9	2000	0.5
Beryllium	01/16/01	ND	20	0.5
Cadmium	01/16/01	ND	4	0.5
Calcium	01/16/01	91500	NLE	20.0
Chromium	01/16/01	1.60	100	0.5
Cobalt	01/16/01	ND	NLE	0.5
Copper	01/16/01	ND	1000	2.0
Iron	01/16/01	11500	300	2.0
Lead	01/16/01	ND	10	1.0
Magnesium	01/16/01	9330	NLE	10.0
Manganese	01/16/01	23.0	50	0.5
Mercury	01/17/01	ND	2	0.1
Nickel	01/16/01	1.26	100	1.0
Potassium	01/16/01	3000	NLE	40.0
Selenium	01/16/01	5.34	50	3.0
Silver	01/16/01	ND	20	1.0
Sodium	01/16/01	20000	50000	20.0
Thallium	01/16/01	ND	10	2.0
Vanadium	01/16/01	3.87	NLE	0.5
Zinc	01/16/01	36.5	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

Report of Analysis

U.S. Army, Fort Monmouth Environmental Laboratory

NJDEP Certification # 13461

Client: U.S. Army
 DPW, SELFM-PW-EV
 Bldg. 173
 Ft. Monmouth, NJ 07703

Lab ID #: 149
 Sample Received: 1/11/01
 Sample Matrix: Aqueous

Site: CW-2
 Ft. Monmouth, New Jersey

Field ID#: OCW2MW33

Method of Digestion: E.P.A SW-846, Method 3015A
 Method of Analysis: Std. Methods 18th, Method 3120B, 3112B

TAL-METALS RESULTS SUMMARY (ug/L)

Element	Date of Analysis	Result (ug/L)	Regulatory Level (ug/L)*	MDL (ug/L)
Aluminum	01/16/01	37.1	200	10.0
Antimony	01/16/01	ND	20	2.0
Arsenic	01/16/01	3.02	8	2.0
Barium	01/16/01	204	2000	0.5
Beryllium	01/16/01	ND	20	0.5
Cadmium	01/16/01	ND	4	0.5
Calcium	01/16/01	51900	NLE	20.0
Chromium	01/16/01	5.90	100	0.5
Cobalt	01/16/01	ND	NLE	0.5
Copper	01/16/01	182	1000	2.0
Iron	01/16/01	106000	300	2.0
Lead	01/16/01	41.2	10	1.0
Magnesium	01/16/01	5890	NLE	10.0
Manganese	01/16/01	251	50	0.5
Mercury	01/17/01	0.2	2	0.1
Nickel	01/16/01	7.50	100	1.0
Potassium	01/16/01	9650	NLE	40.0
Selenium	01/16/01	ND	50	3.0
Silver	01/16/01	ND	20	1.0
Sodium	01/16/01	12800	50000	20.0
Thallium	01/16/01	ND	10	2.0
Vanadium	01/16/01	0.866	NLE	0.5
Zinc	01/16/01	346	5000	5.0

ND = Not Detected, MDL = Method Detection Limit, NLE = No Limit Established

* Higher of PQL's and Ground Water Quality Criteria as per N.J.A.C. 7:9-6

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	9100	69	ND	ND	ND	6.45				V,S,P,M
07/10/1997	FMETL	12590	73	25	5.0	ND	7.05				V,S,P,M
10/22/1997	FMETL	34800	171	175	5.0	5.0	7.60				V,S,P,M
01/08/1998	FMETL	2795	5.0	204	ND	4.0	5.20				V,S,P,M
04/07/1998	FMETL	3504	39.3	196	5.6	ND	6.56				V,S,P,M
07/14/1998	FMETL	10900	57.8	65.7	ND	ND	6.89				V,S,P,M
11/24/1998	FMETL	27500	182	ND	11.5	3.15	7.86				V,S,P,M
02/11/1999	FMETL	11000	100	505	8.3	ND	7.24				V,S,P,M
06/09/1999	FMETL	8210	145	521	6.33	ND	7.21				V,S,P,M
08/04/1999	FMETL	44800	212	304	9.05	6.02	7.43				V,S,P,M
11/03/1999	FMETL	6540	36.3	92.7	6.06	ND	7.02				V,S,P,M
02/15/2000	FMETL	1840	2.69	20.4	ND	ND	7.02				V,S,P,M
05/08/2000	FMETL	7410	73.1	105	ND	46.6	7.15				V,S,P,M
05/08/2000D	FMETL	8090	74.9	133	ND	13.7	7.15				V,S,P,M
08/02/2000	FMETL	2040	15.2	ND	ND	21.8	6.86				V,S,P,M
10/12/2000	FMETL	8150	39.4	100	3.95	ND	7.31				V,S,P,M
01/11/2001	FMETL	9730	54.6	38.1	3.48	ND	7.32				V,S,P,M

SOURCE: 0CW2MW30

Sampling Dates:
04/24/1997 - 01/11/2001

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 1 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW30

Sampling Dates:
04/24/1997 - 01/11/2001

LEGEND:

PARAMETER

- o = Date Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 1 of 4, Graph



U.S.ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	59900	277	ND	ND	ND	6.38				V,S,P,M
07/10/1997	FMETL	11830	267	ND	1.0	ND	7.00				V,S,P,M
10/22/1997	FMETL	52300	243	93	ND	6.0	7.50				V,S,P,M
01/08/1998	FMETL	68450	240	129	ND	25	6.30				V,S,P,M
04/07/1998	FMETL	115100	266	ND	ND	ND	6.35				V,S,P,M
07/14/1998	FMETL	83600	311	390	ND	4.85	6.71				V,S,P,M
11/24/1998	FMETL	72800	322	ND	ND	2.33	7.78				V,S,P,M
02/11/1999	FMETL	71900	316	ND	ND	ND	7.07				V,S,P,M
06/09/1999	FMETL	104000	326	27.9	ND	ND	7.15				V,S,P,M
08/04/1999	FMETL	77500	347	ND	ND	ND	7.65				V,S,P,M
11/03/1999	FMETL	64600	309	14.9	ND	ND	7.18				V,S,P,M
02/15/2000	FMETL	111000	301	11.7	ND	ND	7.03				V,S,P,M
05/08/2000	FMETL	86000	343	ND	ND	ND	6.96				V,S,P,M
08/02/2000	FMETL	68900	294	14.7	ND	2.44	6.73				V,S,P,M
10/12/2000	FMETL	62100	294	20.6	ND	ND	7.16				V,S,P,M
01/11/2001	FMETL	78800	294	ND	ND	ND	7.16				V,S,P,M

SOURCE: 0CW2MW31

Sampling Dates:
04/24/1997 - 01/11/2001

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 2 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW31

Sampling Dates:
04/24/1997 - 01/11/2001

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 2 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	18400	125	ND	ND	ND	6.65				V,S,P,M
07/10/1997	FMETL	270	181	595	ND	ND	7.20				V,S,P,M
10/22/1997	FMETL	51100	260	297	ND	7.0	7.70				V,S,P,M
01/08/1998	FMETL	1484	3.7	163	ND	ND	4.50				V,S,P,M
04/07/1998	FMETL	19280	287	ND	ND	ND	6.81				V,S,P,M
07/14/1998	FMETL	67500	287	78.1	2.51	3.99	7.06				V,S,P,M
11/24/1998	FMETL	106000	342	166	9.32	4.08	7.94				V,S,P,M
02/11/1999	FMETL	4480	7.02	137	ND	ND	7.33				V,S,P,M
06/09/1999	FMETL	64300	310	59.5	ND	ND	7.49				V,S,P,M
08/04/1999	FMETL	76000	369	67.4	ND	ND	7.85				V,S,P,M
11/03/1999	FMETL	11500	27	162	4.09	ND	6.53				V,S,P,M
02/15/2000	FMETL	11300	53.9	95.7	ND	ND	6.54				V,S,P,M
02/15/2000D	FMETL	112000	297	53.1	ND	ND	6.54				V,S,P,M
05/08/2000	FMETL	55700	382	51.4	ND	ND	7.29				V,S,P,M
08/02/2000	FMETL	4700	8.74	21.8	4.14	2.96	5.93				V,S,P,M
08/02/2000D	FMETL	4130	7.99	28.1	ND	38.3	5.93				V,S,P,M
10/12/2000	FMETL	39900	326	238	4.55	ND	7.35				V,S,P,M
01/11/2001	FMETL	11500	23.0	63.2	5.59	ND	6.98				V,S,P,M

SOURCE: 0CW2MW32

Sampling Dates:
04/24/1997 - 01/11/2001

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 3 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW32

Sampling Dates:
04/24/1997 - 01/11/2001

LEGEND:

PARAMETER

o = Date
Sampled

NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 3 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV

	Lab	Iron	Manganese	Aluminum	Arsenic	Lead	Depth to Water				Notes
Units:	-	ug/l	ug/l	ug/l	ug/l	ugl	Feet				-
NJDEP Criteria:	-	300	50	200	8	10	-				-
04/24/1997	FMETL	88600	424	ND	ND	ND	8.95				V,S,P,M
07/10/1997	FMETL	10260	519	2.1	1.0	ND	9.10				V,S,P,M
10/22/1997	FMETL	26800	151	94	ND	4.0	9.10				V,S,P,M
01/08/1998	FMETL	104700	342	217	6.0	4.0	9.00				V,S,P,M
04/07/1998	FMETL	19780	110	119	3.4	ND	9.50				V,S,P,M
07/14/1998	FMETL	35900	130	411	ND	4.19	9.09				V,S,P,M
11/24/1998	FMETL	25400	87.8	125	ND	ND	9.13				V,S,P,M
02/11/1999	FMETL	11300	81.2	67.8	ND	ND	8.13				V,S,P,M
06/09/1999	FMETL	69600	214	336	5.82	ND	9.13				V,S,P,M
08/04/1999	FMETL	35900	149	69	8	3.25	9.15				V,S,P,M
11/03/1999	FMETL	19500	47.2	52.8	ND	ND	6.14				V,S,P,M
02/15/2000	FMETL	54400	201	96.2	2.67	3.77	9.09				V,S,P,M
05/08/2000	FMETL	36500	242	29.3	ND	ND	8.13				V,S,P,M
08/02/2000	FMETL	13400	81.4	38.2	ND	1.50	9.12				V,S,P,M
10/12/2000	FMETL	38800	188	109	3.69	29.7	9.11				V,S,P,M
10/12/2000D	FMETL	40900	183	110	2.43	ND	9.11				V,S,P,M
01/11/2001	FMETL	106000	251	37.1	3.02	41.2	9.14				V,S,P,M
01/11/2001D	FMETL	143000	253	282	5.88	2.10	9.14				V,S,P,M

SOURCE: 0CW2MW33

Sampling Dates:
04/24/1997 - 01/11/2001

NOTES:







FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 4 of 4



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV



SOURCE: 0CW2MW33

Sampling Dates:
04/24/1997 - 01/11/2001

LEGEND:

PARAMETER

○ = Date
Sampled

◇ NJDEP Criteria

FORT MONMOUTH

GW MONITORING
Bldg CW-2

Source 4 of 4, Graph



U.S. ARMY
FORT MONMOUTH
SELF-M-PW-EV