United States Army

Fort Monmouth, New Jersey

Underground Storage Tank Closure and Site Investigation Report

Building 142B Main Post

NJDEP UST Registration No. 090010-73 Emergency UST Removal Spill Case No. 94-7-21-1561-45

February 1997





UNDERGROUND STORAGE TANK CLOSURE AND SITE INVESTIGATION REPORT

BUILDING 142B

MAIN POST
NJDEP UST REGISTRATION NO. 090010-73
EMERGENCY UST REMOVAL
SPILL CASE NO. 94-7-1561-45

FEBRUARY 1997

PROJECT NO. 09-5004-08
CONTRACT NO. DACA51-94-D-0014

PREPARED FOR:

UNITED STATES ARMY, FORT MONMOUTH, NEW JERSEY
DIRECTORATE OF PUBLIC WORKS
BUILDING 167
FORT MONMOUTH, NJ 07703

PREPARED BY:

SMITH TECHNOLOGY CORPORATION BROMLEY CORPORATE CENTER THREE TERRI LANE BURLINGTON, NEW JERSEY 08016

TABLE OF CONTENTS

EXECUTIVE SUMMARY	IV
1.0 UNDERGROUND STORAGE TANK DECOMMISSIONING ACTIVITIES	1
1.1 OVERVIEW 1.2 SITE DESCRIPTION	1 2
1.2.1 Geological/Hydrogeological Setting	2
1.3 HEALTH AND SAFETY 1.4 REMOVAL OF UNDERGROUND STORAGE TANK	3 4
1.4.1 General Procedures 1.4.2 Underground Storage Tank Excavation and Cleaning	4 4
1.5 UNDERGROUND STORAGE TANK TRANSPORTATION AND DISPOSAL 1.6 MANAGEMENT OF EXCAVATED SOILS	4 5
2.0 SITE INVESTIGATION ACTIVITIES	. 6
2.1 OVERVIEW 2.2 FIELD SCREENING/MONITORING 2.3 SOIL SAMPLING	6 6 7
3.0 CONCLUSIONS AND RECOMMENDATIONS	8
3.1 SOIL SAMPLING RESULTS 3.2 CONCLUSIONS AND RECOMMENDATIONS	8 8
Following Pag	ge No.
TABLES	
Table 1 Summary of Post-Excavation Sampling Activities Table 2 Post-Excavation Soil Sampling Results	7 8

TABLE OF CONTENTS (CONTINUED)

		Following Page No.
FIGURES		
Figure 1 Figure 2 Figure 3	Site Location Map Site Map Soil Sampling Results	1 2 8
APPENDIC	ES	
Appendix I Appendix I Appendix I Appendix I	B Waste Manifest C UST Disposal Certificate	

EXECUTIVE SUMMARY

UST Closure

On July 21, 1994, a steel underground storage tank (UST) was closed by removal in accordance with the New Jersey Department of Environmental Protection (NJDEP) at U.S. Army Fort Monmouth, Fort Monmouth, New Jersey. The UST was discovered during decommissioning of 090010-13 at Building 142A. The UST was found to be located immediately adjacent to Building 142B in the Main Post area of U.S. Army, Fort Monmouth. The UST was removed as an emergency since it was not previously registered with the NJDEP nor previously known to exist. The UST was later registered with the NJDEP on September 14, 1994, and was assigned registration No. 090010-73. UST No. 090010-73 was a 550-gallon No. 2 fuel oil UST. The UST fill port was located directly above the tank. The tank closure was performed by Cleaning Up The Environment Inc. (CUTE Inc.).

Site Assessment

The site assessment was performed by U.S. Army personnel in accordance with the NJDEP *Technical Requirements for Site Remediation* (N.J.A.C. 7:26E) and the NJDEP *Field Sampling Procedures Manual*. Soils surrounding the tank were screened visually and with air monitoring equipment for evidence of contamination. Following removal, the UST was inspected for corrosion holes. Holes were noted in the UST and evidence of potentially contaminated soil was observed surrounding the tank.

On July 21, 1994, following the removal of the UST, approximately 30 cubic yards of potentially contaminated soils was removed from the excavation due to visible contamination. Post-excavation soil samples A, B, C, D, E, F, and DUP A were collected from a total of six (6) locations along the sidewalls of the excavation. The samples were collected at a depth of 5.5 feet below ground surface (bgs). All samples were analyzed for total petroleum hydrocarbons (TPHC). No fuel lines were found during the emergency removal of UST No. 090010-73.

Based on the inspection of the UST, and field screening of subsurface soils, the DPW has concluded that an historical discharge was associated with the UST. On July 21, 1994, a spill was reported to the NJDEP "Hotline" for UST No. 090010-73 and was assigned Spill Case No. 94-7-21-1561-45.

Findings

All post-excavation soil samples collected from the UST excavation at Building 142B contained TPHC concentrations below the NJDEP residential direct contact total organic contaminants soil cleanup criteria of 10,000 milligrams per kilogram (mg/kg) (N.J.A.C. 7:26D and revisions dated

February 3, 1994). All samples (samples A, B, C, D, E, F, and DUP A) contained non-detectable concentrations of TPHC.

Site Restoration

Following receipt of all post-excavation soil sampling results, the excavation was backfilled to grade with a combination of uncontaminated excavated soil and certified clean fill. The excavation site was then restored to its original condition.

Site Assessment Quality Assurance

The sampling and laboratory analysis conducted during the site assessment were performed in accordance with Section 7:26E-2.1 of the *Technical Requirements for Site Remediation*.

Discrepancies

The removal contractor collected soil samples using polystyrene scoops instead of NJDEP approved stainless steel scoops. The results of the soil samples were therefore evaluated at 50% of the actual value to compensate for any potential loss due to absorbency of the polystyrene scoop.

Conclusions and Recommendations

Based on the post-excavation soil sampling results, soils with TPHC concentrations exceeding the NJDEP soil cleanup criteria for total organic contaminants of 10,000 mg/kg, do not exist in the former location of the UST.

No further action is proposed in regard to the closure and site assessment of UST No. 090010-73 at Building 142B.

1.0 UNDERGROUND STORAGE TANK DECOMMISSIONING ACTIVITIES

1.1 OVERVIEW

One underground storage tank (UST), was closed at Building 142B at U.S. Army Fort Monmouth, Fort Monmouth, New Jersey on July 21, 1994. Refer to site location map on Figure 1. The UST was discovered during decommissioning of UST No. 090010-13 at Building 142A. The UST was found to be located immediately adjacent to Building 142B in the Main Post area of U.S. Army, Fort Monmouth. The UST was removed as an emergency since it was not previously registered with the NJDEP nor previously known to exist. The UST was registered with the NJDEP on September 14, 1994 and was assigned registration No. 090010-73. The UST was a steel 550-gallon tank containing No. 2 fuel oil.

Decommissioning activities for UST No. 090010-73 complied with all applicable Federal, State and Local laws and ordinances in effect at the date of decommissioning. These laws included but were not limited to: N.J.A.C. 7:14B-1 et seq., N.J.A.C. 5:23-1 et seq., and Occupational Safety and Health Administration (OSHA) 1910.146 & 1910.120. All permits including but not limited to the NJDEP-approved Decommissioning/Closure Plan were posted onsite for inspection. CUTE Inc., the contractor that conducted the decommissioning activities, is registered and certified by the NJDEP for performing UST closure activities. Closure of UST No. 090010-73 proceeded under the approval of the NJDEP Bureau of Underground Storage Tanks (NJDEP-BUST). The signed certifications for UST No. 090010-73 are included in Appendix A.


Based on an inspection of the UST, and field screening of subsurface soils, the DPW has concluded that an historical discharge was associated with the UST. On July 21, 1994, a spill was reported to the NJDEP "Hotline" for UST No. 090010-73 and was assigned Spill Case No. 94-7-21-1561-45.

This UST Closure and Site Investigation Report has been prepared by Smith Technology Corporation, to assist the United States Army Directorate of Public Works (DPW) in complying with the NJDEP Bureau of Underground Storage Tanks (NJDEP-BUST) regulations. The applicable NJDEP-BUST regulations at the date of closure were the *Interim Closure Requirements for Underground Storage Tank Systems* (N.J.A.C. 7:14B-1 et seq. September 1990 and revisions dated November 1, 1991).

This report was prepared using information required at the time of closure. Section 1 of this UST Closure and Site Investigation Report provides a summary of the UST decommissioning activities. Section 2 of this report describes the site investigation activities. Conclusions and recommendations, including the results of the soil sampling investigation, are presented in the final section of this report.

U.S. Army Department of Public Works Fort Monmouth, New Jersey





Project No. 09-5004-08

Figure 1
Site Location Map

1.2 SITE DESCRIPTION

Building 142B is located in the northeastern portion of the Main Post area of Fort Monmouth, as shown on Figure 1. UST No. 090010-73 was located east of Building 142B. The fill port area was located directly above the tank, however, no fuel lines were found upon removal of the UST. A site map is provided on Figure 2.

1.2.1 Geological/Hydrogeological Setting

The following is a description of the geological/hydrogeological setting of the area surrounding Building 142B. Included is a description of the regional geology of the area surrounding Fort Monmouth as well as descriptions of the local geology and hydrogeology of the Main Post area.

Regional Geology

Monmouth County lies within the New Jersey Section of the Atlantic Coastal Plain physiographic province. The Main Post, Charles Wood, and the Evans areas are located in what may be referred to as the Outer Coastal Plain subprovince, or the Outer Lowlands.

In general, New Jersey Coastal Plain formations consist of a seaward-dipping wedge of unconsolidated deposits of clay, silt, and gravel. These formations typically strike northeast-southwest with a dip ranging from 10 to 60 feet per mile and were deposited on Precambrian and lower Paleozoic rocks (Zapecza, 1989). These sediments, predominantly derived from deltaic, shallow marine, and continental shelf environments, date from Cretaceous through the Quaternary Periods. The mineralogy ranges from quartz to glauconite.

The formations record several major transgressive/regressive cycles and contain units which are generally thicker to the southeast and reflect a deeper water environment. Over 20 regional geologic units are present within the sediments of the Coastal Plain. Regressive, upward coarsening deposits are usually aquifers (e.g., Englishtown and Kirkwood Formations, and the Cohansey Sand) while the transgressive deposits act as confining units (e.g., the Merchantville, Marshalltown, and Navesink Formations). The individual thicknesses for these units vary greatly (i.e., from several feet to several hundred feet). The Coastal Plain deposits thicken to the southeast from the Fall Line to greater than 6,500 feet in Cape May County (Brown and Zapecza, 1990).

Local Geology

Based on the regional geologic map (Jablonski, 1968), the Cretaceous age Red Bank and Tinton Sands outcrop at the Main Post area. The Red Bank sand conformably overlies the Navesink Formation and dips to the southeast at 35 feet per mile. The upper member

U.S. Army Department of Public Works Fort Monmouth, New Jersey Sy O 454 455 112 87 455 SITE Source: Smith Technology Corporation (110) ጀ07 SCALE 0 100'

Project No. 09-5004-08

Figure 2

Building T-142B

(Shrewsbury) of the Red Bank sand is a yellowish-gray to reddish brown clayey, medium-to-coarse-grained sand that contains abundant rock fragments, minor mica and glauconite (Jablonski). The lower member (Sandy Hook) is a dark gray to black, medium-to-fine grained sand with abundant clay, mica, and glauconite.

The Tinton sand conformably overlies the Red Bank Sand and ranges from a clayey medium to very coarse grained feldspathic quartz and glauconite sand to a glauconitic coarse sand. The color varies from dark yellowish orange or light brown to moderate brown and from light olive to grayish olive. Glauconite may constitute 60 to 80 percent of the sand fraction in the upper part of the unit (Minard, 1969). The upper part of the Tinton is often highly oxidized and iron oxide encrusted (Minard).

Hydrogeology

The water table aquifer in the Main Post area is identified as part of the "composite confining units," or minor aquifers. The minor aquifers include the Navesink formation, Red Bank Sand, Tinton Sand, Hornerstown Sand, Vincentown Formation, Manasquan Formation, Shark River Formation, Piney Point Formation, and the basal clay of the Kirkwood Formation.

Based on records of wells drilled in the Main Post area, water is typically encountered at depths of 2 to 9 feet below ground surface (bgs). According to Jablonski, wells drilled in the Red Bank and Tinton Sands may produce 2 to 25 gallons per minute (gpm). Some well owners have reported acidic water that requires treatment to remove iron.

Due to the proximity of the Atlantic Ocean to Fort Monmouth, shallow groundwater may be tidally influenced and may flow toward creeks and brooks as the tide goes out, and away from creeks and brooks as the tide comes in. However, an abundance of clay lenses and sand deposits were noted in borings installed throughout Fort Monmouth. Therefore the direction of shallow groundwater should be determined on a case by case basis.

1.3 HEALTH AND SAFETY

Before, during, and after all decommissioning activities, hazards at the work site which may have posed a threat to the Health and Safety of all personnel who were involve with, or were affected by, the decommissioning of the UST system were minimized. All areas which posed, or may have been suspected to pose a vapor hazard were monitored by a qualified individual utilizing an organic vapor analyzer (OVA). The individual ascertained if the area was properly vented to render the area safe, as defined by OSHA.

1.4 REMOVAL OF UNDERGROUND STORAGE TANK

1.4.1 General Procedures

- All underground obstructions (utilities, etc.) were marked out by the contractor performing the closure prior to excavation activities.
- All activities were carried out with the greatest regard to safety and health and the safeguarding of the environment.
- All excavated soils were visually examined and screened with an OVA for evidence of contamination. Potentially contaminated soils were identified and logged during closure activities.
- Surface materials (i.e., asphalt, concrete, etc.) were excavated and staged separately from all soil and recycled in accordance with all applicable regulations and laws.
- A Sub-Surface Evaluator from the DPW was present during all site assessment activities.

1.4.2 Underground Storage Tank Excavation and Cleaning

Prior to UST decommissioning activities, surficial soil was removed to expose the UST and associated piping. All free product present in the piping was drained into the UST, and the UST was purged to remove vapors prior to cutting and removal of the piping. After removal of the associated piping, a manway was made in the UST to allow for proper cleaning. The UST was completely emptied of all liquids prior to removal from the ground. Approximately 922 gallons of liquid were transported by Freehold Cartage Inc. to Lionetti Oil Recovery Co. Inc., a NJDEP-approved petroleum recycling and disposal company located in Old Bridge, New Jersey. Refer to Appendix B for the waste manifest (NJA-1603196).

The UST was cleaned prior to removal from the excavation in accordance with the NJDEP-BUST regulations. After the UST was removed from the excavation, it was staged on polyethylene sheeting and examined for holes. Holes were observed in the UST during the inspection by the Sub-Surface Evaluator. Soils surrounding the UST were screened visually and with an OVA for evidence of contamination. Evidence of potentially contaminated soil was observed surrounding the tank.

1.5 UNDERGROUND STORAGE TANK TRANSPORTATION AND DISPOSAL

The tank was transported by CUTE Inc. to Mazza and Sons Inc. for disposal in compliance with all applicable regulations and laws. See Appendix C for UST Disposal Certificate.

The removal contractor labeled the UST prior to transport with the following information:

- site of origin
- contact person
- NJDEP UST Facility ID number
- name of transporter/contact person
- destination site/contact person

1.6 MANAGEMENT OF EXCAVATED SOILS

Based on visual observations, approximately 30 cubic yards of soil was removed from the excavation on July 21, 1994. All potentially contaminated soils were stockpiled separately from other excavated material and were placed on and covered with polyethylene sheets. Potentially contaminated soils were transported to the hazardous storage area on Main Post prior to ultimate disposal at Soil Remediation of Philadelphia. Soils that did not exhibit signs of contamination were used as backfill following removal of the UST.

2.0 SITE INVESTIGATION ACTIVITIES

2.1 OVERVIEW

The Site Investigation was managed and carried out by U.S. Army DPW personnel. All analyses were performed and reported by U.S. Army Fort Monmouth Environmental Laboratory, a NJDEP-certified testing laboratory. All sampling was performed under the direct supervision of a NJDEP Certified Sub-Surface Evaluator according to the methods described in the NJDEP Field Sampling Procedures Manual (1992). Sampling frequency and parameters analyzed complied with he NJDEP-BUST document Interim Closure Requirements for Underground Storage Tank Systems (September 1990 and revisions dated November 1, 1991) which was the applicable regulation at the date of the closure. All records of the Site Investigation activities are maintained by the Fort Monmouth DPW Environmental Office.

The following Parties participated in Closure and Site Investigation Activities.

• Closure Contractor: Cleaning Up The Environment Inc. (CUTE Inc.)

Closure Supervisor: George Bernotsky

Phone Number: (201) 427-2881 NJDEP Certification No.: 3249

Subsurface Evaluator: Dinkerrai M. Desai

Employer: U.S. Army, Fort Monmouth

Phone Number: (908) 532-1475 NJDEP Certification No.: E0002266

• Analytical Laboratory: U.S. Army Fort Monmouth Environmental Laboratory

Contact Person: Brian K. McKee Phone Number: (908) 532-4359

NJDEP Company Certification No.: 13461

Hazardous Waste Hauler: Freehold Cartage Inc.

Contact Person: Barry Olsen Phone Number: (908) 721-0900

NJDEP Hazardous Waste Hauler No.: 2265

2.2 FIELD SCREENING/MONITORING

Field screening was performed by a NJDEP Certified Sub-Surface Evaluator using an OVA and visual observations to identify potentially contaminated material. Soils were removed from the excavation until no evidence of contamination remained.

2.3 SOIL SAMPLING

On July 21, 1994, post-excavation soil samples A, B, C, D, E, F, and DUP A were collected from a total of six (6) locations along the sidewalls of the excavation, at a depth of 5.5 feet below ground surface (bgs). No fuel lines were found during the removal of the UST.

The site assessment was performed by U.S. Army personnel in accordance with the NJDEP Technical Requirements and the NJDEP Field Sampling Procedures Manual. A summary of sampling activities including parameters analyzed is provided in Table 1. The post-excavation soil samples were collected using polystyrene scoops. Actual soil TPHC values may be higher than reported, due to sample utensil absorbency. If absorbency resulted in reducing the actual soil TPHC concentration by 50 percent, the highest soil contaminant would still have been non-detectable. Following soil sampling activities, the samples were chilled and delivered to U.S. Army Fort Monmouth Environmental Laboratory located in Fort Monmouth, New Jersey, for analysis.

TABLE 1 PAGE 1 OF 1

SUMMARY OF SAMPLING ACTIVITIES BUILDING 142B, MAIN POST FORT MONMOUTH, NEW JERSEY

Sample ID	Date of Collection	Matrix	Sample Type	Analytical Parameters (and USEPA Methods) *	Sampling Method
Α	7/21/94	Soil	Post-Excavation	ТРНС	Polystyrene Scoop
В	7/21/94	Soil	Post-Excavation	TPHC	Polystyrene Scoop
C	7/21/94	Soil	Post-Excavation	TPHC	Polystyrene Scoop
D	7/21/94	Soil	Post-Excavation	TPHC	Polystyrene Scoop
E	7/21/94	Soil	Post-Excavation	TPHC -	Polystyrene Scoop
F	7/21/94	Soil	Post-Excavation	TPHC	Polystyrene Scoop
Dup A	7/21/94	Soil	Post-Excavation	TPHC	Polystyrene Scoop

* Note:

TPHC

Total Petroleum Hydrocarbons (Method 418.1 / soil and aqueous)

Smith Technology Corporation (Project No. 09-5004-08)

soil142B.doc

3.0 CONCLUSIONS AND RECOMMENDATIONS

3.1 SOIL SAMPLING RESULTS

To evaluate soil conditions following removal of the UST, post-excavation soil samples were collected from a total of six (6) locations on July 21, 1994. All samples were analyzed for TPHC. The post-excavation sampling results were compared to the NJDEP residential direct contact total organic contaminants soil cleanup criteria of 10,000 mg/kg (N.J.A.C. 7:26D and revisions dated February 3, 1994). A summary of the analytical results and comparison to the NJDEP soil cleanup criteria is provided in Table 2 and the soil sampling results are shown on Figure 3. The analytical data package is provided in Appendix D.

All post-excavation soil samples collected on July 21, 1994, from the UST excavation contained concentrations of TPHC below the NJDEP soil cleanup criteria. All post-excavation soil samples collected on July 21, 1994 contained non-detectable concentrations of TPHC.

3.2 CONCLUSIONS AND RECOMMENDATIONS

The analytical results for all post-excavation soil samples collected from the UST closure excavation at Building 142B were below the NJDEP soil cleanup criteria for total organic contaminants.

Based on the post-excavation sampling results, soils with TPHC concentrations exceeding the NJDEP soil cleanup criteria for total organic contaminants of 10,000 mg/kg, do not exist in the former location of the UST.

The existing discrepancy as listed in the Executive Summary is believed to be acceptable as explained and does not warrant further investigation or explanation. Procedures have been corrected to eliminate recurrences in the future.

No further action is proposed in regard to the closure and site assessment of UST No. 090010-73 at Building 142B.

TABLE 2 PAGE 1 OF 1

POST-EXCAVATION SOIL SAMPLING RESULTS BUILDING 142B FT. MONMOUTH, NEW JERSEY

Sample ID/Depth	Sample Laboratory ID	Sample Date	Analysis Date	Compound Name	Sample Quantitation Limit (mg/kg)	Compound of Concern	Result (mg/kg)	NJDEP Soil Cleanup Criteria * (mg/kg)	Exceeds Cleanup Criteria
A/5.5-6.0 ¹	1578.1	7/21/94	7/22/94	Total Solid			83 %		
				TPHC .	6.6	yes	ND	10,000	
3/5.5-6.01	1578.2	7/21/94	7/22/94	Total Solid			. 84 %	·	
	•			TPHC	6.6	yes	ND	10,000	
2/5.5-6.01	1578.3	7/21/94	7/22/94	Total Solid			· 79 %	.	
			* * * * * * * * * * * * * * * * * * * *	TPHC	6.6	yes	ND	10,000	
75.5-6.01	1578.4	7/21/94	7/22/94	Total Solid			88 %		
			•	TPHC	6.6	yes	ND	10,000	
E/5.5-6.01	1578.5	7/21/94	7/22/94	Total Solid	1		82 %		
•			• • •	TPHC	6.6	yes	ND	10,000	
F/5.5-6.01	1578.6	7/21/94	7/22/94	Total Solid		-,-	84 %	- -	
			• •	TPHC	6.6	yes	ND	10,000	
oup A/5.5-6.01	1578.7	7/21/94	7/22/94	Total Solid			81 %	<u>.</u> _	
• • • • • • • • • • • • • • • • • • • •				TPHC	6.6	yes	ND	10,000	

Notes:

* Cleanup criteria for total organics

-- Not applicable / does not exceed criteria


TPHC Total Petroleum Hydrocarbons

Actual soil TPHC values may be higher than reported due to absorbency by polystyrene scoops. If absorbency resulted in reducing the actual soil TPHC concentration by 50%, the highest soil contaminant would still have been non-detectable mg/kg.

Smith Technology Corporation (Project No. 09-5004-08)

soil142B.doc

SMITH



Project No. 09-5004-08

Figure 3 **Building 142B Soil Sampling Results**



APPENDIX A CERTIFICATIONS

UNDERGROUND STORAGE TANK (UST) CLOSURE CERTIFICATION

UST-014 2/91



FOR STATE USE ONLY
UST#
Date Rec'd.
TMS #
Sult

Karl J. Delaney Director

State of New-Jersey Department of Environmental Protection and Energy

Division of Responsible Party Site Remediation CN 028 Trenton, NJ 08625-0028

Scott A. Weiner - Commissioner

Trenton, NJ 08625-0028 Tel. # 609-984-3156 Fax. # 609-292-5604

UNDERGROUND STORAGE TANK SITE ASSESSMENT SUMMARY

Under the provisions of the Underground Storage of Hazardous Substances Act in accordance with N.J.A.C. 7:14B

This Summary form shall be used by all owners and operators of Underground Storage Tank Systems (USTS) who have either reported a release and are subject to the site assessment requirements of N.J.A.C. 7:148-8.2 or who have closed USTS pursuant to N.J.A.C. 7:148-9.1 et seq. and are subject to the site assessment requirements of N.J.A.C. 7:148-9.2 and 9.3.

INSTRUCTIONS:

- Please print legibly or type.
- Fill in all applicable blanks. This form will require various attachments in order to complete the Summary. The
 technical guidance document, <u>Interim Closure Requirements for UST's</u>, explains the regulatory (and technical)
 requirements for closure and the <u>Scope of Work, Investigation and Corrective Action Requirements for Discharges from Underground Storage Tanks and Piping Systems</u> explains the regulatory (and technical)
 requirements for corrective action.
- Return one original of the form and all required attachments to the above address.
- Attach a scaled site diagram of the subject facility which shows the information specified in Item IV 8 of this form.
- * Explain any "No" or "N/A" response on a separate sheet.

•		Date of Submi	ssion	-
			00-9001	n-73
•	Bldg. 142B	- 4		EGISTRATION #
FACILITY NAME AND ADD	DRESS	•		
US Army Fort M	onmouth, New Jers	ev	•	
	Public Works, Bl			
	NJ 07703	County Monm	outh	<u> </u>
	0 0 = 4 mm · · · · · · · · ·		••	4 0
i elepnone No. <u>908-5</u>	32=1475			
and the second	DRESS, if different from above			
Telephone No. 908-5				
and the second				

11.	DI	SCHARGE REPORTING REQUIREMENTS
-	Ą.	Was contamination found? X Yes No If Yes, Case No. 94-7-21-1561-45 (Note: All discharges must be reported to the Environmental Action Hotline (609) 292-7172)
•	B	The substance(s) discharged was(were) #2 fuel oil
	·C.	Have any vapor hazards been mitigated? Yes No X N/A
111.	DE	COMMISSIONING OF TANK SYSTEMS Closure Approval No. N/A Emergency Removal
	do de loc to	e site assessment requirements associated with tank decommissioning are explained in the Technical vidance Document, Interim Closure Requirements for UST's, Section V. A-D. Attach complete cumentation of the methods used and the results obtained for each of the steps of tank commissioning used. Please include a site map which shows the locations of all samples and borings, the action of all tanks and piping runs at the facility at the beginning of the tank closure operation and annotated differentiate the status of all tanks and piping (e.g., removed, abandoned, temporarily closed, etc.). The me site map can be used to document other parts of the site assessment requirements, if it is properly and ibly annotated.
IV.	SIT	E ASSESSMENT REQUIREMENTS
	A.	Excavated Soil
	•	Any evidence of contamination in excavated soil will require that the soil be classified as either Hazardous Waste or Non-Hazardous Waste. Please include all required documentation of compliance with the requirements for handling contaminated excavated soil (if any was present) as explained in the technical guidance documents for closure and corrective action. Describe amount of soil removed, its classification, and disposal location.
	₿.	Scaled Site Diagrams
		1. Scaled site diagrams must be attached which include the following information:
		a. North arrow and scale
		b. The locations of the ground water monitoring wells-
8.3	•	Location and depth of each soil sample and boring d. All major surface and sub-surface structures and utilities.
•		Approximate property boundariés
		f. All existing or closed underground storage tank systems, including appurtenant piping
		g. A cross-sectional view indicating depth of tank, stratigraphy and location of water table
		h. Locations of surface water bodies
	C.	Soil samples and borings (check appropriate answer)
, , .		1. Were soil samples taken from the excavation as prescribed? X Yes No N/A
•		2. Were soil borings taken at the tank system closure site as prescribed? Yes No X
	•	3. Attach the analytical results in tabular form and include the following information about each sample a. Customer sample number (keyed to the site map) b. The depth of the soil sample c. Soil boring logs d. Method detection limit of the method used

The sales of the s

	D.	Ground Water Monitoring	•
		Number of ground water monitoring wells inst	alled 0
		2. Attach the analytical results of the groun information for each sample from each well:	d water samples in tabular form; include the following
		a Site diagram number for each well installe	d i
		b. Depth of ground water surface .	
		c. Depth of screened interval	\mathcal{L}_{i}
		d. Method detection limit of the method used	
		e. Well logs	•
		f. Well permit numbers g. QA/OC Information as required	•
		g. exac montains as required	
Ι,	SO	IL CONTAMINATION	
	A. \	Was soil contamination found? $\ _$ Yes $\ \underline{X}$ N	io
		if "Yes", please answer Question B-E	
	!	ff TNoT, please answer Question 8	·
-	B. 1	The highest soil contamination still remaining in the	e ground has been determined to be:
	1	1. N/A ppb total BTEX. N/A 2. N/A ppb total B/N, N/A	ppb total non-targeted VOCppb total non-targeted B/N
•		3. ND pom TPHC	opo total non-targeted B/M
	2	4. N/A ppb	(for non-petroleum substance)
		***************************************	por non-portonoun addarding
	C. F	Remediation of free product contaminated soils	
			to exist below the water table $\underline{\hspace{0.1cm}}$ Yes $\underline{\hspace{0.1cm}}$ No to exist off the property boundaries. Yes $\underline{\hspace{0.1cm}}$ No
	D. V	Was the vertical and horizontal extent of contamin	ation determined? Yes No X N/A
	E., 0	Oges soil contamination intersect ground water?	YesNo XN/A
l	GRC	DUND WATER CONTAMINATION N/A	
	A. Y	Vas ground water contamination found?	s No
		"Yes", please answer Questions 8-G.	
	it		
		"No", please answer only Question B.	
	P		
,			sampling location and at any 1 sampling event to date has
	b	The highest ground water contamination at any 1 een determined to be:	
) 1	The highest ground water contamination at any 1 een determined to be: ppb total BTEX.	pob total non-targeted VOC
,	1 2	he highest ground water contamination at any 1 een determined to be: ppb total BTEX,	ppb total non-targeted VOC ppb total non-targeted B/N
	5 1 2 3	The highest ground water contamination at any 1 een determined to be: ppb total BTEX, ppb total BTN, ppb total MTBE.	ppb total non-targeted VOC ppb total non-targeted B/N ppb total TBA
	1 2 3 4	he highest ground water contamination at any 1 een determined to be: ppb total BTEX,	ppb total non-targeted VOC ppb total non-targeted B/N ppb total TBA (for non-petroleum substance)
	1 2 3 4 5	The highest ground water contamination at any 1 een determined to be: ppb total BTEX, ppb total B/N, ppb total MTBE, ppb greatest thickness of separate phase product	ppb total non-targeted VOCppb total non-targeted B/Nppb total TBA(for non-petroleum substance)
	1 2 3 4 5	he highest ground water contamination at any 1 een determined to be: ppb total BTEX,	ppb total non-targeted VOCppb total non-targeted B/Nppb total TBA(for non-petroleum substance)
	1 2 3 4 5 6	The highest ground water contamination at any 1 een determined to be: ppb total BTEX, ppb total B/N, ppb total MTBE, ppb greatest thickness of separate phase product	ppb total non-targeted VOCppb total non-targeted B/Nppb total TBA(for non-petroleum substance)
	5 3 4 5 6 C. R	The highest ground water contamination at any 1 een determined to be: ppb total BTEX, ppb total B/N, ppb total MTBE, ppb greatest thickness of separate phase product separate phase product has been delineated lesult(s) of well search	ppb total non-targeted B/N ppb total TBA (for non-petroleum substance) ound Yes No N/A
	5 3 4 5 6 C. R	The highest ground water contamination at any 1 een determined to be: ppb total BTEX, ppb total B/N, ppb total MTBE, ppb greatest thickness of separate phase product separate phase product has been delineated lesult(s) of well search A well search (including a review of manual well)	ppb total non-targeted VOCppb total non-targeted B/Nppb total TBA(for non-petroleum substance)

F)

	D. Proximity of Wells and contaminant plume
	1. The shallowest depth of any well noted in the well search which may be in the horizontal or vertical potential path(s) of the contaminant plume(s) isfeet below grade (consideration has been given for the effects of pumping, subsurface structures, etc. on the direction(s) of contaminant migration). This well isfeet from the source and its screening begins at a depth offeet.
	2. The shallowest depth to the top of the well screen for any well in the potential path of the plume(s) (as described in D1 above) isfeet below grade. This well is locatedfeet from the source.
	3. The closest horizontal distance of a private, commercial or municipal well in the potential path of the plume (as determined in D1) is feet from the source. This well is feet deep and screening begins at a depth of feet.
	E. A plan for separate phase product recovery has been includedYesNoN/A
	F. A ground water contour map has been submitted which includes the ground water elevations for each well. YesNoNA
	G. Delineation of contamination
	The ground water contaminants have been delineated to MCLs or lower values at the property boundaries. Yes No
	The plume is suspected to continue off the property at concentrations greater than MCLs. YesNo
	3. Off property access (circle one): is being sought has been approved has been denied
VII.	SITE ASSESSMENT CERTIFICATION [preparer of site assessment plan - N.J.A.C. 7:148-8.3(b) &9.5(a)3]
	The person signing this certification as the "Qualified Ground Water Consultant" (as defined in N.J.A.C.7:148-1.6) responsible for the design and implementation of the site assessment plan as specified in N.J.A.C. 7:148-8.3(a) & 9.2(b)2, must supply the name of the certifying organization and certification number.
	"I certify under penalty of law that the information provided in this document is true; accurate, and complete and was obtained by procedures in compliance with N.J.A.C., 7:14B-8 and 9:11 am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment."
	NAME (Print or Type) Dinkerrai M. Desai SIGNATURE
	COMPANY NAME US Army Fort Monmouth DATE
	(Preparer of Site Assessment Plan)
	CERTIFYING ORGANIZATION NUMBER E0002266

f.

2/91	
VIII	- TANK DECOMMISSIONING CERTIFICATION [person performing tank decommissioning portion of closure plan - N.J.A.C. 7:148-9.5(a)4]
	"I certify under penalty of law that tank decommissioning activities were performed in compliance with NJA.C. 7:14B-9.2(b)3. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment."
	NAME (Print or Type) See Appendix A SIGNATURE
	NAME (Print or Type) See Appendix A SIGNATURE COMPANY NAME DATE (Performer of Tank Decommissioning)
•	(Performer of Tank Decommissioning)
IX.	CERTIFICATIONS BY THE RESPONSIBLE PARTY(IES) OF THE FACILITY
-	A. The following certification shall be signed by the highest ranking individual with overal responsibility for that facility [N.J.A.C. 7:148-2.3(c)1i].
	"I certify under penalty of law that the information provided in this document is true, accurate, and complete. I am aware that there are significant penalties for submitting false inaccurate, or incomplete information, including fines and/or imprisonment."
	NAME (Print or Type) James Ott SIGNATURE
•	COMPANYNAME US Army Fort Monmouth DATE
	B. The following certification shall be signed as follows [according to the requirements of N.J.A.C. 7:14B-2.3(C)2i]:
	 For a corporation, by a principal executive officer of at least the level of vice president. For a partnership or sole proprietorship, by a general partner or the proprietor, respectively; or For a municipality, State, Federal or other public agency by either the principal executive officer or ranking elected official. In cases where the highest ranking corporate partnership, governmental officer or official at the facility as
	required in A above is the same person as the official required to certify in B, only the certification in A-
	need to be made. In all other cases, the certifications of A and B shall be made.
	"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this application and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment."
	"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this application and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including



APPENDIX B WASTE MANIFEST



he esset of an amorganist of high little fall the trains the distribution at and the N.J. Leph. of Editionalist principal and also every every every every as a second and also every ever

State of New Jersey Department of Environmental Protection and Energy Hazardous Wests Regulation Program Manifest Section CN 028, Transon, NJ 05825-0028 Janed for use on 888 12-88th Properties.

the or have at recent service desiding in the oil sites (17-bit)			40, KOSUAUJY, ENDRES 9-30-31
UNIFORM HAZARDOUS 1. Genoralor's US EPA WASTE MANIFEST AFSISISING	Document No.	l e l fannir	lion in the shaded areas aquired by Federal ies.
3. Generator's Name and Mulling Address ASSESSED TO THE CONTRACT OF THE CONTRACT CONTRACT Many Past Contract Contract Contract ASSESSED TO THE C	15 Electronics Comm	A. State Manifest Docum	18073196
	584	B. Sinte Constalor's ID	1000100
AH SELF Phone (96B) F3E-6213 Fortm			
5. Transporter 1 Company Name	US EPA III Number	<u> </u>	20 47 47 - V
Freehold Carfey PMC MT. 7. Transporter 2 Company Namy	DISISAIFISICIE EN	C. State TreN JEDE D. Transporter's Phone	
	11111111	E. State Trans. 10	77,27,25
Designated Facility Name and Sita Address 10.	US SPA ID Number	,	
Ruyon + chesenet RD.	•	F. Transporter's Phorse G. State Profile's IO	<u> </u>
	मेशकारामा अवस्था		181721-0900
11. US DOT Description declaring Proper Shipping Name, Hacard Class.	1 12 000		TA. Unit Wasta No. "
1 PC+10/ch-01/105 class30		100 33309	1
			6 × 7:22
Petroleum or Musclessal	to lean of	irm arra an	BY ZE
1 10 1			
Jeans atible byon 2 mu 177		111:00032	(2) X.71 21 2
1 /2 /2040/cmm = 1/2/02 4/28231	Tours between)		1 1
150 144 Fracid States de grand por 12		TT 0019122	16 X17 12 12 1
1 - Francisco 100 5 cles 53	(Pertroteum. 1)		
X come of blibson & MAIZE	الماما كالمام د	100000459	GRITIZE
J Additional Descriptions for Materials Listed Above	olo,	- K-Handling Codes for	Wastes Histed Apove
was 40% Lit	40%	704	16. Ed fation
	0%	784	704
busta 40% L. T. dwaler	40/0 1.1	b. Ail trails	no Either Por
13. Special Handing Instructions and Additional Information. Not EPA Regulation - Notheracles		ruepe dogod	o1-
24hr. Emer # 201-429-2881	sousois-18 P) w	JOEPE octoo	10-134
*DEC=1 == 55404		TOPPEOOL	
18. GENÉRATOR'S CERTIFICATION: I hermy declare that the contents of appaint, packed, marked, and labeled, and are in all respects in a government regulations.	iroper conclutor, for transport by high	way according to applicat	international and national
If I am a large quantity generalize, I carrily that I have a program in plu economically preciliable and that I have selected the procileable meth-	od oj kte <u>jmeni. Pomos</u> iz disposaj di	HTWILLY EVELLEDIE OF MALEY	ich minimizus the prosont and
name it all the second of the	quantity unmenter, i have made a goo	n eximinim at polic ditel b	y waste generation and soloci
Printed/Typed Naming	Bignows (40 con	m I	Blanth Day Your
T 17. Transporter 1 Actinoviedgement of Receipt of Materials		Y - Tak	EUN 111577
2 - Specialists - I Street	Bioderice	 	Month Day Your
I PAULU K. MEDEIROS	1,000	<u>/~~~~</u>	1017113194
PAULO R. MEDEIROS 18. Transporter & Admirosofedgement of Receipt of Malarials Printed Typed Name	Singshive	\	Honth Day Year
A surround Athers territion	Signature		
19, Discrepancy Indication Space	······································		حما مرحا حفاجه المحادث واستطعم وصرحة ا
4	•		•
20. Facility Constant Operator: Cartification of receipt of hezardous mater	rials povered by this montest except a	noted in Item 19.	
Y Printed/Typed Name	Signatura		Month Day Year
CPA Form 8700-62 (Flav, title) Promous addlors are obscious.	SIGNATURE AND INFORM	ATION MUST BE LE	GIBLE ON ALL COPIES

CALCULATION SHEET

Building No. 142B

Tank Size 1000 gal

NJDEPE Reg. No. 6090010 - 13 (

Tank Void 7.5 tons

CLEAN FILL

 ITEM NO.
 DESCRIPTION
 QUANTITY
 TICKET #

 1-;1/
 22,18
 1881/

 22,35
 18810

 15,03
 1872/

TOTAL 59,56

STONE

ITEM NO. DESCRIPTION QUANTITY TICKET #

TOTAL &

ID#27 soil to stockpile (+59.56) - 7.5 = 52.06 tons Chargeable clean fill 52.06Chargeable stone

Name Light Address C./s.m.	1453 W. Park Ave., Wayaldi Asbury Park, NJ. 07712 908-493-3333		18811 1. 18811 1. 18811 1. 18811 1. 18811 1. 18811 1. 18811 1. 18811 1. 18811 1. 18811
* Item(a)	Quantity / Measure (tons, Ibs., yds., ea.)	Unit Price	- Total 13
	G 69910		
	T 25500	22.18 too	
	N-44.360 :		, d
	Control of the second		144 pt
Driver	-130E 33614	Sub Total	100 h
Réceived Production Réceived		Delivery , ·	-
* Company not responsible for damage done-off public roads, Color not guaranteed!		N.J. Tax	
F	evel will travell ace 1925	Total	·
	· ·	•	• • • •

Name Big Address C/4	1453 W. Park Ave., Waysid Astury Park, NJ, 07712 908-499-3333 ATMCK Ky		18810
· (tem(s)	Cuantity / Measure (tona, loa., yds., ea.)	Unit Price	Total /
	9 2020000		
	7 2550 a 144 700 164	22.35 ton	
		. 25,25 (8)	
Driver	a. Abuta	Sub Total	
Received_		Delivery	1
* Company not responsibly for damage	done off public roads, Color not guaranteed!	N.J. Tax	<u> </u>
	el will travell o 1925	Total of	

	,		
Name Sulla Kull	808-493-3333	Order Date Order Date Deliver Date Delivered F.O.B./P.U.	18774 1 Co.D. Cherge
(item(s)	Quantity / Measure (tons, ibs., yds., es.)	Unit Price	Total
	12 - 170:650		
	25 5%	22.53 ton	\$
	H Start	· .	
	19 (1800)	f.	
Driver UNITS	The Bearing	Sub Total	ب.
Received Cally		Dolivery_	
* Company not responsible for damage	done off public roses. Color not guaranteed!	NJ. Tax-	
,	ed will travel!	Total	
·	The same of the sa	1	

Bldg 142A 7.5 tons Bldg 142B 15.03 Tons



APPENDIX C UST DISPOSAL CERTIFICATE

411-US	T-009001008	MAZZA & SONS, INC. Metal Recyclers Auto and Truck	DATE / Any 97
1426- 1426- atom for	0090010-45 No 4577009	3230 Shatto Rd. Tinion Falls, NJ (908) 922-9292	
	Address		
. •			
Make of		•	Weight Pri
Ruios	,	43520 LB 6	Cast fron
		•	(Steel
			LL from
		38380 FB E	Copper #1
			Copper #2
(irea		1578	LI. Copper
Tacık			Bress
Price,			Alum Clean—
		AUG _ 1 1994	Lead
· · · · · · · · · · · · · · · · · · ·		114 AUG - 1104 1))	Statriess
	•		Rediators
			Battery
		1 Land Control of the	
	•	,	TOTAL AMOUNT:
~ ~~~		•	
			<u> </u>
	•		•
	•		Cllis



APPENDIX D SOIL ANALYTICAL DATA PACKAGE

Report of Analysis U.S. Army, Fort Monmouth Environmental Laboratory NJDEPE Certification # 13461

Client: U.S. Army

DPW, SELFM-PW-EV

Bldg. 167

Ft. Monmouth, NJ 07703

Lab. ID #: 1578.1-.7

Sample Rec'd: 07/21/94

Analysis Start: 07/22/94 Analysis Comp: 07/22/94

Analysis: 418.1 (TPH)

'Matrix: Soil

Analyst: S. Hubbard

Ext. Meth: Sonc.

NJDEPE UST Reg.#:

Closure #:

DICAR #:

Location #: Bldg. 142B

Lab ID.	Description	%Solid	Result (mg/K	
1578.1	Site A, N.W. Corner, OVA= 61	83	ND	6.6
1578.2	Site B, N.E. Corner OVA= 2	84	ND	6.6
1578.3	Site C, East OVA= 1	79	ND	6.6
1578.4	Site D, South East OVA= 8	. 88	ND	6.6
1578.5	Site E, South West OVA= 2	82	ND	6.6
1578.6	Site F, West OVA= 2	84	ND	6.6
1578.7	Site G, N.W. Dup OVA= 50	81	ND	6.6
		·		
		- '		-
M. Bl.	Method Blank	100	ND	3.3

Notes: ND = Not Detected, MDL = Method Detection Limit

* = Silica Gel Added, NA = Not Applicable

1578.7 dup= 100% 1578.7 s= 114% 1578.7 sd= 107% RPD= 6.3%

Brian K. McKee Laboratory Director

SERV-AIR,INC.

Sample: Date / Time Rhalysis Start: Omer: D. DeSau Site Name: BUG 142 B Preserv Matrix Bottles Remarks Finish Remarks Remarks Preserv Remarks Remarks 1578-1 7/21 1-30 B NE (())	
Site Name: BUG 142B e: Sample Date/Time Customer Sample Matrix Bottles Date/Time Location/ID Number Matrix Bottles 1578. 7/21 -\$12 A NW Corner Sample Matrix Bottles	•
Sample Customer Sample Sample Of Remarks 1578. 7/21 -3° A NW Corner So. L	n: '
Sample Date/Time Customer Sample Sample # of Remarks 578. 7/21 1-10 A NW Corner Sample Matrix Bottles	vation
	Method
1.2 1-20 B NE "	
1.3 130 C East	
4 1-40 D SOURTENT 1 8	
1,5 1-50 E SOLHWAY , 2	
16 1-59 F West 2 05A5N A52114	
V 27 1 2-04 6- NW- (DUP) 1 50 COL 7-21-94	13:16
DAIZ + 9.5 ppm	=44
Read 66	
- High Hanson	, 1
nquished By (signature) Date / Time Received By (signature) Shipped By:	B.20
nquished By (signature) Date / Time Received for Lab by (signature): Date / Time	
: A drawing depicting sample location should be attached or drawn on the reverse side of this chain of custody.	in
ENV COC form 01 Page of Pages Rev. A Date: 02 Apr 93	

Report of Analysis U.S. Army, Fort Monmouth Environmental Laboratory NJDEPE Certification # 13461

Client: U.S. Army

DPW, SELFM-PW-EV

Bldg. 167

Ft. Monmouth, NJ 07703

Lab. ID #: 1578.1-.7

Sample Rec'd: 07/21/94

Analysis Start: 07/22/94

Analysis Comp: 07/22/94

Analysis: Munsel

	<u> </u>
Lab ID#	Soil Color
1578.1	2.5Y 4/4 Olive Brown
1578.2	10YR 4/6 Dark Yellowish Brown
1578.3	2.5Y 4/4 Olive Brown
1578.4	2.5Y 4/4 Olive Brown
1578.5	2.5Y 5/6 Light Olive Brown
1578.6	2.5Y 5/6 Light Olive Brown
1578.7	2.5Y 4/4 Olive Brown

Brian K. McKee Laboratory Director

PHC Conformance/Non-conformance Summary Report No Yes	<u>s</u>
1. Blank Contamination - If yes, list the sample and the corresponding concentrations in each blank	•,
2. Matrix Spike/Matrix Sp Dup. Recoveries Meet Criteria	
3. IR Spectra submitted for standards, blanks, & samples	
4. Chromatograms submitted for standards, blanks, and samples if GC fingerprinting was conducted.	14
5. Extraction holding time met. (If not met, list number of days exceeded for each sample)	
	,
6. Analysis holding time met. (If not met, list number of days exceeded for each sample)	<u>-</u>
Comments:	

Laboratory Authentication Statement

I certify under penalty of law, where applicable, that this laboratory meets the Laboratory Performance Standards and Quality Control requirements specified in N.J.A.C. 7:18 and 40 CFR Part 136 for Water and Wastewater Analyses and SW 846 for Solid Waste Analysis. I have personally examined the information contained in this report, and to the best of my knowledge, I believe that the submitted information is true, accurate, complete, and meets the above referenced standards where applicable. I am aware that there are significant penalties for purposefully submitting falsified information, including the possibility of a fine and imprisonment.

Project #1578

Brian K. McKee Laboratory Manager