## **United States Army**

Fort Monmouth, New Jersey

# Underground Storage Tank Closure and Site Investigation Report

Building 2506 Charles Wood Area



NJDEP UST Registration No. 0081515-17

December 1997

# UNDERGROUND STORAGE TANK CLOSURE AND SITE INVESTIGATION REPORT

#### **BUILDING 2506**

# CHARLES WOOD AREA NJDEP UST REGISTRATION NO. 0081515-17

#### **DECEMBER 1997**

#### PREPARED FOR:

UNITED STATES ARMY, FORT MONMOUTH, NEW JERSEY
DIRECTORATE OF PUBLIC WORKS
BUILDING 167
FORT MONMOUTH, NJ 07703

#### PREPARED BY:

SMC ENVIRONMENTAL SERVICES GROUP 501 ALLENDALE ROAD KING OF PRUSSIA, PA 19406

PROJECT NO. 2429-3080

## **TABLE OF CONTENTS**

EXECUTIVE SUMMARY	iv
1.0 UNDERGROUND STORAGE TANK DECOMMISSIONING ACTIVITIES 1.1 OVERVIEW 1.2 SITE DESCRIPTION	1 1 2
1.2.1 Geological/Hydrogeological Setting	2
1.3 HEALTH AND SAFETY 1.4 REMOVAL OF UNDERGROUND STORAGE TANK	4 4
1.4.1 General Procedures 1.4.2 Underground Storage Tank Excavation and Cleaning	4
1.5 UNDERGROUND STORAGE TANK TRANSPORTATION AND DISPOSAL 1.6 MANAGEMENT OF EXCAVATED SOILS	5 5
2.0 SITE INVESTIGATION ACTIVITIES	6
2.1 OVERVIEW 2.2 FIELD SCREENING/MONITORING 2.3 SOIL SAMPLING	6 6 6
3.0 CONCLUSIONS AND RECOMMENDATIONS	8
3.1 SOIL SAMPLING RESULTS 3.2 CONCLUSIONS AND RECOMMENDATIONS	8

#### **TABLE OF CONTENTS (CONTINUED)**

#### **TABLES**

Table 1 Summary of Post-Excavation Sampling Activities

Table 2 Post-Excavation Soil Sampling Results

#### **FIGURES**

Figure 1 Site Location Map

Figure 2 Site Map

Figure 3 Cross Sectional View

Figure 4 Soil Sampling Location Map

#### **APPENDICES**

Appendix A NJDEP Standard Reporting Form

Appendix B Site Assessment Summary

Appendix C Waste Manifest

Appendix D UST Disposal Certificate

Appendix E Soil Analytical Data Package

Appendix F Photographs

#### **EXECUTIVE SUMMARY**

#### **UST Closure**

On June 12, 1997, a fiberglass-coated steel underground storage tank (UST) was closed by removal in accordance with the New Jersey Department of Environmental Protection (NJDEP) closure procedures at the Charles Wood area of the U.S. Army Fort Monmouth, Fort Monmouth, New Jersey. The UST, NJDEP Registration No. 0081515-17 (Fort Monmouth ID No. 2506), was located south of Building 2506 in the Charles Wood area of U.S. Army, Fort Monmouth. UST No. 0081515-17 was a 1,000-gallon No. 2 fuel oil UST. The UST fill port was located directly above the tank.

#### Site Assessment

The site assessment was performed by U.S. Army personnel in accordance with the NJDEP *Technical Requirements for Site Remediation* (N.J.A.C. 7:26E) and the NJDEP *Field Sampling Procedures Manual*. The sampling and laboratory analysis conducted during the site assessment were performed in accordance with Section 7:26E-2.1 of the *Technical Requirements for Site Remediation*. Soils surrounding the tank were screened visually and with air monitoring equipment for evidence of contamination. Following removal, the UST was inspected for corrosion holes. No holes were noted in the UST and no evidence of potentially contaminated soils was observed surrounding the tank. Samples contained non-detectable levels of TPHC.

#### **Site Restoration**

5113

713

6.1

Following receipt of all post-excavation soil sampling results, the excavation was backfilled to grade with native topsoil and restored to its original condition.

#### Conclusions and Recommendations

Based on the post-excavation soil sampling results, soils with TPHC concentrations exceeding the NJDEP soil cleanup criteria for total organic contaminants of 10,000 mg/kg, do not exist in the former location of the UST or associated piping.

No further action is proposed in regard to the closure and site assessment of UST No. 0081515-17 at Building 2506.

# 1.0 UNDERGROUND STORAGE TANK DECOMMISSIONING ACTIVITIES

#### 1.1 OVERVIEW

N. Da

7.13

k 1/4

1 15

2.11

One underground storage tank (UST), New Jersey Department of Environmental Protection (NJDEP) Registration No. 0081515-17, was closed at Building 2506 at the Charles Wood area of U.S. Army Fort Monmouth, Fort Monmouth, New Jersey on June 12, 1997. Refer to site location map on Figure 1. This report presents the results of the Department of Public Works' (DPW) implementation of the UST Decommissioning/Closure Plan approved by the NJDEP. The UST was a fiberglass-coated steel 1,000-gallon tank containing No. 2 fuel oil.

Decommissioning activities for UST No. 0081515-17 complied with all applicable Federal, State and Local laws and ordinances in effect at the date of decommissioning. These laws included but were not limited to N.J.A.C. 7:14B-1 et seq., N.J.A.C. 5:23-1 et seq., and Occupational Safety and Health Administration (OSHA) 1910.146 & 1910.120. All permits including but not limited to the NJDEP-approved Decommissioning/Closure Plan were posted onsite for inspection. The decommissioning activities were conducted by DPW personnel who are registered and certified by the NJDEP for performing UST closure activities. Closure of UST No. 0081515-17 proceeded under the approval of the NJDEP Bureau of Underground Storage Tanks (NJDEP-BUST). The NJDEP-BUST Standard Reporting Form and signed Site Assessment Summary form for UST No. 0081515-17 are included in Appendices A and B, respectively.

Based on inspecting the UST, field screening of subsurface soils, and reviewing analytical results of collected soil samples, the DPW has concluded that no significant historical discharges are associated with the UST or associated piping.

This UST Closure and Site Investigation Report has been prepared by SMC Environmental Services Group, to assist the U.S. Army in complying with the NJDEP-BUST regulations. The applicable NJDEP-BUST regulations at the date of closure were the *Interim Closure Requirements for Underground Storage Tank Systems* (N.J.A.C. 7:14B-1 et seq. October 1990 and revisions dated November 1, 1991).

This report was prepared using information collected at the time of closure. Section 1 of this UST Closure and Site Investigation Report provides a summary of the UST decommissioning activities. Section 2 of this report describes the site investigation activities. Conclusions and recommendations, including the results of the soil sampling investigation, are presented in the final section of this report.

#### 1.2 SITE DESCRIPTION

Building 2506 is located in the Charles Wood area of the Fort Monmouth Army Base, as shown on Figure 1. UST No. 0081515-17 was located south of Building 2506 and appurtenant copper piping ran approximately twenty-eight (28) feet north from the excavation to Building 2506. The fill port area was located directly above the tank. A site map is provided on Figure 2.

#### 1.2.1 Geological/Hydrogeological Setting

The following is a description of the geological/hydrogeological setting of the area surrounding Building 2506. Included is a description of the regional geology of the area surrounding Fort Monmouth as well as descriptions of the local geology and hydrogeology of the Charles Wood area.

#### Regional Geology

Monmouth County lies within the New Jersey Section of the Atlantic Coastal Plain physiographic province. The Main Post, Charles Wood, and the Evans areas are located in what may be referred to as the Outer Coastal Plain subprovince, or the Outer Lowlands.

In general, New Jersey Coastal Plain formations consist of a seaward-dipping wedge of unconsolidated deposits of clay, silt, and gravel. These formations typically strike northeast-southwest with a dip ranging from 10 to 60 feet per mile and were deposited on Precambrian and lower Paleozoic rocks (Zapecza, 1989). These sediments, predominantly derived from deltaic, shallow marine, and continental shelf environments, date from Cretaceous through the Quaternary Periods. The mineralogy ranges from quartz to glauconite.

The formations record several major transgressive/regressive cycles and contain units which are generally thicker to the southeast and reflect a deeper water environment. Over 20 regional geologic units are present within the sediments of the Coastal Plain. Regressive, upward coarsening deposits are usually aquifers (e.g., Englishtown and Kirkwood Formations, and the Cohansey Sand) while the transgressive deposits act as confining units (e.g., the Merchantville, Marshalltown, and Navesink Formations). The individual thicknesses for these units vary greatly (i.e., from several feet to several hundred feet). The Coastal Plain deposits thicken to the southeast from the Fall Line to greater than 6,500 feet in Cape May County (Brown and Zapecza, 1990).

#### **Local Geology**

113

1. 1.1

Based on the regional geologic map (Jablonski, 1968), the Cretaceous age Red Bank and Tinton Sands outcrop at the Charles Wood area. The Red Bank sand conformably overlies the Navesink Formation and dips to the southeast at 35 feet per mile. The upper member (Shrewsbury) of the Red Bank sand is a yellowish-gray to reddish brown clayey, medium-to-coarse-grained sand that contains abundant rock fragments, minor mica and glauconite (Jablonski). The lower member (Sandy Hook) is a dark gray to black, medium-to-fine grained sand with abundant clay, mica, and glauconite.

The Tinton sand conformably overlies the Red Bank Sand and ranges from a clayey medium to very coarse grained feldspathic quartz and glauconite sand to a glauconitic coarse sand. The color varies from dark yellowish orange or light brown to moderate brown and from light olive to grayish olive. Glauconite may constitute 60 to 80 percent of the sand fraction in the upper part of the unit (Minard, 1969). The upper part of the Tinton is often highly oxidized and ironoxide encrusted (Minard).

Over the last 80 years, the natural topography of Fort Monmouth has been altered by excavation and filling activities by the military. Topographic elevations for the Charles Wood area range from 20 feet above mean seal level (MSL) to 71 feet above MSL.

#### Hydrogeology

r (a

The water table aquifer in the Charles Wood area is identified as part of the "composite confining units", or minor aquifers. The minor aquifers include the Navesink formation, Red Bank Sand, Tinton Sand, Hornerstown Sand, Vincentown Formation, Manasquan Formation, Shark River Formation, Piney Point Formation, and the basal clay of the Kirkwood Formation.

Six well records for monitor wells installed at locations within the Charles Wood area in February 1981 were used for reference. The wells were completed to total depths ranging from 20 to 25 feet below ground surface (bgs). Water was encountered at depths ranging from 5 to 12 feet bgs.

The lithologic descriptions for these borings described deposits that were primarily fine to coarse, glauconitic sands, with traces of gravel, silt, and clay. These sediments are part of the Hornerstown Marl, from the Tertiary Period (Paleocene Series, approximately 58 to 66 Ma). According to Jablonski, wells drilled in the Red Bank and Tinton Sands may produce from 2 to 25 gallons per minute (gpm). Some well owners have reported acidic water that requires treatment to remove iron.

Shallow groundwater is locally influenced within the Charles Wood area by the following factors:

- tidal influence (based on proximity to the Atlantic Ocean, rivers, and tributaries)
- topography
- nature of the fill material within the Charles Wood area
- presence of clay and silt lenses in the natural overburden deposits
- local groundwater recharge areas (i.e., streams, lakes)

Due to the fluvial nature of the overburden deposits (i.e., sand and clay lenses), shallow groundwater flow direction is best determined on a case-by-case basis. Building 2506 is located, approximately 100 feet north of Wampum Brook, the nearest water body. Based on the Charles Wood area topography, the groundwater flow in the area of Building 2506 is anticipated to be to the southeast.

#### 1.3 HEALTH AND SAFETY

Before, during, and after all decommissioning activities, hazards at the work site which may have posed a threat to the Health and Safety of all personnel who were involved with, or were affected by, the decommissioning of the UST system were minimized. All areas, which posed, or may have been suspected to pose a vapor hazard were monitored by a qualified individual utilizing an organic vapor analyzer (OVA). The individual ascertained if the area was properly vented to render the area safe, as defined by OSHA.

#### 1.4 REMOVAL OF UNDERGROUND STORAGE TANK

#### 1.4.1 General Procedures

V. La

< 15

7.13

- All underground obstructions (utilities, etc.) were identified by the contractor performing the closure prior to excavation activities.
- All activities were carried out with the greatest regard to safety and health and the safeguarding of the environment.
- All excavated soils were visually examined and screened with an OVA for evidence of contamination. Potentially contaminated soils were identified and logged during closure activities.
- Surface materials (i.e., asphalt, concrete, etc.) were excavated and staged separately from all soil and recycled in accordance with all applicable regulations and laws.
- A Sub-Surface Evaluator from the DPW was present during all site assessment activities.

#### 1.4.2 Underground Storage Tank Excavation and Cleaning

Prior to UST decommissioning activities, surficial soil was removed to expose the UST and associated piping. All free product present in the piping was drained into the UST, and the UST was purged to remove vapors prior to cutting and removal of the piping. After removal of the associated piping, a hole was made in the UST to allow for proper cleaning. The UST was completely emptied of all liquids prior to removal from the ground. Approximately 20 gallons of liquid from the UST and its associated piping were transported to the Fort Monmouth waste oil holding facility. Refer to Appendix C for a copy of the waste manifest.

The UST was cleaned prior to removal from the excavation in accordance with the NJDEP-BUST regulations. After the UST was removed from the excavation, it was staged on polyethylene sheeting and examined for holes. No holes or punctures were observed during the inspection by the Sub-Surface Evaluator. Soils surrounding the UST were screened visually and with an OVA for evidence of contamination. No evidence of contamination was observed. Soil screening was also performed along the piping associated with the UST. No contamination was noted anywhere along the piping length. See Figure 3 for a cross-sectional view of the excavated area.

#### 1.5 UNDERGROUND STORAGE TANK TRANSPORTATION AND DISPOSAL

The fiberglass-coated steel tank was transported to Mazza & Sons, Inc. for disposal in compliance with all applicable regulations and laws. See Appendix D for a copy of the UST disposal certificate and Appendix F for photographs of the UST.

The UST was labeled prior to transport with the following information:

- Site of origin
- Contact person
- NJDEP UST Facility ID number
- Former Contents

#### 1.6 MANAGEMENT OF EXCAVATED SOILS

Based on OVA air monitoring and TPHC analysis results from the post-excavation soil samples, no soils exhibited signs of contamination. Therefore, the excavated soils were used as backfill following removal of the UST.

#### 2.0 SITE INVESTIGATION ACTIVITIES

#### 2.1 OVERVIEW

1.1.3

1.13

11

117

1 1.3

The Site Investigation was managed and carried out by U.S. Army DPW personnel. All analyses were performed and reported by U.S. Army Fort Monmouth Environmental Laboratory, a NJDEP-certified testing laboratory. All sampling was performed under the direct supervision of a NJDEP Certified Sub-Surface Evaluator according to the methods described in the NJDEP *Field Sampling Procedures Manual* (1992). Sampling frequency and parameters analyzed complied with the NJDEP-BUST document *Interim Closure Requirements for Underground Storage Tank Systems* (October 1990 and revisions dated November 1, 1991) which was the applicable regulation at the date of the closure. All records of the Site Investigation activities are maintained by the Fort Monmouth DPW Environmental Office.

The following Parties participated in Closure and Site Investigation Activities:

 Subsurface Evaluator: Eugene W. Lesinski Employer: U.S. Army, Fort Monmouth

Phone Number: (908) 532-0989 NJDEP Certification No.: 0014537

Analytical Laboratory: U.S. Army Fort Monmouth Environmental Laboratory

Contact Person: Daniel K. Wright Phone Number: (908) 532-4359

NJDEP Company Certification No.: 13461

#### 2.2 FIELD SCREENING/MONITORING

Field screening was performed by a NJDEP Certified Sub-Surface Evaluator using an OVA and visual observations to identify potentially contaminated material. Soil excavated from around the tank and appurtenant piping, as well as the UST excavation sidewalls and bottom, did not exhibit any evidence of potential contamination.

#### 2.3 SOIL SAMPLING

On June 12 and 13, 1997, following the removal of the UST, post-excavation soil samples A, B, C, D, E, F, G, H, and DUP E were collected from a total of eight (8) locations of the UST excavation. On June 12, 1997, samples A, B, and C were collected along the centerline of the excavation floor at a depth of 6.0 feet bgs and sidewall samples, D, E and DUP E were collected at a depth of 5.5 feet bgs. On June 13, 1997, samples F, G, and H were collected along the former piping length of the excavation, which was approximately twenty-eight (28) feet in length. The piping samples were collected at a depth of 1.0 feet bgs. All samples were analyzed for total petroleum hydrocarbons (TPHC) and total solids.

U.S. Army personnel in accordance with the NJDEP Technical Requirements and the NJDEP Field Sampling Procedures Manual performed the site assessment. A summary of sampling activities including parameters analyzed is provided in Table 1. The post-excavation soil samples were collected using NJDEP *Field Sampling Procedures Manual* (1992) standard sampling procedures. Following soil sampling activities, the samples were chilled and delivered to U.S. Army Fort Monmouth Environmental Laboratory located in Fort Monmouth, New Jersey, for analysis.

#### 3.0 CONCLUSIONS AND RECOMMENDATIONS

#### 3.1 SOIL SAMPLING RESULTS

6 16

4 17

4.19

To evaluate soil conditions following removal of the UST and associated piping, post-excavation soil samples were collected from a total of eight (8) locations on June 12 and 13, 1997. All samples were analyzed for TPHC and total solids. The post-excavation sampling results were compared to the NJDEP residential direct contact total organic contaminants soil cleanup criteria of 10,000 mg/kg (N.J.A.C. 7:26D and revisions dated February 3, 1994). A summary of the analytical results and comparison to the NJDEP soil cleanup criteria is provided in Table 2 and the soil sampling locations are shown on Figure 4. The analytical data package is provided in Appendix E.

All post-excavation soil samples collected on June 12 and 13, 1997, from the UST excavation and from below piping associated with the UST contained concentrations of TPHC below the NJDEP soil cleanup criteria. Samples contained non-detectable levels of TPHC.

#### 3.2 CONCLUSIONS AND RECOMMENDATIONS

The analytical results for all post-excavation soil samples collected from the UST closure excavation at Building 2506 were below the NJDEP soil cleanup criteria for total organic contaminants.

Based on the post-excavation sampling results, soils with TPHC concentrations exceeding the NJDEP soil cleanup criteria for total organic contaminants of 10,000 mg/kg, do not exist in the former location of the UST or associated piping.

No further action is proposed in regard to the closure and site assessment of UST No. 0081515-17 at Building 2506.

**TABLES** 

i, i

Link

6.74

TABLE 1
SUMMARY OF POST-EXCAVATION SAMPLING ACTIVITIES
BUILDING 2506, CHARLES WOOD AREA
FORT MONMOUTH, NEW JERSEY

Page 1 of 1

Sample ID	Date of Collection	Date Analysis Started	Matrix	Sample Type	Analytical Parameters*	NJDEP Method
Α .	6/12/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
В	6/12/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
С	6/12/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
D	6/12/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
E	6/12/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
F	6/13/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
G	6/13/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
H	6/13/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
DUP E	6/12/97	6/18/97	Soil	Post-Excavation	TPHC	OQA-QAM-025

Note:

<sup>\*</sup> TPHC Total Petroleum Hydrocarbons

TABLE 2 POST-EXCAVATION SOIL SAMPLING RESULTS BUILDING 2506, CHARLES WOOD AREA FORT MONMOUTH, NEW JERSEY

Page 1 of 1

Sample ID/ Depth	Sample Laboratory ID	Sample Date	Analysis Date	Analytical Method Used	Sample Quantitation Limit (mg/kg)	Compound of Concern	Results (mg/kg) *	NJDEP Soil Cleanup Criteria ** (mg/kg)	Exceeds Cleanup Criteria
A/6.0'	2692.01	6/12/97	6/18/97	Total Solid			82.29 %		
				TPHC	169	yes	ND	10,000	No
B/6.0°	2692.02	6/12/97	6/18/97	Total Solid			81.10 %		
				TPHC	176	yes	ND	10,000	No
C/6.0'	2692.03	6/12/97	6/18/97	Total Solid			87.16 %		
				TPHC	174	yes	ND	10,000	No
D/5.5'	2692.04	6/12/97	6/18/97	Total Solid			86.12 %		
				TPHC	176	yes	ND	10,000	No
E/5.5'	2692.05	6/12/97	6/18/97	Total Solid			89.04 %		
				TPHC	170	yes	ND	10,000	No
F/1.0'	2692.06	6/13/97	6/18/97	Total Solid			90.89 %		
			•	TPHC	163	yes	ND	10,000	No
G/1.0'	2692.07	6/13/97	6/18/97	Total Solid			91.15 %		
				TPHC	171	yes	ND	10,000	No
H/1.0'	2692.08	6/13/97	6/18/97	Total Solid			89.73 %		
				TPHC	172	yes	ND	10,000	No
DUP E/ 5.5'	2692.09	6/12/97	6/18/97	Total Solid			87.42 %		
				TPHC	175	yes	ND	10,000	No

#### Note:

Total solid results are expressed as a percentage.


NJDEP Residential Direct Contact soil cleanup criteria for total organics

Not Detected above stated sample quantitation limit \*\*

ND

-- Not applicable
TPHC Total Petroleum Hydrocarbons

**FIGURES** 





#### LONG BRANCH, NJ

**40073-C8-TF-024** 1954

PHOTOREVISED 1981 DMA 6164 I SE -SERIES V822



Quadrangle Location

Mapped, edited and published by the Geological Survey

#### FIGURE 1

#### SITE LOCATION MAP

Building 2506

Charles Wood Area
Fort Monmouth Army Base
Monmouth County, NJ



#### **SMC Environmental Services Group**


Engineers, Managers, Scientists, & Planners Valley Forge, Pennsylvania

Scale:

1''=2,000'

Date:

**DEC 1997** 






FIGURE 3
CROSS SECTIONAL VIEW
BUILDING 2506
FORT MONMOUTH ARMY BASE
MONMOUTH COUNTY, NJ



SMC ENVIRONMENTAL SERVICES GROUP

Engineers, Managers, Scientists & Planners VALLEY FORGE, PA.

SCALE: NTS

DATE: OCT. 1997

f + 1

مساحا

1 | 13

24

 $F^{-\pm 1}$ 

4-11


A. har

1.18

*(1*1)

1 14

FIT



#### **APPENDIX A**

NJDEP-STANDARD REPORTING FORM



 $\mathcal{R}^{(j)}(x,\cdot)$ 

# Divisio... of Responsible Party Site Remediation CN 028 Trenton. NJ 08625-0029 Departmen

ATTN: UST Program

Date Rec'd.	<u> </u>
Auth.	
Routing	
UST NO.	

(60	19) 984-3156		
	<del></del>		
•	, NDARD REPORTIN	G FORM	
	onling activities at an		
General Facility Information  Closure (Abandonment of Temporary Closure  Change in Service	on Changes	Sale or Transfer Substantial Modification Financial Responsibility Address Change Only	清
Check ONLY One Ty	pe of Activity - Comp	lete Form For That Activity	
(More tha	n one tank can be lis	ted per activity)	
tacilities must submit a	NEW tank Installati Registration Ques	ions at existing registered tionnaire for the new tanks.	
Unswer questions 1 through 5 and others as ap-	olicable.		
. Company name and address (as it	U.S. ARN	Y - FORT MONMOUTH	
appears on registration questionnaire):	DPUI -	3ULDING 173	
•	EDOT M	DNUDUTH NIT OTTO	3
	1000	EUGENE IN LESINSI	<del>51</del>
· · · · · · · · · · · · · · · · · · ·	ATTN:	EUGENE IN LESINS	$\preceq$
Facility name and location			
(if different from above):	<del></del>		
•			
	<del></del>		
. Contact person for this activity:	GENE	LESINSKI	
. Contact person for this activity.			
	Telephone Numi	Ser. (908) 532-0989	
. The identification number of the affected tar	k as it appears in Or	uestion Number 12 on the Registration Que:	stion
BING 2506	17		
10200 2300	)(°س د:	```\	
. Registration Number (If known):	ਂ ust - <u>੯ ਂ ਂ</u>	3/5/5	
Excellent Each IIV BIEDDIA (2004)			
For GENERAL FACILITY INFORMATION char	ges (accress, telepho	ne. Corazo person, etc. – supply NETY RECITE	חכננו
a. Facility name:		· \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	
a. Facility name:			
c. Owner's mailing address:			
<del></del>			
			· :
d. Block: Lot:	<del></del>		
e. Contact person (facility operator):	<del></del>	•	
Contact telephone number: (	1		
g. Other (Specify):			
(about)!-			
	(OVER)	·	4:5

Abanc Abanc				. /2 ~~~ ~		o imenta	Social	tor .	
	necessary in ment per NJJ			i (a copie:	s) and all or	oumentad	певаеа	ior	- 1
b. Ø Remo	val Date:	6 1 1	2797	7 . Ca	se No.				:7
<b>,</b> −	necessary in			-	_			•	
•	•	•		•	•				
8. For CHANGE								. II bassaria	
a. 🗆 Tempo substance	es; leave tank		estarum (m	ne — <del>sa</del> e i	NJ.A.G. 711	46-9.1(0))	. Membye i	III nazarogus	
b. 🗆 Chang	je in service fi	rom a regula	Ited substar	nce to a n	on-regulate	d substan	ce. Tank m.	ist be cleaned	
and site a	ssessment pe	rdormed per	NJAC.7	:148-9.1(	e). ·				
c. 🗆 Chang	es in service	trom one reg	juiated haz	ardous su	ot scanstadi	another re	gulated ha	zardous substa	nce
	No					New		<u> </u>	
	No								
Tank	No					New	<del></del>		<del></del>
		. •	SCOUDING!	eve erz z ı	nore space	IS negueo	7		
9. For TRANSFI					:/				
8. New Own	er (operator)	<del></del>							
b. New Facil	ny Name	<del></del>	<del></del>	<del></del>					
		<del></del>					<del>u</del>	·	
			· · · · · · · · · · · · · · · · · · ·		•	*			
			C	ounty			-		
•							_	•	
c. Closing At The For SUBSTAN monitoring system.  Type of Minds NOTE:	NTIAL MODIF stems, cathod odification Substantial m	ic protection  odifications	(to include 1, etc.):	any retro	er NJA.C.	7:148-10.	e addition  Date:	·	
19. For SUBSTAN monitoring sys a. Type of M	NTIAL MODIFICATION CONTINUES TO SUBSTANTIAL IN FINANCIAL B. Policy b. Policy	ic protection odifications RESPONS Type:	(to include t, etc.): fequire a p	any ratro ermat und (check ap d. Co	er NJA.C.	7:148-10. hanges an	e addition  Date:	·	
17. For SUBSTAN monitoring sys a. Type of Mi b. "NOTE"	NTIAL MODIF stems, cathod odification Substantial m in FINANCIAL 8. Policy	ic protection odifications RESPONS Type:	(to include t, etc.): fequire a p	any ratro ermat und (check ap d. Co	er N.J.A.C. propriate c	7:148-10. hanges an	e addition  Date:	·	
17. For SUBSTAN monitoring sys a. Type of Mi b. "NOTE"	NTIAL MODIFICATION CONTINUES TO SUBSTANTIAL IN FINANCIAL B. Policy b. Policy	ic protection odifications RESPONS Type:	(to include t, etc.): fequire a p	any ratro ermat und (check ap d. Co	er N.J.A.C. propriate c	7:148-10. hanges an	e addition  Date:	·	
17. For SUBSTAN monitoring sys a. Type of Mi b. "NOTE"	NTIAL MODIFICATION CONTINUES TO SUBSTANTIAL IN FINANCIAL B. Policy b. Policy	ic protection  odifications RESPONS Type:   Number:	(to include i, etc.): require a p IBILITY to (	any ratro ermat und (check ap d. Co	er N.J.A.C. propriate c	7:148-10. hanges an	e addition  Date:	·	
17. For SUBSTAN monitoring sys a. Type of Mi b. "NOTE"	NTIAL MODIFICATION CONTINUES TO SUBSTANTIAL IN FINANCIAL B. Policy b. Policy	ic protection  odifications RESPONS Type:   Number:	(to include t, etc.): fequire a p	any ratro ermat und (check ap d. Co	er N.J.A.C. propriate c	7:148-10. hanges an	e addition  Date:	·	
19. For SUBSTAN monitoring sy:  a. Type of Mi b. "NOTE":  11. For changes i	NTIAL MODIFICATION CONTINUES AND POLICY D. POLICY C. Carar.	ic protection odifications RESPONS Type: [] Number: [] (S	(to include it, etc.):  require a p  (BILITY to (	any retro ermat und (check ap d. Cc e. Es	er N.J.A.C. propriate company/Ca piration Da	y - e.g. the 7:148-10. Hanges and mier:	Date:	pies of new into	
19. For SUBSTAN monitoring sy:  a. Type of Mi b. "NOTE":  11. For changes i	NTIAL MODIFICATION CONTINUES CONTINU	ic protection odifications RESPONS Type: [] Number: [] (S	(to include it, etc.):  require a p  (BILITY to (	any retro ermat und (check ap d. Cc e. Es	er N.J.A.C. propriate company/Ca piration Da	y - e.g. the 7:148-10. Hanges and mier:	Date:	pies of new into	
nonitoring system.  Type of Minds.  NOTE:  T1. For changes it	NTIAL MODIFICATION CONTINUES CONTINU	ic protection odifications RESPONS Type:  Number:  (S applicable   leral agenci	(to include i, etc.): require a p (BILITY to (  permits, lice es must be	any ratro emit und (check ap d. Cx e. Ex	er N.J.A.C. propriate company/Ca piration Da d certificate separately	7:148-10. hanges and rier:  te:  te:  te:  te:  trom this i	Date: dattach co	pies of new into	in tr
19. For SUBSTAN monitoring sy:  a. Type of Mi b. NOTE:  11. For changes it  NOTE: ALL applical, st	NTIAL MODIF stems, cathod odification Substantial m in FINANCIAL a. Policy b. Policy c. Other: cropriate and rate and/or fec	ic protection  odifications RESPONS Type:  Number:  (S  applicable   leral agenci	(to include i, etc.): require a p (BILITY to (  permits, lice es must be	any ratro emit und (check ap d. Cx e. Ex	er N.J.A.C. propriate company/Ca piration Da d certificate separately	7:148-10. hanges and rier:  te:  te:  te:  te:  trom this i	Date: dattach co	pies of new into	· · · · · · · · · · · · · · · · · · ·
NOTE: ALL applical, st	NTIAL MODIFICATION CARRIES TO SUBSTANTIAL IN SUBSTANTIAL IN FORCY  B. Policy B. Policy C. Other:  Corporate and are and/or fection form shall 17.148-2.3 (a)	ic protection  odifications  RESPONS Type:   Number:   (S  applicable   feral agenci	(to include it, etc.):  require a positive to ( pecify)  permits, lice es must be  ( y the higher	ermit und check ap d. Ct e. Es enses an obtained	er N.J.A.C. propriate of principle of certificate separately carriers and carriers are carriers are carriers and carriers are carriers and carriers are carriers are carriers and carriers are carriers are carriers and carriers are carriers and carriers are carriers and carriers are carriers and carriers are carriers are carriers and carriers are carriers are carriers and carriers are carriers and carriers are carri	7:148-10. hanges and mer:  te:  te:  te:  te:  te:  te:  te:  te	Date:  d strach co  i by the at  notification.	pies of new into	s) to
NOTE: ALL applical, st	NTIAL MODIFICATION CARRIES TO SUBSTANTIAL IN CONTROL OF PORCY  D. PORCY  D. PORCY  C. Char.  Corporate and are and/or fed and/or fed and/or fed analy of law sensity of law	ic protection  odifications  RESPONS Type:   Number:   (S  applicable   feral agenci  be signed by  1).***	(to include it, etc.):  require a positive to ( pecify)  permits, lice es must be ( y the highermation pro-	ermit und check ap d. Ct e. Es enses an obtained covided in	er N.J.A.C. propriate of propriation Date of Certificate Separately CATION of Individuations documents of the communication of the comm	7:148-10. hanges and mer:   ss requires from this in the fact the	Date:  d stach co  i by the at  notification.	pies of new introversell responsitions complete.	i) to
NOTE: ALL applical, st	NTIAL MODIFICATION CONTINUES A POLICY  b. Policy  c. Other:  cropriate and ate analyor fectors analyor fectors are analyon fectors are analyon fectors are analysis and analysis and analysis are analysis and analysis are analysis and analysis and analysis are analysis and analysis are analysis and analysis and analysis are analysis and analysis and analysis and analysis are analysis and analysis analysis and analysis analysis and analysis analysis and analysis analysis and analysis analysis and analysis analysis analysis analysis and analysis anal	ic protection  odifications  RESPONS Type:   Number:   (S  applicable   feral agenci  be signed by  1).***	(to include it, etc.):  require a positive to ( pecify)  permits, lice es must be ( y the highermation pro-	ermit und check ap d. Ct e. Es enses an obtained covided in	er N.J.A.C. propriate of propriation Date of Certificate Separately CATION of Individuations documents of the communication of the comm	7:148-10. hanges and mer:   ss requires from this in the fact the	Date:  d stach co  i by the at  notification.	pies of new introversell responsitions complete.	i) to
NOTE: ALL application facility (N.J.A.C. 7) fines and/or impri	NTIAL MODIFICATION CONTINUES A POLICY  b. Policy  c. Other:  cropriate and ate analyor fectors analyor fectors are analyon fectors are analyon fectors are analysis and analysis and analysis are analysis and analysis are analysis and analysis and analysis are analysis and analysis are analysis and analysis and analysis are analysis and analysis and analysis and analysis are analysis and analysis analysis and analysis analysis and analysis analysis and analysis analysis and analysis analysis and analysis analysis analysis analysis and analysis anal	ic protection  odifications  RESPONS Type:   Number:   (S  applicable   feral agenci  be signed by  1).***	(to include it, etc.):  require a positive to ( pecify)  permits, lice es must be ( y the highermation pro-	ermit und check ap d. Ct e. Es enses an obtained covided in	er N.J.A.C. propriate of propriation Date of Certificate Separately CATION of Individuations documents of the communication of the comm	7:148-10. hanges and mer:   ss requires from this in the fact the	Date:  d stach co  i by the at  notification.	pies of new introversell responsitions complete.	in the second se
NOTE: ALL application of the state of the st	NTIAL MODIFICATION CONTINUES CONTINU	ic protection  odifications  RESPONS Type:   Number:   (S  applicable    leral agenci  that the info	(to include it, etc.):  require a principle include it provide it	ermit und check ap d. Ct e. Es enses an obtained covided in	er N.J.A.C. propriate of propriation Date of Certificate Separately CATION of Individuations documents of the communication of the comm	7:148-10. hanges and mer:   ss requires from this in the fact the	Date:  d stach co  i by the at  notification.	pies of new introversell responsitions complete.	i) to
NOTE: ALL application facility (N.J.A.C. 7) fines and/or impri	NTIAL MODIFICATION CONTINUES CONTINU	ic protection  odifications  RESPONS Type:   Number:   (S  applicable    leral agenci  be signed by  that the info	(to include it, etc.):  require a position position production pro	any ratro ermit und (check ap d. Cc e. Es enses an obtained est rankin ovided in	er N.J.A.C. propriate company/Ca piration Da discertificate separately cation g individua this docum thing false,	7:148-10. hanges and mier:   te:   strength this is the factor of the fa	Date:  d stach co  i by the at  notification.	pies of new introversell responsitions complete.	i) to
NOTE: ALL application of the state of the st	NTIAL MODIFICATION CONTINUES CONTINU	ic protection  odifications  RESPONS Type:   Number:   (S  applicable    leral agenci  that the info	(to include it, etc.):  require a position position production pro	any ratro ermit und (check ap d. Cc e. Es enses an obtained est rankin ovided in	er N.J.A.C. propriate of propriation Date of Certificate Separately CATION of Individuations documents of the communication of the comm	7:148-10. hanges and mier:   te:   strength this is the factor of the fa	Date:  d stach co  i by the at  notification.	pies of new introversell responsitions complete.	office of the state of the stat

#### APPENDIX B

SITE ASSESSMENT SUMMARY

UST-01	4
2/91	

FOR STATE USE ONLY
UST#
Date Rec'd
TMS#
Staff

## STATE OF NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION

Division of Responsible Party Site Remediation CN 029 TRENTON, N.J. 08625-0028

Scott A. Weiner Commisioner

TRENTON, N.J. 08625-0028 Tel. # 609-984-3156 Fax.# 609-292-5604

Karl J. Delaney Director

## UNDERGROUND STORAGE TANK SITE ASSESSMENT SUMMARY

Under the provisions of the Underground Storage of Hazardous Substances Act in accordance with N.J.A.C. 7:14B

This Summary form shall be used by all owners and operators of Underground Storage Tank Systems (USTS) who have either reported a release and are subject to the site assessment requirements of N.J.A.C. 7:14B-8.2 or who have closed USTS pursuant to N.J.A.C. 7:14B-9.1 et seq. and are subject to the site assessment requirements of N.J.A.C. 7:14B-9.2 and 9.3.

#### **INSTRUCTIONS:**

- ♦ Please print legibly or type.
- Fill in all applicable blanks. This form will require various <u>attachments</u> in order to complete the Summary. The technical guidance document, <u>Interim Closure Requirements for UST's</u>, explains the regulatory (and technical) requirements for closure and the <u>Scope of Work. Investigation and Corrective Action Requirements for Discharges from Underground Storage Tanks and Piping Systems</u> explains the regulatory (and technical) requirements for corrective action.
- Return one original of the form and all required attachments to the above address.
- Attach a scaled site diagram of the subject facility which shows the information specified in Item IV B of this
  form.
- ◆ Explain any "No" or "N/A" response on a separate sheet.

	Date of Submission:
Building No. 2506 UST No. 81515-17	0192477-1
1. FACILITY NAME AND ADDRESS:	Facility Registration #
U.S. Army Fort Monmouth New Jersey	
Directorate of Engineering and Housing Building 167	
Fort Monmouth New Jersey 07703 County Monr	nouth
Telephone No. 908-532-6224	
OWNER'S NAME AND ADDRESS, if different from above.	
Telephone No.	

II.	DISCHARGE REPORTING REQUIREMENTS
	A. Was contamination found?YesX No If Yes, Case No(Note: All discharges must be reported to the Environmental Action Hotline (609) 292-7172)
	B. The substance(s) discharged was (were)N/A
	C. Have any vapor hazards been mitigated?YesNoX N/A
III.	DECOMMISSIONING OF TANK SYSTEMS Closure approval No. NJDEP "Blanket Closure"
	The site assessment requirements associated with <u>tank decommissioning</u> are explained in the Technica Guidance Document, Interim Closure Requirements for UST's, Section V. AD. <u>Attach</u> complete documentation of the methods used and the results obtained for each of the steps of <u>tank decommissioning</u> used. Please include a <u>site</u> map which shows the locations of all samples and borings, the location of all tanks and piping runs at the facility at the beginning of the tank closure operation and annotated to differentiate the status <u>of all tanks and piping</u> (e.g., removed, abandoned, temporarily closed, etc.). The same site map can be used to document other parts of the site assessment requirements, if it is properly and legibly annotated.
IV.	SITE ASSESSMENT REQUIREMENTS
	A. Excavated Soil
	Any evidence of contamination in excavated soil will require that the soil be classified as either Hazardous Waste or Non-Hazardous Waste. Please include all required documentation of compliance with the requirements for handling contaminated excavated soil (if any was present) as explained in the technica guidance documents for closure and corrective action. Describe amount of soil removed, its classification and disposal location.
	B. Scaled Site Diagrams
	1. Scaled site diagrams must be attached which include the following information:
	<ul> <li>a. North arrow and scale</li> <li>b. The locations of the ground water monitoring wells</li> <li>c. Location and depth of each soil sample and boring</li> <li>d. All major surface and subsurface structures and utilities</li> <li>e. Approximate property boundaries</li> <li>f. All existing or closed underground storage tank systems, including appurtenant piping</li> <li>g. A cross-sectional view indicating depth of tank, stratigraphy and location of water table</li> <li>h. Locations of surface water bodies</li> </ul>
	C. Soil samples and borings (check appropriate answer)
	1. Were soil samples taken from the excavation as prescribed? X_Yes No N/A
	2. Were soil borings taken at the tank system closure site as prescribed?Yes NoX_ N/A
	3. Attach the analytical results in tabular form and include the following information about each sample
	<ul> <li>a. Customer sample number (keyed to the site map)</li> <li>b. The depth of the soil sample</li> <li>c. Soil boring logs</li> <li>d. Method detection limit of the method used</li> <li>e. QA/QC Information as required</li> </ul>

D. Ground Water Monitoring	
Number of ground water monitoring wells installed	
<ol><li>Attach the analytical results of the ground water samples in tabular form. Include the following inf sample from each well:</li></ol>	formation for each
<ul> <li>a. Site diagram number for each well installed</li> <li>b. Depth of ground water surface</li> <li>c. Depth of screened interval</li> <li>d. Method detection limit of the method used</li> <li>e. Well logs</li> <li>f. Well permit numbers</li> <li>g. QA/QC Information as required</li> </ul>	
V. SOIL CONTAMINATION	
A. Was soil contamination found?YesX No If "Yes", please answer Question B-E If "No", please answer Question B	
B. The highest soil contamination still remaining in the ground has been determined  1. N/A ppb total BTEX, N/A ppb total non-targe  2. N/A ppb total B/N, N/A ppb total non-targe  3. ND ppm TPHC  4. N/A ppb N/A (for non-petroleum substance)	eted VOC
C. Remediation of free product contaminated soils  1. All free product contaminated soil on the property boundaries and above the water table to have been removed from the subsurface Yes No  2. Free product contaminated soils are suspected to exist below the water table  3. Free product contaminated soils are suspected to exist off the property boundaries	Yes No
D. Was the vertical and horizontal extent of contamination determined?Yes	No N/A
E. Does soil contamination intersect ground water?YesNoN	N/A
VI. GROUND WATER CONTAMINATION	
A. Was ground water contamination found?YesXNo If "Yes", please answer Questions B-G. If "No", please answer only Question B.	
B. The highest ground water contamination at any 1 sampling location and at any 1 sampling been determined to be: N/A	event to date has
1ppb total BTEXppb total non-targeted VOC 2ppb total B/Nppb total non-targeted B/N 3ppb total MTBEppb total TBA 4ppb(for non-petroleum substance)	ce)
4ppb	<del></del>

( ) [ 5

C.	Resu	ults (s) of well search
		A well search (including a review of manual well records) indicates that private, municipal or commercial rells do exist within the distances specified in the Scope of WorkYesNo N/A
	2. 1	The number of these wells identified is
D.	Pro	ximity of wells and contaminant plume
		The shallowest depth of any well noted in the well search which may be in the horizontal or vertical potential path(s) of the contaminant plume(s) is feet below grade (consideration has been given for the effects of pumping, subsurface structures, etc. on the direction(s) of contaminant migration). This well is feet from the source and its screening begins at a depth of feet.
	2.	The shallowest depth to the top of the well screen for any well in the potential path of the plume(s) (as described in D1 above above) is feet below grade. This well is located feet from the source.
	3.	The closest horizontal distance of a private, commerical, or municipal well in the potential path of the plume (as determined in D1) is feet from the source. This well is feet deep and screening begins at a depth of feet.
E.	Α	plan for separate phase product recovery has been includedYes No N/A
F.		ground water contour map has been submitted which includes the ground water elevations for each wellYesNo N/A
G.	De	elineation of contamination
	1.	The ground water contaminants have been delineated to MCLs or lower values at the property boundaries. Yes No
		The plume is suspected to continue off the properly at concentrations greater than MCLs.  YesNo
	3.	Off property access (circle one): is being sought has been approved has been denied
VII.		<u>SITE ASSESSMENT CERTIFICATION</u> [preparer of site assessment plan - N.J.A.C. 7:14B-8.3(b) &9.5(a)3]
		The person signing this certification as the "Qualified Ground Water Consultant" (as defined in N.J.A.C.7:14B-1.6) responsible for the design and implementation of the site assessment plan as specified in N.J.A.C. 7:14B-8.3(a) & 9.2(b)2, must supply the name of the certifying organization and certification number.
		"I certify under penalty of law that the information provided in this document is true, accurate, and complete and was obtained by procedures in compliance with N.J.A.C. 7:14B-8 and 9. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment."
		NAME (Print or Type)
		CERTIFYING ORGANIZATION NUMBER 0014537

VIII. TANK DECOMMISSIONING CERTIFICATION [person performing tank decommissioning portion of closure plan - N.J.A.C. 7:14B-9.5(a)41 "I certify under penalty of law that tank decommissioning activities were performed in compliance with N.J.A.C. 7:14B-9.2(b)3. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment." NAME (Print or Type) SAME AS SITE ASSESSMENT SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_ COMPANY NAME (Peformer of Tank Decommissioning) IX. CERTIFICATIONS BY THE RESPONSIBLE PARTY(IES) OF THE FACILITIES A. The following certification shall be signed by the highest ranking individual with overall responsibility for that facility [N.J.A.C. 7:14B-2.3(c)11]. "I certify under penalty of law that the information provided in this document is true, accurate, and complete. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment." NAME (Print or Type) \_\_\_\_\_\_ SIGNATURE \_\_\_\_\_ COMPANY NAME U.S. Army Fort Monmouth The following certification shall be signed as follows [according to the requirements of N.J.A.C. 7:14B-2.3(C)2I]: B. 1. For a corporation, by a principal executive officer of at least the level of vice president. 2. For a partnership or sole proprietorship, by a general partner or the proprietor, respectively; or For a municipality, State, Federal or other public agency by either the principal executive officer or ranking 3. elected official. In cases where the highest ranking corporate partnership, governmental officer or official at the facility as 4. required in A above is the same person as the official required to certify in B, only the certification in A need to be made. In all other cases, the certifications of A and B shall be made. "I certify under penalty of law that I have personally examined and am familiar with the information submitted in this application and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment." NAME (Print or Type) \_\_\_\_\_SIGNATURE \_\_\_\_\_ COMPANY NAME DATE \_\_\_\_\_

# J ARMY, SELFM-PW-F DAILY UST SUBSURFACE REMOVAL LOG

	BLDG.#: 2506 REG.#: 008/5/5 - 17 CLOSURE#: NA	
414	. DATE: 6-12-97 TOA: */3/5 TOD: 1500	
A LAN	GOV. SSE: Lesinski - NJDEP CERT. #: 0074537	
أفراعة	REMOVAL CONTRACTOR: SAL Inc. // SCHOOL CLOSURE SUPERVISOR:   SAL Inc. // NJDEP CERT.#:	
// 17 b. ia	WEATHER: PARTLY CLOUDY - 85°T	
/ <sup>1</sup>	ACTIVITY	YES/
ii lah	THE SUPERVISOR (CLOSURE CERT.) WAS ON-SITE DURING ALL CLOSURE RELATED ACTIVITIES	Y
6)   Ny	THE SSE WAS ON-SITE DURING UST REMOVAL AND SITE SCREENING AND SAMPLING ACTIVITIES	Y
إرايا	ALL ON-SITE PERSONNEL HAD TRAINING IAW ALL SAFETY REQUIREMENTS (E.G. 29CFR)	Y
	A CONFINED ENTRY PERMIT WAS COMPLETED AND POSTED ON-SITE BY THE CONTRACTOR	WA
	THE UST WAS PLACED ONTO PLASTIC, SCRAPED OFF, INSPECTED FOR HOLES AND PHOTOGRAPHED	7
7 1	A DISCHARGE WAS REPORTED TO THE NJDEP (609-292-7172), CASE#	N
\li	PHOTOS HAVE UST#, BLDG. #, DATE, TIME, NAME OF SSE AND DESCR. WRITTEN ON BACK	Y
[]1	GROUNDWATER WAS ENCOUNTERED AT FEET BG, A SHEEN (WAS/WAS NOT) OBSERVED ON GW	N
[. ].i	IF OVA/Hnu WAS USED: WAS IT CAL. AND FOUND TO BE OPERATIONAL (cal. data on COC)	Y
("[\]	IF SAMPLES WERE TAKEN: COC, SCALED SITE MAP (VERT. SOIL HORIZONS AND PLOT PLAN)	Y
Llv	ALL SAMPLE COLLECTION ACTIVITIES WERE AS DESCRIBED IN THE NJDEP FSPM, 1992	Y
[1]1.	ALL SAMPLING WAS BIASED TOWARD HIGHEST OVA/FID RECORDED SITES IAW 7:26E-3.6 et seg.	
4.1.2	ALL PETROL. CONT. SOILS WERE SECURED FROM THE WEATHER BY CLOSE OF BUSINESS TODAY	NIA
[1]	THE SSE AUTHORIZED BACKFILLING THE EXCAVATION (STONE TO 1" ABOVE GROUNDWATER)	Y
نيا يا	ADDITIONAL NOTES WERE TAKEN AND ARE RECORDED ON THE BACK OF THIS FORM	$\mathcal{N}$
U.D.	THE FOLLOWING DOCUMENTS WERE ADDED TO THE PROJECT FOLDER TODAY: (CIRCLE EACH)	
('[5	SCRAP TICKET, CSE PERMIT, ACCIDENT REPORT, HAZ. WASTE MANIFEST, DAILY UST CLOSURE LOG, SCALED SITE MAP (SAMPLING), SRF, CLOSURE, CHAIN OF CUSTODY, SOIL ANALYTICAL RESULTS, CLEAN FILL TICKETS (IN YDS <sup>3</sup> ), PHOTOGRAPHS (UST, EXCAVATION, SAMPLING POINTS)	>
I	certify under penalty of law that tank decommissioning activities	
	erformed in compliance with N.J.A.C. 7:14B-9.2(b)3 and 7:26 et seq I	
th	nat there are significant penalties for submitting false, inaccura	ate, or
in	acomplete information, including fines and/or imprisonment.	
sı	IGNATURE: DATE: 6-12-97	
<sub>/ˈiː</sub> ca\	\ms\ust\removal\sitessls.doc	
[],(	_	

**APPENDIX C** 

**WASTE MANIFEST** 

Month Day Year

	en e				1				2506	
		BD 1 B/	PETROLEUM DX 5A - OLD	SERVICES	108857					
	NON-HAZARDOUS WASTE MANIFEST	1. Generator's US W5.2 · 2 · 1 · (	EPA ID No.		Manifest Document No.	2. Page of	1	NHZ	0048	56
<b>A</b>	3. Generator's Name and Mailing Address U.S. ARMY Communications Experience Charles wood A AHN: SELFM - PW - EV 4. Generator's Phone (905) 532 - C	ort monk	ies G Poseph Pouth,	FAILO. N.J.	ind ~, Bldg.17. 07703	3				
	5. Transporter 1 Company Name LIONETTI OIL RECOVERY CO	INC	ЙÌр	<del></del>	0 4 4 0 6	4	sporter's Ph 908 7	21-0	900	
	Transporter 2 Company Name     Designated Facility Name and Site Address		8.  10.		<u></u>		sporter's P			
9. Designated Facility Name and Site Address LIONETTI OIL RECOVERY CO INC DBA LORCO PETROLEUM SVCS RUNYON&CHEESEQUAKE RDS OLD BRIDGE, NJ 08857 IN J D 0 8 4 0 4 4 0 6 4 908 721-0							0			
	11. Waste Shipping Name and Description					<b></b>	12. Cont	ainers Type	13. Total Quantity	14. Unit Wt/Vol
	PETROLEUM OIL (PETROLEUM ( COMBUSTIBLEL LIQUID UN12)						0.0.	1 .T	TXX:535	G
GEZER	b.									
R A T O R	c.			, , , , , , , , , , , , , , , , , , ,						
Ì	d.					<del></del>				
	D. Additional Descriptions for Materials Listed Abo	ove				E. Har	ndling Code	s for Wa	stes Listed Above	<u> </u>
	T,L PETROLEUM OIL 99% WATER / %					T	04 FIL	TRAT	ION	
	15. Special Handling Instructions and Additional In 24 HR EMERGENCY RESPONSE DECAL#73432 ERG#128 DEXS MANIFEST USED FOR TRACKI	<b>#(908) 721-</b>	-0900 FRESUL SONLY	۷), ۱ TS <u>.</u>	_					
					7/	+-/	P			
	16. GENERATOR'S CERTIFICATION: I certify the	S/NS/		gnature	mentifiect to telleral per	gulations for	reporting pro	oper disp	osal of Hazardous Wi Month Day	
	17. Transporter 1 Acknowledgement of Receipt	f Materials	Si	ignature	A. O		9		Month Day	y Year
	18. Transporter 2 Acknowledgement of Receipt of Printed/Typed Name	f Materials	of S	ignature		P		A	Month Da	y 799
	Printed/Typed Name  EVGENE W LESTA  19. Discrepancy Indication Space	JSKT OU		<del>Jed</del>	ma/	Plan	will	1	0.6 2	5 17 Grus
	F			U					•	w

20. Facility Owner or Operator: Certification of receipt of waste materials covered by this manifest except as noted in Item 19.

**ORIGINAL - RETURN TO GENERATOR** 

**APPENDIX D** 

**UST DISPOSAL CERTIFICATE** 

## MAZZA & SONS, INC.

Metal Recyclers 3230 Shafto Rd. Tinton Falls, NJ (908) 922-9292 NO. 2591

DATE. 7 5/2/97

Customer's Name	TECour - Vinetic	Sidner
Weight Price Cast Iron	23620	Weight Price
Steel /40.02 Ll. Iron	4000	Brass Alum Clean
Copper #2	n 42n-B	Lead Stainless
	B. 2506	Battery
		TOTAL AMOUNT:

### **APPENDIX E**

**SOIL ANALYTICAL DATA PACKAGE** 

# US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY NJDEPE # 13461

#### **REPORT OF ANALYSIS**

Client:

U.S. Army

DPW, SELFM-PW-EV

Bldg. 173

Ft. Monmouth, NJ 07703

Project:

Total Petroleum Hydrocarbons

96-1262

B.2506

Project #

2692

Date Rec.

06/13/97

Date Compl. 06/18/97

Released by:

Daniel K. Wright Laboratory Director

## **Table of Contents**

Section	<u>Pages</u>
Cover Sheet	1
Table of Contents	2
Method Summary	3
Conformance/Non-Conformance	4
Chain of Custody	5
Results Summary	6
Initial Calibration Summary	7
Continuing Calibration Summary	8
Surrogate Results Summary	9
MS/MSD Results Summary	10
Quality Control Spike Summary	11
Raw Sample Data	12-29
Laboratory Deliverable Checklist	30

### **Method Summary**

#### NJDEP Method OOA-OAM-025-10/97

#### Gas Chromatographic Determination of Total Petroleum Hydrocarbons in Soil

Fifteen grams (15g)(wet weight) of a soil sample is added to a 125 mL acid cleaned, solvent rinsed, capped Erlenmeyer flask. 15g anhydrous sodium sulfate is added to dry sample. Surrogate standard spiking solution is then added to the flask.

Twenty five milliliters(25mL) Methylene Chloride is added to the flask and it is secured on a gyrotory shaker table. The agitation rate is set to 400rpm and the sample is shaken for 30 minutes. The flask is the removed from the table and the particulate matter is allowed to settle. The extract is transferred to a Teflon capped vial. A second 25mL of Methylene Chloride is added to the flask and shaken for an additional 30 minutes. The flask is again removed and allowed to settle. The extracts are combined in the vial then transferred to a 1mL autosampler vial.

The extract is then injected directly into a GC-FID for analysis. The sample is analyzed for petroleum hydrocarbons covering a range of C8-C42 including pristane and phytane. Total Petroleum Hydrocarbon concentration is determined by integrating between 5 minutes and 22 minutes. The baseline is established by starting the integration after the end of the solvent peak and stopping after the last peak.

The final concentration of Total Petroleum Hydrocarbons is calculated using percent solid, sample weight and concentration.



# Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703
Tel (908)532-4359 Fax (908)532-3484 EMail:appleby@doim6.monmouth.army.mil
NJDEP Certification #13461

**Chain of Custody Record** 

Customer: GEL	JE LESINSKI-DPW	Project N	0. 96-12	62				Ana	lysis	Paran	eters			Comments:
Phone #: 20984	ĵ	t	-				ಇ	J						#=SAMPLES KEPT BELOW 4°C.
()DERA (O)OMA		B. 2506				77	$\mathcal{G}$				0	Berow 4°c.		
Samplers Name / Con	mpany : GARY D'MA	RTINIS-	TUS	Sample	#		2 Salles	Masser					OVA	
Lab Sample I.D.	Sample Location	Date	Time	Туре	bottle		7	1					0	Remarks / Preservation Method
2692.01	2506-A	6-12-9	1 1449	SOIL		$\boxtimes$	$\boxtimes$	$\boxtimes$					ND	CENTER LINE 66.0' *
.02	2506-B		1451										ND	
-03	2506-C		1453										ND	V
.04	2506-0		1444										NO	SIDEWALL @ S.S'
.05	2506-E	V	1457										ND	
اط0.	2506-F	6-13-9	7 0902										ND	Piping Run @1.0'
-07	2506-G		0905										ND	
.08	2506-H	<b>V</b>	0909										NI	↓
· .09	2506-DUP(E)			V	$\lor$		V	$\downarrow$					-	FIELD DUPLICATE V
			, [											
NOTE: OUA (#	AS1903 CALIBRAT	ED 4/	FSppm C	Hy +	ZE	Ro (c	PA	RE	7/4	304	Rs.	مان	5-12	-97 by G. DIMARTIN
OUA C	ALIBRATION CHECKE	v Q C	1830 HRS	ON	6-1	3-9	7.							,
11	1.1	_ ^ _												
Relinguished by (signatur	Date/Time:	Received by	(signature):		Relin	quished	by (sig	nature):		Date/	Time:	Receiv	ed by (	signature):
SulfyVIV	16139 1119	V	D+-											
Relinquished by (signature): Date/Time: F		Received by	Received by (signature):		Relin	quished	by (sig	nature):		Date/	Time:	Receiv	ed by (	signature):
						<del></del>				<u>L.</u>		<u> </u>		
Report Type: ()Full, M	Reduced, ()Standard, ()Screen	/ non-certifi	ed			Rema	rks:	ATT	מ מ	Ams	M	, 70	かし	s USED.
Turnaround time: Stand	lard 4 wks, () Rush Days,	()ASAP V	erbalHrs.					-// (	, ,,	1				

#### Response Factor Report Fi TCD

Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)
Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997

Calibration Files

=T01476.D 2 =T01473.D 5 =T01475.D 3 = T01474.D1

=T01472.D

_		Compound	1	2	3	4	5	Avg		%RSD
	) t	C8						1.414		3.40
	) t	C10	1.524	1.488	1.439	1.438	1.402	1.458	$\mathbf{E4}$	3.30
	) t	C12	1.623	1.588	1.542	1.535	1.499	1.557	E4	3.09
4	) t	C14	1.667	1.643	1.592	1.582	1.543	1.605	E4	3.09
5	) t	C16	1.733	1.692	1.641	1.631	1.587	1.657	E4	3.42
6	) t	C18	1.966	1.953	1.897	1.892	1.862	1.914	E4	2.30
7	) t	C20	1.917	1.871	1.814	1.805	1.757	1.833	<b>E4</b>	3.39
8	) t	C22	1.901	1.855	1.799	1.792	1.741	1.818	E4	3.40
	) t	C24	1.942	1.905	1.846	1.840	1.785	1.864	$\mathbf{E4}$	3.28
	) t	C26	1.950	1.900	1.844	1.841	1.783	1.863	E4	3.42
	) t	C28	1.928	1.898	1.844	1.845	1.776	1.858	E4	3.14
	) t	C30						1.877		4.15
	) t	C32						1.786		6.86
	) t	C34						1.633		7.43
	) t	C36						1.337		9.98
	) t	C38						0.937		10.12
	, ) t	C40						5.402		13.16
	, . ) t	C42						2.467		14.48
19	-		1.835							4.19
	) T		1.935							3.63
	) s		2.166	2.100	2.027	2.018	1.957	2.053	E4	3.94
	, ) t	TPHC - total						2.235		24.34

# Report of Analysis U.S. ...my, Fort Monmouth Environmental Labora...y NJDEP Certification # 13461

## Blank Spike Recovery Report

Lab. ID#:

2692

Location #:

B2506

Sample	Date Extracted	Spike Amount Added (ppm)	Matrix Spike Amount (ppm)	Percent Recovery	QC Limits %	
Blank Spike	17-Jun-97	630	793.18	125.90	75-125	

Data File : C:\HPCHEM\1\DATA\970618\T01638.D

Acq On : 18 Jun 97 10:20 am

Vial: 4 Operator: Skelton

Sample : 2692.01

ri ir

7 n

,cj ii

11 1

Inst : FID/TCD

Misc : Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 18 15:45 1997 Quant Results File: TPH8.RES


Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997 Response via : Multiple Level Calibration

DataAcq Meth : TPH8.M

Volume Inj. : 1 ul Signal Phase : HP-5



#### Quantitation Report (QT Reviewed)

Vial: 5

Data File : C:\HPCHEM\1\DATA\970618\T01639.D

Acq On : 18 Jun 97 11:03 am Operator: Skelton Sample : 2692.02 Inst : FID/TCD Misc Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 18 15:45 1997 Quant Results File: TPH8.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

: TPHC Calibration 06/05/97 21 peaks Title

Last Update : Thu Jun 05 14:02:46 1997

Response via: Initial Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

Compound	R.T.	Response	Conc (	Jnits
System Monitoring Compounds				
21) s o-terphenyl	13.68	241919	11.783	mq/L
Spiked Amount 10.000		very =	117.83%	٥,
_		4		
Target Compounds				
1) t C8	0.00	0	N.D.	mg/L
2) t C10	0.00	0	N.D.	mg/L
3) t C12	0.00	0	N.D.	mg/L
4) t C14	0.00	0	N.D.	mg/L
5) t C16	0.00	0	N.D.	mg/L
6) t C18	0.00	0	N.D.	mg/L
7) t C20	0.00	0	N.D.	mg/L
8) t C22	0.00	0	N.D.	mg/L
9) t C24	0.00	0	N.D.	mg/L
10) t C26	0.00	0	N.D.	mg/L d
11) t C28	0.00	0	N.D.	mg/L d
12) t C30	0.00	0	N.D.	mg/L d
13) t C32	0.00	0	N.D.	mg/L d
14) t C34	0.00	0	N.D.	mg/L d
15) t C36	0.00	0	N.D.	mg/L d
16) t C38	0.00	0	N.D.	mg/L d
17) t C40	0.00	0	N.D.	mg/L d
18) t c42	0.00	0	N.D.	mg/L d
19) T Pristane	0.00	0	N.D.	mg/L
20) T Phytane	0.00	0	N.D.	mg/L
22) t TPHC - total	0.00	0	N.D.	mg/L d

Data File : C:\HPCHEM\1\DATA\970618\T01639.D

Vial: 5 Acq On : 18 Jun 97 11:03 am Operator: Skelton : 2692.02 Sample Inst : FID/TCD Misc Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 18 15:45 1997 Quant Results File: TPH8.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)


Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997 Response via : Multiple Level Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

Signal Info :  $30m \times 0.32mm$ 



1.19

Quantitation Report (QT Reviewed) Data File : C:\HPCHEM\1\DATA\970618\T01640.D Vial: 6 Acq On : 18 Jun 97 11:46 am Sample : 2692.03 Operator: Skelton Sample Inst : FID/TCD Misc Multiplr: 1.00 IntFile : TPHCINT.E Quant Time: Jun 18 15:45 1997 Quant Results File: TPH8.RES Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator) : TPHC Calibration 06/05/97 21 peaks Title Last Update : Thu Jun 05 14:02:46 1997 Response via : Initial Calibration DataAcq Meth : TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc (	Jnits
System Monitoring Compounds 21) s o-terphenyl Spiked Amount 10.000	13.68 Reco	262060 very =	12.763 127.63%	mg/L
Target Compounds		•		/-
1) t C8	0.00	0	N.D.	mg/L
2) t C10	0.00	0	N.D.	mg/L
3) t C12	0.00	0	N.D.	mg/L
4) t C14	0.00	0	N.D.	mg/L
5) t C16	0.00	0	N.D.	mg/L
6) t C18	0.00	0	N.D.	mg/L
7) t C20	0.00	0	N.D.	mg/L
8) t C22	0.00	0	N.D.	mg/L
9) t C24	0.00	0	N.D.	mg/L
10) t C26	0.00	0	N.D.	mg/L d
11) t C28	0.00	0	N.D.	mg/L d
12) t C30	0.00	0	N.D.	mg/L d
13) t C32	0.00	0	N.D.	mg/L
14) t C34	0.00	0	N.D.	mg/L
15) t C36	0.00	0	N.D.	mg/L
16) t C38	0.00	0	N.D.	mg/L
17) t C40	0.00	0	N.D.	mg/L
18) t c42	0.00	0	N.D.	mg/L
19) T Pristane	0.00	0	N.D.	mg/L
20) T Phytane	0.00	0	N.D.	mg/L
22) t TPHC - total	0.00	0	N.D.	mg/L d

याः क

Data File : C:\HPCHEM\1\DATA\970618\T01640.D

Vial: 6 : 18 Jun 97 11:46 am Operator: Skelton

: 2692.03 Sample Inst : FID/TCD Misc Multiplr: 1.00

: TPHCINT.E IntFile

Acq On

الد ووديا

(1.)

1.1-4

3.15.3

Care de

Quant Time: Jun 18 15:45 1997 Quant Results File: TPH8.RES


Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997 Response via: Multiple Level Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5



Response

Conc Units

Vial: 7 Data File : C:\HPCHEM\1\DATA\970618\T01641.D

Acq On : 18 Jun 97 12:29 pm Operator: Skelton Sample : 2692.04 : FID/TCD Inst Misc Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 18 15:45 1997 Quant Results File: TPH8.RES

Quant Method: C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

R.T.

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997

Response via : Initial Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

Compound

late at

Ni and

/1:3

	compound	10.1.	response	00110	0111100
21) s	tem Monitoring Compounds o-terphenyl Amount 10.000	13.68 Recovei	265031 ry =	12.908 129.08%	mg/L
Tar	get Compounds				
1) t	C8	0.00	0	N.D.	mg/L
2) t	C10	0.00	0	N.D.	mg/L
3) t	C12	0.00	0	N.D.	mg/L
4) t	C14	0.00	0	N.D.	mg/L
5) t	C16	0.00	0	N.D.	mg/L
6) t	C18	0.00	0	N.D.	mg/L
7) t	C20	0.00	0	N.D.	mg/L
8) t	C22	0.00	0	N.D.	mg/L
9) t	C24	0.00	0	N.D.	mg/L
10) t	C26	0.00	0	N.D.	mg/L d
<b>11</b> ) t	C28	0.00	0	N.D.	mg/L d
<b>12</b> ) t	C30	0.00	0	N.D.	mg/L d
13) t	C32	0.00	0	N.D.	mg/L d
<b>14</b> ) t	C34	0.00	0	N.D.	mg/L d
15) t	C36	0.00	0	N.D.	mg/L d
16) t	C38	0.00	0	N.D.	mg/L d
17) t	C40	0.00	0	N.D.	mg/L
<b>1</b> 8) t	c42	0.00	0	N.D.	mg/L
19) T	Pristane	0.00	0	N.D.	mg/L
20) T	Phytane	0.00	0	N.D.	mg/L
22) t	TPHC - total	0.00	0	N.D.	mg/L d

Data File: C:\HPCHEM\1\DATA\970618\T01641.D

Vial: 7 : 18 Jun 97 12:29 pm Operator: Skelton : 2692.04 Sample Inst : FID/TCD Misc Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 18 15:45 1997 Quant Results File: TPH8.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997 Response via: Multiple Level Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

\-iasi

613.4


7.18.1

card

7.1.1

Lora d

7.1.3



Response Conc Units

Data File : C:\HPCHEM\1\DATA\970618\T01642.D Vial: 8 Acq On : 18 Jun 97 1:12 pm Operator: Skelton Sample : 2692.05 Inst : FID/TCD Misc Multiplr: 1.00 IntFile : TPHCINT.E

Quant Time: Jun 18 15:46 1997 Quant Results File: TPH8.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

R.T.

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997

Response via: Initial Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

Compound

Signal Info :  $30m \times 0.32mm$ 

		compound	10.1.	Response	00110	5111 05
1	21) s	em Monitoring Compounds o-terphenyl Amount 10.000	13.68 Recover	263769 TY =	12.847 128.47%	mg/L
ud.	Taro	get Compounds				
	1) t	C8	0.00	0	N.D.	mg/L
,	2) t	C10	0.00	0	N.D.	mg/L
,	3) t	C12	0.00	0	N.D.	mg/L
	4) t	C14	0.00	0	N.D.	mg/L
1	5) t	C16	0.00	0	N.D.	mg/L
i	6) t	C18	0.00	0	N.D.	mg/L
	7) t	C20	0.00	0	N.D.	mg/L
1	8) t	C22	0.00	0	N.D.	mg/L
	9) t	C24	0.00	0	N.D.	mg/L
· al	<b>1</b> 0) t	C26	0.00	0	N.D.	mg/L d
4	11) t	C28	0.00	0	N.D.	mg/L d
	<b>1</b> 2) t	C30	0.00	0	N.D.	mg/L d
*	13) t	C32	0.00	0	N.D.	mg/L d
	<b>14</b> ) t	C34	0.00	0	N.D.	mg/L
1	15) t	C36	0.00	0	N.D.	mg/L
d	16) t	C38	0.00	0	N.D.	mg/L
	<b>17</b> ) t	C40	0.00	0	N.D.	mg/L
8	<b>1</b> 8) t	c42	0.00	0	N.D.	mg/L
	19) T	Pristane	0.00	0	N.D.	mg/L
	20) T	Phytane	0.00	0	N.D.	mg/L
4	22) t	TPHC - total	0.00	0	N.D.	mg/L d

11 2

Data File: C:\HPCHEM\1\DATA\970618\T01642.D

Acq On : 18 Jun 97 1:12 pm

Vial: 8 Operator: Skelton Inst : FID/TCD

Misc

ide a

614.3

011.3

Nin.B

2111

440.6

7113

Sample : 2692.05

Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 18 15:46 1997 Quant Results File: TPH8.RES


Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

: TPHC Calibration 06/05/97 21 peaks Title

Last Update : Thu Jun 05 14:02:46 1997 Response via : Multiple Level Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5



Vial: 9 Data File : C:\HPCHEM\1\DATA\970618\T01643.D : 18 Jun 97 Operator: Skelton 1:56 pm Sample : 2692.06 : FID/TCD Inst Misc Multiplr: 1.00 IntFile : TPHCINT.E Quant Time: Jun 18 15:46 1997 Quant Results File: TPH8.RES Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks Last Update : Thu Jun 05 14:02:46 1997

Response via : Initial Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

7.10

Last

Link

2.1-1

7.1 3

L.J		Compound	R.T.	Response	Conc (	Jnits
- 1						
د.	Syst	tem Monitoring Compounds o-terphenyl	13.68	266118	12.961	ma/I.
ţ		Amount 10.000	Recove		129.61%	g/ 1
	Брикса	7	1100011	-	123.010	
4.4	Taro	get Compounds				
,	1) t	C8	0.00	0	N.D.	mg/L
	2) t	C10	0.00	0	N.D.	mg/L
ı. J	3) t	C12	0.00	0	N.D.	mg/L
	4) t	C14	0.00	0	N.D.	mg/L
1	5) t	C16	0.00	0	N.D.	mg/L
ı. J	6) t	C18	0.00	0	N.D.	mg/L
	7) t	C20	0.00	0	N.D.	mg/L
1	8) t	C22	0.00	0	N.D.	mg/L
	9) t	C24	0.00	0	N.D.	mg/L
4.1	<b>1</b> 0) t	C26	0.00	0	N.D.	mg/L d
. (	11) t	C28	0.00	0	N.D.	mg/L d
	<b>12</b> ) t	C30	0.00	0	N.D.	mg/L d
i	<b>1</b> 3) t	C32	0.00	0	N.D.	mg/L
	<b>14</b> ) t	C34	0.00	0	N.D.	mg/L
ı	15) t	C36	0.00	0	N.D.	mg/L
ı i	16) t	C38	0.00	0	N.D.	mg/L
	<b>17</b> ) t	C40	0.00	0	N.D.	mg/L
ι	18) t	c42	0.00	0	N.D.	mg/L
	19) T	Pristane	0.00	0	N.D.	mg/L
d	20) T	Phytane	0.00	. 0	N.D.	mg/L
	22) t	TPHC - total	0.00	0	N.D.	mg/L d

Data File : C:\HPCHEM\1\DATA\970618\T01643.D

Vial: 9 Acq On : 18 Jun 97 1:56 pm Operator: Skelton Sample : 2692.06 : FID/TCD Inst Misc Multiplr: 1.00

IntFile : TPHCINT.E

Lite #

6111

sant.

71.4

4.7

Your J

7.124

3-4-4

Quant Time: Jun 18 15:46 1997 Quant Results File: TPH8.RES


Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

: TPHC Calibration 06/05/97 21 peaks Title

Last Update : Thu Jun 05 14:02:46 1997 Response via : Multiple Level Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase : HP-5



Multiplr: 1.00

Data File : C:\HPCHEM\1\DATA\970618\T01644.D Vial: 10 Acq On : 18 Jun 97 2:40 pm Operator: Skelton Sample : 2692.07 Inst : FID/TCD

Misc

IntFile : TPHCINT.E

Quant Time: Jun 18 15:46 1997 Quant Results File: TPH8.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997

Response via: Initial Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

148 1

14.3

71.3

. . . .

71-3

		Compound	R.T.	Response	Conc Uni	its
1						
,	Syst	em Monitoring Compounds				
	21) s	o-terphenyl	13.68	264514	12.883 mg	g/L
	Spiked	Amount 10.000	Reco	very =	128.83%	
	Taro	get Compounds				
	1) t	C8	0.00	0	N.D. mo	g/L
	2) t	C10	0.00	0		g/L
•	3) t	C12	0.00	0		g/L
	4) t	C14	0.00	0		J/L
	5) t	C16	0.00	. 0		g/L
,	6) t	C18	0.00	. 0		J/L
	7) t	C20	0.00	0	N.D. mg	g/L
1	8) t	C22	0.00	0	N.D. mg	g/L
	9) t	C24	0.00	0	N.D. mg	g/L
	10) t	C26	0.00	0	N.D. mg	g/L d
	11) t	C28	0.00	0	N.D. mg	g/L d
	<b>1</b> 2) t	C30	0.00	0	N.D. mg	g/L d
ì	13) t	C32	0.00	0	N.D. mg	g/L d
	14) t	C34	0.00	0		g/L d
	15) t	C36	0.00	0	N.D. mg	g/L d
	16) t	C38	0.00	0	N.D. mg	g/L d
	17) t	C40	0.00	0	N.D. mg	g/L d
,	18) t	c42	0.00	0		g/L d
	19) T	Pristane	0.00	0		g/L d
ı	20) T	Phytane	0.00	0		g/L d
ı	22) t	TPHC - total	0.00	0	N.D. mg	g/L d

Data File : C:\HPCHEM\1\DATA\970618\T01644.D

Acq On : 18 Jun 97 2:40 pm

Vial: 10 Operator: Skelton

Sample : 2692.07

: FID/TCD Inst

Misc Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 18 15:46 1997 Quant Results File: TPH8.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997 Response via : Multiple Level Calibration

DataAcq Meth : TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

فدونت

7.13.8

Lan Z

11.1


- 1 - 1

فسالط

7.133

A 164

11.4



'QT Reviewed)

Data File : C:\HPCHEM\1\DATA\970618\T01646.D Vial: 12 Acq On : 18 Jun 97 4:08 pm Operator: Skelton : 2692.08 Sample Inst : FID/TCD Misc Multiplr: 1.00 IntFile : TPHCINT.E Quant Time: Jun 25 9:49 1997 Quant Results File: TPH8.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

: TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997

Response via: Initial Calibration

DataAcq Meth : TPH8.M

Volume Inj. : 1 ul Signal Phase : HP-5

Signal Info :  $30m \times 0.32mm$ 

Compound	R.T.	Response	Conc (	Jnits
System Monitoring Compounds 21) s o-terphenyl	13.68	268236	13.064	mg/L m
Spiked Amount 10.000	Recov	ery =	130.64%	-
Target Compounds				
1) t C8	0.00	0	N.D.	mg/L
2) t C10	0.00	0	N.D.	mg/L
3) t C12	0.00	0	N.D.	mg/L
4) t C14	0.00	0	N.D.	mg/L
5) t C16	0.00	0	N.D.	mg/L
6) t C18	0.00	0	N.D.	mg/L
7) t C20	0.00	0	N.D.	mg/L
8) t C22	0.00	0	N.D.	mg/L
9) t C24	0.00	0	N.D.	mg/L
10) t C26	0.00	0	N.D.	mg/L d
11) t C28	0.00	0	N.D.	mg/L d
<b>12</b> ) t C30	0.00	0	N.D.	mg/L d
13) t C32	0.00	0	N.D.	mg/L d
14) t C34	0.00	0	N.D.	mg/L d
15) t C36	0.00	0	N.D.	mg/L d
16) t C38	0.00	0	N.D.	mg/L d
17) t C40	0.00	0	N.D.	mg/L d
18) t c42	0.00	0	N.D.	mg/L d
19) T Pristane	0.00	. 0	N.D.	mg/L d
20) T Phytane	0.00	0	N.D.	mg/L d
22) t TPHC - total	0.00	0	N.D.	mg/L d

(m)=manual int.

T01646.D TPH8.M Wed Jun 25 09:49:43 1997

Data File : C:\HPCHEM\1\DATA\970618\T01646.D

Vial: 12 : 18 Jun 97 4:08 pm Operator: Skelton Sample : 2692.08 Inst : FID/TCD Misc Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 25 9:49 1997 Quant Results File: TPH8.RES


Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997 Response via: Multiple Level Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5



Data File : C:\HPCHEM\1\DATA\970618\T01649.D Vial: 15 Acq On : 18 Jun 97 6:22 pm Operator: Skelton

Sample : 2692.09 Inst : FID/TCD Misc Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 19 16:16 1997 Quant Results File: TPH8.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks

Last Update : Thu Jun 05 14:02:46 1997

Response via: Initial Calibration

DataAcq Meth : TPH8.M

Volume Inj. : 1 ul Signal Phase : HP-5

Compound	R.T.	Response	Conc U	nits
System Monitoring Compounds 21) s o-terphenyl Spiked Amount 10.000	13.68 Reco	265530 overy =	12.932 1 129.32%	mg/L
Target Compounds  1) t C8  2) t C10  3) t C12  4) t C14  5) t C16  6) t C18  7) t C20  8) t C22  9) t C24  10) t C26  11) t C28  12) t C30  13) t C32	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	0 0 0 0 0 0 0 0	N.D. 11 N.D. 12 N.D. 13 N.D. 14 N.D. 15 N.D. 16 N.D. 17 N.D. 17 N.D. 18 N.D. 1	mg/L mg/L mg/L mg/L mg/L mg/L d mg/L d mg/L d mg/L d
14) t C34 15) t C36 16) t C38 17) t C40 18) t c42 19) T Pristane 20) T Phytane 22) t TPHC - total	0.00 0.00 0.00 0.00 0.00 0.00	0 0 0 0 0 0 0	N.D. N.D. N.D. N.D. N.D. N.D.	mg/L mg/L mg/L mg/L mg/L mg/L mg/L mg/L d

Data File : C:\HPCHEM\1\DATA\970618\T01649.D

Vial: 15 : 18 Jun 97 6:22 pm Operator: Skelton : 2692.09 Sample Inst : FID/TCD Misc Multiplr: 1.00

IntFile : TPHCINT.E

Quant Time: Jun 19 16:16 1997 Quant Results File: TPH8.RES

Quant Method: C:\HPCHEM\1\METHODS\TPH8.M (Chemstation Integrator)

Title : TPHC Calibration 06/05/97 21 peaks


Last Update : Thu Jun 05 14:02:46 1997 Response via: Multiple Level Calibration

DataAcq Meth: TPH8.M

Volume Inj. : 1 ul Signal Phase: HP-5

DELLA

Signal Info : 30m x 0.32mm



711%

#### LABORATORY DELIVERABLES CHECKLIST AND NON-CONFORMANCE SUMMARY

## THIS FORM MUST BE COMPLETED BY THE LABORATORY OR ENVIRONMENTAL CONSULTANT AND ACCOMPANY ALL DATA SUBMISSIONS

The following Laboratory Deliverables checklist and Non-Conformance Summary shall be included in the data submission. All deviations from the accepted methodology and procedures, of performance values outside acceptable ranges shall be summarized in the Non-Conformance Summary. The Technical Requirements for Site Remediation, effective June 7, 1993, provides further details. The document shall be bound and paginated, contain a table of contents, and all pages shall be legible. Incomplete packages will be returned or held without review until the data package is completed.

It is recommended that the analytical results summary sheets listing all targeted and non-targeted compounds with the method detection limits, practical quantitation limits, and the laboratory and/or sample numbers be included in one section of the data package <u>and</u> in the main body of the report.

1.	Cover page, Title Page listing Lab Certification #, facility name and address, & date of report submitted	
2.	Table of Contents submitted	
3.	Summary Sheets listing analytical results for all targeted and non-targeted compounds submitted	
4.	Document paginated and legible	
5.	Chain of Custody submitted	
6.	Samples submitted to lab within 48 hours of sample collection	
7.	Methodology Summary submitted	
8.	Laboratory Chronicle and Holding Time Check submitted	
9.	Results submitted on a dry weight basis	
10.	Method Detection Limits submitted	~
11.	Lab certified by NJDEP for parameters of appropriate category of parameters or a member of the USEPA CLP	
Laboratory Manager or Environmental Consultant's Signature  Date 1/16/97		

\*Refer to NJAC 7:26E - Appendix A, Section IV - Reduced Data Deliverables - Non-USEPA/CLP Methods for further guidance

Laboratory Certification #13461

**APPENDIX F** 

**PHOTOGRAPHS** 



December 1997

## PHOTOGRAPHIC LOG

UST No. 81515-17

Building 2506
Charles Wood Area
Fort Monmouth



**SMC Environmental Services Group** 

Engineers, Managers, Scientists, & Planners Valley Forge, Pennsylvania